




1461 E. CHEVY CHASE DR. #200, GLENDALE, CA 91206 818•549•9959 TEL 818•543•3747 FAX "Trust the Name You Know"

GEOLOGIC AND GEOTECHNICAL ENGINEERING REPORT PROPOSED ADDITION, FOUR NEW BUILDINGS, RETAINING WALLS, AND SWIMMING POOL LOT 1, TRACT 23823 3900 STANSBURY AVENUE SHERMAN OAKS, CALIFORNIA FOR THE BUCKLEY SCHOOL THE J. BYER GROUP, INC. PROJECT NUMBER JB 19376-B JUNE 6, 2006



GEOLOGIC AND GEOTECHNICAL ENGINEERING REPORT PROPOSED ADDITION, FOUR NEW BUILDINGS, RETAINING WALLS, AND SWIMMING POOL LOT 1, TRACT 23823 3900 STANSBURY AVENUE SHERMAN OAKS, CALIFORNIA FOR THE BUCKLEY SCHOOL THE J. BYER GROUP, INC. PROJECT NUMBER JB 19376-B JUNE 6, 2006

INTRODUCTION

Per your written authorization, The J. Byer Group has prepared this report to summarize findings of our geologic and geotechnical engineering exploration performed at the site. The purpose of this study is to evaluate the nature, distribution, engineering properties, relative stability, and geologic structure of the earth materials underlying the site with respect to constructing additions, four new buildings, retaining walls, and a swimming pool.

<u>INTENT</u>

It is the intent of this report to assist in the design and completion of the proposed projects. The recommendations are intended to reduce geotechnical risks affecting the projects. The professional opinions and advice presented in this report are based upon commonly accepted standards and are subject to the general conditions described in the <u>NOTICE</u> section of this report.

EXPLORATION

The scope of the recent exploration was determined from a site observation by John Byer and review of the new Master Plan Design prepared by Jeffrey M. Kalban & Associates. Exploration was conducted using techniques normally applied to this type of project in this setting. This report is limited to the area of the exploration as shown on the enclosed Geologic Map and cross sections. Conditions affecting portions of the property outside the area explored are beyond the scope of this report.

The original exploration was conducted on September 27, October 1, and October 6, 2003. The recent testing was done on December 22, 2005. The combined exploration includes 10 hand dug test pits and 19, eight inch hollow-stem auger borings. Soil samples were obtained from the test pits and borings and returned to our soils engineering laboratory for testing and analysis. The borings and test pits were logged by the undersigned engineering geologist, project geologist, and our project engineer.

Office tasks included review of laboratory testing, review of the City of Los Angeles, Department of Building and Safety (LADBS), grading records for the subject property, preparation of the Geologic Map, preparation of Sections A through F and I, and engineering analysis of the existing slopes and proposed structures. A description of the earth materials can be found on the enclosed Log of Test Pits and Log of Borings. Appendix I contains a discussion of the laboratory testing procedures and results.

The proposed project, surface geologic conditions, test pit and boring locations are shown on the Geologic Map. Subsurface distribution of the earth materials, projected geologic structure, and the proposed projects are shown on Sections A through F and I.

RESEARCH - PRIOR WORK

LADBS files contain numerous reports which were prepared for the property dating back to 1968. These reports provide geotechnical and geologic information with respect to development of the school and the site conditions at each of the existing structures. Copies of the reports, which describe geologic and geotechnical conditions for the buildings and the city approval letters are attached to this report as Appendix II. The Geologic Map indicates the date that the building sites were developed and shows the approximate limits of the grading as determined from the previous reports. The data contained in the previous reports was reviewed and considered as part of our work on this project.

PROPOSED DEVELOPMENT

Information concerning the proposed project was provided by Jeffrey M. Kalban & Associates. It is proposed to construct four new buildings at the school facility. The three new academic buildings and a library/tech center will be located on the lower portion of the campus. The proposed Main Academic Building will consist of two stories of classrooms and offices over two levels of partial subterranean parking. The Academic Building West will be two stories. The Library/Tech Center Building will be two stories and a basement. The Aquatic Center Building will be two stories and will be located on the north portion of the athletic field. The swimming pool is to be located to the southeast of the Aquatic Center Building. The addition is planned for the north side of the Academic Building South.

SITE DESCRIPTION

The subject property is located on the north flank of the Santa Monica Mountains, south of Ventura Boulevard and east of Beverly Glen Boulevard (33.1401°N Latitude, 118.4436°W Longitude). Access is provided by Stansbury Avenue, which leads up to the school from the north. Several

The J. Byer Group, Inc.

interior roads allow traffic to proceed through the school. Parking is provided by the main lot near Stansbury Avenue. The property consists of a north draining canyon, which has periodically been filled with compacted and uncompacted soil imported to the property. Natural slopes ascend from the graded areas to the west up to Camino De La Cumbre Avenue at an average 2:1 slope gradient. Natural slopes ascend above the east side of the canyon between 275 feet high at a 1.8:1 gradient and 325 feet high at an overall 2:1 slope gradient. These natural slopes are underlain by bedrock and show no signs of past instability or soil erosion. The slopes are covered with a thick growth of native brush. Secondary drainage swales enter the property from the east and carry natural runoff to the storm drain system. Drainage within the graded portion of the school site is collected in numerous surface drains and catch basins and transferred to the storm drainage system.

GROUNDWATER

The majority of the borings did not encounter groundwater. The bedrock formation is generally tight and not a groundwater producer. Water was noticed in Boring 1 at a depth of 55 feet and in Boring 13 at a depth 56½ feet. The groundwater apparently is perched on the top of the bedrock and is seeping along the bedrock/alluvium contact. It is the opinion of The J. Byer Group that groundwater will not be a factor in the construction of the proposed buildings and additions to the school. It should be noted that seasonal fluctuations in groundwater levels may occur due to variations in climate, irrigation, and other factors not evident at the time of the exploration. Fluctuations in groundwater levels may also occur across the site.

EARTH MATERIALS

Compacted Fill

Several generations of compacted fill are present at the school dating back to the original grading performed in 1968. The fill consists of soil imported to the site and compacted under the site observation of Advanced Foundation Engineers and Converse, Davis and Associates. Copies of the Compaction Reports and city approval letters can be found in Appendix II. The fill locations are shown on the Geologic Map.

<u>Fill</u>

Fill was imported to the property to generate a level area at the front for the parking lot and in the southern portion of the property for the athletic field. This fill was not compacted and was not tested by a geotechnical engineer. The fill exposed in Boring 1 consists of an upper layer of clayey sand that is brown, moist, medium dense, and contains some gravel. At a depth of about 14 feet, the fill changes to a dark gray clayey sand that is moist and dense. The fill contains small pebbles of slate that are rounded. The imported clayey sand fill with slate chips is relatively consistent throughout the property. The fill is 25 feet thick in Boring 1, which is at the north end of the school. The fill thins to less than 20 feet to the south, east, and west. Fill was found in Borings 10, 11, and 12 in the south-central portion of the school to a depth of 24 feet in Boring 11. The fill in Boring 11 also contained some construction debris and rubble. Fill underlies the athletic field to a depth of 43 feet as indicated in Boring 13. The fill consists of clayey sand that is reddish brown to dark gray and contains small slate gravel.

Alluvium

Natural alluvial soils underlie the fill and consist of an upper layer of silty clay that is brown, moist, firm, and very porous. The alluvium becomes coarser with depth and grades to light brown silty sand with gravel. It contains large gravel and some small cobbles with depth. The alluvium extends to a depth of 59 feet below grade in Boring 1. The alluvial section becomes thinner to the south where borings encountered bedrock at 43 feet below the surface. The alluvium in Boring 14, which is at the southern end of the school, was found to terminate at 28 feet below grade.

<u>Soil</u>

Natural residual soil blankets the ascending slopes around the property and was encountered in Borings 7 through 10. The soil consists of clayey sand that is dark brown, damp, dense, porous, and contains numerous shale fragments.

<u>Bedrock</u>

Bedrock underlying the property consists of diatomaceous siltstone with interbedded sandstone which is part of the Miocene Modelo Formation. The bedrock is well exposed on cut slopes along Camino De La Cumbre Avenue as well as natural outcrops within the school property. The diatomaceous siltstone and sandstone is well bedded, light gray to tan, and moderately hard.

GEOLOGIC STRUCTURE

Bedding planes within the bedrock strike nearly east-west and dip 25 to 30 degrees to the north. The bedding planes mapped are consistent from the north end of the campus to the south. The geologic structure is also consistent with regional trends. The geologic structure of the bedrock is favorably oriented with respect to gross geologic stability of the site.

GENERAL SEISMIC CONSIDERATIONS

The subject property and all of southern California are located in an active seismic region (CBC Seismic Zone IV). Moderate to strong earthquakes can occur on numerous local faults. The United States Geological Survey, California Geological Survey, private consultants, and universities have been studying earthquakes in southern California for several decades. Early studies were directed toward earthquake prediction and estimation of the effects of strong ground shaking. Studies indicate that earthquake prediction is not practical and not sufficiently accurate to benefit the general public. Governmental agencies are shifting their focus to earthquake resistant structures as opposed to prediction. The purpose of the code seismic design parameters is to prevent collapse during strong ground shaking. Cosmetic damage should be expected.

Within the past 35 years, southern California and vicinity have experienced an increase in seismic activity beginning with the San Fernando earthquake in 1971. In 1987, a moderate earthquake struck the Whittier area and was located on a previously unknown fault. Ground shaking from this event caused substantial damage to the City of Whittier, and surrounding cities.

The January 17, 1994, Northridge Earthquake was initiated along a previously unrecognized fault below the San Fernando Valley. The energy released by the earthquake propagated to the southeast, northwest, and northeast in the form of shear and compression waves, which caused the strong ground shaking in portions of the San Fernando Valley, Simi Valley, City of Santa Clarita, and City of Santa Monica.

Southern California faults are classified as active or potentially active. Faults from past geologic periods of mountain building that do not display any evidence of recent offset are considered "potentially active." Faults that have historically produced earthquakes or show evidence of movement within the past 11,000 years are known as "active faults." No known active faults cross the subject property.

The J. Byer Group, Inc.

The nearest known potentially active fault is located approximately 3½ kilometers to the south (Santa Monica-Hollywood Fault). From a Building Code (Chapter 16) standpoint, the nearby Santa Monica-Hollywood Fault is classified as a Type "B" fault. The following table lists the applicable CBC seismic coefficients for the project:

BUILDING CODE SEISMIC COEFFICIENTS			
Earth Materials	Compacted Fill/Alluvium		
Soil Profile Type	. S _D		
Seismic Coefficient (C _a)	0.44N _a		
Seismic Coefficient (C_v)	0.64N _v		
Near-Source Factor (N _a)	1.15		
Near-Source Factor (N _v)	1.4		

The principal seismic hazard to the subject property and proposed project is strong ground shaking from earthquakes produced by local faults. Modern, well-constructed buildings are designed to resist ground shaking through the use of shear panels and reinforcement. Additional precautions may be taken to protect personal property and reduce the chance of injury, including strapping water heaters and securing furniture. It is likely that the subject property will be shaken by future earthquakes produced in southern California. However, secondary effects such as surface rupture, lurching, liquefaction, consolidation, ridge shattering, and landsliding should not occur at the subject property.

Liquefaction

The California Geologic Survey has not mapped the site within an area of historic liquefaction. A high groundwater table is not present below the site and the earth materials are fine grained and not subject to liquefaction.

The J. Byer Group, Inc. 1461 East Chevy Chase Drive • Suite 200 • Glendale, California 91206 • (818) 549-9959 • Fax (818) 543-3747 *"Trust the Name You Know"*

SLOPE STABILITY

Gross Stability

Slopes on the subject property include a natural slope in bedrock that is 275 feet high at 1.8:1 gradient (see Section I). The gross and seismic stability of the slope was analyzed using Bishop's method with a software program by Taga, Copyright 1983.

The analysis shows that the natural ascending slope is grossly stable with a factor of safety in excess of 1.5. The calculations use the shear tests of samples believed to represent the weakest bedrock encountered during exploration. The cross section used is the most critical for the slopes analyzed.

Surficial Stability

Based upon the enclosed calculations, it is reasonable to assume that the natural residual soil is surficially stable. The method of analysis used is the "parallel seepage model" recommended by the American Society of Civil Engineers and the Building and Safety Advisory Committee (August 16, 1978). The assumptions of this method are a uniform planar slope, uniform soil density and shear strength, and uniform seepage parallel to the slope. The validity of the analysis depends, in part, on how closely the assumptions model the field conditions.

For surficial deposits overlying natural slopes, it is the opinion of The J. Byer Group, Inc. that the assumptions of the "parallel seepage model" are not completely satisfied. Thus, though the calculation shows that the surficial materials on the site are stable with a factor of safety in excess of 1.5, the mitigating measures recommended in the "Conclusions and Recommendations" of this report should be implemented during development of the site.

ENVIRONMENTAL GEOLOGY

1. Purpose

The purpose of this section is to provide data for support of the environmental impact report being prepared for the Buckley School improvements. The "Conclusions and Recommendations" section of this report discusses the technical issues with respect to constructing new facilities at the Buckley School. General geologic conditions are discussed in this report, but are summarized in this section.

2. Regional Geology

The subject property is located on the enclosed Regional Geologic Map, which shows the north flank of the Santa Monica Mountains and the southern edge of the San Fernando Valley. This area of the Santa Monica Mountains is underlain by sedimentary bedrock formations consisting of Miocene sandstone and shales, which strike nearly east-west and dip to the north at 25 to 30 degrees. Geologic conditions discovered during our exploration are consistent with regional trends. The north draining canyons contain natural alluvium, which has washed into the canyons from the side walls. The alluvium consists of a mixture of sand, silt, and clay, along with gravel and cobbles of the bedrock. At the subject property, the alluvium has been covered with a layer of fill imported to the site and placed for support of structures and to gain additional level area. There are no landslides indicated from our exploration and none are shown on the Regional Geologic Map. Development of the school facility should have a minimal impact on the existing geologic conditions provided the conclusions and recommendations of this study are incorporated into the building plans and implemented during development of the structures.

3. Site Seismicity

The subject property is <u>NOT</u> located within an Alquist-Priolo special study zone. No known active faults pass through the school property. The computer program EQSEARCH is a database of historical earthquakes, including the 1994 Northridge, 1992 Landers, 1987 Whittier, and 1971 San Fernando. The peak ground acceleration is calculated for each earthquake and is shown on the following table.

HISTORICAL EARTHQUAKES				
Earthquake	Year	Calculated Ground Acceleration (%g)		
San Fernando	1971	0.104		
Whittier	1987	0.059		
Landers	1992	0.017		
Northridge	1994	0.335		

The 1994 Northridge Earthquake is the most significant historic event and occurred on a "blind" fault located below the San Fernando Valley approximately 6½ miles northwest of the school. It generated a ground acceleration of 0.335g. The site is <u>NOT</u> within an area of liquefaction potential, but portions of the ascending slope are in a seismic landslide hazard zone, as shown on the enclosed Seismic Hazard Map. Calculations performed on the slopes above the school indicate that the natural slopes in bedrock are grossly and seismically stable (Calculation Sheets 1-6). The Northridge Earthquake did cause damage to the elementary school building on the northwest corner of the school. The area was developed in 1968 by placing compacted fill over the existing grade. The previous geotechnical engineer did not recognize the need to remove and recompact the upper four feet of the existing alluvium, which is porous and subject to collapse upon saturation or earthquake loading. This is a local condition and the building was repaired by placing underpinning piles into the bedrock. A copy of the report describing the repair can be found in Appendix II.

The J. Byer Group, Inc.

4. Soil Stability

Natural ascending slopes surround the school and are underlain by natural soil over shale bedrock. The natural slopes on the subject property do not show any signs of surficial slope failures or erosion. A surficial failure did occur offsite in response to the record rainfall of the 2004/2005 rainy season. The failure occurred on the slope west of Camino De La Cumbre, near the rear gate of the school. Concentrated drainage from Beverly Ridge Drive residential development flowed over the descending slope causing erosion. The eroded material moved downslope across the small street, Camino de La Solana, and came to rest on Camino De La Cumbre. The mud was removed from the street. Natural drainages enter the property from the east and can be sources of eroded soil material. Erosion control is recommended for those areas where concentrated offsite flows can carry mud and water onto the school site.

5. Mineral Resources

The Miocene shale at the site does not contain any mineral resources. The shale layers do contain some fish fossils. These fossils are scattered throughout the formation and are not unique or rare.

6. Seismic Safety

The proposed school project is not located in an area where seismic safety is an issue with respect to development of the new buildings. The site is not subject to fault displacement. Ground shaking from local earthquakes will occur at the site. However, modern, well designed buildings are resistant to ground shaking. Liquefaction is not a hazard at the subject property. Seismic settlement of the school building at the northwest corner of the school did occur as the result of shaking from the Northridge Earthquake. The building has been repaired by underpinning. None of the other structures were adversely affected by the strong seismic waves. There are no bodies of water surrounding the school site. Inundation due to tsunami, seiches, and mudflow is not a hazard.

The J. Byer Group, Inc.

7. Geologic and Geotechnical Conditions

Based upon our exploration and testing there are no landslides within the property. No offsite landslides were discovered during our exploration. The subject property is protected from flooding by a large storm drain system. Subsidence of the older portion of the school did occur in the past due to strong ground shaking from the Northridge Earthquake. Subsidence of the remaining portion of the school should not occur as the buildings were placed on certified compacted fill pads tested by a geotechnical engineer. Subsidence of the open space fill areas may occur, but will not affect any structure. The earth materials underlying the school are not subject to lateral spreading. The earth materials are capable of supporting the proposed school buildings. The conclusions and recommendations contained in the following sections of this report should be included in the plans. There will be no impacts on mineral resources.

The expansion potential of the fill on the site was tested using the procedures outlined in ASTM D 4829-03. The results of the testing range from an expansion index of 18 to 42. These test results are in the very low to low range.

The data and conclusions of this exploration, testing, and report are subject to review by geotechnical engineers and engineering geologists employed by LADBS.

CONCLUSIONS AND RECOMMENDATIONS

General Findings

The conclusions and recommendations of this exploration are based upon 19 borings, 10 test pits, field geologic mapping, research of previous reports, consultation with Jeffrey M. Kalban & Associates, and over 30 years experience providing similar studies on similar sites. It is the finding of The J. Byer Group, Inc. that construction of the proposed buildings, addition, and swimming pool

The J. Byer Group, Inc.

is feasible from a geologic and soils engineering standpoint provided the advice and recommendations contained in this report are included in the plans and are implemented during construction. The following section is a discussion of the general site conditions as they pertain to the existing and proposed buildings.

The recommended bearing material for the proposed buildings, additions, and swimming pool is the bedrock. Due to the depth of fill and alluvium underlying portions of the site it will be necessary to utilize a deepened foundation system consisting of friction piles and grade beams. Where bedrock is at the finished grade of the proposed buildings, a conventional foundation system may be utilized.

It is proposed to re-grade the access road from the entrance to the athletic field. This will require cut and fill grading along the alignment of the road. In some areas the grade will be raised seven feet. The road alignment is underlain by fill and alluvium over bedrock. The existing fill is not certified. Due to the depth of the existing fill and an existing storm drain, it is not practical to remove and recompact the existing fill. In order to place new fill over uncertified fill it will be necessary to obtain a modification from the Building Code.

Excavation Characteristics

The test pits and borings did not encounter hard, cemented bedrock. Some of the existing fill contains construction debris including concrete and asphalt. The deeper sections of the alluvium contain cemented cobbles and boulders which could impede drilling progress. The diatomaceous siltstone bedrock is moderately hard and can be excavated with conventional drilling equipment. However, cemented layers are known to occur within this bedrock formation at random locations and depths and may be encountered during foundation excavation.

SWIMMING POOL

The proposed swimming pool will be located in an area of deep fill and alluvium. The swimming pool should utilize a free-standing design and be supported on a deepened foundation system extending into the bedrock.

FOUNDATION DESIGN

General Conditions

The following foundation recommendations are minimum requirements. The structural engineer may require footings that are deeper, wider, or larger in diameter, depending on the final loads. Foundation design may change depending upon the final location of the buildings and the elevations of the finished grades.

Spread Footings

Conventional spread footings may be used to support future buildings provided they are founded in bedrock. The use of conventional spread footings will depend upon the building location and the elevations of the finished floors. Continuous footings should be a minimum of 12 inches in width. Pad footings should be a minimum of 24 inches square. The following chart contains the recommended design parameters.

Bearing Material	Minimium Embedment Depth of Foating (Inches)	Vertical Bearing (psf)	Coefficient of Friction	Passive Liarth Ptessure (p.cf)	Maximum Earth Ptessure (pst)
Bedrock	12	2,000	0.4	400	4,000

The J. Byer Group, Inc.

Increases in the bearing value are allowable at a rate of 20 percent for each additional foot of footing width or depth to a maximum of 4,000 pounds per square foot. For bearing calculations, the weight of the concrete in the footing may be neglected.

The bearing values shown above are for the total of dead and frequently applied live loads and may be increased by one third for short duration loading, which includes the effects of wind or seismic forces. When combining passive and friction for lateral resistance, the passive component should be reduced by one third.

All continuous footings should be reinforced with a minimum of four #4 steel bars; two placed near the top and two near the bottom of the footings. Footings should be cleaned of all loose soil, moistened, free of shrinkage cracks and approved by the geologist prior to placing forms, steel or concrete.

Deepened Foundations - Friction Piles

Drilled, cast-in-place concrete friction piles are recommended to support buildings in areas of old fill. Piles should be a minimum of 24 inches in diameter and a minimum of eight feet into bedrock. Piles may be assumed fixed at eight feet into alluvium or four feet into bedrock. The piles may be designed for a skin friction of 600 pounds per square foot for the bedrock and 300 pounds per square foot for the alluvium. Foundation piles should be tied in two horizontal directions with grade beams.

Shoring Piles

Shoring will be required for excavations along the south and west side of the proposed Main Academic Building. The excavations will be up to 20 feet high and expose fill. Cast-in-place concrete shoring piles may be utilized to support these temporary excavations. Soldier piles should be a minimum of 24 inches in diameter and a minimum of eight feet into bedrock below the base of

The J. Byer Group, Inc.

the future excavations. Piles may be assumed fixed four feet into bedrock below the base of the excavations. The piles may be designed for a skin friction of 600 pounds per square foot for that portion of pile in contact with the bedrock. Shoring piles should be spaced a maximum of 10 feet on center. Shoring piles may be designed for an equivalent fluid pressure of 43 pounds per cubic foot per the enclosed calculation sheet #9. The fluid pressure should be multiplied by the pile spacing. Lagging between the shoring piles may be required for piles supporting existing fill. The shoring piles should be designed for the full anticipated lateral pressure. However, the pressure on the lagging will be less due to arching in the soils. Lagging should be designed for the recommended earth pressure, but may be limited to a maximum value of 400 pounds per square foot.

Lateral Design

The friction value is for the total of dead and frequently applied live loads and may be increased by one third for short duration loading, which includes the effects of wind or seismic forces. Resistance to lateral loading may be provided by passive earth pressure within the firm alluvium or bedrock.

For alluvium, passive earth pressure may be computed at 200 pounds per cubic foot. For bedrock, passive earth pressure may be computed at 400 pounds per cubic foot. The maximum allowable earth pressure is 4,000 pounds per square foot. For design of isolated piles, the allowable passive and maximum earth pressures may be increased by 100 percent. Piles spaced more than $2\frac{1}{2}$ pile diameters on center may be considered isolated.

Foundation Settlement

Settlement of the foundation system is expected to occur on initial application of loading. A settlement of $\frac{1}{4}$ to $\frac{1}{2}$ inch may be anticipated. Differential settlement should not exceed $\frac{1}{4}$ inch.

Toe of Slope Clearance


The Building Code requires a level setback between the toe of an ascending slope and the wall of the proposed structure of one half the slope height to a maximum 15 feet clearance for slopes steeper than 3:1. For swimming pools the setback is one fourth the slope height to a maximum 7.5 feet clearance for slopes steeper than 3:1. For retained slopes, the face of the retaining wall is considered the toe of the slope. Building Code setbacks will be evaluated on a building by building basis depending upon their location.

RETAINING WALLS

General Design

Basement and cantilevered retaining walls are planned for the proposed project. The basement walls will be up to 25 feet high. Cantilevered retaining walls may be up to 15 feet high. Cantilevered

retaining walls with a level to 2:1 backslope should be designed for an equivalent fluid pressure of 43 pounds per cubic foot. Restrained retaining walls for basements, where deflection at the top of the wall is limited, should be designed to resist a trapezoidal distribution of pressure. The maximum earth pressure is 27H pounds per square foot, where H is the height of the retaining wall in feet. The design earth pressure assumes a subdrain and that excess hydrostatic pressures are not developed.



<u>Backfill</u>

Retaining wall backfill should be compacted to a minimum of 90 percent of the maximum density as determined by ASTM D 1557-02, or equivalent. Where access between the retaining wall and the temporary excavation prevents the use of compaction equipment, retaining walls should be backfilled with ³/₄ inch crushed gravel to within two feet of the ground surface. Where the area between the wall and the excavation exceeds 18 inches, the gravel must be vibrated or wheel-rolled, and tested for compaction. The upper two feet of backfill above the gravel should consist of a compacted fill blanket to the surface. Retaining wall backfill should be capped with a paved surface drain.

Foundation Design

Retaining wall footings may be sized per the "Deepened Foundations" and "Spread Footings" sections of this report.

Freeboard

Retaining walls surcharged by a sloping condition should be provided with a minimum of 18 inches of freeboard for slough protection. An open "V" drain should be placed behind the wall so that all upslope flows are directed around the structure.

Temporary Excavations

Temporary excavations will be necessary to construct some of the proposed buildings. Excavations for the main Academic Building will be up to 20 feet. The existing fill can be cut vertically for a height of five feet. Slopes in excess of five feet should be trimmed to a 1:1 gradient. For excavations along the south and west sides of the main Academic Building trimming is not feasible.

The J. Byer Group, Inc.

These excavations may be supported by shoring designed for an equivalent fluid pressure of 43 pounds per cubic foot per the enclosed Calculation Sheet #9. For bedrock slopes, vertical excavations up to eight feet may be planned with natural soil above trimmed back to a 1:1 gradient.

FLOOR SLABS

Portions of the Library/Tech Center Building, Academic Building West, and addition to the Academic Building South will be constructed in areas of existing uncertified fill, floor slabs should be designed to bridge between the pile foundations. For portions of the building where the finished grade will be below the existing fill, the floor slab can be supported on the firm alluvium or bedrock. The upper portion of the alluvium is porous and may require removal and recompaction for slab support. The main academic building will be constructed on certified compacted fill. The floor slabs may be supported on grade, reinforced with #4 bars on 16 inch centers, each way and protected by a plastic vapor barrier.

<u>PAVING</u>

Paving sections utilizing flexible A/C paving should be designed per the following table. As an alternative to flexible paving, rigid concrete may be utilized. The concrete should be a minimum of four inches thick and be reinforced with #4 steel bars placed on 16 inch centers each way. The upper 24 inches of soils below the base coarse or subgrade should be removed, moistened as required to obtain optimum moisture content, and recompacted to 90 percent of the maximum dry density, as determined by ASTM D 1557-02. Trench backfill below paving, should be compacted to 90 percent of the maximum dry density. Irrigation water should be prevented from migrating under paving. The following table shows the recommended pavement sections:

Service	Pavement Thickness (Inches)	Base Course (Inches)
Passenger Cars and Light Trucks (T.I. = 4)*	. 3	4
Medium to Heavy Trucks (T.I. = 5)*	4	6

*T.I. - Traffic Index

Base course should be compacted to a minimum of 95 percent of maximum density

DRAINAGE

Control of site drainage is important for the performance of the proposed project. Pad and roof drainage should be collected and transferred to the street or existing storm drain system in nonerosive drainage devices. Drainage should not be allowed to pond on the pad or against any foundation or retaining wall. Drainage should not be allowed to flow uncontrolled over any descending slope. Planters located within retaining wall backfill should be sealed to prevent moisture intrusion into the backfill. Planters located next to raised floor type construction also should be sealed to the depth of the footings or grade beams. Drainage control devices require periodic cleaning, testing and maintenance to remain effective.

WATERPROOFING

Interior and exterior retaining walls are subject to moisture intrusion, seepage, and leakage and should be waterproofed. Waterproofing paints, compounds, or sheeting can be effective if properly installed. Equally important is the use of a subdrain that daylights to the atmosphere. The subdrain should be covered with ³/₄ inch crushed gravel to help the collection of water. Yard areas above the

The J. Byer Group, Inc.

wall should be sealed or properly drained to prevent moisture contact with the wall or saturation of wall backfill.

Construction of raised floor buildings where the grade under the floor has been lowered for joist clearance can also lead to moisture problems. Surface moisture can seep through the footing and pond in the underfloor area. Positive drainage away from the footings, waterproofing the footings, compaction of trench backfill and subdrains can help to reduce moisture intrusion.

PLAN REVIEW

Formal plans ready for submittal to the Building Department should be reviewed by The J. Byer Group. Any change in scope of the project may require additional work.

SITE OBSERVATIONS DURING CONSTRUCTION

The Building Department requires that the geotechnical company provide site observations during construction. The observations include foundation excavations, keyways for fill, benching, pool excavations, temporary slopes and permanent cut slopes. All fill that is placed should be tested for compaction and approved by the soils engineer prior to use for support of engineered structures. LADBS requires that all retaining wall subdrains be observed by a representative of the geotechnical company and the City Inspector.

Please advise The J. Byer Group, Inc. at least 24 hours prior to any required site visit. The agency approved plans and permits should be at the job site and available to our representative. The project consultant will perform the observation and post a notice at the job site of his visit and findings. This notice should be given to the agency inspector.

CONSTRUCTION SITE MAINTENANCE

It is the responsibility of the contractor to maintain a safe construction site. When excavations exist on a site, the area should be fenced and warning signs posted. All pile excavations must be properly covered and secured. Soil generated by foundation and subgrade excavations should be either removed from the site or properly placed as a certified compacted fill. Soil must not be spilled over any descending slope. Workers should not be allowed to enter any unshored trench excavations over five feet deep.

GENERAL CONDITIONS

This report and the exploration are subject to the following <u>NOTICE</u>. Please read the <u>NOTICE</u> carefully, it limits our liability.

<u>NOTICE</u>

In the event of any changes in the design or location of any structure, as outlined in this report, the conclusions and recommendations contained herein may not be considered valid unless the changes are reviewed by us and the conclusions and recommendations are modified or reaffirmed after such review.

The subsurface conditions, excavation characteristics, and geologic structure described herein and shown on the enclosed cross sections have been projected from excavations on the site as indicated and should in no way be construed to reflect any variations that may occur between these excavations or that may result from changes in subsurface conditions.

Fluctuations in the level of groundwater may occur due to variations in rainfall, temperature, irrigation, and other factors not evident at the time of the measurements reported herein. Fluctuations also may occur across the site. High groundwater levels can be extremely hazardous. Saturation of earth materials can cause subsidence or slippage of the site.

If conditions encountered during construction appear to differ from those disclosed herein, notify us immediately so we may consider the need for modifications. Compliance with the design concepts, specifications, and recommendations requires geotechnical review during the course of construction.

THE EXPLORATION WAS PERFORMED ONLY ON A PORTION OF THE SITE, AND CANNOT BE CONSIDERED AS INDICATIVE OF THE PORTIONS OF THE SITE NOT EXPLORED.

This report is issued and made for the sole use and benefit of the client, is not transferable and is as of the exploration date. Any liability in connection herewith shall not exceed the fee for the exploration. No warranty, expressed or implied, is made or intended in connection with the above exploration or by the furnishing of this report or by any other oral or written statement.

THIS REPORT WAS PREPARED ON THE BASIS OF THE PRELIMINARY DEVELOPMENT PLAN FURNISHED. FINAL PLANS SHOULD BE REVIEWED BY THIS OFFICE AS ADDITIONAL GEOTECHNICAL WORK MAY BE REQUIRED.

The J. Byer Group appreciates the opportunity to provide our service on this project. Any questions concerning the data or interpretation of this report should be directed to the undersigned.

Respectfully submitted, THE J. BYER GROUP, INC.

udea

James E. Tucker R. G. 6628

bhn W. Bver E. G. 883

Robert I. Zweigler E. G. 1210/G. E. 2120

JET:JWB:RIZ:flh:mh S:\FINAL\REPORTS\19376_The_Buckley_School_Geologic_and_Geotechnical_Report.wpd

Enc: Appendix I - Laboratory Testing (2 Pages) Shear Test Diagrams (5 Pages) Consolidation Curves (29 Pages) Vicinity Map Regional Geologic Map Seismic Hazard Zones Map Log of Test Pits dated December 3, 2003 (4 Pages) Log of Borings 1-19 (37 Pages) Figure 3.3 - Seismic Hazard Zone Map - Peak Ground Acceleration Figure 3.4 - Seismic Hazard Zone Map - Predominant Earthquake EQFAULT Summary (2 Pages) Section I Calculation Sheets #1 - 6 (6 Pages) Section I-I Slope Stability Map Calculation Sheets #7, 8, and 9 (3 Pages)

Enc. (Continued) Appendix II - Previous Work (94 Pages) Sections A, B, C, D, E and F (4 Sheets)

In Pocket: Geologic Map

xc: (4) Addressee

.

- (1) Englekirk & Sabol
- (2) Project Development Group, Attention: James J. Shelton, Jr.
- (5) Bruce A. Miller
- (3) Jeffrey M. Kalban & Associates
- (1) PCR Services Corporation, Attention: Stephanie Eyestone-Jones

APPENDIX I

LABORATORY TESTING

Undisturbed and bulk samples of the fill, soil, alluvium, and bedrock were obtained from the test pits and borings and transported to the laboratory for testing and analysis. The samples were obtained by driving a ring lined barrel sampler conforming to ASTM D 3550-01 with successive drops of the sample hammer. Experience has shown that sampling causes some disturbance of the sample, however the test results remain within a reasonable range. The samples were retained in brass rings of 2.50 inches outside diameter and 1.00 inches in height. The central portions of the samples were stored in close fitting, waterproof containers for transportation to the laboratory.

Moisture-Density

The dry density of the samples was determined using the procedures outlined in ASTM D 2937-00. The moisture content of the samples was determined using the procedures outlined in ASTM D 2216-98. The results are shown on the Log of Test Pits and Log of Borings.

Maximum Density

The maximum dry density and optimum moisture content of the future compacted fill was determined by remolding bulk samples using the procedures outlined in ASTM D 1557-00, a five-layer standard.

Boring/ Test Pit	Depth (Feet)	Soil Type	Maximum Density (pcf)	Optimum Moisture	Expansion Index
TP2	2 - 4	Medium Brown Clayey Sand with Slate Chips	129.0	10.5	18 - Very Low
TP3	5 - 6	Gray Brown Clayey Sand with Shale Chips	108.0	19.5	42 - Low
B1	4 - 5	Dark Brown Clayey Sand	113.0	17.5	29 - Low


APPENDIX I (Continued)


Shear-Tests


Shear tests were performed on samples of existing fill, soil, alluvium, and bedrock using the procedures outlined in ASTM D 3080-98 and a strain controlled, direct shear machine manufactured by Soil Test, Inc. The rate of deformation was 0.025 inches per minute. The samples were tested in an artificially saturated condition. Following the shear test, the moisture content of the samples was determined to verify saturation. The results are plotted on the "Shear Test Diagrams."


Consolidation


Consolidation tests were performed on insitu samples of the fill and alluvium using the procedures outlined in ASTM D 2435-96. Results are graphed on the "Consolidation Curves."







































CONSOLIDATION DIAGRAM #9


JB: 19376-B CONSULTANT: JWB


CLIENT: Buckley School

Earth Material:	Alluvium		
Sample Location:	B6 - 25'	Specific Gravity:	2.65
Dry Weight (pcf):	92.4	Initial Void Ratio:	0.79
Initial Moisture:	26.8%	Water Added At (psf):	1206.0
Initial Saturation:	90.0%	Consolidation Coef. (Cc):	0.1021













CONSOLIDATION DIAGRAM #13


JB: <u>19376-B</u> CONSULTANT <u>JWB</u>


CLIENT: Buckley School


Earth Material:	FILL		
Sample Location:	B11 - 15'	Specific Gravity:	2.65
Dry Weight (pcf):	113.3	Initial Void Ratio:	0.46
Initial Moisture:	12.2%	Water Added At (psf):	1203.0
Initial Saturation:	70.4%	Consolidation Coef. (Cc):	0.1158







































CONSOLIDATION DIAGRAM #25


JB: <u>19376-B</u> CONSULTANT <u>JWB</u>


CLIENT: Buckley School


Earth Material:	Fill		
Sample Location:	B14 - 20'	Specific Gravity:	2.65
Dry Weight (pcf):	93.7	Initial Void Ratio:	0.77
Initial Moisture:	16.3%	Water Added At (psf):	1203.0
Initial Saturation:	56.4%	Consolidation Coef. (Cc):	0.0938
















11X17





	LOG OF TEST PITS									
				IDINIC						
			an a second de la companya de la com	JP, INC.	JB: <u>19376-B</u> CLIENT: <u>BUCKLEY SCHOOL</u>					
	GEOLOGIST: <u>JC/JWB</u> DATE LOGGED: <u>9/27/03</u>									
1461 E.	1461 E. CHEVY CHASE DRIVE SUITE 200, GLENDALE, CA 91206 818-549-9959 Tel 818-543-3747 Fax REPORT DATE: 12/3/03									
TEST	TEST PIT #1 Elevation: 788 Feet Surface Conditions: Planted Slope									
SAMPLE										
DEPTH (feet)	CONTENT (%)	DENSITY (pcf)	INTERVAL (feet)	MATERIAL						
2 5	18.0 17.5	113.6 113.4	0 - 8	FILL:	Clayey Sand, reddish brown, very moist, medium dense, slate chips, roots					
10	20.5	104.6	8 - 11		Silty Sand, brownish gray, very moist, medium dense to dense, with shale chips					
					wet at 8 feet					
			End at *1	1 Feet; No Wat	er; No Caving; Fill to Total Depth.					
TEST F	47 #2		Elevation: 7	792 Feet	Surface Conditions: Grass					
2	17.3	112.3	0 - 4	FILL:	Clayey Sand, reddish brown, very moist to saturated, medium dense to dense, black slate chips, roots, debris					
5	19.3	103.1	4 - 6		Clayey Sand, brownish gray, wet, soft, shale debris, brick fragments					
10	15.9	109.8	6 - 10		Silty Sand, brownish bray, very moist, slightly to medium dense					
					brick debris at 9 feet					
			ayaa aadaa dagaa ahaa ahaa ahaa dagaa ahaa ah	galaningan di Karangaran karangan karangan karangan karangan karangan karangan karangan karangan karangan karan						
	a the activity of		End at 10) Feet; No Wate	r; No Caving; Fill to Total Depth.					
TEST P	<i>IT #3</i>		Elevation: 7	90 Feet	Surface Conditions: Planter					
2	14.1	105.0	0 - 4		Clayey Sand, gray brown, very moist, dense, slate chips, roots, debris					
5 10	22.1 16.7	99.5 83.7	4 - 12		Clayey Sand, brownish-gray, very moist, dense, shale chips, brick debris, roots					
			12 - 13		large brick blocks					
15	22.7	89.4	13 - 16	9,000,00,00,000,000,000,000,000,000,000	glass fragments					
	End at 16 Feet; No Water; No Caving; Fill to Total Depth.									

NOTE: The stratification depths shown on the Log of Test Pits are approximate and are based upon visual classification of samples and cuttings. The actual depths may vary. Variations between test pits may also occur.

	LOG OF TEST PITS							
	HE I. P	YER	GROL	IP, INC.	JB: <u>19376-B</u> CLIENT: <u>BUCKLEY SCHOOL</u>			
	· · · · · · · · · · · · · · · · · · ·	in the second	the second se	ING FIRM	GEOLOGIST: JC/JWB DATE LOGGED: 9/27/03			
1461 E.	CHEVY CH/ 818•549•		SUITE 200, GLI 818•543•	ENDALE, CA 9120 3747 Fax	06 REPORT DATE: 12/3/03			
TEST	P/T #4		Elevation: 7	80 Feet	Surface Conditions: Soil Slope			
SAMPLE DEPTH (feet)	MOISTURE CONTENT (%)	DRY DENSITY (pcf)	DEPTH INTERVAL (feet)	EARTH MATERIAL	LITHOLOGIC DESCRIPTION			
2	10.6	107.7	0 - 2 ½	FILL :	Silty Sand, brownish gray, moist, medium dense to dense, roots, shale fragments, porous			
5	28.3	80.2	2 ½ - 8		Silty Sand, reddish-brown, very moist, medium dense to dense, shale fragments, slate chips			
			8 - 9		concrete, pipe, and glass bottle			
10	22.1	83.1	9 - 11		Silty Sand, brown, very moist, slightly dense, gravel, rock chips			
			<u> </u>		ar No Coving: Fill to Total Denth			
TEST	o <i>it:</i> #6		Elevation: 7		er; No Caving; Fill to Total Depth. Surface Conditions: Natural Slope			
2	17.2	60.9 63.9	0 - 6	SOIL:	Silty Sand, brownish gray, slightly moist, medium dense, roots, shale fragments, porous			
10	28.1	68.3	6 - 11	BEDROCK:	Diatomaceous Shale, light brown, soft, well bedded			
					Bedding: N55W; 27N			
	<u></u>				Marchan Marchan Marchan			
					o Water; No Caving; No Fill. Surface Conditions: Natural Slope			
TEST	PIT #6		Elevation. 7 0 - 4½	SOIL:	Silty Sand, brownish gray, slightly moist, medium dense, roots, porous, shale fragments			
			4 ½ - 6 ½	BEDROCK:	Diatomaceous Shale, light brown, slightly hard, well bedded			
					Bedding: N88W; 31N			
				and a second				
****	End at 6½ Feet; No Water; No Caving; No Fill.							

NOTE: The stratification depths shown on the Log of Test Pits are approximate and are based upon visual classification of samples and cuttings. The actual depths may vary. Variations between test pits may also occur.

LOG OF TEST PITS							
" -	1 <u>E J. E</u>	SYER	GROU	<u>JP, INC.</u>	JB: <u>19376-B</u> CLIENT: <u>BUCKLEY SCHOOL</u>		
	A GEOTECHNICAL CONSULTING FIRM GEOLOGIST: JC/JWB DATE LOGGED: 9/27/03						
1461 E.		ASE DRIVE 9959 Tel		ENDALE, CA 9120 •3747 Fax			
	REPORT DATE: 12/3/03						
TEST	TEST PIT #7 Elevation: 820 Feet Surface Conditions: Natural Slope						
SAMPLE DEPTH (feet)	DEPTH CONTENT DENSITY INTERVAL MATERIAL						
			0 - 3	SOIL:	Silty Sand, brownish gray, slightly moist, medium dense, porous, shale fragments		
			3 - 5 ½	BEDROCK:	Diatomaceous Shale, brown, soft, well bedded		
			-		Bedding: N6OW; 34N		
			landa de la contra d				
			End	at 5½ Feet; N	o Water; No Caving; No Fill.		
TEST I	PIT #8		Elevation: 7	/85 Feet	Surface Conditions: Natural Slope		
2	13.2	77.9	0 - 4	SOIL:	Silty Sand, brownish gray, damp, medium dense, shale fragments, roots, porous		
			4 - 6½	BEDROCK:	Diatomaceous Shale, light brown, soft, well bedded		
					Bedding: N60W; 27N		
			End	at 6½ Feet; No	o Water; No Caving; No Fill.		
TEST P	NT #9		Elevation: 7	and the second	Surface Conditions: Natural Slope, Minor Vegetation		
		2	0 - 8		Silty Sand, brownish gray, slightly moist, slightly to medium dense, shale fragments		
			8 - 10	BEDROCK:	Diatomaceous Shale, light brown, white, soft, well bedded		
					Bedding: N89W; 32N		
			1477)	94-36emeren angeren angeren ander anderen anderen angeren anderen anderen anderen anderen anderen anderen ander			
	End at 10 Feet; No Water; No Caving; No Fill.						

NOTE: The stratification depths shown on the Log of Test Pits are approximate and are based upon visual classification of samples and cuttings. The actual depths may vary. Variations between test pits may also occur.

		<u> </u>		a a an ann an Anna Anna an Anna Anna An	LOG OF TEST PITS					
A	GEOTEC	HNICAL ASE DRIVE	SUITE 200, GL	IP, INC. TING FIRM ENDALE, CA 912 3747 Fax	JB: <u>19376-B</u> CLIENT: <u>BUCKLEY SCHOOL</u> GEOLOGIST: <u>JC/JWB</u> DATE LOGGED: <u>9/27/03</u>					
TEST	PIT #10		Elevation:	802 Feet	Surface Conditions: Natural Slope					
SAMPLE DEPTH (feet)	MOISTURE CONTENT {%}	DRY DENSITY (pcf)	DEPTH INTERVAL (feet)	EARTH MATERIAL	LITHOLOGIC DESCRIPTION					
			0 - 6 ½	SOIL:	Silty Sand, brownish gray, very moist, medium dense, porous, roots, shale fragments					
			6½ = 8	BEDROCK:	Diatomaceous Shale, light brown, soft, well bedded					
					Bedding: N75W; 32N					
	End at 8 Feet; No Water; No Caving; No Fill.									

JB No: 19376-B

Log of Boring: 1

Client: THE BUCKLEY SCHOOL

Logged By: JWB

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

Site Location: 3900 Stansbury Avenue, Sherman Oaks

		SUBSURFACE PROFILE			SA					
Elevation	Depth	Description	Symbol	uscs	Type	Blow Count	Moisture Content (%)	Dry Density	Saturation %	Remarks
777.0	1	<i>FILL:</i> Silty Clay, brown, moist, firm	×							
776.0	2		\otimes							
775.0-	31		\otimes							
774.0	4	Clayey Sand, mottled brown, moist, medium dense, some gravel	-							
773.0	5		\otimes		R	17	22.9	89.9		
772.0	6		\otimes							
771.0	7		\otimes							
770.0	8		\otimes							
769.0	9 +	Layers of Gravelly Clay, Silty Sand, Silty Clay, mottled brown, gray, reddish brown, moist, firm to medium dense	-88							
768.0		gray, reddish brown, moist, nin to mediani dense			R	14	43.7	73.6		
767.0	11		\otimes							
766.0	12		\otimes							
765.0	13									
764.0	14	Gravelly Sand, dark gray, moist, dense, clay binder	-83							
763.0	15-				R	35	11.8	122.1		
762.0	16					-				
761.0	17		\otimes							
760.0	18		\otimes							
759.0	19-		\bigotimes							
758.0	20	Clayey Sand, dark gray, moist, dense			_					
757.0	21-				R	23	31.0	85.6		
756.0	22		\bigotimes							
755.0	23		\bigotimes							
754.0	24		\bigotimes							
753.0	25	7	<u> X</u>							
		halt Parking - 3 Inches AC/3 Inches Base		: 8 Inc						
		: Hollow-Stem Auger Drill Rig eptember 27, 2003		ation: et: 1 o		Feet				

Log of Boring: 1

Client: THE BUCKLEY SCHOOL

Logged By: JWB

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

		SUBSURFACE PROFILE				SAI	MPLE						
Elevation	Depth	Description	Symbol	nscs	Type	Blow Count	Moisture Content (%)	Dry Density	Saturation %	Remarks			
752.0	26	ALLUVIUM: Silty Clay, brown, moist, firm, very porous, small rock chips	×										
751.0	27		*										
750.0	28		× × ×										
749.0	29												
748.0	30	Sandy Silt, gray brown, damp, soft, porous, some decomposed wood, small rockchips			R	12	23.0	74.7					
747.0	31		* * *										
746.0	32		к х х										
745.0	33		х х х										
744.0	34		* *										
743.0	35	Sandy layers			R	16	10.6	97.7					
742.0	36												
741.0													
740.0		Silty Sand, light brown, damp, slightly dense, porous, small gravel	* *										
739.0			K K X										
738.0	40		× . × .		R	17	19.9	87.2					
737.0	41		* * *							÷			
736.0	42		* * * *										
735.0	43		× × × ×										
733.0	44		x x										
732.0	40	Clayey Sand, light brown, moist, slightly dense, porous, small rock chips			R	16	33.6	84.9					
731.0	40 -												
730.0	48												
729.0	49												
728.0	50												
	Surface: Asphalt Parking - 3 Inches AC/3 Inches Base						Size: 8 Inch						
		: Hollow-Stem Auger Drill Rig	Elevation: 778 Feet										
Drill E	Date: Se	eptember 27, 2003	Shee	et: 2 of	f 3	·							

Log of Boring: 1

Client: THE BUCKLEY SCHOOL

Logged By: JWB

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

		SUBSURFACE PROFILE			_	SAI	MPLE			
Elevation	Depth	Description	Symbol	uscs	Type	Blow Count	Moisture Content (%)	Dry Density	Saturation %	Remarks
727.0	51	very moist, more gravel to 1 inch diameter, less porous								
726.0	52									
725.0	53						1			
724.0	54									
723.0	55	wet - seep at 55 feet			R	39				No Recovery
722.0	56	Sandy Gravel, brown, saturated, dense, rocks to 3 inches								
721.0	57									
720.0	58-		 							
719.0	59 	BEDROCK: Diatomaceous Siltstone and Sandstone, gray, moist, soft, well								
718.0	601	bedded, friable			R	22	39.2	01.2		
717.0	61	End at 61 Feet; Seep at 55 Feet; Fill to 25 Feet.			ĸ	22	39.2	81.2		
716.0	62									
715.0	63									
714.0	64					1				
713.0	65									
712.0	66									
711.0	67									
710.0	68									
709.0	69									
708.0	70					-				
707.0	71									
706.0	72									
705.0	73								Y - 4	
704.0	74		****							
703.0	75-									
Surfa	ce: As	phalt Parking - 3 Inches AC/3 Inches Base	Size	8 Incl	h					
Drill N	/lethoo	: Hollow-Stem Auger Drill Rig	Eleva	ation:	778	Feet				
Drill E	Date: S	eptember 27, 2003	Shee	et: 3 of	3					

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

Client: THE BUCKLEY SCHOOL

Logged By: JWB

		SUBSURFACE PROFILE				SA	MPLE			······································
Elevation	Depth	Description	Symbol	uscs	Type	Blow Count	Moisture Content (%)	Dry Density	% Saturation	Remarks
776	0-	Ground Surface								
775	1111	FILL: Clayey Sand, brown, moist, medium dense, layers of Sand								
774-	2-1									
773-	3111									
772-	4									
771-	5									
770	6	Gravelly Clay with Slate chips, blue gray, moist, very firm								
769-	7									
768	8 1 1									
767	9111									
766										
765 764 –	11				Stationard and Annual Stationard Stationard					
763	13									
762	14								-	
761	15	rocky layer Gravelly Clay, dark gray, moist, firm, no								
760	16	slate								
759	17									
758 -	18	ALLUVIUM:								
757	19-1	Clayey Sand, brown, moist, slightly dense, porous, rock chips								
756	20-			-						
	Surface: Asphalt Parking - 3 Inches AC/3 Inches Base						Size: 8		. <u>.</u> .	
		: Hollow-Stem Auger Drill Rig					Elevatio		i Feet	
Drill D	ate: S	eptember 27, 2003					Sheet:	- 013		

Log of Boring: 2

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

Client: THE BUCKLEY SCHOOL

Logged By: JWB

Line Description Topological Line Line Line Line Line Remarks 10 10 23.1 82.7 10 23.1 82.7 10<
755 21 754 22 753 23 752 24
753 23 752 24 752 24 752 752 752 752 752 752 752 752 752 752
751 _ 25 _ Gravelly Sand, light brown, damp, medium _ 30 m R 15 11.3 96.4
751 25 Gravelly Sand, light brown, damp, medium 8 15 11.3 96.4 750 26 9 9 9 15 11.3 96.4 749 27 9 8 9 15 11.3 96.4
748 28 Clayey Sand, gray brown, moist, medium dense, porous
747 29 Iayers of Silty Sand, light brown, damp, dense 746 30 746 30 R 14 17.3 86.8
745 31 31 32 32 33 33 33 33 33 33 33 33 33 33 33
743 33
742 34 741 35 Clayey Sand, light brown, moist, medium dense, porous, few rock chips
740 36 37 - 37
737 39 736 40
Surface: Asphalt Parking - 3 Inches AC/3 Inches Base Size: 8 Inch
Drill Method: Hollow-Stem Auger Drill RigElevation: 776 FeetDrill Date: September 27, 2003Sheet: 2 of 3

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

Client: THE BUCKLEY SCHOOL

Logged By: JWB

Site	Location:	3900	Stansbury	Avenue,	Sherman	Oaks
------	-----------	------	-----------	---------	---------	------

1		SUBSURFACE PROFILE				SA	MPLE			
Elevation	Depth	Description	Symbol	uscs	Type	Blow Count	Moisture Content (%)	Dry Density	% Saturation	Remarks
735-	- - 41 -	BEDROCK: Diatomaceous Siltstone with Sandstone, light brown, moist, soft, bedded	* * * * * * * * * * * * *		R	17	33.1	86.9		
734	42-1		×××××× ×××××××× ××××××××××××××××××××××							
733	43		* * * * * * * * * * * * * * * * * *							
732-	44	moderately hard	*****							
731 -	45		****		R	31	38.0	85.8		
730-	46	End at 46 Feet; No Water; Fill to 18 Feet.	*****							
729-	47	End of Borehole								
728-	48									
727-	49-1									
726	50									
725-	51								-	
724	52-									
723	53									
722	54									
721	55									
720	56									
719	57									
718	58									
717	59									
716	- 60 -									
		ohalt Parking - 3 Inches AC/3 Inches Base			,l	i	Size: 8	Inch		
Drill M	ethod	: Hollow-Stem Auger Drill Rig				E	Elevatio	on: 776	Feet	
Drill Di	ate: Se	eptember 27, 2003				5	Sheet: 3	3 of 3		

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

Client: THE BUCKLEY SCHOOL

Logged By: JWB

Site Location: 3900) Stansbury	Avenue,	Sherman Oaks	
---------------------	-------------	---------	--------------	--

		SUBSURFACE PROFILE				SA	MPLE		·	
Elevation	Depth	Description	Symbol	NSCS	Type	Blow Count	Moisture Content (%)	Dry Density	% Saturation	Remarks
781	0-	Ground Surface								
780		FILL: Clayey Sand, dark brown, damp, medium dense, slate gravel								
779-	2-1									
778	3 1									
777	4 1									
776	5									
775	6									
774	7									
773 -	8									
772-	9									
771	10									
770	11-									
769	12	ALLUVIUM: Sandy Silt, dark gray brown, moist, firm,	×××							
768-	13-	rock chips	× ×							
767	14		х х х х х х							
766	15	light brown, damp, porous	× × × ×		R	10	31.3	63.3		
765	16		х х х х							
764		Clayey Sand, light brown, very moist, medium dense	×							
763 -	18-1									
762	19									
761	20-									
		phalt Parking - 3 Inches AC					Size: 8		_	
		t: Hollow-Stem Auger Drill Rig september 27, 2003					Elevati Sheet:	on: 781 1 of 2	Feet	
						·····		. 0, 2		

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

Client: THE BUCKLEY SCHOOL

Logged By: JWB

Operation Operation <t< th=""><th></th><th></th><th>SUBSURFACE PROFILE</th><th></th><th></th><th></th><th>SA</th><th>MPLE</th><th></th><th></th><th></th></t<>			SUBSURFACE PROFILE				SA	MPLE			
759 22 756 23 757 24 756 25 BEDROCK: Diatomacous Silistone with Sandatone, brown mot lynt gray, most, medum hard, well bedded, tight, no open fradures 756 26 757 24 756 25 BEDROCK: 1 757 26 Diatomacous Silistone with Sandatone, brown mot lynt gray, most, medum hard, well bedded, tight, no open fradures 752 29 753 28 754 27 755 28 756 31 766 33 766 33 767 34 768 33 744 37 744 33 744 34 745 35 744 37 744 37 744 37 744 37 744 37 744 37 744 38 744 39 End at 40 F	Elevation	Depth	Description	Symbol	uscs	Type	Blow Count	Moisture Content (%)	Dry Density	% Saturation	Remarks
741 40 End at 40 Feet; No Water; Fill to 12 Feet. Surface: Asphalt Parking - 3 Inches AC Size: 8 Inch Drill Method: Hollow-Stem Auger Drill Rig Elevation: 781 Feet	759 758 757 756 755 754 755 754 752 751 750 749 748 747 746 745 744 743	22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38	Diatomaceous Siltstone with Sandstone, brown and light gray, moist, medium hard,				50 7"	44.3			
Drill Method: Hollow-Stem Auger Drill Rig Elevation: 781 Feet			End at 40 Feet; No Water; Fill to 12 Feet.	× × × × × × × × × × × × × * ×		к	7"	58.1	bb.4		
Drill Method: Hollow-Stem Auger Drill Rig Elevation: 781 Feet	Surfa	ce: As	sphalt Parking - 3 Inches AC	4		i		Size: 8	Inch		
										1 Feet	
Drill Date: September 27, 2003 Sheet: 2 of 2											

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

Client: THE BUCKLEY SCHOOL

Logged By: JWB

Site Location:	3900 Stansbury	Avenue,	Sherman Oaks
----------------	----------------	---------	--------------

		SUBSURFACE PROFILE				SA	MPLE	•		
Elevation	Depth	Description	Symbol	uscs	Type	Blow Count	Moisture Content (%)	Dry Density	% Saturation	Remarks
780	0+	Ground Surface		-						
779	1111	FILL: Clayey Sand, brown, moist, medium dense								
778	2									
777	3									
776	4									
775	5-1-1									
774	6	Clayey Sand, dark gray brown, very moist, medium dense, some debris								
773	7-11									
772	81111									
771	9	Clayey Silt, dark brown, moist, firm								
770	10				R	15	23.0	98.9		
769										
768	12-									
767-	13-1									
766		ALLUVIUM: Clayey Sand, dark brown, moist, medium dense, porous	 							
765	15 - - - 16 -				R	10	24.7	84.3		
763	10									
762	18-									
761	10									
760-	20-									
		phalt Drive - 3 Inches AC/5 Inches Gravel	<u> </u>				Size: 8	Inch	1	
		d: Hollow-Stem Auger Drill Rig					Elevati) Feet	
		2. Hollow-Stern Auger Dhir Rig September 27, 2003					Sheet:			

Client: THE BUCKLEY SCHOOL

Logged By: JWB

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

		SUBSURFACE PROFILE				SA	MPLE			
Elevation	Depth	Description	Symbol	uscs	Type	Blow Count	Moisture Content (%)	Dry Density	% Saturation	Remarks
759	21-	Gravelly Clay, dark gray brown, moist, very firm, rock fragments to 2 inches			R	23	28.3	97.8		
758-	22-	Clayey Sand, brown, moist, medium dense, porous, rock chips and some gravel								
757	23-									
755	25									
754	26									
753	27									
752	28-									
751	29									
750- - - 749-	30-				R	30	25.8	95.0		
749	31 	Gravelly Clay layer, large rock fragments	· · · · · · · · · · · · · · · · · · ·						1	
747	33-									
746	34-1									
745	35	Sandy Gravel, light brown, moist, dense, hard drilling, shale fragments over 3 inches, coarse sand matrix			R	46	24.4	94.5		
743	37		40°8°8							
742	38 -		0.00							
741	39		3 0 0 0 0 0 0 0 0 0							
740	40-		3							
Surfa	ce: As	phalt Drive - 3 Inches AC/5 Inches Gravel				1	Size: 8	Inch		
		1: Hollow-Stem Auger Drill Rig					Elevatio) Feet	
Drill [Date: S	September 27, 2003					Sheet:	2 of 3		

Client: THE BUCKLEY SCHOOL

Logged By: JWB

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

	SUBSURFACE PROFILE						MPLE					
Elevation	Depth	Description	Symbol	uscs	Type	Blow Count	Moisture Content (%)	Dry Density	% Saturation	Remarks		
739	41-	Clayey Gravel, light brown, moist, dense, shale fragments			R	25	25.5	96.4				
738-	42		·									
737-	43		·									
736-	44 		* * *_									
735	45		* 		R	38	17.8	96.7				
734	46		÷_• 									
733-	47 -											
732	48	BEDROCK:										
731-	49	Diatomaceous Siltstone and Sandstone, gray, moist, moderately hard, well bedded, tight										
730-	50		·		R	50 9"	45.3	73.3				
729-	51-	End at 51 Feet; No Water; Fill to 14 Feet.	• • • •									
728	52	End of Borehole										
727 -	53 -											
726-	54											
725	55								AU 40 40			
724	56											
723	57											
722	58											
721	59											
720-	60											
Surfac	ce: As	phalt Drive - 3 Inches AC/5 Inches Gravel					Size: 8 Inch					
		: Hollow-Stem Auger Drill Rig					Elevation: 780 Feet					
Drill D	ate: S	eptember 27, 2003		· ··			Sheet:	3 of 3				

Client: THE BUCKLEY SCHOOL

Logged By: JWB

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

		SUBSURFACE PROFILE				SA	MPLE	L		······································
Elevation	Depth	Description	Symbol	uscs	Type	Blow Count	Moisture Content (%)	Dry Density	% Saturation	Remarks
771	0	Ground Surface	~~~~							
770	1 1 1 1	FILL: Gravelly Sand, gray brown, moist, dense, slate gravel, clay binder			8					
769	2									
768 - 	3		*							
- 767 - -	4									
766	5111									
765	6		*							
764	7									
763-	8111									
762	9111									
761-		Refusal at 10 Feet; Hard Rock?, Fill to Total Depth.	×××						The second second	
760	11 - - - 12 -	End of Borehole								
758	13									
757	14-									
756	15									
755	16									
754	17									
753										
752	19									
751	20-									
		halt Parking	I .		k	 S	Size: 8 I	nch	i_	
Drill M	lethod	: Hollow-Stem Auger Drill Rig				E	Elevatio	n: 771	Feet	
Drill D	ate: Se	eptember 27, 2003					Sheet: 1	of 1		

Client: THE BUCKLEY SCHOOL

Logged By: JWB

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

	_004	tion: 3900 Stansbury Avenue, Sherman Oaks SUBSURFACE PROFILE		SAMPLE						
Elevation	Depth	Description	Symbol	uscs	Type	Blow Count	Moisture Content (%)	Dry Density	% Saturation	Remarks
779	0-	Ground Surface	000							
778	1-	FILL: Clayey Sand, brown, moist, medium dense								
777	2-									
776	3-									
774	4 - 	dark brown layer			R	22	10.1	115.8		
773	61	Gravelly Sand, brown, moist, dense, some clay			Α	~~~	12.1	0.011		
772	7									
771	8 -									
770	9111	Clayey Silt, dark gray brown, very moist, firm								
769 - - - - 768 -	10- 				R	19	31.1	91.6		
767	12									
766	13									
765 -	14 14 1									
764	15	sample disturbed			R	17	24.0	77.6		
763					v viter					
762	17-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-									
760	19	ALLUVIUM:								
759-	20-	Sandy Silt, dark gray, moist, soft to firm, few rock chips	× × ×							
Surfa	ce: As	phalt Road - 3 Inches AC/6 Inches Base					Size: 8	Inch		
Drill N	Nethod	1: Hollow-Stem Auger Drill Rig						on: 779	Feet	
Drill D	Date: S	September 27, 2003					Sheet:	1 of 3		

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

Client: THE BUCKLEY SCHOOL

Logged By: JWB

Site Location.	: 3900 Stansbur	y Avenue,	Sherman	Oaks
----------------	-----------------	-----------	---------	------

		SUBSURFACE PROFILE				SA	MPLE			
Elevation	Depth	Description	Symbol	nscs	Type	Blow Count	Moisture Content (%)	Dry Density	% Saturation	Remarks
758 - 757 - 756 -	22				R	15	26.8	91.6		
755 754 753 752 751	24 25 26 27 27 28	Clayey Sand, dark and light brown, moist, medium dense, numerous rock chips in layers			R	13	26.8	92.4		
750 749 748	29	Silty Sand, brown and light brown, moist, medium dense			R	21	24.4	91.8		
746 745 744 743 742 742	33 34 35 36 37 37 38	Gravel layer, Clayey Sand layers			R	26	24.7	96.7		
	40- ace: As	phalt Road - 3 Inches AC/6 Inches Base f: Hollow-Stem Auger Drill Rig	·				Size: 8 Elevati			
		September 27, 2003					Sheet:			

Client: THE BUCKLEY SCHOOL

Logged By: JWB

The J. By er Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

0 0 Description 0 <th0< th=""> 0 <th0< th=""> <th0< th=""> 0 0<</th0<></th0<></th0<>			SUBSURFACE PROFILE				SA	MPLE	·d			
Gravely Sanc, gray and brown, molet. R 27 21.1 98.5 735 44 736 43 736 43 736 44 737 42 738 44 738 44 738 44 738 44 738 44 738 44 738 44 738 44 738 45 Sampler on rook 45 End al 45 Feet, Refusal - Hand Rook, Fill to 10 Feet End of Borenole 731 48 732 47 10 Feet End of Borenole 729 50 729 50 729 50 724 55 725 54 726 53 727 52 728 54 729 50 729 50 721 58 722 57 723 56 724 55 725 54 726 59 727 58 728 57 72	Elevation	Depth	Description	Symbol	USCS	Type	Blow Count	Moisture Content (%)	Dry Density	% Saturation	Remarks	
738 4-1	-	-	Gravelly Sand, gray and brown, moist,	<u> </u>		_						
737 43 43 17 18 <t< td=""><td>738-</td><td>41-</td><td>medium dense, graver to 3 inches</td><td>+ 0</td><td></td><td>R</td><td>27</td><td>21.1</td><td>98.5</td><td></td><td></td></t<>	738-	41-	medium dense, graver to 3 inches	+ 0		R	27	21.1	98.5			
736 43				<u> </u>								
735 44 45 Sampler on nock R 17	737-	42-		- <u>-</u> « - •								
735 44 45 Sampler on nock R 17	736	43-		· 								
734 45 Sampler on rock R 17 Image: Constraint of the constraint of t												
733 46 End af 46 Feet, Refusal - Hard Rock, Fill to 13 Feet. 733 48 734 48 735 48 734 48 735 48 736 49 737 48 736 49 737 48 736 49 737 48 736 49 728 50 728 51 726 53 726 53 727 52 54 1 724 56 725 54 724 56 725 54 724 56 725 54 724 56 725 57 721 58 722 57 724 56 725 54 726 59 727 52 54 54 725 54	735-	44-										
733 46 End af 46 Feet, Refusal - Hard Rock, Fill to 13 Feet. 733 48 734 48 735 48 734 48 735 48 736 49 737 48 736 49 737 48 736 49 737 48 736 49 728 50 728 51 726 53 726 53 727 52 54 1 724 56 725 54 724 56 725 54 724 56 725 54 724 56 725 57 721 58 722 57 724 56 725 54 726 59 727 52 54 54 725 54				·			17					
733 46 End af 46 Feet, Refusal - Hard Rock, Fill to 13 Feet. 733 48 734 48 735 48 734 48 735 48 736 49 737 48 736 49 737 48 736 49 737 48 736 49 728 50 728 51 726 53 726 53 727 52 54 1 724 56 725 54 724 56 725 54 724 56 725 54 724 56 725 57 721 58 722 57 724 56 725 54 726 59 727 52 54 54 725 54	/34-	45-	Sampler on rock			R	9"				No Recovery	
19 Feet End of Borehole 731 48 733 49 734 49 725 50 726 53 727 52 728 51 729 52 726 53 727 52 728 54 729 54 729 54 724 55 725 54 724 55 725 54 724 55 725 54 721 58 722 57 721 58 722 57 721 58 722 59 719 60 Surface: Asphalt Road - 3 Inches AC/6 Inches Base Size: 8 Inch Drill Method: Hollow-Stem Auger Drill Rig Elevation: 779 Feet	733	46	End at 46 East: Defusal - Hard Rock Fill to	<u> </u>								
731 48 730 49 729 50 728 51 727 52 726 53 725 54 726 53 725 54 724 55 725 54 724 55 725 54 724 55 725 54 726 53 727 52 54 1 724 55 725 54 726 53 727 56 728 56 729 56 720 59 719 60 Surface: Asphalt Road - 3 Inches AC/6 Inches Base Size: 8 Inch Drill Method: Hollow-Stem Auger Drill Rig Size: 8 Inch			19 Feet.									
730 49 729 50 728 51 727 52 53 - 726 53 725 54 723 56 724 55 725 54 726 53 727 56 728 56 729 56 720 56 721 58 722 57 721 58 720 59 721 58 720 59 721 58 722 57 721 58 722 57 723 56 724 56 725 56 720 59 721 58 722 57 733 66 74 56 720 59 721 58 722 59 73	732-	47-	End of Borehole									
730 49 729 50 728 51 727 52 53 - 726 53 725 54 723 56 724 55 725 54 726 53 727 56 728 56 729 56 720 56 721 58 722 57 721 58 720 59 721 58 720 59 721 58 722 57 721 58 722 57 723 56 724 56 725 56 720 59 721 58 722 57 733 66 74 56 720 59 721 58 722 59 73	731	48-								1		
729 50 728 51 727 52 53	=	1										
728 51 727 52 726 53 725 54 724 55 725 54 724 55 725 54 724 55 725 54 724 55 725 54 724 55 725 54 724 55 725 54 724 55 725 54 720 59 721 58 59 59 719 60 Surface: Asphalt Road - 3 Inches AC/6 Inches Base Size: 8 Inch Drill Method: Hollow-Stem Auger Drill Rig Size: 8 Inch	730-	49-										
728 51 727 52 726 53 725 54 724 55 725 54 724 55 725 54 724 55 725 54 724 55 725 54 724 55 725 54 724 55 725 54 724 55 725 54 720 59 721 58 59 59 719 60 Surface: Asphalt Road - 3 Inches AC/6 Inches Base Size: 8 Inch Drill Method: Hollow-Stem Auger Drill Rig Size: 8 Inch	720	50-										
727 52 726 53 725 54 724 55 723 56 724 55 725 54 724 55 725 54 724 55 725 56 726 57 727 56 728 56 729 56 720 59 719 60 Surface: Asphalt Road - 3 Inches AC/6 Inches Base Size: 8 Inch Drill Method: Hollow-Stem Auger Drill Rig Size: 8 Inch	123											
726 53 725 54 724 55 724 55 725 56 724 56 725 56 726 57 727 56 721 58 720 59 719 60 Surface: Asphalt Road - 3 Inches AC/6 Inches Base Size: 8 Inch Drill Method: Hollow-Stem Auger Drill Rig Elevation: 779 Feet	728	51-										
726 53 725 54 724 55 724 55 725 56 724 56 725 56 726 57 727 56 721 58 720 59 719 60 Surface: Asphalt Road - 3 Inches AC/6 Inches Base Size: 8 Inch Drill Method: Hollow-Stem Auger Drill Rig Elevation: 779 Feet												
725 54 724 55 723 56 723 56 724 57 725 57 727 58 720 59 719 60 Surface: Asphalt Road - 3 Inches AC/6 Inches Base Size: 8 Inch Drill Method: Hollow-Stem Auger Drill Rig Elevation; 779 Feet	727	52-1										
725 54 724 55 723 56 723 56 724 57 725 57 727 58 720 59 719 60 Surface: Asphalt Road - 3 Inches AC/6 Inches Base Size: 8 Inch Drill Method: Hollow-Stem Auger Drill Rig Elevation; 779 Feet	- 726-	53-										
724 55 723 56 723 56 722 57 721 58 720 59 720 59 700 59 700 59 700 59 719 60 Surface: Asphalt Road - 3 Inches AC/6 Inches Base Size: 8 Inch Drill Method: Hollow-Stem Auger Drill Rig Elevation: 779 Feet	111	11										
723 56 722 57 721 58 720 59 719 60 Surface: Asphalt Road - 3 Inches AC/6 Inches Base Size: 8 Inch Drill Method: Hollow-Stem Auger Drill Rig Elevation: 779 Feet	725-	54								Ì		
723 56 722 57 721 58 720 59 719 60 Surface: Asphalt Road - 3 Inches AC/6 Inches Base Size: 8 Inch Drill Method: Hollow-Stem Auger Drill Rig Elevation: 779 Feet	724	55										
722 57 721 58 721 58 720 59 60 59 719 60 Surface: Asphalt Road - 3 Inches AC/6 Inches Base Size: 8 Inch Drill Method: Hollow-Stem Auger Drill Rig Elevation: 779 Feet	, <u>,</u> , , , , , , , , , , , , , , , , ,											
721 58 720 59 719 60 Surface: Asphalt Road - 3 Inches AC/6 Inches Base Size: 8 Inch Drill Method: Hollow-Stem Auger Drill Rig Elevation: 779 Feet	723-	56-										
721 58 720 59 719 60 Surface: Asphalt Road - 3 Inches AC/6 Inches Base Size: 8 Inch Drill Method: Hollow-Stem Auger Drill Rig Elevation: 779 Feet												
720 59 719 60 Surface: Asphalt Road - 3 Inches AC/6 Inches Base Size: 8 Inch Drill Method: Hollow-Stem Auger Drill Rig Elevation: 779 Feet	/22-	5/ 										
719 60 Surface: Asphalt Road - 3 Inches AC/6 Inches Base Size: 8 Inch Drill Method: Hollow-Stem Auger Drill Rig Elevation: 779 Feet	721	58										
719 60 Surface: Asphalt Road - 3 Inches AC/6 Inches Base Size: 8 Inch Drill Method: Hollow-Stem Auger Drill Rig Elevation: 779 Feet												
Surface: Asphalt Road - 3 Inches AC/6 Inches Base Size: 8 Inch Drill Method: Hollow-Stem Auger Drill Rig Elevation: 779 Feet	720- -	59- -										
Surface: Asphalt Road - 3 Inches AC/6 Inches Base Size: 8 Inch Drill Method: Hollow-Stem Auger Drill Rig Elevation: 779 Feet	719-	- 60-										
Drill Method: Hollow-Stem Auger Drill Rig Elevation: 779 Feet			phalt Road - 3 Inches AC/6 inches Base					Size: 8	Inch			

Log of Boring: 7

Client: THE BUCKLEY SCHOOL

Logged By: JWB

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

Elevation Depth Symbol USCS Moisture Content (%) Dry Density Dry Density Dry Density	irks
Elevati Depth Dopth Type Blow C Dry De Satt	
FILL: Silty Sand, brown, damp, medium dense, with shale 787.0 1 fragments	-,,,
786.0 2 SolL: Clayey Sand, dark brown, damp, dense, porous, shale	
785.0 3 fragments	
783.0 5 5 7 R 19 17.1 92.0	
778.0 10 ALLUVIUM: 8 50 30.7 71.9 Clayey Sand, brown, damp, medium dense, large shale 10 10 10 10 777.0 11 fragments 10 10 10	
776.0 12 BEDROCK: Diatomaceous Siltstone and Sandstone, tan, damp, well	
775.0 13 bedded, moderately hard	
773.0 15 15 R 50 11" 32.4 72.0	
772.0 16 End at 16 Feet; No Water; Fill to 2 Feet.	
771.0 17	
765.0 23	
763.0 25	
Surface: Asphalt Drive - 3 Inches AC/5 Inches Base Size: 8 Inch	
Drill Method: Hollow-Stem Auger Drill Rig Elevation: 788 Feet	
Drill Date: October 6, 2003 Sheet: 1 of 1	

Log of Boring: 8

Client: THE BUCKLEY SCHOOL

Logged By: JWB

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

7850 7860			SUBSURFACE PROFILE				SA	_	SAMPLE				
25.0 1 Sing Sand, brown, damp, medium dense, brick fragment, slate chips, shale fragments, rubble 786.0 3 786.0 4 786.0 4 786.0 5 80.1 Clayey Sand, brownsh gray, damp, medlum dense, porous 786.0 6 786.0 7 786.0 7 786.0 7 786.0 7 786.0 7 786.0 7 786.0 7 786.0 7 786.0 7 786.0 7 786.0 8 786.0 8 786.0 8 786.0 10 786.0 10 786.0 11 11 ALLUMUK: Clayey Sand, light brown, damp, medlum dense, porous, with she chips 11 ALLUMUK: 780.0 18 110 16 111 16 112 hard drilling 710.0 16 16 18	Elevation	Depth	Description	Symbol	uscs	Type	Blow Count	Moisture Content (%)	Dry Density	% Saturation	Remarks		
783.0 3 782.0 4 781.0 5 500.1 SOL. 780.0 6 777.0 9 777.0 9 777.0 9 777.0 9 777.0 9 777.0 9 777.0 9 777.0 9 777.0 9 777.0 9 777.0 9 777.0 9 777.0 9 777.0 9 777.0 9 777.0 9 777.0 9 777.0 9 777.0 9 777.0 10 10 12 11 12 12 14 777.0 13 13 16.7 14 12 17 15 17 16 17 16 18 17 18 18 <	785.0	1111 111	Silty Sand, brown, damp, medium dense, brick fragment,	×									
782.0 4 781.0 5 6 Cityey Sand, brownish gray, damp, medium dense, porous 778.0 6 777.0 9 777.0 9 777.0 9 777.0 9 777.0 9 777.0 9 777.0 9 777.0 9 777.0 9 777.0 9 777.0 12 nard drilling 8 777.0 13 777.0 14 777.0 12 nard drilling 8 770.0 16 Clayey Sand, light brown, damp, medium dense, porous, with shale chips 770.0 16 770.0 17 780.0 18 780.0 18 780.0 18 780.0 17 780.0 18 780.0 17 780.0 17 780.0 18 780.0 18 18 <td>784.0</td> <td>2</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>	784.0	2											
781.0 5 SOU: Clayey Sand. brownish gray, damp. medium dense, porous R 18 25.1 77.7 778.0 6 Clayey Sand. brownish gray, damp. medium dense, porous R 13 16.7 83.8 777.0 9 7 R 13 16.7 83.8 777.0 9 7 R 13 16.7 83.8 777.0 11 12 hard drilling R 13 16.7 83.8 777.0 13 R 13 16.7 83.8 13 16.7 83.8 772.0 14 ALLWWM. Clayey Sand, light brown, damp, medium dense, porous, with shale chips R 18 10.0 91.8 760.0 17 16 16 18 19 10.0 91.8 766.0 120 brown, damp, dense, porous, shale chips (hard drilling) 11 11 14 14 765.0 21 hard drilling 11 14 14 14 762.0 22 18 16.7 18 14 14 <td< td=""><td>783.0</td><td>311</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></td<>	783.0	311											
6 Clayey Sand, brownish gray, damp, medium dense, porous 1 1 1 1 1 1 7780 8 7 7 7 1<	782.0	4											
7800 6 7750 7 7780 8 7770 9 7760 10 7770 11 7770 12 hard driling 13 11 Clayey Sand, light brown, damp, medium dense, porous, with shale chips 7710 16 7760 17 18 10.0 91.8 7710 16 7710 16 7710 16 7710 16 7710 16 7710 16 7710 16 7710 16 7710 16 7710 16 7710 16 7710 16 7710 17 7710 18 7710 18 7710 18 7710 18 7710 18 7710 18 7710 18 7710 18 7710 18 <t< td=""><td>781.0</td><td>5</td><td></td><td></td><td></td><td>R</td><td>18</td><td>25.1</td><td>77.7</td><td></td><td></td></t<>	781.0	5				R	18	25.1	77.7				
775.0 77 778.0 8 777.0 9 776.0 10 776.0 10 777.0 9 776.0 10 777.0 9 777.0 9 777.0 12 hard drilling 13 777.0 14 771.0 12 hard drilling 14 771.0 15 Clayey Sand, light brown, damp, medium dense, porous, with shale chips 18 760.0 10 766.0 20 brown, damp, dense, porous, shale chips (hard drilling) 14 766.0 21 hard drilling 14 762.0 22 18 10.0 19 14 762.0 22 18 10.0 19 11 100 18 762.0 22 100 18 762.0 22 18 10.0 19 14	780.0	6	Clayey Sand, brownish gray, damp, medium dense, porous										
777.0 9 776.0 10 775.0 11 777.0 12 hard drilling 13 773.0 13 777.0 13 777.0 14 ALLUWUM: Clayey Sand, light brown, damp, medium dense, porous, with shale chips 770.0 16 760.0 17 760.0 17 760.0 17 760.0 18 760.0 18 760.0 18 760.0 18 760.0 18 760.0 18 760.0 18 762.0 21 hard drilling 18 764.0 22 10.0 23 762.0 24 762.0 24 10.0 23 762.0 24 10.0 23 762.0 24 762.0 24 762.0 24 10.0 25 10.0 <td< td=""><td>779.0</td><td>7</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></td<>	779.0	7											
776.0 10 775.0 11 777.0 12 hard drilling 11 773.0 13 772.0 14 ALLUVUM: Clayey Sand, light brown, damp, medium dense, porous, with shale chips 18 10.0 91.8 760.0 16 16 18 10.0 91.8 760.0 16 17 18 10.0 91.8 760.0 16 17 18 10.0 91.8 766.0 20 brown, damp, dense, porous, shale chips (hard drilling) 16 16 766.0 21 hard drilling 16 16 763.0 23 10 14 14 764.0 22 14 16 16 763.0 23 18 10.0 91.8 764.0 22 10 14 14 763.0 23 16 16 16 763.0 23 16 16 16 763.0 23 16 16 16 763.0 <td>778.0</td> <td>8</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>	778.0	8											
775.0 11 774.0 12 hard drilling 11 ALLUVIUM: 11 Clayey Sand, light brown, damp, medium dense, porous, with shale chips 18 770.0 16 766.0 20 brown, damp, dense, porous, shale chips (hard drilling) 11 766.0 20 brown, damp, dense, porous, shale chips (hard drilling) 11 766.0 21 hard drilling 11 762.0 24 hard drilling 11 762.0 24 brown, damp, dense, porous, shale chips (hard drilling) 11 762.0 24 610 25 Surface: Asphalt Pavement - 4 Inches AC/5 Inches Base Size: 8 Inch	777.0	9											
774.0 12 hard drilling 773.0 13 772.0 14 ALLUVIUM: Clayey Sand, light brown, damp, medium dense, porous, with shale chips 770.0 16 768.0 18 767.0 19 66.0 20 brown, damp, dense, porous, shale chips (hard drilling) 766.0 21 hard drilling 764.0 22 13 ALLUVIUM: 765.0 21 hard drilling Hard drilling 764.0 22 10 23 762.0 24 10 23 762.0 24 5urface: Asphalt Pavement - 4 Inches AC/5 Inches Base	776.0					R	13	16.7	83.8				
773.0 13 777.0 14 ALLUVIUM: Clayey Sand, light brown, damp, medium dense, porous, with shale chips 770.0 16 769.0 17 768.0 18 18 10.0 91.8 769.0 17 769.0 18 769.0 18 769.0 18 769.0 18 769.0 18 769.0 18 766.0 20 brown, damp, dense, porous, shale chips (hard drilling) 764.0 22 18 10.0 91.8 18 764.0 22 18 10.0 19 10 762.0 24 762.0 24 762.0 24 762.0 24 762.0 24 762.0 24 762.0 24 762.0 24 763.0 23 764.0 25 765.0 21	775.0	11											
772.0 14 772.0 14 ALLUVIUM: Clayey Sand, light brown, damp, medium dense, porous, with shale chips 1 770.0 16 768.0 17 766.0 20 brown, damp, dense, porous, shale chips (hard drilling) 766.0 21 hard drilling 764.0 22 764.0 22 764.0 22 764.0 22 10.0 24 10.0 24 10.0 24 10.0 23 762.0 24 22 Surface: Asphalt Pavement - 4 Inches AC/5 Inches Base	774.0		hard drilling										
771.0 15 ALLUVIUM: Clayey Sand, light brown, damp, medium dense, porous, with shale chips R 18 10.0 91.8 769.0 17 768.0 18 767.0 19 767.0 19 766.0 20 brown, damp, dense, porous, shale chips (hard drilling) T R 28 23.1 84.4 763.0 22 10.0 22 10.0 10.0 10.0 10.0 764.0 22 10.0 10.0 10.0 10.0 10.0 10.0 763.0 23 10.0 10.0 10.0 10.0 10.0 10.0 763.0 23 10.0 10.0 10.0 10.0 10.0 10.0 761.0 25 10.0 10.0 10.0 10.0 10.0 10.0 761.0 25 10.0 10.0 10.0 10.0 10.0 10.0 761.0 25 10.0 10.0 10.0 10.0 10.0 10.0 761.0 25 10.0 10.0 10.0 10.0 10.0 10.0 <td>773.0</td> <td>13</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>	773.0	13											
771.0 15 Clayey Sand, light brown, damp, medium dense, porous, with shale chips R 18 10.0 91.8 770.0 16 R 18 10.0 91.8 768.0 18 R 18 10.0 91.8 766.0 20 brown, damp, dense, porous, shale chips (hard drilling) R 28 23.1 84.4 764.0 22 R 28 23.1 84.4 763.0 23 761.0 25 Surface: Asphalt Pavement - 4 Inches AC/5 Inches Base Size: 8 Inch	772.0	14											
770.0 16 769.0 17 768.0 18 767.0 19 766.0 20 brown, damp, dense, porous, shale chips (hard drilling) 766.0 21 hard drilling 763.0 22 763.0 23 762.0 24 761.0 25 Surface: Asphalt Pavement - 4 Inches AC/5 Inches Base Size: 8 Inch	771.0	15	Clayey Sand, light brown, damp, medium dense, porous, with			R	18	10.0	91.8				
768.0 18 767.0 19 766.0 20 brown, damp, dense, porous, shale chips (hard drilling) 765.0 21 hard drilling 764.0 22 763.0 23 762.0 24 761.0 25 Surface: Asphalt Pavement - 4 Inches AC/5 Inches Base Size: 8 Inch	770.0	16											
767.0 19 766.0 20 brown, damp, dense, porous, shale chips (hard drilling) 765.0 21 hard drilling 764.0 22 763.0 23 762.0 24 761.0 25 Surface: Asphalt Pavement - 4 Inches AC/5 Inches Base Size: 8 Inch	769.0												
766.0 20 brown, damp, dense, porous, shale chips (hard drilling) A 765.0 21 hard drilling 764.0 22 763.0 23 762.0 24 761.0 25 Surface: Asphalt Pavement - 4 Inches AC/5 Inches Base Size: 8 Inch	768.0	18							ĺ				
765.0 21 hard drilling 764.0 22 763.0 23 762.0 24 761.0 25 Surface: Asphalt Pavement - 4 Inches AC/5 Inches Base Size: 8 Inch	767.0	19											
765.0 21 hard drilling 764.0 22 763.0 23 762.0 24 761.0 25 Surface: Asphalt Pavement - 4 Inches AC/5 Inches Base Size: 8 Inch	766.0	20	brown, damp, dense, porous, shale chips (hard drilling)										
763.0 23 762.0 24 761.0 25 Surface: Asphalt Pavement - 4 Inches AC/5 Inches Base Size: 8 Inch	765.0	21	hard drilling			К	28	23.1	84.4				
762.0 24 761.0 25 Surface: Asphalt Pavement - 4 Inches AC/5 Inches Base Size: 8 Inch	764.0	22											
761.0 25 Surface: Asphalt Pavement - 4 Inches AC/5 Inches Base Size: 8 Inch	763.0	23											
Surface: Asphalt Pavement - 4 Inches AC/5 Inches Base Size: 8 Inch	762.0	24											
	Surfac	ce: Asp	ohalt Pavement - 4 Inches AC/5 Inches Base	:	Size:	8 Inch	ĩ						
Drill Method: Hollow-Stem Auger Drill Rig Elevation: 786 Feet								eet			ł		
Drill Date: October 6, 2003 Sheet: 1 of 2	Drill D	ate: 0	ctober 6, 2003		Shee	t: 1 of	2						

Log of Boring: 8

Client: THE BUCKLEY SCHOOL

Logged By: JWB

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

Elevation Depth Describtion Type Dry Density Dry Density Dry Density Dry Density Dry Density	:S					
758.0 28						
756.0 30 Clayey Sand, light brown, damp, dense, large shale R 31 34.6 86.0 fragments						
	1					
751.0 35 - R 25 42.3 77.9						
747.0 39 BEDROCK: Diatomaceous Shale, brown-gray, moist, well bedded, 746.0 40						
745.0 41 End at 41 Feet; No Water; Fill to 5 Feet.						
742.0 = 44 =						
741.0 45						
739.0 47 -						
738.0 48						
736.0 3 50 3 Surface: Asphalt Pavement - 4 Inches AC/5 Inches Base Size: 8 Inch						
Drill Method: Hollow-Stem Auger Drill Rig Elevation: 786 Feet						
Drill Date: October 6, 2003 Sheet: 2 of 2						

Log of Boring: 9

Client: THE BUCKLEY SCHOOL

Logged By: JWB

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

		SUBSURFACE PROFILE				SA	MPLE			
Elevation	Depth	Description	Symbol	uscs	Type	Blow Count	Moisture Content (%)	Dry Density	% Saturation	Remarks
795.0	1	FILL: Clayey Sand, brown, damp, dense, rubble, shale fragments, roots	\bigotimes							
794.0	2		\otimes		R	18	20.2	104.1		
793.0	3	<i>SOIL:</i> Clayey Sand, brown gray, damp, medium dense, shale chips,								
792.0	4	roots			-					
791.0	5				R	24	51.3	69.0		
790.0	6 7	Sandstone and Shale fragments							i	
788.0	8									
787.0	911 91									
786.0	10				R	50 9"				No Recovery
785.0	11									
784.0	12									
783.0	13	BEDROCK: Diatomaceous Siltstone, light brown, moist, well bedded,	****							
782.0	14	moderately hard	****							
781.0	15		× × × × × × × × × × × × × × × × × × ×		R	45	59.5	66.2		
779.0	17 -	End at 16 Feet; No Water; Fill to 3 Feet.		1						
778.0	18	· · · · · · · · · · · · · · · · · · ·								
777.0	19 19									
776.0	20									
775.0	21									
774.0	22					6				
773.0	23								and the second	
772.0	24									
		sphalt Pavement - 3 Inches AC/4 Inches Base	<u>, .</u>	Size:	8 Inci	¹ h		<u>_</u>		
		d: Hollow-Stem Auger Drill Rig		Eleva			eet			
		October 6, 2003		Shee						

Log of Boring: 10

Client: THE BUCKLEY SCHOOL

Logged By: JWB

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

		SUBSURFACE PROFILE			i	SA	MPLE			
Elevation	Depth	Description	Symbol	uscs	Type	Blow Count	Moisture Content (%)	Dry Density	% Saturation	Remarks
828.0	1	FILL: Clayey Sand, dark gray, moist, medium dense, gravel	×							
827.0	2		\otimes							
826.0	311		\otimes							
825.0	4	SOIL: Sandy Clay, brown, moist, firm, rock fragments	××							
824.0	5111	Sandy Glay, brown, molst, nini, rock nagments								
823.0	6									
822.0	7									
821.0	8									
820.0	9111		 							
819.0		BEDROCK: Diatomaceous Siltstone and Sandstone, brown-gray, moist,	****		R	50 10"	13,5	93.5		
818.0	-	moderately hard, minor fractures, bedded	× × × × × × × × × × × × × × × × × × ×							
817.0 	Ē		****							
815.0	14		****						and	
814.0	15		× × × : × × × : × × × :		R	36	40.9	81.2		
813.0	16	End at 16 Feet; No Water; Fill to 4 Feet.	****		ι.	50	40.5	01.2		
812.0	17	End at 10 reet, NO Water, Fill to 4 reet.								
811.0	18									
810.0	19									
809.0	20									
808.0	21									
807.0	22									
806.0	23									
805.0	24			1						
804.0-	25-	phalt Parking - 4 Inches AC/6 Inches Base		Size:	8 Incl	<u> </u>				
		1: Hollow-Stem Auger Drill Rig	Size: 8 Inch Elevation: 829 Feet							
		October 6, 2003		Sheet: 1 of 1						

Log of Boring: 11

Client: THE BUCKLEY SCHOOL

Logged By: JWB

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

		SUBSURFACE PROFILE				SA	MPLE			
Elevation	Depth	Description	Symbol	uscs	Type	Blow Count	Moisture Content (%)	Dry Density	% Saturation	Remarks
829.0	1 1 1 1 1	FILL: Clayey Sand, reddish-brown, damp, medium dense, some rubble, blue slate chips	×							
828.0	2									
827.0	3									
826.0	4									
825.0	5	Clayey Sand, brownish-gray, damp, medium dense, some	- 🖄							
824.0	611	rubble, brick fragments	 							
823.0	7									
822.0	8									
821.0	91		 							
820.0	10 +	sample barrel on concrete	-		R	25	15.3	106.6		
819.0		Clayey Sand, dark gray, damp, dense, rubble, slate chips,	- +							
818.0	12	twigs								
817.0	13									
816.0	14	Clayey Sand, dark gray, damp, medium dense to dense,	-							
815.0	15	asphalt rubble, slate chps			R	20	12.2	113.3		
814.0	16									
813.0	17		 							
812.0	18									
811.0 	19									
810.0	20	Clayey Sand, brown, damp, medium dense to dense, rubble,				20	00.0	107.0		
809.0	21	slate chips			R	20	20.3	107.0		
808.0	22	hard drilling at 22 to 24 feet (possible rock)								
807.0	23									
806.0 E	24									
805.0	25		x x x							
		phalt Pavement/Parking - 5 Inches AC/3 Inches Base		Size:			inct.			
		d: Hollow-Stem Auger Drill Rig Dctober 1, 2003		Elevation: 830 Feet Sheet: 1 of 2						
		· · · · · · · · · · · · · · · · · · ·								

Log of Boring: 11

Client: THE BUCKLEY SCHOOL

Logged By: JWB

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

SUBSURFACE PROFILE SAMPLE										
Elevation	Depth	Description	Symbol	uscs	Type	Blow Count	Moisture Content (%)	Dry Density	Saturation %	Remarks
Image: Second	26 27 28 29 30 31 32	Silty Sand, brown, damp, medium dense to dense, small rock/gravel, more coarse, shale chips Clayey Sand, brown, damp, medium dense to dense, porous, large amounts of shale fragments	Symbol 2011 Strate Stra	nscs	R R	17	30.1	83.4 86.8	Satura %	
793.0 792.0 791.0 790.0 789.0 788.0 788.0 787.0 786.0 785.0 785.0 784.0 783.0 784.0 783.0	37 38 39 40 41 42 43 44 45 46 47 48 49 50	BEDROCK: Diatomaceous Siltstone/Sandstone, brown and gray, moderately hard, minor fractures, weathered, well bedded End at 46 Feet; No Water; Fill to 24 Feet.				50 7"	28.3	87.3		No Recovery
Surfa	ce: As	· · ·		e: 8 Inc		Foot	!	<u> </u>		
				ation: et: 2 o		⊢eet				
			0116	01.20						

Client: THE BUCKLEY SCHOOL

Logged By: JWB

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

Unit Description Image: Constraint of the	3e,	lens
821 1 Clayey Sand, brown, damp, medium dense, some rubble, asphalt, gravel 820 2 819 3 818 4 817 5 818 4 817 5 818 4 817 5 818 4 817 5 818 4 817 5 818 6 Clayey Sand, dark brown, damp, dense, small gravel (slate)		iens
821 1 Clayey Sand, brown, damp, medium dense, some rubble, asphalt, gravel 820 2 819 3 818 4 817 5 816 6 Clayey Sand, dark brown, damp, dense, small gravel (slate)		lens
819 3 818 4 817 5 816 6 Clayey Sand, dark brown, damp, dense, small gravel (slate)	R 28 16.2 105.6	
818 4 817 5 817 5 816 6 Clayey Sand, dark brown, damp, dense, small gravel (slate)	R 28 16.2 105.6	
817 5 816 6 Clayey Sand, dark brown, damp, dense, small gravel (slate) 815 7 815 7	R 28 16.2 105.6	
816 Clayey Sand, dark brown, damp, dense, small gravel (slate) 815 7	R 28 16.2 105.6	
Small gravel (slate)		
815 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7		e,
814 8 8		
813 9 9		
812 10 Clayey Sand, dark gray brown, moist, Clayey Sand, dark gray brown, moist, medium dense, gravel, sandstone fragment	R 45 13.0 113.0	
811 - 11 - in sample tip		me
807 - 15 - Clayey Sand, gray and brown layers, moist, medium dense, gravel R 31 19.4 97.1	.t, R 31 19.4 97.1	nois
803 - 19 -		
802 20		
Surface: Asphalt Parking - 4 Inches AC/3 Inches Base Size: 8 Inch	Size: 8 Inch	se
Drill Method: Hollow-Stem Auger Drill Rig Elevation: 822 Feet	Elevation: 822 Feet	
Drill Date: October 1, 2003 Sheet: 1 of 2	Sheet: 1 of 2	

Client: THE BUCKLEY SCHOOL

Logged By: JWB

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

		SUBSURFACE PROFILE	· · ·			SA	MPLE		-	
Elevation	Depth	Description	Symbol	uscs	Type	Blow Count	Moisture Content (%)	Dry Density	% Saturation	Remarks
801	21-	ALLUVIUM: Gravelly Clay, tan, damp, firm, small fragments of shale, sandstone, siltstone	· · · ·		R	48	35.3	74.3		
800-	22-				-					
799	23 -									
798-	24 - - - 25 -									
796	26 -	rock in sample tip			R	40	44.8	73.2		
795-	27									
794	28		· 							
793 - 	29 - -		°							
792	30	BEDROCK: Diatomaceous Siltstone and Sandstone, gray and brown, damp, soft as rock, well bedded, tight	X K X X X X X X X X X X X X X X X X X X		R	50	32.2	82.2		
791 -	31-	End at 31 Feet; No Water; Fill to 20 Feet.								
790	32	End of Borehole								
789-	33									
787	35									
786	36									
785	37									
784	38							approved a second s		
783	39 1 40									
Surfac	ce: As	phalt Parking - 4 Inches AC/3 Inches Base				ç	Size: 8	Inch		
		: Hollow-Stem Auger Drill Rig					Elevatio		Feet	
Drill D	ate: C	October 1, 2003					Sheet:	2 of 2		

Log of Boring: 13

Client: THE BUCKLEY SCHOOL

Logged By: JWB

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

		SUBSURFACE PROFILE				SA	MPLE	,	,	
Elevation	Depth	Description	Symbol	nscs	Type	Blow Count	Moisture Content (%)	Dry Density	Saturation %	Remarks
839.0	1-	FILL: Clayey Sand, brown, damp, medium dense, rubble, brick fragments, slate chips								
838.0	2									
837.0-	3-									
836.0	4									
835.0	5		\otimes							
834.0	6	Clayey Sand, reddish-brown, damp, medium dense, slate chips, rubble, shale fragments	🞇							
833.0	7	rubble, shale hagments								
832.0	8									
831.0	911									
830.0	10 =	Clayey Sand, reddish brown, damp, medium dense, shale			R	11	17.7	108.0		
829.0	11	fragments, slate chips, rubble, roots								
828.0	12									
827.0	13									
826.0	14		\otimes							
825.0	15									
824.0		Clayey Sand, dark gray, damp, medium dense, slate chips, rubble	-88							
823.0										
822.0	18									
821.0	19									
820.0	20									
819.0	21				R	15	21.5	103.1		
818.0	22	color change to very dark gray-green	- 💥							
817.0	23	- · · · · ·	\otimes							
816.0	24		\otimes							
815.0	25		\otimes							
Surfa	ce: Gra	ass Field	Size	: 8 Inc	h					
		: Hollow-Stem Auger Drill Rig		ation:		Feet				
Drill D	Date: C	October 6, 2003	Shee	et: 1 o	13]

Log of Boring: 13

Client: THE BUCKLEY SCHOOL

Logged By: JWB

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

		SUBSURFACE PROFILE		SAMPLE						
Elevation	Depth	Description	Symbol	uscs	Type	Blow Count	Moisture Content (%)	Dry Density	% Saturation	Remarks
-	-		\otimes						ļ	
814.0	26-									
813.0	27-									
812.0	28									
811.0	29-									
	-									
810.0	-	Clayey Sand, brown, damp, medium dense, slate chips, rubble	\mathbb{X}		R	17	15.6	114.0		
809.0	31-									
808.0	32-									
807.0	33	Clayey Sand, dark gray, moist, medium dense, rubble, slate	\mathbb{X}							
806.0	34	chips								
805.0	35									
804.0	36									
803.0	37	hard drilling	×							
E 802.0	38									
801.0	39 1									
	11									
800.0	40	Clayey Sand, gray-green, damp, medium dense, shale fragments, rubble			R	16	28.0	91.7		
799.0	41									T
798.0	42-									
797.0	43	ALLUVIUM:	×							
796.0-	44	Clayey sand, light brown, light gray, damp, dense, large shale fragments								
795.0	45				R	33	52.6	67.7		
794.0	46									
793.0	47									
Ę										
792.0	48									
791.0	49									
790.0	50-									
		ass Field			8 Incl					
		₫: Hollow-Stem Auger Drill Rig Dotober 6, 2003			ation: t: 2 of		eet			

Client: THE BUCKLEY SCHOOL

JB No: 19376-B

Logged By: JWB

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

				SAI	MPLE				
Elevation Depth	Description	Symbol	USCS	Type	Blow Count	Moisture Content (%)	Dry Density	% Saturation	Remarks
789.0 51 788.0 52 787.0 53 786.0 54 785.0 55 784.0 56	Clayey Sand, brown, damp, medium dense, rock fragments			R	23	43.1	76.0		
783.0 57 782.0 58 781.0 59 780.0 60 779.0 61 777.0 63 777.0 63 776.0 64	water at 56.5 Feet								
775.0 65 774.0 66 773.0 67 777.0 68 777.0 70 769.0 71 768.0 72 766.0 74 765.0 75	Gravelly Sand, Clayey Sand mix, brown and gray, wet, dense, large shale fragments End at 66 Feet; Water at 56.5 Feet, Fill to 43 Feet.	2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2		R	25	23.6	96.1		
Surface: G	rass Field	<u>بل</u>	Size:	8 Inc	h			1	
	d: Hollow-Stem Auger Drill Rig October 6, 2003	-	Eleva Shee			eet			

Log of Boring: 14

Client: THE BUCKLEY SCHOOL

Logged By: JWB

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

Bit Mathematical State Description No. No. No. No. No. No. No. No. No. 3350 1 <			SUBSURFACE PROFILE	SAMPLE							
233.0 7.2. Silp Sand, brown, damp, medium dense, some gravel R 3 20.7 98.1 333.0 4 Clayey Sand, brown, saturated, soft, slate chips, roots R 3 20.7 98.1 333.0 4 Clayey Sand, brown, saturated, soft, slate chips, roots R 3 20.7 98.1 333.0 7 Clayey Sand, brown, saturated, soft, slate chips, roots R 1 20.7 98.1 333.0 7 Clayey Sand, reddsh-brown, saturated, soft, slate chips, wood fragments R 10 16.6 16.8 825.0 11 Clayey Sand, reddsh-brown, saturated, soft, slate chips, wood fragments R 10 16.6 16.8 825.0 11 Clayey Sand, dark gray, damp, medium dense, slate chips, grant is granter fragments R 15 20.5 96.4 825.0 11 Clayey Sand, dark gray, damp, medium dense, slate chips, chips, shate chips, fragment of Sandstone R 14 16.3 95.7 816.0 22 R 14 16.3 95.7 14 16.3 95.7	Elevation	Depth	Description	Symbol	uscs	Type	Blow Count	Moisture Content (%)	Dry Density	% Saturation	Remarks
334.0 3 - Clayey Sand, brown, saturated, soft, siate chips, roots - R 3 26.7 96.1 831.0 6 - - R 3 26.7 96.1 832.0 6 - - R 3 26.7 96.1 832.0 7 - - R 10 18.6 109.5 822.0 8 - - R 10 18.6 109.5 822.0 11 - - R 10 18.6 109.5 822.0 11 - - R 10 18.6 109.5 822.0 11 - - R 10 18.6 109.5 823.0 14 - - R 14 14 16.5 199.5 823.0 14 - - R 14 16.3 93.7 813.0 19 - - R 14 16.3 93.7 814.0 22 - - R 1	836.0	1111									
832.0 5 <td>-</td> <td>3</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>	-	3									
831.0 6 830.0 7 820.0 9 827.0 10 Clayey Sand, reddish-brown, saturated, soft, siate chps, wood fragments		4	Clayey Sand, brown, saturated, soft, slate chips, roots	×		-					
829.0 8 828.0 9 927.0 10 Clayey Sand, reddish-brown, saturated, soft, slate chps, wood fragments R 10 18.6 109.9 825.0 12		5 6 11111				R	3	26.7	98.1		
828.0 9	E	7		\otimes							
826.0 11 826.0 11 825.0 12 823.0 14 823.0 17 823.0 17 820.0 17 820.0 17 818.0 19 91.0 18 818.0 19 92.0 23 ALLUVIUM: Clayey Sand, dark green/blue, very moist, medium dense, slate 813.0 24 92.1 14 93.1 14 93.1 14 93.1 14 93.1 14 93.1 14 93.7											
826.0 11 825.0 12 824.0 13 823.0 14 822.0 15 Clayey Sand, dark gray, damp, medium dense, slate chips, granite fragments	E I	10	Clayey Sand, reddish-brown, saturated, soft, slate chps, wood fragments	\bigotimes		R	10	18.6	109.5		
624 0 13 823.0 14 822.0 15 Clayey Sand, dark gray, damp, medium dense, siate chips, granite fragments 821.0 16 820.0 17 810.0 18 19 Clayey Sand, light brown, damp, moist, medium dense, slate chips, shale chips 818.0 19 Clayey Sand, light brown, damp, moist, medium dense, slate chips, shale chips 816.0 21 816.0 21 816.0 22 816.0 21 816.0 22 813.0 24 fragment of Sandstone	Ē	=									
822.0 15 Clayey Sand, dark gray, damp, medium dense, slate chips, granite fragments R 15 23.5 99.4 821.0 16 granite fragments R 15 23.5 99.4 820.0 17 R 15 23.5 99.4 819.0 18 19 Clayey Sand, light brown, damp, moist, medium dense, slate chips, shale chips R 14 16.3 93.7 816.0 21 R 14 16.3 93.7 R 14 16.3 93.7 815.0 22 R 14 16.3 93.7 R 14 16.3 93.7 814.0 23 ALLUVIUM: Clayey Sand, dark green/blue, very moist, medium dense, fragment of Sandstone 14 16.3 93.7 813.0 24 fragment of Sandstone 14 16.3 14 16 812.0 25 Dirtl Field Size: 8 Inch 14 16 14 14 brill Method: Hollow-Stem Auger Drill Rig Elevation: 837 Feet 15 16 16 16		13									
821.0 16 granite fragments 818.0 19 Clayey Sand, light brown, damp, moist, medium dense, slate 818.0 19 Clayey Sand, light brown, damp, moist, medium dense, slate 817.0 20 816.0 21 816.0 22 814.0 23 ALLUVIUM: Clayey Sand, dark green/blue, very moist, medium dense, 613.0 24 613.0 25 Surface: Dirt Field Drill Method: Hollow-Stem Auger Drill Rig		=		\bigotimes							
819.0 18 818.0 19 Clayey Sand, light brown, damp, moist, medium dense, state chips, shale chips 817.0 20 816.0 21 816.0 21 814.0 23 ALL UVIUM: Clayey Sand, dark green/blue, very moist, medium dense, fragment of Sandstone 813.0 24 fragment of Sandstone 812.0 25 Surface: Dirt Field Size: 8 Inch Drill Method: Hollow-Stem Auger Drill Rig Elevation: 837 Feet		T	Clayey Sand, dark gray, damp, medium dense, slate chips, granite fragments	\bigotimes		R	15	23.5	99.4		
817.0 20 816.0 21 816.0 21 816.0 22 814.0 23 ALLUVIUM: Clayey Sand, dark green/blue, very moist, medium dense, fragment of Sandstone 813.0 24 Surface: Dirt Field Size: 8 Inch Drill Method: Hollow-Stem Auger Drill Rig Elevation: 837 Feet	=			\bigotimes							
816.0 21 816.0 22 815.0 22 814.0 23 ALLUVIUM: Clayey Sand, dark green/blue, very moist, medium dense, fragment of Sandstone 812.0 25 Surface: Dirt Field Size: 8 Inch Drill Method: Hollow-Stem Auger Drill Rig Elevation: 837 Feet	-		Clayey Sand, light brown, damp, moist, medium dense, slate chips, shale chips	×				n, vi v vi transmonten			
814.0 23 ALLUVIUM: Clayey Sand, dark green/blue, very moist, medium dense, fragment of Sandstone 813.0 24 Fragment of Sandstone 812.0 25 Surface: Dirt Field Size: 8 Inch Drill Method: Hollow-Stem Auger Drill Rig Elevation: 837 Feet	816.0	21		\bigotimes		R	14	16.3	93.7		
ALLO VIOW. Clayey Sand, dark green/blue, very moist, medium dense, fragment of Sandstone 813.0 24 Surface: Dirt Field Size: 8 Inch Drill Method: Hollow-Stem Auger Drill Rig Elevation: 837 Feet	1		A 1 1 1 15 // 1 RA-	×							
Surface: Dirt FieldSize: 8 InchDrill Method: Hollow-Stem Auger Drill RigElevation: 837 Feet	813.0		Clayey Sand, dark green/blue, very moist, medium dense,								
Drill Method: Hollow-Stem Auger Drill Rig Elevation: 837 Feet								[
	Surfac	ce: Dir	Field		Size:	8 Incl	٦				
Drill Date: October 1, 2003 Sheet: 1 of 2								eet			
	Drill D										

Log of Boring: 14

Client: THE BUCKLEY SCHOOL

Logged By: JWB

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

		SUBSURFACE PROFILE				SA	MPLE			
Elevation	Depth	Description	Symbol	uscs	Type	Blow Count	Moisture Content (%)	Dry Density	% Saturation	Remarks
811.0	26-			-						
810.0	-					-				
809.0	28		1.	-1						
	-	Diatomaceous Siltstone and Sandstone, brown, gray layers,	***	4					ς -	
808.0	29-	moderately hard, well bedded	× × × × × × × × ×							
807.0	30-		× * * × * * × * *		R	26	45.8	77.7		
806.0	31 -		* * * * * * * * *							
805.0	32		***	, , ,						
	-		***	*						
804.0	33-		* * *							
803.0 1	34 -		* * * * * * * * *	1						
802.0	35-	Diatomaceous officiane and oundatone, brown, gray layers,	× × × × × × × × ×		R	50 11"	25.6	89.7		
801.0	36	moderately hard, fractured, well bedded	* * * * * * * * * *							
E E 800.08	37 -		* * * * * * * * *						-	
Ē	-		***							
799.0	38-		* * * * * * * * *							
798.0	39		***		R	50 6"	32.9	82.7		
797.0	40	Diatomaceous Siltstone and Sandstone, brown and gray,	* * *							
796.0	41	moderately hard, minor fractures, bedded	***							
795.0	42									
- T										
794.0	43-								1	
793.0	44									
792.0	45									
791.0	46									
790.0	47									
789.0	11									
=	48									
788.0	49			l						
787.0	<u>50</u> -	<u></u>				}				
		rt Field		Size:						
		d: Hollow-Stem Auger Drill Rig		Eleva			eet			
	ate: (October 1, 2003		Shee	ι. ∠ 01 -	2			<u></u>	

Log of Boring: 15

Client: THE BUCKLEY SCHOOL

Logged By: JWB

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

Site Location: 3900 Stansbury Avenue

		SUBSURFACE PROFILE				SA	MPLE			
Elevation	Depth	Description	Symbol	uscs	Type	Blow Count	Moisture Content (%)	Dry Density	% Saturation	Remarks
837.0	1	FILL: Clayey Sand, reddish-brown, damp, medium dense, some rubble, slate chips and shale fragments								
836.0	2									
835.0	3									
834.0	4									
833.0	5									
832.0	6	Clayey Sand, brown, damp, medium dense to dense, shale					-			
831.0	7	fragments, rubble								
830.0	8	ALLUVIUM: Clayey Sand, brown, damp, medium dense, rock fragments								
829.0	9									
828.0					R	18	28.6	80.2	1	
827.0										
826.0	12									
825.0	13									
824.0	14									
823.0	15	Clayey Sand, brown, damp, medium dense, large shale fragments, porous			R	14	32.1	71.9	-	
822.0	16								1	
821.0										
820.0	18									
819.0	19									
818.0	20				R	14	26.3	83.1		
817.0 	21									
815.0	22	hard drilling at 22 feet, rocky layer								
815.0	24	BEDROCK: Diatomaceous Siltstone and Sandstone, brown and gray, moderately hard, fractured, bedded								
813.0	25	····								
Surfac	ce: Asp	halt Driveway - 4 Inches AC/3 Inches Base		Size:	8 Inc	h				1
		Hollow-Stem Auger Drill Rig				838 F	eet			
Drill D	ate: O	ctober 6, 2003		Shee	t: 1 of	2	· · ·			

Log of Boring: 15

Client: THE BUCKLEY SCHOOL

Logged By: JWB

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

Site Location: 3900 Stansbury Avenue

		SUBSURFACE PROFILE	SAMPLE							
Elevation	oth	Description	Symbol	SS	Ð	Blow Count	Moisture Content (%)	Dry Density	% Saturation	Remarks
Шe	Depth		Syn	uscs	Type	Blo	Moi	Dry	%	
812.0	26	End at 26 Feet; No water; Fill to 7.5 Feet								
811.0	27-									
810.0	28									
809.0-	29									
808.0	30-		3							
807.0	31-									
806.0	32									
805.0	33									
804.0	34 -									
803.0	35 -									
802.0 - -	36-									
801.0 T	37 -									:
	38-									
799.0	39-									
798.0 - 	40									
797.0-	41									-
796.0	42									
795.0	43									
794.0	44									
793.0	45									
792.0	46									
791.0	47									
790.0	48 -									
789.0	49									
788.0	50-7]	
		phalt Driveway - 4 Inches AC/3 Inches Base		Size:						
		d: Hollow-Stem Auger Drill Rig		Eleva			eet			
Urill L	Jate: (October 6, 2003		Sheet						

Client: THE BUCKLEY SCHOOL

Logged By: JWB

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

		SUBSURFACE PROFILE				SA	MPLE			
Elevation	Depth	Description	Symbol	nscs	Type	Blow Count	Moisture Content (%)	Dry Density	% Saturation	Remarks
843	0-	Ground Surface	~~~~						-	
842 - 	1	FILL: Clayey Sand, brown, moist, medium dense, some rock fragments concrete in sample								
841 -	2-									
840 - 	3 1 1									
839 - 	4 1 1									
838-	5-				R	26	23.6	96.1		
837-			\bigotimes							
836	7117	light brown and dark brown layers, medium dense to dense								
835-	8									
834	9 111 9									
833		Clayey Sand, dark gray brown, very moist, medium dense, gravel and rock fragments			R	18	20.6	92.3		
832	11									
831-	12									
830	13-1									
829					90 A.					
828-	15	more gravel and rocks, less dense, more moisture			R	16	9.4	109.6		
827-	16-									
826									******	
825		rocky layers, hard drilling								
824 	19 1 1 20									
Surfac			<u>~~~</u>				Size: 8	Inch		
		" I: Hollow-Stem Auger Drill Rig						on: 843	Feet	
		Ctober 6. 2003					Sheet:			

Client: THE BUCKLEY SCHOOL

Logged By: JWB

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

	SUBSURFACE PROFILE SAMPLE									
Elevation	Depth	Description	Symbol	uscs	Type	Blow Count	Moisture Content (%)	Dry Density	% Saturation	Remarks
822	21-				R	19	21.0	104.9		
821-	22									
820-	23									
819-	24	fill contains cobbles of granite								
818 - - 817 -	25 	hard drilling			R	21	2.4	106.0		
816	27									
815	28	BEDROCK:								
814-	29	Siltstone and Sandstone, light and dark brown, damp, moderately hard, well bedded	* * * * * *							
813	30		* *		R	50 10"	25.0	84.9		
812-	31		* *							
811 - - - 810 - -	32	refusal - too hard to drill End at 32 Feet; No Water; Fill to 28 Feet. End of Borehole	****							
809	34 -									
808	35									
807	36									
806	37-									
805	38-1									
803	39 1 40									
Surfac	i			1			Size: 8	Inch		
		I: Hollow-Stem Auger Drill Rig					Elevatio		Feet	
Drill D	ate: C	October 6, 2003					Sheet: 3	2 of 2		

Log of Boring: 17

Client: THE BUCKLEY SCHOOL

Logged By: JWB

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

		SUBSURFACE PROFILE			SAMPLE					<u> </u>				
Elevation	Depth	Description	Symbol	uscs	Type	Blow Count	Moisture Content (%)	Dry Density	% Saturation	Remarks				
843.0	1	FILL: Silty Sand, light brown, damp, dense, rubble, brick and shale fragments, roots												
842.0	2													
841.0	3	SOIL: Clayey Sand, light brown, damp, dense, white diatomaceous												
840.0	4	shale fragments												
839.0	5	BEDROCK: Diatomaceous Sandstone and Siltstone, brownish-gray,	***		R	50 10"	27.1	89.9		-				
838.0 837.0	61117	damp, moderately hard, fractured, roots	***											
836.0	8 1 8		* * * * *											
835.0	91	Diatomaceous Sandstone and Siltstone, brownish-gray,	****			-								
834.0	10	damp, moderately hard, well bedded, cemented limestone layers	****		R	50 5"	27.1	86.6						
833.0		End at 11 Feet; No Water; Fill to 3 Feet.	* * * :											
832.0	12													
831.0	13													
830.0 														
828.0	16													
827.0	17													
826.0	18													
825.0	19													
824.0 	20				, , , ,									
822.0	22													
821.0	23													
820.0	24													
819.0	25-			<u> </u>	0.1									
						Size: 8 Inch								
	Drill Method: Hollow-Stem Auger Drill Rig Drill Date: October 6, 2003						Elevation: 844 Feet Sheet: 1 of 1							

Log of Boring: 18

Client: THE BUCKLEY SCHOOL

Logged By: JET

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

B B Description B <th< th=""><th></th><th></th><th>SUBSURFACE PROFILE</th><th></th><th></th><th colspan="5">SAMPLE</th><th></th></th<>			SUBSURFACE PROFILE			SAMPLE					
783.0 71 5 5 10 nch nock fragments 783.0 10 nch nock fragments 10 nch nock fragments 10 nch nock fragments 783.0 10 nch nock fragments 10 nch nock fragments 10 nch nock fragments 773.0 14 18 21.9 101.4 777.0 7 7 7 776.0 6 18 20 20.2 777.0 7 7 760.0	Élevation	Depth	Description	Symbol	uscs	Type	Blow Count	Moisture Content (%)	Dry Density	% Saturation	Remarks
783.0 1 783.0 2 781.0 2 781.0 3 783.0 4 778.0 5 Caper Sitt dark brown is brown, motal, tim, some grave! - 778.0 6 6 - 778.0 6 778.0 7 778.0 7 778.0 7 778.0 8 778.0 8 778.0 7 778.0 8 778.0 7 778.0 7 778.0 7 778.0 7 778.0 8 779.0 7 779.0 7 779.0 7 779.0 7 779.0 7 779.0 7 779.0 7 779.0 7 779.0 7 780.0 7 780.0 7 780.0 7 783.0 7			Fill:	X		<u> </u>		-	+		
7810 3 10 non-rock regments 7780 4 7780 5 7780 6 7770 7 7780 7 7780 7 7780 8 7780 8 7780 8 7780 8 7780 7 7780 8 7800 16 7800 <t< td=""><td>783.0</td><td>1</td><td>Silty Clay, dark brown, very moist, slightly firm to soft</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></t<>	783.0	1	Silty Clay, dark brown, very moist, slightly firm to soft								
781.0 3 780.0 4 779.0 5 Clayey Stit, dark bown to brown, most, firm, some grave. R 778.0 6 777.0 7 778.0 6 777.0 7 778.0 8 778.0 9 778.0 9 778.0 9 778.0 8 778.0 9 778.0 9 778.0 9 778.0 9 778.0 9 778.0 9 778.0 9 777.0 7 771.0 7 771.0 11 772.0 11 770.0 14 770.0 14 770.0 14 770.0 14 770.0 14 770.0 14 770.0 14 770.0 17 780.0 16 780.0 16 780.0	782.0	2		\otimes							
779:00 5 Clayey Sit, dark brown to brown, moist, firm, some gravel	781.0 	3	10 inch rock fragments								
778.0 6 7 <td>780.0</td> <td>4 -</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>	780.0	4 -									
777.0 7 776.0 9 777.0 10 10 darx gray, stiff 777.0 11 777.0 11 777.0 11 777.0 11 777.0 11 777.0 11 777.0 11 777.0 12 777.0 12 777.0 12 777.0 14 777.0 14 777.0 14 770.0 14 770.0 14 770.0 14 770.0 14 770.0 14 770.0 14 770.0 14 770.0 14 770.0 16 16 5anty Solit, gray-brown, moist, firm, some clay 768.0 18 765.0 19 762.0 21 97.0 31.0 762.0 22 763.0 24 97.0 35.6	779.0	5	Clayey Silt, dark brown to brown, moist, firm, some gravel	- 💥		R	16	21.9	101.4	91.9	
776.0 8 777.0 10 777.0 11 777.0 11 777.0 11 777.0 12 777.0 13 777.0 14 778.0 14 778.0 14 778.0 14 778.0 14 778.0 14 778.0 14 778.0 14 778.0 14 778.0 14 778.0 14 778.0 14 778.0 14 768.0 16 768.0 16 768.0 16 768.0 17 768.0 18 768.0 19 768.0 19 768.0 19 768.0 19 768.0 19 768.0 19 769.0 20 761.0 20 762.0 22 763.0 21 <	778.0	6									
775.0 9 774.0 10 10	777.0	7									
7774 0 10	776.0	8-1-8									
773.0 11	775.0	91									
772.0 12 777.0 13 777.0 14 779.0 14 769.0 15 5andySilt.gray-brown, moist, firm, some clay 768.0 16 766.0 17 766.0 18 766.0 18 766.0 18 766.0 18 766.0 18 766.0 18 766.0 18 766.0 18 766.0 18 766.0 18 766.0 19 766.0 19 767.0 77 768.0 16 769.0 20 769.0 21 Sandy Sill/Silly Sand, light gray, light brown, slightly moist, dense, some gravel 761.0 22 761.0 23 761.0 24 761.0 25 761.0 24 761.0 25 762.0 24 763.0 24 76	774.0	10 =	dark gray, stiff			R	20	26.2	93.9	91.1	
7771.0 13 7771.0 14 769.0 15 5andySill, gray-brown, moist, firm, some clay 768.0 16 766.0 17 766.0 18 766.0 18 766.0 19 766.0 18 766.0 19 766.0 18 766.0 18 766.0 18 766.0 18 766.0 18 766.0 18 766.0 18 767.0 17 768.0 18 769.0 20 21 ALLUVIUM: Sandy Sill/Silly Sand, light gray, light brown, slightly moist, dense, some 762.0 22 761.0 23 762.0 24 763.0 24 763.0 24 763.0 24 763.0 24 763.0 24 763.0 24 763.0 24	773.0	11									
770.0 14 769.0 15 SandySilt, gray-brown, moist, firm, some clay 768.0 16 767.0 17 766.0 18 766.0 18 766.0 19 766.0 19 766.0 19 766.0 20 ALLUVIUM: SandySilty Sand, light gray, light brown, slightly moist, dense, some gravel 762.0 22 763.0 21 Sandy Silt/Silty Sand, light gray, light brown, slightly moist, dense, some gravel 762.0 22 763.0 21 Sandy Silty Sand, light gray, light brown, slightly moist, dense, some gravel Surface: Asphalt Size: 8 Inch Diameter Drill Method: Hollow-Stem Auger Drill Rig Elevation: 784 Feet	772.0	12									
769.0 15 SandySilt_gray-brown, moist_firm, some clay R 17 22.6 94.1 79.3 768.0 16 R 17 22.6 94.1 79.3 768.0 17 R 17 22.6 94.1 79.3 767.0 17 R 14 14 14 14 14 766.0 18 R 20 27.7 83.6 75.2 763.0 21 Sandy Silt/Silty Sand, light gray, light brown, slightly moist, dense, some R 20 27.7 83.6 75.2 761.0 23 R 20 27.7 83.6 75.2 760.0 24 R 20 27.7 83.6 75.2 761.0 23 R 20 27.7 83.6 75.2 760.0 24 R 20 14 14 14 769.0 25 R 16 14 14	771.0	13-									
768.0 16 767.0 17 766.0 18 766.0 18 766.0 19 766.0 19 766.0 19 767.0 17 768.0 18 766.0 18 767.0 17 766.0 18 767.0 17 768.0 20 ALLUVIUM: Sandy Sil/Silly Sand, light gray, light brown, slightly moist, dense, some gravel 761.0 23 761.0 23 766.0 24 759.0 25 Surface: Asphalt Size: 8 Inch Diameter Drill Method; Hollow-Stem Auger Drill Rig Elevation: 784 Feet	770.0	14									
767.0 17 766.0 18 765.0 19 764.0 20 ALLUVIUM: Sandy Silt/Silty Sand, light gray, light brown, slightly moist, dense, some gravel R 20 27.7 83.6 75.2 763.0 21 Sandy Silt/Silty Sand, light gray, light brown, slightly moist, dense, some gravel R 20 27.7 83.6 75.2 761.0 23 Surface: Asphalt Size: 8 Inch Diameter Drill Method: Hollow-Stem Auger Drill Rig Elevation; 784 Feet	769.0	15	SandySilt, gray-brown, moist, firm, some clay	×		R	17	22.6	94.1	79.3	
766.0 18 765.0 19 764.0 20 ALLUVIUM: Sandy Silt/Silty Sand, light gray, light brown, slightly moist, dense, some gravel R 20 27.7 83.6 75.2 763.0 21 Sandy Silt/Silty Sand, light gray, light brown, slightly moist, dense, some gravel R 20 27.7 83.6 75.2 761.0 23 R 24 R R 20 27.7 83.6 75.2 761.0 23 R 24 R R 20 27.7 83.6 75.2 761.0 23 R	768.0	16					1				
765.0 19 764.0 20 763.0 21 Sandy Sil/Silty Sand, light gray, light brown, slightly moist, dense, some gravel R 762.0 22 761.0 23 760.0 24 765.0 24 765.0 24 761.0 25 Surface: Asphalt Size: 8 Inch Diameter Drill Method: Hollow-Stem Auger Drill Rig Elevation: 784 Feet	767.0	17 -									
764.0 20 ALLUVIUM: Sandy Sit/Sity Sand, light gray, light brown, slightly moist, dense, some gravel R 20 27.7 83.6 75.2 763.0 21 gravel R 20 27.7 83.6 75.2 761.0 23 760.0 24 R 24 R	766.0	18									
Sandy Silt/Silty Sand, light gray, light brown, slightly moist, dense, some 763.0 21 762.0 22 761.0 23 760.0 24 759.0 25 Surface: Asphalt Size: 8 Inch Diameter Drill Method: Hollow-Stem Auger Drill Rig Elevation: 784 Feet	765.0	19									
763.0 21 gravel 762.0 22 761.0 23 760.0 24 769.0 25 Surface: Asphalt Size: 8 Inch Diameter Drill Method: Hollow-Stem Auger Drill Rig Elevation: 784 Feet	764.0	20 1	ALLUVIUM:			R	20	27.7	83.6	75.2	
761.0 23 760.0 24 759.0 25 Surface: Asphalt Size: 8 Inch Diameter Drill Method: Hollow-Stem Auger Drill Rig Elevation: 784 Feet	763.0	21	Sandy Silt/Silty Sand, light gray, light brown, slightly moist, dense, some gravel	× × ×							
760.0 24 759.0 25 Surface: Asphalt Size: 8 Inch Diameter Drill Method: Hollow-Stem Auger Drill Rig Elevation: 784 Feet	762.0	22		X X							
759.0 25 Surface: Asphalt Size: 8 Inch Diameter Drill Method: Hollow-Stem Auger Drill Rig Elevation: 784 Feet	761.0	23		× × ×							
Surface: AsphaltSize: 8 Inch DiameterDrill Method: Hollow-Stem Auger Drill RigElevation: 784 Feet	760.0	24		× × ×							
Drill Method: Hollow-Stem Auger Drill Rig Elevation: 784 Feet	759.0	25		× × ×							
	Surfac	Surface: Asphalt Size: 8 Inch Diameter									
Drill Date: December 22, 2005 Sheet: 1 of 2	Drill N	lethod	: Hollow-Stem Auger Drill Rig	1	Eleva	tion:	784 F	eet			
	Drill D	ate: D	ecember 22, 2005		Shee	t: 1 of	2				

Log of Boring: 18

Client: THE BUCKLEY SCHOOL

Logged By: JET

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

		SUBSURFACE PROFILE				SA	MPLE			
Elevation	Depth	Description	Symbol	uscs	Type	Blow Count	Moisture Content (%)	Dry Density	% Saturation	Remarks
1		Silty Sand, gray, slightly moist, dense, some gravel	*		5		00.0	0.1.5	00.0	
758.0-	26		× × × ×		R	44	26.3	94.5	93.0	
757.0	27		* * * 2							
756.0	28		× *							
755.0	29		* * *							
754.0	30	Gravelly Sand, tan, gray, slightly moist, dense, rock fragments to 4	×		R	51	15.8	89.6	49.5	
753.0	31	inches	0 12 (G							
752.0	32		0 ° 8 7							
751.0	33		5 4 0 0 4 0 4 0 4 0 4 0 4 0 4 0 4 0 4 0							
750.0	34		10 0 0 0 0 0							
749.0	35	Sandy Gravel, gray-brown, gray, tan, slightly moist to dry, dense to very	6 4 D		R	71	13.8	99.8	55.5	
748.0	36	dense	5.0							
747.0	37		4 0 5 3 9							
746.0	38		4 0 5							
745.0	39	BEDROCK: Siltstone, Claystone, tan, light gray, soft to moderately hard, thinly bedded			R	21	33.8	85.9	97.0	
744.0	40									
743.0	41									
742.0	42 +	Refusal at 42 Feet; No Water; Fill to 20 Feet.								
741.0	43									
740.0	44									
739.0	45									
738.0	46									
737.0	47 -									
736.0	48									
735.0	49									
	<u>50</u>	phalt		Size:	8 Incl	n Diar	neter			
		1: Hollow-Stem Auger Drill Rig		Eleva						
		December 22, 2005		Shee						

Log of Boring: 19

Client: THE BUCKLEY SCHOOL

Logged By: JET

The J. Byer Group, Inc. 1461 E. Chevy Chase Dr., Ste 200 Glendale, CA. 91206 (818) 549-9959

	·····	SUBSURFACE PROFILE		SAMPLE										
Elevation	Depth	Description	Symbol	uscs	Type	Blow Count	Moisture Content (%)	Dry Density	% Saturation	Remarks				
111	=	FILL: Silty Sand, dark brown, slightly moist to moist	\otimes											
790.0	1-					-								
789.0	2		\otimes											
788.0														
	-													
787.0	4-													
786.0	5-				R	21	13.2	112.0						
785.0	6													
784.0	7		\otimes				÷							
783.0	8													
782.0	9													
781.0	10	End of 4DEach No Mistor Fill to Total Danth	X											
780.0	-	End at 10Feet; No Water; Fill to Total Depth Unable to Continue Due to Utility Line												
779.0	-													
778.0	-													
777.0	1													
776.0	1													
775.0-	16													
774.0	17													
773.0	18													
772.0	19													
771.0	20-													
770.0	21													
769.0	1													
768.0	1													
767.0	7													
, -	1													
766.0	766.0 - 25 - Surface: Asphalt Size: 8 Inch Diameter													
	Drill Method: Hollow-Stem Auger Drill Rig													
		December 22, 2005	Elevation: 791 Feet Sheet: 1 of 1											

VAN NUYS 7.5 MINUTE QUADRANGLE AND PORTIONS OF ADJACENT QUADRANGLES

10% EXCEEDANCE IN 50 YEARS PEAK GROUND ACCELERATION (g)

1998 **ALLUVIUM CONDITIONS**



Figure 3.3

Kilometers




VAN NUYS 7.5 MINUTE QUADRANGLE AND PORTIONS OF ADJACENT QUADRANGLES

10% EXCEEDANCE IN 50 YEARS PEAK GROUND ACCELERATION

1998

PREDOMINANT EARTHQUAKE Magnitude (Mw) (Distance (km))



EQFAULT SUMMARY

DETERMINISTIC SITE PARAMETERS

	APPROX		ESTIMATED	MAX. EARTHQ	UAKE EVENI
ABBREVIATED FAULT NAME	DIST. mi 	ANCE (km)	MAXIMUM EARTHQUAKE MAG.(Mw)	ACCEL. g	
HOLLYWOOD		6.8)		0.437	•
SANTA MONICA	4.4(7.1)	6.6	0.455	X
NEWPORT-INGLEWOOD (L.A.Basin)	8.6(6.9	0.278	IX
MALIBU COAST	8.9(14.4)	6.7	0.290	IX
NORTHRIDGE (E. Oak Ridge)	9.0(14.5)	6.9 6.7	0.365	IX
VERDUGO	9.3(15.0)	6.7		IX
SIERRA MADRE (San Fernando)	12.7(12.7(20.5)	6.7 6.5		VIII
RAYMOND	12.7(20.5)	6.5		I VIII
PALOS VERDES	13.4(21.6) 22.4)	7.1		i VIII
	13.9(22.4)	6.6		I VIII
COMPTON THRUST		22.7)			IX
SIERRA MADRE	14.2(22.8)	7.0		IX
SAN GABRIEL	15.5(25.0)	7.0	0.168	VIII
ELYSIAN PARK THRUST	14.2(15.5(16.2(17.6(26.1)	6.7		VIII
ANACAPA-DUME	17.6(28.3)	7.3	0.215	•
HOLSER	19.0(23.1(30.5)	6.5	0.112	VII
DAK RIDGE (Onshore)	23.1(37.1)	6.9		VII
SIMI-SANTA ROSA	23.4(37.6)	6.7		VII
CLAMSHELL-SAWPIT	24.0(38.7)	6.5		I VII
WHITTIER	26.7(42.9)	6.8		I VII
SAN CAYETANO	26.7(45.9)	6.8	0.085	VII
SAN 005E	32.0(52.5/	0.5	0.057	
SAN ANDREAS - Mojave	33.7(54.3)	7.1		I VII
SAN ANDREAS - 1857 Rupture	33.7(54.3)			VII
CHINO-CENTRAL AVE. (Elsínore)	38.8(62.5)	6.7 1	0.053	VI
CUCAMONGA	38.8(62.5)	7.0	0.067	I VI
	39.0(40.1(VI VI
				0.054	
/ENTURA - PITAS POINT DAK RIDGE(Blind Thrust Offshore)	42.6(0.051 0.057	VI
CHANNEL IS. THRUST (Eastern)	40.0(76 21	7.4	0.081	VI VII
1.RIDGE-ARROYO PARIDA-SANTA ANA	47.3(70.2/1	6.7	0.040	
1.RIDGE-ARROIO PARIDA-SANIA ANA 10NTALVO-OAK RIDGE TREND	48.3(VI
NEWPORT-INGLEWOOD (Offshore)		78.1)			V I V
LISINORE-GLEN IVY		80.8)		0.039	
RED MOUNTAIN		84.0)	6.8	0.039	v
	53.7(86 411	6.8 7.3	0.047	
SAN ANDREAS - San Bernardino	53.7(86.41	7.4	0.051	VI
SAN JACINTO-SAN BERNARDINO	54.0(86 911	7.4 6.7	0.029	V I V
GARLOCK (West)	54.1(v

DETERMINISTIC SITE PARAMETERS

Page 2

	דעסממא		ESTIMATED MAX. EARTHQUAKE EVENT			
ABBREVIATED FAULT NAME			EARTHQUAKE	SITE ACCEL. g	MOD . MERC.	
			7.2		1	
BIG PINE	56.8(91.4)	6.7	0.027	l V	
				0.023	•	
			6.8	0.031		
	•		7.4	0.038	•	
NORTH FRONTAL FAULT ZONE (West)				0.032	, · · ·	
	69.0(3			0.038	l V	
SAN JACINTO-SAN JACINTO VALLEY				0.024		
	71.5(1			0.022	IV	
SANTA YNEZ (West)	72.1(1	116.1)	6.9	0.023		
NORTH CHANNEL SLOPE	72.2(1	116.2)	7.1		v	
			7.1	0.025		
				0.027		
LENWOOD-LOCKHART-OLD WOMAN SPRGS	83.7(1	134.7)	7.3	0.026		
SANTA ROSA ISLAND			6.9	0.023		
			6.9	0.017	•	
			7.2	0.022	•	
NORTH FRONTAL FAULT ZONE (East)				0.017	•	
			6.9	0.016	•	
			7.1	0.018		
PINTO MOUNTAIN	98.6(1	158.7)	7.0	0.017	•	
			7.1	0.022	IV	
LOS ALAMOS-W. BASELINE ************************************	99.4(1	160.0)	6.8	0.017	IV	

-END OF SEARCH- 63 FAULTS FOUND WITHIN THE SPECIFIED SEARCH RADIUS.

THE HOLLYWOOD FAULT IS CLOSEST TO THE SITE. IT IS ABOUT 4.2 MILES (6.8 km) AWAY.

LARGEST MAXIMUM-EARTHQUAKE SITE ACCELERATION: 0.4554 g

.

****** * ****** + + * * * * * * * * * * TSTAB slope stability analysis * * Revision 2.52 - 01/06/86 * * * * * * ______ * * * * * * TAGA Engineering Software Services * * * * Berkeley, California USA + + * * * * * * IBM PC & 8086/8088 MS-DOS Version by * * * * * * Design Professionals Management Systems * * * * * * Kirkland, Washington USA * * * * * * * * copyright (c) 1983,84,85 TAGA * * * * copyright (c) 1983,84,85 DPMS * * * * ****** CALCULATE THE GROSS STABILITY OF SECTION I ********** ANALYSIS BY BISHOP'S SIMPLIFIED METHOD ***** INPUT DATA ***** CONTROL DATA, AUTOMATIC SEARCH FOR CRITICAL CIRCLE NUMBER OF DEPTH LIMITING TANGENTS 0 NUMBER OF VERTICAL SECTIONS 16 NUMBER OF SOIL LAYER BOUNDARIES 2 NUMBER OF POINTS DEFINING COHESION PROFILE 0 NUMBER OF CURVES DEFINING COHESION ANISOTROPY 0 NUMBER OF BOUNDARY LINE LOADS 0 NUMBER OF BOUNDARY PRESSURE LOADS 0 SEISMIC COEFFICIENT = .000 ATMOSPHERIC PRESSURE = 2116.000 UNIT WEIGHT OF WATER = 62.400 UNIT WEIGHT OF WATER IN TENSION CRACK = 62.400 SEARCH STARTS AT CENTER (600.0, -1400.0), WITH FINAL GRID OF 25.0 ALL CIRCLES PASS THROUGH THE POINT (585.0, -775.0)

GEOMETRY

JECTIONS	-1000.00	15.00	50.00	72.00	160.00	210.00	246.00	280.00
T. CRACKS W IN CRACK BOUNDARY 1 BOUNDARY 2	-1050.00	-1050.00 -1050.00	-1053.00		-1025.00	-1000.00	-975.00 -975.00 -975.00 .00	-950.00 -950.00 -950.00 .00
SECTIONS	320.00	368.00	405.00	465.00	510.00	554.00	585.00	602.00
T. CRACKS W IN CRACK BOUNDARY 1 BOUNDARY 2	-925.00 -925.00 -925.00 .00	-900.00 -900.00 -900.00 .00	-875.00 -875.00 -875.00 .00	-850.00 -850.00 -850.00 .00	-825.00 -825.00 -825.00 .00	-800.00 -800.00 -800.00 .00	-775.00 -775.00 -775.00 .00	-770.00 -770.00 -770.00 .00

SOIL PROPERTIES

LAYER 1	DENSITY 105.00	COHESION 951.00	FRICTION ANGLE 30.00	DELTA PHI .00
*********** RESULTS ********				
NUMBER TANGE	NT RADIUS	(X) CENT	FER (Y) CENTER	F.S.
$ \begin{array}{cccccccccccccccccccccccccccccccccccc$	625.2 626.0 675.2 628.4 575.2 625.1 650.2 626.3 600.2 650.1 675.2 651.2 675.1 676.2	600.0 550.0 600.0 650.0 600.0 625.0 600.0 575.0 600.0 625.0 625.0 625.0 625.0 625.0	$\begin{array}{cccc} -1400.0 \\ -1450.0 \\ -1450.0 \\ -1400.0 \\ -1350.0 \\ -1400.0 \\ -1425.0 \\ -1400.0 \\ -1425.0 \\ -1425.0 \\ -1425.0 \\ -1425.0 \\ -1425.0 \\ -1450.$	1.549 1.577 1.549 1.608 1.561 1.554 1.548 1.563 1.553 1.558 1.549 1.554 1.554 1.566 1.550

F.S. MINIMUM= 1.548 FOR THE CIRCLE OF CENTER (600.0, -1425.0)

+ + +

ŧ

+

+

* +

+ +

++

+

_

XXXXX000000 OXXXXXXXXXXXXX OOXXXXXXXXXXXXXXX OOXXXXXXXXXXXXXXX 000XXXXXXXXXXXXX000 OXXXXXXXXXXXXXXXXX 000XXXXXXXXXXXXXXXX000 000XXXXXXXXXXXXXX000 OXXXXXXXXXXXXXXXXXXOOOO 000XXXXXXXXXXXXXXXXXXXXX OOXXXXXXXXXXXXXXXXXXXXXXXXXXXX 000XXXXXXXXXXXXXXXXXXXXX000 0000XXXXXXXXXXXXXXXXXXXXX0000 0 00000XXXXXXXXXXXXXXXXXXXXXXX0000 0 0000XXXXXXXXXXXXXXXXXXXXXX 0 000XXXXXXXXXXXXXXXXX000 0 0 0 0 000000000000 0 0

******** * * * * * * * * * * * * TSTAB slope stability analysis * * * * Revision 2.52 - 01/06/86 * * * * * * * * * * TAGA Engineering Software Services * * * * Berkeley, California USA * * * * * * * * IBM PC & 8086/8088 MS-DOS Version by * * * * * * Design Professionals Management Systems * * * * Kirkland, Washington USA * * * * * * * * copyright (c) 1983,84,85 TAGA * * * * copyright (c) 1983,84,85 DPMS * * * * * * CALCULATE THE SEISMIC STABILITY OF SECTION I ANALYSIS BY BISHOP'S SIMPLIFIED METHOD **************** **** INPUT DATA **** CONTROL DATA, AUTOMATIC SEARCH FOR CRITICAL CIRCLE NUMBER OF DEPTH LIMITING TANGENTS 0 NUMBER OF VERTICAL SECTIONS 16 NUMBER OF SOIL LAYER BOUNDARIES 2 NUMBER OF POINTS DEFINING COHESION PROFILE 0 NUMBER OF CURVES DEFINING COHESION ANISOTROPY 0 NUMBER OF BOUNDARY LINE LOADS 0 NUMBER OF BOUNDARY PRESSURE LOADS 0 .150 SEISMIC COEFFICIENT === 2116.000 ATMOSPHERIC PRESSURE -----62.400 UNIT WEIGHT OF WATER = UNIT WEIGHT OF WATER IN TENSION CRACK = 62.400 SEARCH STARTS AT CENTER (600.0,-1400.0), WITH FINAL GRID OF 25.0 ALL CIRCLES PASS THROUGH THE POINT (585.0, -775.0)

GEOMETRY

ACTIONS	-1000.00	15.00	50.00	72.00	160.00	210.00	246.00	280.00
T. CRACKS W IN CRACK BOUNDARY 1 BOUNDARY 2	-1050.00		-1053.00	-1050.00	-1025.00	-1000.00	-975.00 -975.00 -975.00 .00	-950.00 -950.00 -950.00 .00
SECTIONS	320.00	368.00	405.00	465.00	510.00	554.00	585.00	602.00
T. CRACKS W IN CRACK BOUNDARY 1 BOUNDARY 2	-925.00 -925.00 -925.00 .00	-900.00 -900.00 -900.00 .00	-875.00 -875.00 -875.00 .00	-850.00 -850.00 -850.00 .00	-825.00 -825.00 -825.00 .00	-800.00 -800.00 -800.00 .00	-775.00 -775.00 -775.00 .00	-770.00 -770.00 -770.00 .00


SOIL PROPERTIES

LAYER	DENSITY	COHESION	FRICTION ANGLE	DELTA PHI
1	105.00	951.00	30.00	.00


RESULTS


NUMBER	TANGENT	RADIUS	(X) CENTER	(Y) CENTER	F.S.
7	-774.8	625.2	600 0	-1400.0	1 1 5 7
1			600.0		1.157
2	-774.0	626.0	550.0	-1400.0	1.168
3	-774.8	675.2	600.0	-1450.0	1.152
4	-771.6	628.4	650.0	-1400.0	1.209
5	-774.8	575.2	600.0	-1350.0	1.172
6	-774.9	675.1	575.0	-1450.0	1.158
7	-774.8	700.2	600.0	-1475.0	1.151
8	-773.8	676.2	625.0	-1450.0	1.157
9	-774.8	650.2	600.0	-1425.0	1.154
10	-774.9	700.1	575.0	-1475.0	1.162
11	-774.8	725.2	600.0	-1500.0	1.153
12	-773.9	701.1	625.0	-1475.0	1.153
13	-774.9	725.1	575.0	-1500.0	1.168
14	-773.9	726.1	625.0	-1500.0	1.150
15	-773.8	676.2	625.0	-1450.0	1.157
16	-774.9	675.1	575.0	-1450.0	1.158
17	-773.9	751.1	625.0	-1525.0	1.149
18	-772.1	727.9	650.0	-1500.0	1.160
19	-774.9	750.1	600.0	-1525.0	1.157
	-774.0	776.0	625.0	-1550.0	1.151
	-772.2	752.8	650.0	-1525.0	1.155
	-774.9	775.1	600.0	-1550.0	1.162
	-772.3	777.7	650.0	-1550.0	1.152
	-772.1	727.9	650.0	-1500.0	1.160
	-774.8	725.2	600.0	-1500.0	1.153


F.S. MINIMUM= 1.149 FOR THE CIRCLE OF CENTER (625.0, -1525.0)



OXXXXXXXXXXXXXX0000 00XXXXXXXXXXXXXXX000 00XXXXXXXXXXXXXXXXX000 000XXXXXXXXXXXXXXX000 00XXXXXXXXXXXXXXX00 OXXXXXXXXXXXXXXXXXXX OXXXXXXXXXXXXXXXXX 0000XXXXXXXXXXXXXXXXX0000 0XXXXXXXXXXXXXXXXXXXXXXX0000 0XXXXXXXXXXXXXXXXXXXXXXXXX 00000XXXXXXXXXXXXXXXXXXX0000 000XXXXXXXXXXXXXXXXXXXXX OOXXXXXXXXXXXXXXXXXXXXXXXXXXX 000XXXXXXXXXXXXXXXXXXXX000 000XXXXXXXXXXXXXXXXXXXXX 000000XXXXXXXXXXXXXXXXXXXXXXX000 0 00XXXXXXXXXXXXXXXXX000 0 0000XXXXXXXXXXXXXXX0000 0 000000XXXXXXXXXXXXXXXX0000 00 0 0 00000000









RETAINING WALL

JB: <u>19376-B</u> CONSULTANT: <u>JET</u> CLIENT: <u>BUCKLEY SCHOOL</u>

CALCULATION SHEET # 8

CALCULATE THE DESIGN MINIMUM EQUIVALENT FLUID PRESSURE (EFP) FOR PROPOSED RETAINING WALL SUPPORTING BEDROCK. ASSUME BACKFILL IS SATURATED AND THERE IS NO HYDROSTATIC PRESURE THE RETAINED HEIGHT AND BACKSLOPE AND SURCHARGE CONDITIONS ARE LISTED BELOW. USE THE MONONOBE-OKABE METHOD FOR SEISMIC FORCES.

CALCULATION PARAMETERS

EARTH MATERIAL:	FILL	WALL HEIGHT		25 feet
SHEAR DIAGRAM:	1	BACKSLOPE ANGLE	:	0 degrees
COHESION:	255 psf	SURCHARGE:		0 pounds
PHI ANGLE:	27.5 degrees	SURCHARGE TYPE:		U Uniform
DENSITY	120 pcf	INITIAL FAILURE AN	GLE:	22 degrees
SAFETY FACTOR:	1.5	FINAL FAILURE ANG	GLE:	70 degrees
WALL FRICTION	0 degrees	INITIAL TENSION CF	RACK:	3 feet
CD (C/FS):	170.0 psf	FINAL TENSION CR/	ACK:	50 feet
PHID = ATAN(TAN(PI	HI)/FS) = 1	19.1 degrees		
HORIZONTAL PSEUE	DO STATIC SEISMIC CO	EFFICIENT (k _h)	0 %g	
VERTICAL PSEUDO	STATIC SEISMIC COEFF	ICIENT (k _v)	0 %g	

CALCULATED RESULTS	
CRITICAL FAILURE ANGLE	55 degrees
AREA OF TRIAL FAILURE WEDGE	214.3 square feet
TOTAL EXTERNAL SURCHARGE	0.0 pounds
WEIGHT OF TRIAL FAILURE WEDGE	25720.0 pounds
NUMBER OF TRIAL WEDGES ANALYZED	2352 trials
LÉNGTH OF FAILURE PLANE	26.2 feet
DEPTH OF TENSION CRACK	3.6 feet
HORIZONTAL DISTANCE TO UPSLOPE TENSION CRACK	15.0 feet
CALCULATED HORIZONTAL THRUST ON WALL	13409.0 pounds
CALCULATED EQUIVALENT FLUID PRESSURE	42.9 pcf
DESIGN EQUIVALENT FLUID PRESSURE	43.0 pcf

THE CALCULATION INDICATES THAT THE PROPOSED RETAINING WALL MAY BE DESIGNED FOR AN EQUIVALENT FLUID PRESSURE OF 43 POUNDS PER CUBIC FOOT.



SHORING PILE

JB: <u>19376-B</u> CONSULT: <u>JET</u> CLIENT: <u>BUCKLEY SCHOOL</u>

CALCULATION SHEET # 9

CALCULATE THE DESIGN MINIMUM EQUIVALENT FLUID PRESSURE (EFP) FOR PROPOSED SHORING PILES. THE RETAINING HEIGHT AND BACKSLOPE AND SURCHARGE CONDITIONS ARE LISTED BELOW. ASSUME THE BACKFILLL IS SATURATED WITH NO EXCESS HYDROSTATIC PRESSURE. USE THE MONONOBE-OKABE METHOD FOR SEISMIC FORCES.

CALCULATION PARAMETERS

EARTH MATERIAL:	FILL	RETAINED LENGTH	20	feet
SHEAR DIAGRAM:	1	BACKSLOPE ANGLE:	0	degrees
COHESION:	255 psf	SURCHARGE:	0	pounds
PHI ANGLE:	27.5 degrees	SURCHARGE TYPE:	U	Uniform
DENSITY	123 pcf	INITIAL FAILURE ANGLE:	30	degrees
SAFETY FACTOR:	1.5	FINAL FAILURE ANGLE:	70	degrees
PILE FRICTION	0 degrees	INITIAL TENSION CRACK:	2	feet
CD (C/FS):	170.0 psf	FINAL TENSION CRACK:	40	feet
PHID = ATAN(TAN(PHI	I)/FS) = 19.1	degrees		
HORIZONTAL PSEUDO	O STATIC SEISMIC COEFF	ICIENT (k _b)	0 %g	
VERTICAL PSEUDO S	TATIC SEISMIC COEFFICIE	ENT (k _v)	0 %g	

CALCULATED RESULTS		
CRITICAL FAILURE ANGLE	55	degrees
AREA OF TRIAL FAILURE WEDGE	133.6	square feet
TOTAL EXTERNAL SURCHARGE	0.0	pounds
WEIGHT OF TRIAL FAILURE WEDGE	16432.4	pounds
NUMBER OF TRIAL WEDGES ANALYZED	1599	trials
LENGTH OF FAILURE PLANE	19.2	feet
DEPTH OF TENSION CRACK	4.3	feet
HORIZONTAL DISTANCE TO UPSLOPE TENSION CRACK	11.0	feet
CALCULATED THRUST ON PILE	8077.6	pounds
CALCULATED EQUIVALENT FLUID PRESSURE	40.4	pcf
DESIGN EQUIVALENT FLUID PRESSURE	43.0	pcf

THE CALCULATION INDICATES THAT THE PROPOSED SHORING PILES MAY BE DESIGNED FOR AN EQUIVALENT FLUID PRESSURE OF 43 POUNDS PER CUBIC FOOT. THE FLUID PRESSURE SHOULD BE MULTIPLIED BY THE PILE SPACING.

APPENDIX II - PREVIOUS WORK

GeoSoils Geotechnical Investigation, prepared by GeoSoils, Inc., dated March 24, 1994 (20 Pages)

LADBS Letter, dated June 20, 1994 (3 Pages)

Converse Compaction Report - Administration Building, dated August 7, 1972, with LADBS Letter (7 Pages)

Converse - Report on Compacted Fill - Classrooms, dated August 14, 1972, with LADBS Letter (8 Pages)

Converse - Report on Field Density Tests - Blanket Fill Slope - Proposed Athletic Field, dated May 24, 1971, with LADBS Letter (7 Pages)

Converse - Report on Compacted Fill - Proposed Library, dated September 25, 1972, with LADBS Letter (9 Pages)

Converse - Final on Pavilion With Map, dated June 8, 1977, with LADBS Letter (12 Pages)


Converse - Report on Compacted Fill - Maintenance Building, dated December 13, 1972 (8 Pages)

Advanced Foundation Engineering - Soil Compaction Tests - Progress Report, dated February 16, 1968 (5 Pages)

Advanced Foundation Engineering - Soil Compaction Tests - Progress Report No. 2, dated April 4, 1968 (8 Pages)

Advanced Foundation Engineering - Soil Compaction Tests - Final Report, dated April 12, 1968, with LADBS Letter (6 Pages)

3605 UNBOUND COPY FOR SUBMITTAL TO CITY



. Solding and the second second second

MAY 2 4 1994

DEPARTMENT OF BUILDING & SAFETY VAN NUYS DISTRICT OFFICE GRADING DIVISION

and the second sec

GEOTECHNICAL INVESTIGATION of Elementary School Building 3900 Stansbury Avenue Portion of Lot 1, Tract 23823 Sherman Oaks, California

for

The Buckley School

W.O. 4213-VN March 24, 1994

March 24, 1994 W.O. 4213-VN

حت

The Buckley School 3900 Stansbury Avenue Sherman Oaks, California 91413-5949

Subject:

Geotechnical Investigation of Elementary School Building 3900 Stansbury Avenue, Portion of Lot 1. Tract 23823 Sherman Oaks, California

Gentlemen:

As requested, GeoSoils, Inc., has completed a geotechnical engineering study to evaluate each materials present below one of the elementary school buildings. The building was damaged by the January 17, 1994, earthquake. The following tasks were completed as a part of this geotechnical evaluation:

- 1. Reviewing prior geotechnical reports pertaining to the site. The reports that were reviewed are referenced.
- 2. Completing a floor level manometer survey to assess damage to the structure. The results of the manometer survey are included in this report as Plate 3.
- 3. Excavation, logging and sampling of five exploratory borings with a limited access drill rig. Logs of the borings are included as Plates A-1 through A-7. The approximate locations of the borings are shown on the enclosed Boring Location Map, Plate 1. Subsurface interpretations of the earth materials are shown on the Cross-Sections, Plate 2.
- 4. Laboratory testing of earth materials sampled from the excavations. The results of the laboratory testing are summarized in Appendix A.

Page 2 March 24:01994 W O. 4213-VN

1.

5. Engineering analyses of the data and preparation of this report.

「「「「「「「」」」

. 1

Burger - States and a

- 私政 いうまた 宇宙学校 一時間 日本社

SITE LOCATION

The Buckley school is located at the southern terminus of Stansbury Avenue in Sherman Oaks. The school grounds are located in a north/south trending canyon area, which has been modified by mass grading in the past. The subject elementary school building is the first structure on the west side, as you enter the school grounds from Stansbury Avenue.

SITE DESCRIPTION

The subject elementary school building is a single-story, wood frame, slab-on-grade structure. A 12 to 21-foot high, 2:1 gradient manufactured fill slope, descends from the east side of the building site down to the main parking lot. The building is located within five feet of the top of the east-facing fill slope. There is a playground area along the north side of the building. A $15\pm$ foot, 2:1 gradient manufactured fill slope descends towards the north below the playground area. There is a block fence located immediately along the top of the fill slope that descends east and north from the playground. Additional structures and an asphalt court area are located at the same grade as the subject building south and west of it.

SITE HISTORY

Preliminary geotechnical studies for the elementary school were completed in 1967 by Advanced Foundation Engineering Incorporated. At the time of that investigation, a graded pad had already existed at the present location of the elementary school. The original graded pad was approximately ten feet lower in elevation than the current pad. Borings excavated in the vicinity of the subject elementary school building indicated that the pad was underlain by artificial fill, natural soil and bedrock. The report recommended removal of old fill and unsuitable natural ground prior to placement of additional fill.

Final reports of grading for the elementary school site were completed by Advanced Foundation Engineering, Inc., in 1968. The reports indicate that a non-structural and a structural fill were placed

Page 3 March 24, 1994 W.O. 4213-VN

- 3

٢

دند

as a part of the grading. The limits of the structural and non-structural fill are shown on Plate 1. The report indicates that all structural fill was placed on natural soil and compacted to 90 percent relative density. Based upon our interpretations, removals of existing materials were made prior to the placement of the fill. The non-structural fill was placed directly on top of existing ground without any removal of existing material.

EARTH MATERIALS

Based upon our interpretations of the referenced materials and our observations made during this investigation, it appears that the subject building is underlain by compacted fill, natural soil and bedrock.

Compacted Fill: (Caf(s))

The entire structure is underlain by compacted fill materials. Depth of compacted fill observed in the borings ranged from 15 to 30 feet in thickness. The fill is comprised predominately of a mixture of silt and clay, with some sand and rock fragments. Final reports of grading indicate that in addition to reuse of on-site materials, additional fill materials were also imported to the site.

Natural Soil/Alluvium

Observations made in the borings indicate that the compacted fill materials were placed on top of natural soil/alluvium. The thickness of the aliuvium ranged from 5 to 16 feet in the borings. The natural soil consisted of a mixture of clay, silt and fine sand with scattered rock fragments. Caliche stringers were observed within the natural soil.

Bedrock (Tm):

Bedrock was encountered in all 5 test borings at depths between 20 and 40.5 feet below existing ground surface. The bedrock consist of interbedded diatomaceous siltstones and sandstones.

Page 4 March 24, 1994 W.O. 4213-VN

OBSERVED DISTRESS

The manometer survey indicates that a maximum differential of 6.2 inches exist across the floor slab within the building. The survey suggest that settlement has occurred along the portion of the structure closest to the descending fill slope. Distress to door jambs and windows indicate settlement on the east side of the building. Where floor coverings were removed, several cracks were observed in the floor slab.

In the playground area, on the north side of the building, an open ground fissure traverses in an north/south direction across the playground. The block fence located along the top of the descending fill slope, adjacent to the playground area, was observed to be severely damaged.

CONCLUSIONS

÷.

ļ.

A. AND SEA COLORDON TO AN ADDRESS

が、通知語

The results of the manometer survey indicates a high point at the southwesterly portion of the structure (elevation of +1.4 inches), and a low point at the northeasterly portion of the structure (elevation of -4.6 inches). The northwesterly portion has a manometer elevation of -0.2 inches, while the southeasterly portion has a manometer elevation of -0.2 inches, while the southeasterly portion has a manometer elevation of -2.0 inches. The manometer data tollows the trend of increasing thickness of fill and alluvial material. The thicker the fill and alluvial material, the greater the settlement.

Page 5 March 24, 1994 W.O. 4213-VN

ائى ا

The header of the street

State & Later

The following factors may have contributed to the distress of the structure.

1. Loose Compacted Fill and Alluvium

Our laboratory density tests (see Table I), indicates that the on-site soil materials are loose and has a range of relative compaction of 71 to 86 percent (fill), and 76 to 89 percent (alluvium). It should be noted that the standard of compaction during 1968, when the fill was processed, was lower than todays standard.

The loosely compacted material and the alluvium, which have high consolidation potential, is a major factor which caused the distress of the foundation pad.

2. Creep and/or Settlement of Adjacent Descending Slope

The adjacent toe of the descending fill slope is founded within the designated non-structural fill, i.e., the fill slope toe was placed directly on top of the original ground without any removal (reprocessing) of loose soil material. Settlement of the loose original ground will cause settlement and lateral movement (creep) of the fill slope above. We anticipate that settlement and creep of the adjacent fill slope may have also been a contributing factor to the distress of the foundation pad above.

3. Earthquake Shaking

We suspect that the vibrations ad lateral movement (shaking) generated during the recent January 17, 1994 earthquake, may have increased and/or hastened local consolidation settlement of the loose fill and alluvium material, causing the building pad to undergo additional differential settlement.

RECOMMENDATIONS

The following can be used for remedial repair of the distressed foundation and pad; 1) soil improvement, and 2) remedial underpinning.

Page 6 / March 24, 1994 W.O. 4213-VN

1. Soil Improvement

Soil improvement is the collective term for any physical, chemical, or biological method, or any combination of such methods, employed to improve certain properties of a natural or fill soil to make it serve adequately and intended for engineering purposes. For this particular site; compaction grouting, chemical grouting, slurry grouting, and lime injection may be considered to densify and strengthen the site soil, and therefore, reduce the future settlement. However, it is our opinion that grouting will not be effective due to the low permeability of some layers of the soil deposit, i.e., layers of silt and clay material. A reliable company experience with the above methods should be consulted.

Remedial UnderLinning

Underpinning structures involves the introduction of additional support to the foundation of a structure to deepen or increase its bearing capacity. If done because the foundation is inadequate, it is called remedial underpinning.

Based upon our evaluation, remedial underpinning such as cast-in-place piles or caissons, chance anchors, mini-piles or the perma-jack system, will be the most effective method to reduce the future settlement. Reference materials of chance anchors, mini-piles and the perma-jack system are presented in Appendix B. Companies experienced with the above underpinning methods should be consulted. Recommendations for cast-in-place piles or caissons are presented in Appendix C.

3. Potential Future Distress of Slab-On-Grade

The remedial underpinning can stabilize the wall frames of the building and has less effect on the slab-on-grade unless the slab is rigidly tied with the wall frames. If the slab-on-grade is not tied with the frame, it may have future distress even after the building load is transferred to the subsurface competent layer. However, after the installation of underpinning structures, the building load will be transmitted to the subsurface competent layer, and the near surface soil in proximity to the underpinning structures will not be subjected to vertical dead load except that from slab-on-

Page 7 March 24, 1994 W.O. 4213-VN

grade. Additionally, however saturation of the subgrade material may cause additional settlement. Therefore, we expect that the potential distress of the slab-on-grade is low if the structure strength of the slab is adequate and saturation of the subgrade soil is prevented. Note that because of its loose consistency, the on-site subgrade (fill and alluvium) will continue to settle slowly and the slab-on-grade will be affected by this normal consolidation settlement of the loose subgrade. After releveling the structure, the subgrade area under the slab should be leveled off by either hole grouting through the slab or by complete slab removal then replacement after adding compacted fill to level the subgrade area.

4. <u>Cosmetic Repairs</u>

Cosmetic repairs should be made only after the required underpinning has been done and the structure re-leveled.

5. Drainage

On-site drainage should be corrected to the extent that no water is allowed to pond next to the structure. Improvement of the drainage may help to mitigate future settlement of the slab-on-grade subgrade by not increasing the on-site soil moisture.

RECOMMENDATIONS FOR REMEDIAL REPAIR

It is our recommendation that remedial underpinning such as cast-in-place piles or caissons, chance anchors, mini-piles or a perma-jack system be employed to mitigate the tuture settlemen: of the building. The building load should be transferred to the competent bedrock layer, which ranges from 20 to 25 feet on the west side and is about 38 to 40 feet below the existing ground surface on the east side of the structure. An underpinning contractor should be consulted for the final evaluation of applicable methods and workability. A check of utility line locations will be necessary prior to underpinning and a check of utility line leaks after underpinning and releveling. The soil characteristics at the pile shaft/soil interface will be forwarded once a remedial underpinning method is chosen. It should be noted that no additional soil values are necessary if the perma-jack system is chosen.

Page 8 March 24, 1994 W.O. 4213-VN

ن._

LIMITATION

The analyses, conclusions and recommendations contained in this report are based on site conditions as they presently exist, and we further assume that the exploratory borings are representative of subsurface conditions through the site. Since our investigation is based on the site materials observed, selective laboratory testing and engineering analyses, the conclusions and recommendations contained herein are professional opinions. Further, these opinions have been derived in accordance with current standards of practice, and no warranty is expressed or implied.

We appreciate the opportunity to provide this geotechnical engineering service. If you have any questions regarding this report please do not hesitate to contact us.

GeoSoils, Inc

Very truly yours, GEOSOILS, INC. I.o. GE 217 Exp. MARK A. SWIATEK WILLIAM A. CIRIDON CEG 1781 GE 217 CAL

WAC.MAS/mm.A99:4392

Encl: References Plate 1, Boring Location Map Plate 2, Cross-Sections Plate 3, Manometer Survey Table I, Relative Compaction of On-Site Material Appendix A, Field Exploration and Laboratory Testing Plates A-1 through A-7, Boring Logs Plates SH-1 through SH-4, Shear Test Diagrams Plates C-1 through C-8, Consolidation Tests Appendix B, Chance Anchors, Mini-piles and Perma-Jack System Appendix C, Vertical and Lateral Soil Resistance for Conventional Underpinning Piles/Caissons

CC:

- Addressee
 Ghodsi and Associates, Inc.
- (6) RTK and Associates

March 24, 1994 W.O. 4213-VN

「「「「「「「「「「「「」」」」」

語いたい

「小田田子」「「田田」」」「「田田」」」「田田」」」「田田」」」

REFERENCES

- 1. Allen W. Hazard, October 25, 1967, "Geologic Examination of Buckley Schools Property, Part of Lot 1108, Tract 1000, City of Los Angeles, at 3190 Stansbury Avenue, Sherman Oaks, California".
- 2. Advanced Foundation Engineering Incorporated, October 30, 1967, "Foundation Investigation Proposed New Buckley School Complex, 3190 Stansbury Avenue, Sherman Oaks, California".
- 3. Advanced Foundation Engineering Incorporated, February 16, 1968. "Soil Compaction Tests, Progress Report."
- 4. Advanced Foundation Engineering Incorporated, April 4, 1968, "Soil Compaction Tests, Progress Report #2."
- 5. Advanced Foundation Engineering Incorporated, April 12, 1968, "Soil Compaction Test, Final Report on Structural Areas."
- 6. Advanced Foundation Engineering Incorporated, April 18, 1968, "Supplemental Report to our Final Compaction Report on Structural Areas dated April 12, 1986".

March 24, 1994 W.O. 4213-VN

日本投資が行うしてい

いたのないというのから

TABLE I

把你们就是你们的你

STATES A

State States and the

1

. 2014 MARINE

Relative Compaction of On-Site Material

Boring No. and	On-	Site	Maximum Laboratory	% Relative Compaction	Remarks
Depth	Dry Unit Wt. (pcf)	Moisture (%)	Dry Density (pcf)		
B-1 @ 2'		8.6	1.22.0		Fill
B-1@5'	102.5	12.7	122.0	84.0	Fill
B-1 @ 10'	101.2	17.4 j. j.e	122.0	83.0	Fill
B-1 @ 15'	103.3	13.5	122.0	84.7	Fill
B-1 @ 20'	96.3	9.8	122.0	78.9	Fill
B-1 @ 25'	98.8	12.0	122.0	81.0	Alluvium
B-1 @ 30'	103.9	14.2	122.0	85.2	Aliuvium
B-1 @ 35'	106.1	13.6	122.0	87.0	Alluvium
B-2 @ 3'	103.1	18.6	126.0	81.8	Fill
B-2 @ 8'	104.4	18.2	122.0	85.6	Fill
B-2 @ 13'	101.9	21.1	122.0	83.5	Fill
B-2 @ 18'	93.0	24.1	122.0	76.2	Alluvium
B-3 @ 4'	101.7	21.8	126.0	80.7	Fill
B-3 @ 9'	104.2	19.8	126.0	82.7	Fill
B-3 @ 14'	103.1	20.6	122.0	84.5	Fill
B-3 @ 20'	86.2	33.7	122.0	70.7	Fill

hid Protection

۔ د د -1

「語の法での構成でい

TABLE I

这是我并不可能不可能的

Boring No. and	On-S	Site	Maximum Laboratory	% Relative Compaction	Remarks	
Depth	Dry Unit Wt. (pcf)	Moisture (%)	Dry Density (pcf)			
B-4 @ 5'	89.2	28.9	122.0	73.1	Fill	
B-4 @ 10'	97.0	24.1	122.0	79.5	Fill	
B-4 @ 15'	100.7	23.6	122.0	82.5	Fill	
B-4 @ 20'	95.9	22.5	122.0	78.6	Alluvium	
B-5@3'	94.7	24.2	122.0	77.6	Fill	
B-5 @ 8'	88.1	26.7	122.0	72.2	Fill	
B-5@13'	96.8	23.2	122.0	79.3	Fill	
B-5@18'	105.0	16.3	122.0	86.1	Fill	
B-5 @ 25'	102.5	15.5	122.0	84.0	Fill	
B-5 @ 30'	108.2	16.1	122.0	88.7	Alluvium	
B-5 @ 35'	101.0	21.2	122.0	82.8	Alluvium	

Relative Compaction of On-Site Material

Contraction of the second s

The second s

ş

4

د ر

d.

ر ک

,

G	ieo	Sc	oils.	Inc.			BORING LOG				
-			•				w.o. <u>4213-VN</u>				
PR	OJEC	:7:	BUC	KLEY	r scho	OL	BORING LOG B-1 SHEET 1 OF 2				
							DATE EXCAVATED2-23-94				
Ļ	Sa	mp	ole		<u></u>		SAMPLE METHOD:				
			1		Ξ.	e e	Standard Penetration Test & Water Seepage into Hole				
			9 Sr	<u>م</u>	Dry Unit (pcf)	÷.	Ring Sample				
	Bulk	멹	Blous	USCS SYMBOL	20	Moisture (%)	Description of Material				
Z			12				COMPACTED FILL: (Caf) 0 - 22' 0 - 2', Dark brown, silty fine SAND, moist, loose, some -				
Ľ		\square		M/SC	:	8.6	organic roots. @ 2', Light brown, clayey, silty fine to medium SAND with				
Ł			5				scattered small shale fragments, caliche, moist, medium dense to dense, dark brown, silty fine SAND lenses @ 4 - 5' and				
		Z	8 s 13	M/S¢	102.5	12.7	loose. @ 5', Dark brown, clayey, silty fine to medium SAND				
			-				scattered with some 1" diameter small rocks, loose, moist, occasionally with sandy clay lenses.				
]			14				@ 8 1/2 - 10°, Dark brown, sandy CLAY and clayey fine sand				
		\mathbb{Z}	19 32	CL	101.2	17.4	in layers, plastic. @ 10°, Dark brown, silty, sandy CLAY with scattered rocks up				
-			32				to 2" diameter and sandstone shale fragments, moist, medium.				
			15								
		\mathbf{Z}	31 46	CL	103.3	13.5	@ 15", Dark brown, sandy CLAY with scattered rocks (rock greater than 2" diameter, moist, stiff to very stiff.				
-							greater man 2 diameter, moist, stirr to very stirr.				
-			21								
		Z		IL/SI	1 96.3	9.8	@ 20', Tan, brown, silty fine SAND, shale fragments, caliche, oxidized with piece of root, moist.				
╀		+					ALLUVIUM: (Qal) 22 - 38'				
			10								
	Ł	Z		IL 'SN	98.8	12.0	@ 25', Brown, light gray, fine SAND/SILT shale fragments				
			20				with organic roots, caliche, moist, stiff, plastic.				
			12		:						
	P.	\mathbf{Z}	12 18 22	CL	103.9	14.2	@ 30', Dark brown, sandy CLAY with 1 1/2" diameter light brown, siltstone fragments, stiff to very stiff, caliche, moist.				
-							Stiff, plastic.				
]			11								
	Ł	Z	22 34	CL	106.1	13.6	@ 35', Dark brown, sandy, silty CLAY, moist, very stiff,				
							caliche, porous.				
Γ	1						BEDROCK (Tm) 38' - 45'				

TR.

業

302

	C ~	~~-	ile	lnc.			BORING LOG
	Ge	031	ms,	me.			N.O. <u>4213-V</u>
	PROJ	ECT:	BUC	KLEY	' SCHOO	DL	BORING LOG B-1 SHEET 2 OF 2
							DATE EXCAVATED2-23-94
		Sa:nj	ole				SAMPLE METHOD:
(.1.)			. 8		H L	ų	Standard Penetration Test Water Seepage into Hole
Depth (×	-sib	Blows	USCS	Dry Unit (pcf)	Moisture (%)	Ring Sample
Del	8	turbe turbe	8	SN SYS	6	£	Description of Material
40 -		Z	31 36	BR	100.6	18.6	@ 40', Bedrock, yellowish-brown, silty SANDSTONE bedrock very oxidized, moist, hard to very hard.
-			50/3"				
- 45-			50/3"		NR		@ 45', Dark brown SILT/fine sandstone bedrock, slightly
		14		BR			moist, hard to very hard. Total Depth 45'
-							No Water
50-	1						
-							
-	1		:				
55- -							
-							
- 60-							
- 00							
-							
- 65 -]	
-							
-							
70- -							
-							
-							
75-							
						ŧ	

BORING LOG GeoSoils, Inc. w.o. ____4213-VN PROJECT: BUCKLEY SCHOOL BORING LOG B-2 SHEET 1 OF 1 2-23-94 DATE EXCAVATED SAMPLE METHOD: 8-inch p.H.S. Sample 140 lbs 30-inch Drop Ξ (ff.) Standard Penetration Test ₩ Water Seepage into Hole Dry Unit (pcf) Moisture (%) ŵ Ring Sample Blous Oepth urbe USCS SYMBOI Bulk Ipul Description of Material COMPACTED FILL: (Caf) 0 - 15' 0 - 2', Dark brown, silty fine SAND with organic roots, loose, @ 2 - 3', Light brown, silty fine to medium SAND, occasional 18 15 OL/SNI 103.1 18.6 with small rocks, loose, moist. @ 3', Dark brown, sandy CLAY with silty fine sand in layers, 5 moist, stiff, medium dense, occasional with small rocks and some organic roots. Medium plastic. 10 16 SC/CL 104.4 @ 8', Brown, clayey, silty fine SAND with sandy clay lenses. 18.2 moist, loose to medium dense. One organic root tip of sampler. 10 . 3 10 22 34 @ 13', Dark brown, clayey silty, fine SAND with clay lenses, ... SC/CI 101.9 21.1 moist, medium dense to dense, slight caliche. 15 ALLUVIUM: (Qal) 15 - 20' @ 18', Yellowish-brown, clayey fine, sandy SILT, caliche, 0 moist (near optimum), medium dense to dense, porous, 14 25 38 increased moisture and wet @ approximately 21". ML 93.0 24.1 (ر 20 BEDROCK: (Tm) 20 - 35' 17 25 34 @ 25', White brown, yellowish-brown, tan clayey SILTSTONE, BR 91.6 26.1 49 oxidized, moist, firm. 21 30 45 @ 30', Tan, SILTSTONE BEDROCK, oxidized, moist, hard to BR 93.7 25.2 50/4 very hard. 36 35 @ 35', Brown, light gray SILTSTONE bedrock, oxidized, moist, 074 BR 89.6 29.4 hard to very hard. Total Depth 35' No Water No Caving GeoSoils, Inc. PLATE A 1

「日本ない」の「たちはたいないない」というないない。「「こうない」」」には、「こうない」のないないで、「ないない」」というないでは、「ない」」というないでは、「こうない」」」には、「こうない」」」、「こうない」」、「こうない」」、「こうない」」、「こうない」、「こうない」、「こうない」、「こうない」、「こうない」、「こうない」、「こうない」、「こうない」、「こうない」、「こうない」、「こうない」、「こうない」、「こうない」、「こうない」、「こうない」、「こうない」、「こうない」、「こうない」、

	r	C -		t			BORING LOG
(Geo	50	ons,	inc.			u.o. <u>4213-NN</u>
P	BLOR	CT:	BUC	KLEY	SCHO	OL	BORING LOG B-3 SHEET 1 2" 1
							DATE EXCAVATED 2-24-94
	S	amp	le			1	SAMPLE METHOD:
ft.)			1		± ×	ø	Standard Penetration Test & Water Seepage into Hole
÷	Bulk	hed.	0 8 2	s BOL	ũry Unit (pcf)	Maisture (%)	I Ring Sample
Depth	Bul	되	Blous	USCS	<u></u>	Σο Σ	Description of Material
		~	9				COMPACTED FILL: (Caf) 0 - 21' 0 - 0.5', Asphalt concrete. 0.5 - 4', Light brown to dark brown clayey SILT/SAND with - small rocks. @ 4', Dark brown, silty, sandy CLAY with SILT/SAND lenses.
5			11	L/SM	101.7	21.8	shale fragments, moist, medium stiff, medium dense.
-01 -01 -1-1 1-1			12 13	ML	104.2	19.8	@ 9°, Dark brown, silty fine SAND with (Approximately 2 1/2" black asphalt concrete @ 10.5'), moist, loose. Change to dark brown, sandy, silty clay @ 13', moist, medium stiff, plastic.
15-1-1-1		Z	12 18 22	CL	103.1	20.6	@ 14', Dark brown, gray, sandy CLAY, occasional with silty fine silty fine sand lenses, moist, stiff to very stiff, plastic.
- 20-	Þ		18 42	CT	86.5		
		4	44 20	CL	_86.2	33.7	ALLUYIUM: (Oal) 21 - 25' @ 21', Dark brown, silty sandy CLAY, moist. stiff to very stiff, plastic.
25+		25	43 50/3"	BR	84.8	37.6	BEDROCK (Tm) @ 25', Tan, light brown SILTSTONE befrock, oxidized, caliche, moist, hard Total Depth 25' No Water
30-					-		
5-				an ann an			
						·····	GeoSoils, Inc.

NAME OF STREET

nul i gene

							BORING LOG
	Geo	50	oils,	Inc.			v.o. <u>4213-VN</u>
P	BOJE	C1:	BUC	KLEY	SCHO	OL	BORING LOG B-4 SHEET 1 OF 1
							DATE EXCAVATED2-25-94
	S	anış	ole			1	SAMPLE METHOD:
(:1:)					Ē	61	140 lbs., 30-inch Drop Standard Penetration Test & Water Seepage into Hole
		ped	-9 -5	HBOL	Dry Unit (pcf)	Moisture (%)	Ring Sample
Depth	Bulk		Blous	USC: SYM	<u> </u>	Moi	Description of Material
							COMPACTED FILL: (Caf) 0 - 20' 0 - 5', Brown, sandy, silty CLAY, scattered with small rocks and shale fragments, moist to over optimum, soft to medium stiff, medium plastic to plastic.
5-		72	9 12 13	CL	89.2	28.9	@ 5', Brown, sandy silty CLAY with scattered small rocks and shale fragments, moist to over optimum, soft to medium stiff, plastic.
0		Z	19 22 32	CL	97.0	24.1	@ 10', Brown, silty CLAY/sandy clay with lenses, scattered with rocks and shale fragments, some organic roots, moist, soft to medium stiff, plastic.
5-			7				
		2	8 17	CL	100.7	23.6	@ 15', Dark brown, gray, sandy silty CLAY with scattered rocks and shale fragments, rotten organic and sewer smell, moist, soft to medium stiff.
-			12				د.
+0 + - -	ž	Z	21 24	SC	95.9	22.5	ALLUYIIJM: (Qal) 20-25' @ 20', Dark brown, clayey silty SAND with shale fragments, moist, loose to medium dense, low plastic.
5-+			23				
	ł		5073*	BR	78.7	31.1	BEDROCK: (Tm) 25' - 31' @ 25', Tan. brown, SILTSTONE BEDROCK, moist, medium hard, diatomaceous, oxidized.
0+			27	BR	82.4	39.9	@ 30', Tan, brown, SILTSTONE with thin layer, fine to
		4	-		v7		medium sandstone bedrock, moist, medium hard to hard, oxidized, diatomaceous. Total Depth 30'
5-							No Water
-							

1

00% 2


in star

新新学校

1999年11月1日に、1999年11月1日に、1999年11月1日に、1999年11月1日に、1999年11月1日には、1999年11月1日に、1999年11月1日に、1999年11月1日に、1999年11月1日に、1999年11月1日に、1999年11月1日に、1999年11月1日に、1999年11月1日に、1999年11月1日に、1999年11月1日に、1999年11月1日に、1999年11月1日に、1999年11月1日に、1999年11月1日に、1999年11月1日に、1999年11月1日に

BORING LOG GeoSoils, Inc. 4213-VN W.C. BORING LOG B-5 SHEET 1 OF 2 PROJECT: BUCKLEY SCHOOL 2-24-94 DATE EXCAVATED SAMPLE METHOD: ____ 8-inch & H.S. Sample 140 lbs., 30-inch Drop Ŧ Standard Penetration Test Ny Water Seepage into Hole £ ting bcf) Moisture (%) ō Ring Sample 0epth Snol USCS Bulk ي کر urb **Pro** Description of Material 8 COMPACTED FILL: (Caf) 0 - 30' 0 - 4" Concrete slab. 4" - 12", Dark brown, silty fine SAND, loose, moist. 12" - 3', Dark brown, sandy, silty CLAY with shale fragments. Q 12 CL 94.7 24.2 roots, scattered with small rocks, moist, medium stiff to stiff, 18 plastic. 5 @ 3', Dark brown, sandy, silty CLAY with shale fragments. roots scattered with small rocks, one piece of electrical wire. moist, medium stiff to stiff, plastic. 9 @ 8', Dark brown, sandy, silty CLAY with scattered small CL 88.1 26.7 12 rocks and shale fragments, moist, soft to medium stift, plastic. 10 ай. - Э. ٥ @ 13', Dark brown, sandy, silty CLAY with scattered rocks (approximately 1 1/2" diameter), shale fragments, moist, medium stiff to stiff, plastic. 18 CL 96.8 23.2 .) 23 1 5 3 15 20 @ 18', Dark brown, sandy, silty CLAY with scattered rocks 105.0 CL 16.3 (approximately 2" diameter), red brick and shale fragments, stiff to very stiff, plastic. 32 20 12 25 36 25 CL 102.5 15.5 13 30 22 ALLUVIUM: (Qal) 30 - 40' QL/SM 108.2 16.1 38 @ 30', Dark brown, silty CLAY with silty fine SAND lenses, rock (approximately 2" diameter), small shale fragments, stiff to very stiff, plastic. 13 35 24 @ 35', Dark brown, silty CLAY with silty fine sand lense. CL 101.0 21.2 44 rock (approximately 2" diameter) small shale fragments, stiff to very stiff, plastic. @ 38', Light brown, silty CLAY, moist (over optimum) stiff. GeoSoils, Inc. PLATE

	~	C - 11 -	f			BORING LOG
	360	Soils,	inc.			v.c. <u>4213</u>
P	ROJEC	T: BUC	KLEY	' SCHO	OL	BORING LOG B-5 SHEET 2 OF
						DATE EXCAVATED2-24-94
th (ft.)			or.	Ory Unit Wt. (pcf)	sture (X)	SAMPLE METHOO: <u>Reinch & H.S.</u> 140 lbs., 30-inch 1 Standard Penetration Test Au Water Seepage into Ho Ring Sample
Depth	Bulk	Blous	USCS	ۍر مړ	To is	Description of Material
40		7 19 50/5*	BR	68.7	51.3	plastic. BEDROCK: (Fm) 40.5 - 45' Yellowish-brown, SILTSTONE BEDROCK, moist, hard, oxidized caliche.
45		29 50/4"	BR	76.!	43.9	@ 45', Tan SILTSTONE BEDROCK, moist, hard to very oxidized, caliche. Total Depth 45' No Water
75 -						GeoSolla Inc.



11x17

CITY OF LOS ANGELES DEPARTMENT OF CALIFORNIA COMMISSIONERS BUILDING AND SAFE 400. CITY HALL SCOTT Z ADLER PHESIDEN1 JAMESINA E HENDERSON WARREN V O'BRIEN GEHERAL MANAGER JEANETTE APPLEGATE ARTHUR J. JOHNSON, JR MABEL CHANG JOYCE L FOSTER RICHARD J. RIORDAN MAYOR June 20, 1994 Log # 36054 (SOILS/GEOLOGY FILE-2) Buckley School 3900 Stansbury Avenue Sherman Oaks, CA , n TRACT: 23823 Por 1 LOT: 3900 STANSBURY AVENUE LOCATION: ÷., DATE(S) OF REPORT CURRENT REFERENCE $\mathcal{C}_{\mathcal{C}}$ PREPARED BY DOCUMENT NO. REPORT/LETTER(S) GeoSoils, Inc 4213-VN 03/24/94 $\langle 0 \rangle$ Soils/Geo Report 03/24/94 4213-VN Grading Ovrszd Doc <u>۲</u>۰۰, The subject report concerning settlement within the classroom building resulting from the Northridge earthquake has been reviewed by the Grading Division of the Department of Building and Safety. The report recommends underpinning of the building below the underlying fill and alluvium. The existing concrete slabs could then be structurally tied to the new underpinning. For reasons that are unclear, the report does not recommend compaction grouting. It shall be understood that the proposed method of repair is not in full conformance with current Code regulations and must, therefore, be classified as remedial and intended to improve site conditions over that which presently exists.

The report is acceptable as remedial repair to improve the existing building on the site. The following conditions shall be incorported into the plans:

- 1. Cast in place piles and caissons are an acceptable method of repair. The other referenced method, chance anchors, will require a special design plus product approval from Research Division prior to acceptance by the Department.
- 2. The soils engineer shall review and approve the detailed plans prior to issuance of any permit. This approval shall be by signature on the plans which clearly indicates that the soils engineer has reviewed the plans prepared by the design engineer and that the plans included the recommendations contained in his report.

AN EQUAL EMPLOYMENT OPPORTUNITY APPIRMATIVE ACTION EMPLOYER

Page 2 3900 Stansbury Avenue June 20, 1994

The second s

 \mathbf{C}

C

- 3. The soil engineer shall inspect the excavations for the footings to determine that they are founded in the recommended strata before calling the Department for footing inspection.
- 4. All friction pile or caisson drilling and installation shall be performed under the continuous inspection and approval of the Foundation Engineer.
- 5. Pile and/or caisson foundation ties are required by Code Section 91.2908(b). Exceptions and modification to this requirement are provided in Rule of General Application 662.
- 6. Pile and/or caisson shafts shall be designed for a lateral load of 1000 pounds per linear foot of shaft exposed to fill, soil and weathered bedrock.
- 7. Footings shall be located from the face of the slope a minimum horizontal distance of H/3.
- 8. It shall be understood that the existing building slabs will be subject to settlement within the underpinned building if not tied to the new foundation.
- 9. A grading permit shall be obtained.
- 10. All recommendations of the report which are in addition to or more restrictive than the conditions contained herein shall be incorporated into the plans.
- 11. The applicant is advised that the approval of this report does not waive the requirements for excavations contained in the State Construction Safety Orders enforced by the State Division of Industrial Safety.
- 12. A copy of the subject and appropriate referenced reports and this approval letter shall be attached to the District Office and field set of plans. Submit one copy of the above reports to the Building Department Plan Checker prior to issuance of the permit.
- 13. All roof and pad drainage shall be conducted to the street in an acceptable manner.
- 14. Prior to the placing of compacted fill, a representative of the consulting Soils Engineer shall inspect and approve the bottom excavations. He shall post a notice on the job site for the City Grading Inspector and the Contractor stating that the soil inspected meets the conditions of the report, but that no fill shall be placed until the City Grading Inspector has also inspected and approved the bottom excavations. A written certification to this effect shall be filed with the Department upon completion of the work. The fill shall be placed under the inspection and approval of the Foundation Engineer. A compaction report shall be submitted to the Department upon completion of the compaction.
- 15. Prior to the pouring of concrete, a representative of the consulting Soil Engineer shall

Page 3 3900 Stansbury Avenue June 20, 1994

> inspect and approve the footing excavations. He shall post a notice on the job site for the City Building Inspector and the Contractor stating that the work so inspected meets the conditions of the report, but that no concrete shall be poured until the City Building Inspector has also inspected and approved the footing excavations. A written certification to this effect shall be filed with the Department upon completion of the work.

- 16. A registered grading deputy inspector approved by and responsible to the project geotechnical engineer shall be required to provide continuous inspection for the proposed slot cutting, underpinning, shoring, tie-back, buttress, and the drilling and installation of all deep foundations.
- 17. Existing uncertified fill shall not be used for lateral support of deep foundation.

LARRY WESTPHAL Chief of Grading Division

OBARRUBIAS Epgineering Geologist III

RICARDO TRES Structural Engineer Asst. II

JWC/RT:rlm A:\JUN36054 (213) 485-2160

 \mathbb{C}_{+}^{\ast}

*

•

cc: GeoSoils, Inc RTK & Assoc VN District Office

A State of the second GRAMIT'S ANG Consulting Instances and Country tels CONVERSE, DAVIS AND ASSOCIATES 188 West Del Mar Boulevard, Past Office Box scote, Pasadona, California estes. Islephone (113) 881 1111 AUGI SIGN August 7, 1972 **P and A Construction Co.**, Inc. 1200 West 220th Street Torrance, Salifornia 90502 Attention: Mr. William N. Weeger Project No. 72-143-DG, Report on Compacted Fill Administration Building, Righ School Pecilities The Buckley School, 3900 Stammbury Avenue Subject N Sherman Oaks, California 74007 23793 ž ÷., -Gentlemen: This is to report the results of tests and observations made during the placement of compacted fill on the subject site. Periodic tests and inspections were provided by a representative of Converse, Davis and Associates to check the grading th contractor on compliance with the drawings and job specifications. The presence of our field representative at the site 0 was to provide to the owner a continuing source of professional advice, opinions and recommendations based upon the 0 field representative's observations of the contractor's work and did not include any superintending, supervision or direc-tion of the actual work of the contractor or the contractor's workmen. The opinions and recommendations presented hereafter are based on our tests and observations of the grading procedures used, and represent our engineering judgment as

to the contractor's compliance with the drawings and job

Pesedena, Anahoim, Las Vegas

specifications.

	P and A Construction Co., Inc. Project No. 72-143-DG August 7, 1973 Page two
	The grading operation was observed to be performed in the following general manner:
	 Vegetation, surface trash and miscellaneous debris were cleared from the areas to be graded and were hauled off the property.
	 Unsatisfactory soils were excavated to expose competent materials on which to start the fill.
	 Approved soils were placed in layers on the prepared surface, and each layer was compacted to the speci- fied density before the next layer was added.
~ `	 Placement of the compacted fill was continued to the final grades indicated on Drawing No. 1.
2	5. The minimum acceptable degree of compaction was 90 percent of the maximum density.
~	 Maximum density and optimum moisture content were determined by the A.S.T.M. D1557-70 method.
6	7. The soils used in the compacted fill consisted of clay, silt and sandy silt and were classified as moderately expansive with respect to volume-change characteristics. A list of soil types encountered
1件	during testing is presented in the "Table of Test Results."
3	
Ö	Field density tests were made during the placement of fill to determine the aegres of compaction and moisture content. Where tests or field observations indicated insufficient density, additional compaction with adjustment of the mois- ture content where necessary was performed before the next layer was added. All field density tests are listed in the "Table of Test Results," and their approximate locations are shown on Drawing No. 1. Also shown are the limits and depths of the controlled fill placed during this grading operation.

N.

-

CONVERSE, DAVIS AND ASSOCIATES

9 and A Construction Co., Inc. Project No. 72-143-00 August 7, 1972 Page three

Undisturbed samples were obtained from the compacted fill. The samples were obtained by hand driving a thin-walled steel sampler. One sample was tested at varying normal loads in a direct shear machine to determine the Coulomb shear strength parameter. The sample was saturated and drained prior to testing. The result of the shear test is listed in the "Table of Test Results."

CONCLUSIONS AND RECOMMENDATIONS

Based on the final results of the tests, on observation of the construction procedures used in the field and on our experience, it is our opinion that the controlled compacted fill shown on Drawing No. 1 has been placed in accordance with the applicable portions of the job specifications and with the recommendations of Converse, Davis and Associates. The compacted fill discussed in this report will support spread footings, slabs-on-grade, and pavement. Any fill added beyond the limits or above the grades shown should be placed under engineering control and in accordance with the specifications, if it is to be covered by the recommendations of this report.

Footings should be at least 18 inches in width and bottomed 12 inches and 18 inches below lowest adjacent final surface on controlled compacted fill for interior and exterior footings, respectively. The permissible bearing value is 2000 pounds per square foot on the proper bearing soils, as discussed in the report of the Foundation Investigation.

Footings adjacent to the storm drain at the northwest corner of the Administration Building must be founded below a line rising at 45 degrees from the nearest point of the storm drain pipe.

It is recommended that all footing excevations be inspected by Converse, Davis and Associates prior to pouring concrete to see that they are into satisfactory soils and are free of loss and disturbed materials. If conditions are encountered during building construction that appear to be different from those presented in this report, this office should be notified.

Our findings have been obtained in accordance with accepted professional engineering practice in the fields of engineering and soil mechanics. This warranty is in the of all other warranties, either express or implied.

CONVERSE, DAVIS AND ASSOCIATES

~~

A Generation Co., Inc. Generation 73-143-00 (Dot 7, 1973) in four

The undersigned licensed Civil Engineer certifies that he has personally inspected the placement of and tested the compacted earth fill being reported, and that in his opin-ion the same was placed in conformity with the applicable portions of the City of Los Angeles Building Code."

Respectfully submitted,

57 ~

. The second se ÷Α

2

: 0 .0 Ő CONVERSE, DAVIS AND ASSOCIATES

y Eli Protect Engineer

Reviewed and approved C. R. MasFadyen, Principal Engineer

EJJ/CRI Encl:	Nieg Table of Test Drawing No. 1	Results,	Sheets	1 and 2	ł
Disti	(2) Addressee		_		

(2) City of Los Angles, Department of Building and Safety, Grading Division (2) Regnar C. Qvale and Associates

*For the purpose of this certificate, to "have personally inspected and tested" shall include inspection and testing performed by any person or persons employed by, and responsible to the licensed Civil Engineer signing this report. Where the inspection and testing of all or part of the work above is delegated, full responsibility shall be assumed by the licensed Civil Engineer whose signature is affixed hereon.

CONVERSE, DAVES AND ASSOCIATES

and a final second s

SANLA OF THEF REAULTS

TABLE I FIELD DENSITY TESTS

Test Ng.	Tess Dete	Test Logation	Approx. Test Bleve- tion Cest	Approx. Depth of Fill Below Test-Ft.		Field Noisture Content Percent of Dry Wt.	(2) Soll <u>Type</u>	
16	7/12/72	Northwest	789	2.0	101	19.5	1	92
17	7/12/72	Southeast	763	2.0	96	18.8	2	94
20	7/12/72	Centes	765	4.0	101	16.7	ī	92
21	7/12/72	Southwest	744	2.0	95	22.2	ž	93
22	7/13/72	Northeast	748	8.0	99	19.4	ī	91
23	7/13/72	Southeast	767	6.0	92	18.8	2	90
24	7/13/72	Southwest	769	8.0	94	16.8	ž	94
26	7/13/72	Center	771	10.0	91	22.9	5	84
	7/14/72	Center	771	10.0	90	20.9	j	90

1,0

 (1) Density of the compacted fill was determined in the field by the A.S.T.M. D1556-64 sand cone test. Soil samples obtained from the sand cone tests were oven-dried to obtain the field moisture dontent.

_ (2) \$911 Type is given on Table II, Laboratory Maximum Density Tests.

- A - Twats taken to recheck areas of substandard compaction.

. О

1.


TABLE II LABORATORY MAXINUM DEMSITY TESTS*


· n	scil Type	Soil Description	Naximum Dry Danaity, p.c.f.	Optimum Moisture Content-Percent
0	C. C. C. C. C. T.			fa tis histigaile in di sua institutionil all'admos
	1	Black CLAY	110	14.3
	2	Dark Brown SILT	102	18.0
	3	Brown SANDY SILT	109	16.7

*λ.#.T.M. D1557-70 test method.

CONVERSE, DAVIS AND ARKOCIATER

and the second secon





tota having compacted fills

Approval is granted for compacted fill constructed on the slove lots an described in the compaction report sated from the slove lots an prepared by Report No. 79-148-1


- A. Rootthes for including a set transmitter tare to a constituent from There is a sufficient source for the constraint type Market.
- a, Resting Learning preserve for all i constitue taxes and blood extend a value of constituent and constituent a provide the second surface.
- S. Continuous footings per loss well a di all'are replied.
- (b) A)) footlings supported particles we ally on compacted fill shall be relationed continuously with at least one number 4 tar at the top and particles of the footling.
- E. Spope separtor control, plantic, and tentroling of fill signer, and specific output net are regulared as per second to risklop.
 F. Building or atput ope for the second basic to feet from the face.
- F. Building on at multiple for this, which is set back to feet from the face of elements of feet and on the vertical action where the chart is a provide the vertical set of a contraints of vertical actions where the vertical height of a provident of the feet and the chart is a feet of the description of the train of the contraints of the contraints
- G. Postings of iscond to the story droin at the Porthroat corner of the Aler Structure Hig, mic be remain below of a line rising at the Frontings to be 10 vice. Which fam.

287

14、15年1月1日 14、15日(15年1月1日) 14月1日(16日)

een de Branne Margerau en Br

P.R. BAUER, Oreding Ingineer



est Mart Dat Mar Bastoverd. Post Office Ban száðu, Pasad-na. California preos. Telephune (153) 681-1125

Angent M. 1972



「「「「「「「」」」

 P and A Construction Go., jac.
 Deretinent or summe a setty via nore period origination

 1200 Wort Minh Street
 via nore period origination

 Torrange, Galifornia 90502
 account or summe a setty via nore period origination

 Advention:
 Mr. William N. Weager

 Subject:
 Project No. 72-143-DM, Report on Compacted Fill

 Classroom Buildings, Migh School Taritities, The Buckley Hebest, High School Taritities, School Taritities, The Buckley Hebest, High School Taritities, School Tarities, School Taritities, School Taritities, S

Centlemen:

10.00

0

já k

×.01

10

0

3

This is to report the results of tests and observations made during the placement of compacted fill on the subject site.

Periodic tests and inspections were provided by a representative of Genverse, Davis and Associates to check the grading contraster on compliance with the drawings and job specifications. The presence of our field representative at the site was to provide to the ewner a continuing source of professional advice, opinions and recommendations based upon the field representative's observations of the contractor's work and did not include any superintending, supervision or direction of the actual work of the contractor or the contractor's workand recommendations presented hereafter are based on our tests and observations of the grading procedures used, and represent our engineering judgment as to the contractor's compliance with the drawings and job specifications.

The grading operation was observed to be performed in the following general managers

 Vegetation, surface trash and miscellaneous debris were cleared from the areas to be graded and were hauled off the property.

Peterdana, Anchota, Lee Vegas

And Andrews and Andrews

- Unsatisfactory soils were uncavated to expose competent materials on which to start the fill.
- 3. Approved soils were placed in layers on the prepared surface, and each layer was compacted to the specified density before the next layer was added.
- 4. Placement of the compacted fill was continued to the final grades indicated on Drawing No. 2.
- 5. The minimum acceptable degree of compaction was 70 pereast of the manimum density.
- 6. Maximum density and optimum moleture castoot were determined by the A.S.T.M. D1557-70 method.
- 7. The soils used in the compacted fill consisted of clay, silt and sundy silt and were classified as moderately expansive with respect to volume-change characteristics. A list of soil types encountered during testing is presented in the "Table of Test Results."

Field density tests were made during the placement of fill to determine the degree of compaction and the moisture content. Where tests or field observations indicated insufficient density, additional compreties with adjustment of the moisture content where necessary was performed before the next layer was added. All field density tests are listed in the "Table of Test Results," and their approximate locations are shown of Drawing No. 2. Also shows are the limits and depths of the controlled fill placed during this grading operation.

Undisturbed samples were obtained from the compacted fill. The samples were obtained by hand driving a thin-walled steel sampler. The samples were tested at varying normal loads in a direct shear machine to determine the Coulomb shear strength parameter. The samples we?# Saturated and drained prior to tusting. The results of the shear tests are listed in the "Table of Test Results."

CONVERSE, DAVIS AND ASSOCIATES

1.115日初代表的代表的影响。 新闻的复数形式

Page three

MARKED

39 (S +

CONCLUSIONS AND RECOMMENDATIONS

Based on the final results of the tests, on observations of the construction procedures used in the field and on our experience, it is our opinion that the controlled compacted fill shown on Drawing No. 2 has been placed in accordance with the applicable portions of the job specifications and with the recommondations of Converse, Davis and Associates. The compacted fill discussed in this report will support spread footings, slabs-on-grade, and pavement. Any fill added beyond the limits or above the grades should be glaved under angineering control and in accordance with the specifications, if it is to be proceed by the recommendations of this report. Loose fill on the surface of the north slaps of the Pavilion excevation is to be removed during construction of the Pavilien.

Footings should be at least 18 inches in width and bottomed 12 inches and 18 inches below lowest adjacent final surface on controlled compacted fill for interior and exterior fourings, respectively. The permissible bearing value is 2,000 pounds per square doot on the proper bearing soils, as discussed in the report on the Foundation Investigation.

Footings of the west classroom building adjacent to the storm drain must be founded below a line rising at 45 degrees from the nearest point of the pipe.

It is recommended that all footing excevations be inspected by Converse, Davis and Associates prior to pouring concrete to see that they are into satisfactory soils and are free of losse and disturbed materials. If conditions are encountered during building construction that appear to be different from those presented in this report, this office should be notified.


Our findings have been obtained in secondance with accepted professional engineering practice in the fields of engineering and soil mechanics. This warranty is in lieu of all other warranties, either express or implied.

The undersigned licensed Civil Engineer certifies that he has personally inspected the placement of and tested the compacted earth fill being

CONVERSE, DAVIS AND ASSOCIATES

いいたちの

2



reported, and that in his opinion the same was placed in conformity with the applicable portions of the City of Los Angeles Building Code, +

Respectfully submitted,

CONVERSE, DAVIS AND ASSOCIATES

Reviewed and As Poyed!

C. R. MacTadyes, Principal Engineer

EJJ/CRMAh

- Encl: Table of Test Results, 1, 11 and 111 Drawing No. 2
- Dist: (2) Addresses

- (2) City of Los Angeles, Department of Building and Safety, Grading Division
- (2) Ragnar C. Qvale and Associates

"For the purpose of this certificate, to "have personally inspected and tested" shall include inspection and testing patiented by any person employed by, and responsible to the licensed Civil Engineer signing this report. Where the inspection and testing of all or part of the work above is delegated, full responsibility shall be assumed by the licensed Civil Engineer whose signature is affined hereon.

CONVERSE, DAVIS AND ASSOCIATES

うちちまた

TASLE OF THE COULTS

.

6.1

Projekt

Martin dry 11

TABLE I FIELD DENSITY TESTS

Test	Test	 .	Test Location	Xest Eleve- Lien	Approx. Depth of Fill Below		Field Moisture Content Percont of Dry Wi.	(2) Soll Type	Personi Com-
Ng	Date			Teet					
1	7/6/72	East	Classroom Bidg.	763	2.0	88	23.4	8	86
24	7/6/72		Classroom Bldg.	763	2.0	92	26.6	2	70
3	7/7/72		Classroom Bldg.	765	4.0	98	28.6	2	90
4	7/7/72		Classroom Bldg.	767	1.0	42	33.8	2	80
5A			Classroom Bidg.	767	1.0	96	21.4	3	90
6	7/7/72	East	Cinseroom Bidg.	769	5.0	96	21.0	2	94
7	7/7/72	East	Classroom Bldg.	772	6.0	98	15.4	2	90 :
			Classroom Bldg.	769	3.0	93	24.8	2	91
~9			Classroom Bldg.	771	5.0	98	18.5	3	90
-10			Classroom Bldg.	775	1.6	102	16.4	1	95 -
11			Classroom Bldg.	774	13.0	98	18.4	3	90
12			Classroom Bidg.	775	9.0	92	23.9	2	90
-13			Classroom Bidg	775	14.0	96	23,1	2	94
11			Classroom Bldg.	776	2.0	92	19.9	2	90
			Classroom Bldg.	776	10.0	100	81.4	3	92
18			Classroom Bldg.	779	13.0	93	22.4	2	91
19			Classroom Bldg.	777	16.0	97	21.0	2	95
3			Classroom Bldg.	780	6.0	107	17.2	1	97
-67			Classroom Bldg.	781	18.0	99	12.3	1	90
. 29			Classroom Bldg.	782	16.0	96	22.6	2	94
30			Classroom Bldg.	766	1.0	99	23.0	3	91
31	7718/72	West	Classroom Bldg.	764	2.0	90	21.6	3	63
-J2A			Classroom Bldg.	764	2.0	98	20.2	3	90
33			Classroom Bidg.	765	4.0	84	24.3	2	82
34A			Classroom Bidg.	768	4.0	94	25.0	2	92 :
35 2011			Classroom Bidg.	770	\$.0	90	24.0	- 2	88
39x			Classroom Bldg.	770	5.0	97	24.0	2	95
36			Classroom Bidg.	769	7.0	92	23.2	2	90
38			Classroom Bldg.	773	7.0	100	21.1	3	92
39			Classroom Bldg.	774	10.0	99	20.9	3	90
40			Classroom Bldg.	778	8.0	102	19.5	1	93
41			Classroom Bldg.	774	10.0	105	19.7	1	95
**			Classroom Bldg.	771	10.0	103	23.6	1	94
43			Classroom Bldg.	776	14.0	107	17.2	3	97
44			Classroom Bldg.	778	11.0	92	18.8	2	90
45A	7/21/72	West	Classroom Bldg.	778	11,0	40	21.8	2	94
46	7/21/72	West	Classroom Bidg.	774	2.0	9 9	17.7	3	91

CONVERSE, DAVIS AND ASSOCIATES

State State State State

and a state of the second s




TABLE II LABORATORY MAXIMUM DENSITY TESTS+

Juli Type	Boll Description	Maximum Dry Dessity, Batala	Optimum Moisture ContentsParenat
1	Black CLAY	110	14.3
ž	Dark Brown SILT	108	18.0
5	Brown SANDY SLLT	109	16.7
4	Brown SANDY SLLT (Import)	121	10.3

*A.S.T.M. D1557-70 test method.

~

-


~

 \mathbf{a}

TABLE III Direct shear tests

Samplu Massar	Location	Depth Below Finish Grade (Feet)	c (Pounds Fer Severe Foot)	
· • •	West Classroom Bldg.	1.5	670	31
	East Classroom Bidg.	1.5	520	28
<i></i>				
1 A				
•				

CONVERSE, DAVIS AND ASSOCIATES



11x17

91 j 14 t 14 t	WILLIAMO MAL HAMAGON	CURLEME AND CAPETY
		BAM YORTY MAIDE
I	TRACTION:	DATE: PERMIT: DN/
	Lots having compacted fills	
	Approval is granted for con described in the compaction prepared by	mpacted fill constructed on the above lots as n report dated
	 Footings for one-story Table 17-B without use Footings for one-story Table 17-B without use Footing bearing pressur value of	r Code Section 91.3012 are required. partly or wholly on compacted fill shall be y with at least one number 4 bar at the top ing. planting, and irrigating of fill slopes, and wired as per Code Section 91.3007. Fortings shall be set back 5 feet from the face was in vertical height where the slope angle is to 1 vertical and 2 horisontal to 1 vertical. pht of slope exceeds 20 feet and the slope above, the set back shall be increased 1 foot feet in vertical height over 20 feet to a feet. For slopes exceeding 100 feet in t back shall be 40 feet except as permitted
	v	

• •

1944 - N. Y. H. J.



CONVERSE, DAVIS AND ASSOCIATES

and West Del Mar Buslevard, Prox Office flow astimu, Canadena, California graves. Telephone (sans) on sasa

May 24, 1971

MAY 2 8 1971

ARTMENT OF BUILDING & SAFETY YAM NUYS DISTRICT OFFICE GRADING DIVISION

The Buckley School 3900 Standsbury Avenue "Egrman Cake, Galifornia - 91403

Attention: Mr. Charles McAdam

Subject:

Project No. 71-125-D, Report on Field Density Teata, Blanket Fill Slope, Proposed Athletic Field, 3900 Standsbury Avenue Sherman Oaks, California TRACT - 28733

Gentlomon:

t P

~

This is to report the results of 26 field density tests made during construction of the subject blanket fill slope located along the northernmost perimeter of the proposed athletic field on the subject campus.

607 - 1

Specifications for the proposed grading were prepared by personnol of The Buckley School, Hr. Charles McAdam sutherized Converse, Davis and Associates to perform periodic tests at random locations in the recently compacted fill slope.

Representative samples of the soils encountered at the test locations were tested in the laboratory to determine the maximum dry density and optimum moisture content. The ensite soils encountered during testing were classified as clayey silt and sandy silt. Density of the compacted fill was checked in the field by the sand cone method. A list of all field and laboratory tests made to date is presented in the "Table of Test Regults." The Buckley School Project No. 71-125-D May 24, 1971 Page two

にないまた。「たちにはないない」というな

 \sim

1 1

.^

C

Unless we are notified otherwise, we shall consider our work on this project complete.

Respectfully submitted,

1510 how C Chang, Project Engineer

Reviewed and approved;

Thomas D. Lake, Principal Engineer

WPJC/TDL:08

Encl: Table of Test Results I and II, Sheets 1 and 2 Dist: (4) Addressee

- (1) Ragnar C. Qvale and Associates Architects
- (2) City of Los Angeles, Department of Building and Safety, Grading Division Van Nuys District Office Attention: Mr. John S. Westphal

EDNVERSE DAVISAND ASSOCIATES

Ref. Sec.

Ð

Sheet 1 of 2

The Buckley School Project No. 71+128+D May 24, 1971

TABLE OF TEST REBULTS

TABLE I FIELD DENSITY TESTS

I cal		Test Location	Approx, Tost Eleva- tion Feet	Approx. Depth of Fill Relow Test-Feet	(1) Dry Density <u>p.c.f.</u>	Field Moisture Content Percent C Dry Wt.	(2) Soil Type	Percent Com- paction
)	3/18/71		802	1	93			
2	3/18/71		805	7	104	19.8	1	85
3	3/19/71		807	à	105	17.4	1	96
4	3/10/71	Blanket (11)	AIO	12	100	15.3	ļ	07
5	3/22/71	Blanket Fill	804	2	102	15.7 15.0	Į.	D 2
<u>⊐r</u> 6	3/22/71		013	Ā	105			94
	3/23/71		816	A A	105	21.2 21.6	2	97
* 8	3/24/71	Blanket Pill	818	4	106	18.6	Ĩ	97
m P	3/24/71	Blanket Fill	820	4	100	20.3	l	97
•	3/25/71	Blankot Fill	822	Å	100		1	92
· · ·	3/26/71	Blanket Fill	825	i i	117	19.0	l	97
-12	3/29/71	Blankot P111	027	i i	106	9.1	2	P P
13	3/30/71	Blanket P111	827	Å	112	16.5	1	97
n.a. 14	3/31/71		829	, A	115	8.6	-	PS
15	4/1/71	Blanket Pill	830		110	11.4	2	97
	4/2/71	Blanket Pill	832	4		14.1	2	93
17	4/5/71	Blanket Pill	835		107	17.0	1	08
)	4/6/71	Blankot Pill	837		112	16.7	2	05
1019		Blankot Pill	840	4	104	10.2	1	05
2 U		Blanket Pill	844	9 4	lop	7.5	2	92
		Blanket Fill	844	4	106	4.6	2	90
		Blankot Pili	849	4		8.6	3 8	PS
	· · · · · · · · · · · · · · · · · · ·	"tanget Fill	· •	2	100	14.5	Ì	Ø2
		West Slope	834	4	106	12.5	Ĩ	97
		www.atobe	840	4	97	20.2	ł	90
26		West Slope	840	4	101	14.0	ī	83
₩. ¥2	~/ IV// I 1	Went Slopp	843	4	98	16.0	1	80

(1) Density of the compacted fill was determined in the field by the A.S.T.M. D1850-04 and cone test. Soil samples obtained from the sand cone tests were oven-dried to obtain the field moisture content.

(2) Boll Type is given on Table II, Laboratory Maximum Density Testa,

8 - Tents made in the exposed face of a compacted fill stops,

Shoet 2 of 2

1.5.1

Andrew States

The Suckley School Project No. 71-125-D May 24, 1971


TABLE OF TEST RESULTS (Contid.)

TABLE II LABORATORY MAXIMUM DENSITY TERTS*


8011 <u>Typ</u> e	Soil Description	Maximum Dry Donaity, p.c.f.	Optimum Moistuze <u>Content-Percent</u>
1	Gray-Brown CLAYEY SILT	109	15.0
2	Brown BANDY SILT	118	12.8

*A.S.T.M. DISS7-70 test method.

5 . AQ



1999년 - 1999년 1999년 1999년 1999년 1999년 1997년 1 1997년 - 1997년 19 1997년 - 1997년 1



CITY OF LOS ANGELES SALIPORNIA

2 3 WEERS 14 19 1 (四十十六年) 财务的希望接待

1 1

. 14

 \square



Building and gapety 407 - +18+ 1141 1.018 ANGELED FILLE BOOTE

1.1

医胸膜 法总统

weitler Sehool Stanabury Avanue Cake, California 91403

Attention: Mr. Charles Maadaa

TRACT LOTI

DATE

LOCATION: Careford Const

Lots having compacted fill: Same as above.

EX approval is granted for compacted fill constructed on above lot(s) of subject property as described in report ANT. 69. 1973 dated (No.) . 71 **-** 10 **-** 0 prepared by fans space. Devide A. A ference firsten

The approval is limited exclusively to the area shown in the report and subject to the following rejuirementer

- 1. The compacted fill is approved only as a nonstructural fill. This fill is not to be used for support of structural footings.
- 2. Slope erosion control, planting and irrigating of fill slopes and run-off control are required for those areas outside the building per Section 91.3007.

F.R. MAURE, Grading Magineer



Bas B-143 R3.70

Consulting Engineers and Geologists

ERSE, DAVIS AND ASSOCIATES

126 West Del Mar Boulevard, Post Office Box 22680, Pasadera, California 91105 Telephone (213) 681-1121 September 25, 1972

P and A Construction Co., Inc. 1200 West 220th Street Torrance, California 90502 RECEIVED OCT 1 1 1972

GRADING

DEPARTMENT OF BUILDING & SAFETY VAN NUYS DISTRICT OFFICE GRADING DIVISION

Attention: Mr. William N. Weeger

Subject: Project No. 72-143-DH, Report on Compacted Fill, Proposed Library, High School Facilities The Buckley School, 3900 Stansbury Avenue Sherman Oaks, California

Gentlemen:

This is to report the results of tests and observations made during the

TRACT 23823 LOT 1

This is to report the results of tests and observations made during the placement of compacted fill on the subject site.

Periodic tests and 1 spections were provided by a representative of Converse, Davis and Associates to check the grading contractor on compliance with the drawings and job specifications. The presence of our field representative at the site was to provide to the owner a continuing source of professional advice, opinions and recommendations based upon the field representative's observations of the contractor's work and did not include any superintending, supervision or direction of the actual work of the contractor or the contractor's workmen. The opinions and recommendations presented hereafter are based on our tests and observations of the grading procedures used, and represent our engineering judgment as to the contractor's compliance with the drawings and job specifications.

The grading operations was observed to be performed in the following general manner:

1. Vegetation, surface trash and miscellaneous debris were cleared from the areas to be graded and were hauled off the property.

Pasadena, Anaheim, Las Vegas

- 2. Unsatisfactory soils were excavated to expose competent materials on which to start the fill.
- 3. Approved soils were placed in layers on the prepared surface, and each layer was compacted to the specified density before the next layer was added.
- 4. Placement of the compacted fill was continued to the final grades indicated on Drawing No. 3.
- 5. The minimum acceptable degree of compaction was 90 percent of the maximum density.
- 6. Maximum density and optimum moisture content were determined by the A.S.T.M. D1557-70 method.
- 7. The soils used in the compacted fill consisted of silt and sandy silt and were classified as moderately expansive with respect to volume-change characteristics. A list of soil types encountered during testing is presented in the "Table of Test Results."

Field density tests were made during the placement of fill to determine the degree of compaction and the moisture content. Where tests or field observations indicated insufficient density, additional compaction with adjustment of the moisture content where necessary was performed before the next layer was added. All field density tests are listed in the "Table of Test Results," and their approximate locations are shown on Drawing No. 3. Also shown are the limits and depths of the controlled fill placed during this grading operation. Controlled compacted fill placed in the Administration Building and high school classrooms was reported August 7 and August 14, 1972, respectively.

Undisturbed samples were obtained from the compacted fill. The samples were obtained by hand driving a thin-walled steel sampler. One sample was tested at varying normal loads in a direct shear machine to determine the Coulomb shear strength parameter. The sample was saturated and drained prior to testing. The result of the shear test is listed in the "Table of Test Results."

CONVERSE, DAVIS AND ASSOCIATES

Project No. 72-143-DH September 25, 1972 Page three

Elon Co. Inc.

CONCLUSIONS AND RECOMMENDATIONS

Based on the final results of the tests, on observations of the construction procedures used in the field and on our experience, it is our opinion that the controlled compacted fill shown on Drawing No. 3 has been placed in accordance with the applicable portions of the job specifications and with the recommendations of Converse, Davis and Associates. The compacted fill discussed in this report will support spread footings, slabs-on-grade, and pavement. Any fill added beyond the limits or above the grades shown should be placed under engineering control and in accordance with the specifications, if it is to be covered by the recommendations of this report. Loose fill as indicated on Drawing No. 3 is to be removed during backfilling of the Administration Building. The two to three feet of fill placed above Elevation 771 within the future library are to be removed during construction of the future library.

Footings should be at least 18 inches in width and bottomed 12 inches and 18 inches below lowest adjacent final surface on controlled compacted fill for interior and exterior footings, respectively. The permissible bearing value is 2,000 pounds per square foot on the proper bearing soils, as discussed in the report on the Foundation Investigation.

It is recommended that all footing excavations be inspected by Converse, Davis and Associates prior to pouring concrete to see that they are into satisfactory soils and are free of loose and disturbed materials. If conditions are encountered during building construction that appear to be different from those presented in this report, this office should be notified.

Our findings have been obtained in accordance with accepted professional engineering practice in the fields of engineering and soil mechanics. This warranty is in lieu of all other warranties, either express or, implied.

CONVERSE, DAVIS AND ASSOCIATES

P and A Constantion Co., Inc. Project No. 72+143-DH September 25, 1972 Page four

The undersigned licensed Civil Engineer certifies that he has personally inspected the placement of and tested the compacted earth fill being reported, and that in his opinion the same was placed in conformity with the applicable portions of the City of Los Angeles Building Code.*

Respectfully submitted,

CONVERSE, DAVIS AND ASSOCIATES

By Z ect Engineer J. Jone

Reviewed and approved; C. R. MacFadyen, Principal Engineer

EJJ/CRM:bh

- Encl: Table of Test Results, I, II and III Drawing No. 3
- Dist: (2) Addressee

(2) City of Los Angeles, Department of

- Building and Safety, Grading Division
- (2) Ragnar C. Qvale and Associates
- * For the purpose of this certificate, to "have personally inspected and tested" shall include inspection and testing performed by any person employed by, and responsible to the licensed Civil Engineer signing this report. Where the inspection and testing of all or part of the work above is delegated, full responsibility shall be assumed by the licensed Civil Engineer whose signature is affixed hereon.

CUNVERSE, DAVIS AND ASSOCIATES

TABLE I FIELD DENSITY TESTS

TARLE OF TEST RESULTS

	Test Date	Test Location	Approx. Test Eleva- tion Feet	Approx. Depth of Fill Below <u>Test-Feet</u>	•	Field Moisture Content Percent of Dry Wt.	(2) Soil Type	Percent Com- paction
	8/1/72	Library	757	2	93	22.6	2	91
	8/1/12 8/2/72	Library	759	4	93	21.6	2	91
	8/3/72	Library	761	3	97	17.6	2	95
济 、	8/8/72	Library	764	3	119	7.2	4	98
	8/8/72	Library	763	8	113	10.5	4	93 🖞
	8/9/72	Library	767	7	115	9.7	4	95
	8/9/72	Library	769	8	116	10.8	4	96
	8/9/72	Berm	775	15	112	18.3	4	93
	8/10/72	Berm	779	19	110	8.1	4	91
	8/11/72	Library	771	11	109	11.8	4	90

Density of the compacted fill was determined in the field by the A.S.T.M. D1556-64 sand cone test. Soil samples obtained from the sand cone tests were oven-dried to obtain the field moisture content.

Soil Type is given on Table II, Laboratory Maximum Density Tests.

TABLE II

LABORATORY MAXIMUM DENSITY TESTS*

l De	Soil Description	Maximum Dry Density, p.c.f.	Optimum Moisture Content-Percent
	Black CLAY	110	14.3
	Dark Brown SILT	102	18.0
	Brown SANDY SILT	109	16.7
	Brown SANDY SILT (Import)	121	10.2

A.S.T.M. D1557-70 test method.


CONVERSE, DAVIS AND ASSOCIATES


Same La Barlestolder

and the second second

O		TABLE III DIRECT SHEAR. TESTS		
mple	Location	Depth Below Finish Grade (Feet)	c (Pounds Per Square Foot)	ø Degrees
	Proposed Library	1.5	970	33
			•	лтт то 94 уг 1100 м. Ден ее

CONVERSE, DAVIS AND ASSOCIATES





	ULLIAM6 Manager					DEPARTMENT O BUILDING AND S. 409. City Hall Lob Angeles, Calif	AFETY
	1200 Ves Torrance Attent CT: T: CATION:	in. V. X. Solution Sput Stan	treet 118 90502	blo 28 4.	DATE: PERMIT: DM#	0 etaber 13, 1 5 1453311 7327	72
Ap de pr No	proval is scribed i epared by • 72-143 proval is	in the con 	for compacte mpaction repo	rt dated		the above lots a	_, ct
A. B. C. D. E.	Table 1 Footing value o approve Continu All foo reinfor and bot Slope e runoff Buildin of slop between Where t angle i for eac maximum vertica	s for one 7-B witho bearing d compact but footings sup ced contri- tom of the rosion co control a g or strue be vertice he vertice h additice back h height,	but use of the pressure for lbs. per s red surface. Ings per Code oported partly inuously with he footing. Ontrol, plants are required a reture footing et or less in contal to 1 ve cal height of cribed above, onal 5 feet in cof 10 feet.	e soil beari all other s sq. ft. at Section 91. y or wholly at least on ing, and irr as per Code s shall be vertical he ertical and slope excee the set bac vertical h For slopes	ing value. structures inc 3012 are r on compact ne number 4 rigating of Section 91 set back 5 right where 2 horizont eds 20 feet k shall be reight over exceeding	ed fill shall be bar at the top fill slopes, ar .3007. feet from the f the slope angle al to 1 vertical and the slope increased 1 foc 20 feet to a	l a Low e nd face e is
• ••	footing For ext	terior fo	minimum 18" w otings. Inte	ide. rior footing	gs may use	12"	

Geotechnical Consultants

JUN 29 1977

VAN NUYS DISTRICT OFFICE

GRADING DIVISION

ONVERSE DAVIS DIXON ASSOCIATES

126 West Del Mar Boulevard, Box 2268D, Pasadena, California 91105 • (213) 681-1121

June 8, 1977

Paul W. Speer, Inc. 15450 Cabrito Road Van Nuys, California 91406

Attention: Mr. Paul W. Speer

Subject:

Final Report on Backfill, Pavilion Building and Passage Structure, The Buckley School, Sherman Oaks, California Our Project No. 75-149-DG

Gentlemen:

PASADENA

ANAHEIM

This is to report the results of tests and observations made during the placement of compacted backfill on the subject site.

Periodic tests and observations were provided by a representative of Converse Davis Dixon Associates to check the grading contractor on compliance with the drawings and job specifications. The opinions and recommendations presented hereafter are based on our tests and observations of the backfilling procedures used, and represent our engineering judgment as to the contractor's compliance with the drawings and job specifications.

- 1. Excavations were found to be clean of loose or disturbed materials.
- 2. Approved soils were placed in layers on the prepared surface, and each layer was compacted to the specified density before the next layer was added.
- 3. Placement of the compacted backfill was continued to the final grades indicated on Drawing Nos. 1 and 2.
- 4. The minimum acceptable degree of compaction was 90 percent of the maximum density.
- 5. Maximum density and optimum moisture content were determined by the A.S.T.M. D1557-70 method.
- 6. A list of soi! types encountered during testing is presented in Table II.

LAS VEGAS

SEATTLE

SAN FRANCISCO

Paul W. Speer, Inc. Our Project No. 75-149-DG June 8, 1977 Page two

Field density test were made during backfilling to determine the degree of compaction and moisture content. Where tests or field observations indicated insufficient density, additional compaction with adjustment of the moisture content where necessary was performed before the next layer was added. It is not to be construed that Converse Davis Dixon Associates supervised, directed or superintended the contractor's work, since these functions were the sole responsibility of the contractor.

All field density tests are listed in the "Table of Test Results," and their approximate locations are shown on Drawing Nos. 1 and 2. Also shown are the limits and depths of the compacted backfill.

CONCLUSIONS AND RECOMMENDATIONS

Based on the final results of the tests, on observations of the construction procedures used in the field and on our experience, it is our opinion that the compacted fill shown on Drawing Nos. 1 and 2 have been placed in accordance with the applicable portions of the job specifications and with the recommendations of Converse Davis Dixon Associates. Any fill added beyond the limits or above the grades shown should be placed under engineering control and in accordance with the specifications, if it is to be covered by the recommendations of this report.

The compacted backfill discussed in this report is intended to support outside slabs-on-grade, pavements and passage canopy footings. General recommendations presented in the report on the Foundation Investigation, dated January 27, 1972 (our Project No. 71-486-A), are applicable on the compacted fill.

Services rendered on this project complied with generally accepted soil and foundation engineering practice. No other warranty, either express or implied, is made.

Respectfully submitted,

CONVERSE DAVIS DIXON ASSOCIATES

Algirdas G. Leskys, Senio Engineer

AGL:eh Encl: Table of Test Results Drawing Nos. 1 and 2

Dist: (2) Addressee

- (1) Ragnar C. Qvale & Associates, Architects
- (1) Hillman, Biddison and Leevenguth, Structural Engineers

(2) City of Los Angeles, Department of Building and Safety,

Van Nuys Office CONVERSE DAVIS DIXON ASSOCIATES Diect No. 75-149-D

TABLE OF TEST RESULTS

TABLE I FIELD DENSITY TESTS

						Field		
			Approx.	Approx.	(1)	Moisture		4
			Test	Depth of	Dry	Content	(2)	Perce
	Test		Elevation	Fill Below	Density	Percent	Soil	Com
1	Date	Test Location	Feet	Test Feet	p.c.f.	of Dry Wt.	Туре	pactic
35. 第5. 1 月	12/15/75	Northside	771.0	1.0	96	22.3	6	94
212	12/15/75	Northside	771.4	1.5	99	21.1	1	90
	12/16/75	Northside	773.5	3.5	92	19.8	6	90
	12/16/75	Northside	772.5	2.5	95	23.5	6	93
	12/17/75	Northside	774.5	4.5	94	25.7	6	92
	12/17/75	Westside	772.0	2.0	92	23.0	6	90
	12/18/75	Westside	772.0	2.0	82	23.0	6	80,
	12/19/75	Westside	772.0	2.0	92	14.8	6	90
	12/18/75	Southside	771.0	1.0	99	18.0	6	97
sta Station General Station	12/22/75	Southside	772.5	2.0	111	11.8	7	90
	12/23/75	Southside	774.0	4.0	113	11.7	7	91
C. VOIDEL	12/31/75	Southside	776.0	6.0	98	16.6	3	90
	1/6/76	Eastside	774.0	4.0	93	15.5	6	91
	1/8/76	Eastside	776.5	6.5	90	12.4	6	87
DIZA	1/12/76	Eastside	776.5	6.5	73	34.2	5	90
	1/8/76	Southside	77.0	7.0	96	16.0	6	94
	1/9/76	Southside	778.0	8.0	100	18.7	6	98
	1/12/76	Southside	781.0	11.0	77	29.4	5	95
	1/14/76	Southside	780.5	10.5	104	19.0	1	95
12 0	1/14/76	Southside	782.0	12.0	94	12.1	1	85
ZIA	1/15/76	Southside	782.0	12.0	93	13.3	1	86
EZA	1/16/76	Southside	782.0	23.0	81	25.8	12	88
DA	1/16/76	Southside	782.0	12.0	63	31.6	12	69
24A	1/16/76	Southside	782.0	12.0	75	23.8	12	82
25A	1/19/76	Southside	782.0	12.0	86	26.0	12	93
26	1/20/76	Northside	783.0	13.0	101	23.2	1	92
27	1/21/76	Southside	784.0	14.0	102	19.1	1	93
28	1/22/76	Eastside	776.0	6.0	9 8	19.8	6	95
29	2/19/76	Westside	776.0	6.0	125	5.3	8	94
30	2/20/76	Westside	778.0	8.0	126	7.8	8	95
B ĩ	2/20/76	Westside	780.0	10.0	125	7.8	8	94
	2/20/76	Westside	782.0	12.0	128	6.1	8	96
32 33	2/21/76	Eastside	778.0	8.0	122	8.5	8	92
-39 34	2/21/76	Eastside	780.0	10.0	126	8.5	8	94
35	2/21/76	Eastside	782.0	12.0	127	8.2	8	95
36	2/23/76	Eastside	784.0	14.0	129	8.7	8	97
20	4123110	Lastalde						

CONVERSE DAVIS DIXON ASSOCIATES

Test Date	Test Location	Approx. Test Elevation <u>Feet</u>	Approx. Depth of Fill Below Test Feet	(1) Dry Density <u>P.C.f.</u>	Field Moisture Content Percent of Dry Wt.	(2) Soil Type	Percen Com- paction
4/19/76	Westside	784.0	14.0	126	12.1	8	95
4/19/76	Westside	785.0	15.0	126	10.5	8	95
4/20/76	Northside	776.0	6.0	99	22.0	6	97 🗃
4/20/76	Northside	778.0	8.0	120	10.2	8	90
4/20/76	Northside	780.0	10.0	127	11.0	8	95
4/21/76	Northside	781.5	11.5	125	12.2	8	94
4/21/76	Northside	783.0	13.0	123	8.3	8	92
4/21/76	Northside	784.5	14.5	130	9.4	8	97
4/22/76	Northside	784.5	14.5	122	13.4	8	92
5/3/76	Sewer - West	784.0	2.0	125	9.4	8	94
5/3/76	Sewer - West	784.0	2.0	111	9.0	8	84
5/4/76	Sewer - West	784.0	2.0	125	10.0	8	94
5/3/76	Storm Drain - Southwest	786.0	3.0	122	12.8	8	92
5/ 3/76	Storm Drain - Southwest	788.0	5.0	128	11.2	8	96
5/4/76	Storm Drain - Southw e st	790.0	7.0	101	16.0	1	92
5/4/76	Westside	786.0	16.0	122	12.0	2	93
5/4/76	Southside	786.0	16.0	121	9.0	2	93
5/5/76	Southside	786.0	3.0	9 7	23.4	6	95
5/576	Westside	786.0	16.0	94	17.6	6	92
5/5/76	Southside	787.0	17.0	95	234	6	94
5/5/76	Southside	787.0	17.0	94	28.9	6	92
5/576	Westside	787.0	17.0	95	23.4	6	93
5/6/76	Westside	788.0	18.0	96	21.3	6	94
5/6/ 76	Westside	788.0	18.0	92	17.8	6	91
5/6/76	Southside	788.0	18.0	96	22.4	6	94
5/6/76	Southside	792.0	12.0	91	22.0	6	90
5/7/76	Westside	789.0	19.0	94	22.0	6	92
5/7/76	Southside	789.0	19.0	94	16.6	6	92
5/7/76	Westside	789.0	19.0	97	22.7	6	95
5/7/76	Southside	789.0	19.0	97	20.0	6	95
5/10/76	Eastside	786.J	16.0	94	18.6	6	92
5/10/76	Eastside	786.0	3.0	97	20.1	6	95
5/10/76	Eastside	787.0	17.0	96	15.8	6	94
5/10/76	Eastside	787.0	17.0	9 6	13.6	6	94
5/11/76	Eastside	788.0	18.0	94	15.6	6	92
5/11/76	Eastside	788.0	5.0	98	20.9	6	96
5/11/76	Eastside	789.0	19.0	97	16.0	6	95
5/12/76	Sewer - North	780.0	1.0	9 8	20.1	6	96
5/12/76	Sewer - North	782.0	3.0	95	21.7	6	93

CONVERSE DAVIS DIXON ASSOCIATES

Field

	1					Field		19
			Approx.	Approx.	(1)	Moisture		
	- -		Test	Depth of	Dry	Content	(2)	Percent
	Test		Elevation	Fill Below	Density	Percent	Soil	Com-
	Date	Test Location	Feet	Test Feet	p.c.f.	of Dry Wt.	Туре	paction
	5/12/76	Sewer - North	784.0	5.0	93	17.2	6	91
đ.	5/13/76	Sewer - North	785.0	6.0	96	20.5	6	93
	5/13/76	Southside	784.0	1.0	94	16.8	6	91
	5/13/76	Southside	785.0	2.0	102	15.1	3	93 薀
	5/14/76	Southside	786.0	3.0	87	16.5	3	80 🗿
74	5/20/76	Southside	786.0	3.0	104	19.4	3	95
	5/18/76	Southside	791.0	21.0	119	12.3	9	93
	5/18/76	Westside	790.0	20.0	117	12.1	9	92
1	5/19/76	Eastside	787.5	15.0	122	9.8	9	95
	5/19/76	Eastside	790.0	7.0	108	12.8	9	85
6	5/20/76	Eastside	790.0	7.0	115	11.1	9	90
j.	5/19/76	Eastside	789.0	19.0	116	12.2	9	91 🕺
	5/20/76	Eastside	791.5	21.5	118	8.2	9	92 📲
1.0	5/20/76	Eastside	792.5	22.5	114	8.4	9	90
	5/21/76	Westside	788.0	18.0	117	15.9	9	91
.	5/21/76	Westside	791.0	21.0	118	13.1	9	9 2
	5/24/76	Eastside	791.0	21.0	121	10.9	9	95
	5/24/76	Westside	789.5	19.5	118	16.1	9	92
	5/24/76	Westside	790.5	20.5	120	13.9	9	94 📲
	5/25/76	Westside	790.5	2.0	125	9.8	9	92 94 97 97 93 90
4 3	5/25/76	Westside	792.5	22.5	125	9.3	9	97 🧃
Pi A	5/25/76	Westside	792.0	3.0	119	10.4	9	93 🛔
5	6/15/76	Northside	784.0	10.0	111	11.6	7	
	6/15/76	Northside	783.0	5.0	113	11.1	7	91
	7/13/76	Southside	787.5	2.0	9 9	17.0	6	97
	7/13/76	Northside	772.5	2.5	115	15.0	7	93
1	7/13/76	Southside	790.0	5.0	96	19.5	6	94 🛛
	7/13/76	Southside	792.0	7.0	95	19.7	6	93
	7/14/76	Northside	774.0	4.0	113	15.0	7	91
	7/14/76	Southside	789.5	4.5	103	14.5	1	93
6	7/14/76	Southside	790.5	5.5	100	24.0	1	91
art.	7/14/76	Northside	773.0	2.0	94	11.0	6	92
	7/14/76	Southside	792.5	7.5	9 9	6.0	1	90
9	8/10/76	Northside	774.0	6.0	116	14.1	9	91
013	8/11/76	Northside	776.0	7.0	100	19.4	1	90 💈
卷	8/11/76	Northside	777.0	9.0	102	16.7	1	92 90 91 90 93 93
2	8/12/76	Northside	779.0	9.0	107	17.2	1	70 g
3	8/12/76	Northside	780.0	10.0	102	18.1	1	93
	8/13/76	Northside	782.0	12.0	116	10.4	9	91
5	8/ 13/76	Northside	784.0	14.0	102	19.3	1	93
								,e.

CONVERSE DAVIS DIXON ASSOCIATES

49-DG

No. 75-149-DG

50

	Test <u>Date</u>	Test Location	Approx. Test Elevation <u>Feet</u>	Approx. Depth of Fill Below Test Feet	(1) Dry Density <u>p.c.f.</u>	Field Moisture Content Percent of Dry Wt.	(2) Soil <u>Type</u>	Perce Com pactio
	8/13/76	Northside	786.0	16.0	118	9.7	9	92
214) 672	8/16/76	Northside	787.0	17.0	110	10.9	1	91
	8/16/76	Northside	787.0	17.0	109	4.8	3	90
1.	8/24/76	Northside	789.5	19.5	112	11.7	11	96 🛔
74 49	8/24/76	Northside	788.5	18.5	106	7.9	11	91
1	8/24/76	Northside	786.0	2.0	107	8.2	11	92
	8/25/76	Northside	787.5	17.5	105	6.0	11	91
ЦR.	8/25/76	Northside	790.0	20.0	102	8.0	11	88
	8/25/76	Northside	790.0	20.0	109	12.2	11	94
	8/25/76	Northside	790.0	17.0	110	13.0	11	95
rak Latio	8/26/76	Northside	787.5	0.5	112	11.1	11	96
	8/26/76	Northside	790.0	0.5	108	15.4	11	93
	8/26/76	Northside	790.0	15.0	106	9.0	11	91
	8/27/76	Northside	790.0	18.0	105	17.4	1	95
	8/27/76	Northside	791.0	2.0	106	17.0	11	91
	8/27/76	Northside	791.0	21.0	99	17.7	11	91
	8/31/76	Northside	793.0	23.0	123	10.5	10	92
	8/31/76	Northside	792.5	19.0	128	11.5	10	96
	9/1/76	Northside	791.0	1.5	120	10.0	8	90
	9/1/76	Northside	792.0	2.5	125	13.0	8	94
	9/20/76	Elec. Trench - North	786.0	2.0	119	12.8	8	90
ia del Se	9/21/76	Stairwell - North	784.5	2.5	119	11.7	.8	90
	9/21/76	Elec. Trench – North	792.0	2.0	104	14.6	11	90
	9/21/76	Stairwell - North	784.0	2.0	109	10.8	8	82
A	9/21/76	Stairwell - North	784.0	2.0	121	10.2	8	91 94
	9/21/76	Stairwell - North	788.5	6.5	125	12.9	8	94
	9/21/76	Elec. Trench -	793.0	3.0	121	12.8	8	91
Î.	9/21/76	Stairwell - North	788.0	6.0	122	10.4	8	92
ĩ	9/28/76	Pipe - North	791.5	21.5	108	6.8	11	92
	9/28/76	Pipe - North	793.0	23.0	123	10.2	.8	92 94
•	12/9/76	Canopy Footing Line	790.0	1.0	111	17.0	13	
	12/9/76	Canopy Footing Lin e	790.0	1.0	106	18.6	13	90
2 2	12/9/76	Canopy Footing Line	791.5	2.5	113	16.5	13	96
	12/9/76	Canopy Footing Line	791.5	2.5	113	15.5	13	96
	12/9/76	Canopy Footing Line	792.0	3.0	108	10.8	13	92

COTIVERSE DAVIS DIXON ASSOCIATES

	Test Date	Test Location	Approx. Test Elevation <u>Feet</u>	Approx. Depth of Fill Below Test Feet	(1) Dry Density p.c.f.	Field Moisture Content Percent of Dry Wt.	(2) Soil Type	Percen Com- paction
	12/9/76	Canopy Footing Line	791.5	2.5	111	11.1	13	94
	12/9/76	Canopy Footing Line	793.0	4.0	116	12.1	13	98
	12/10/76	Canopy Footing Line	790.5	1.0	111	13.8	13	94
	12/10/76	Canopy Footing Line	791.0	1.5	119	12.5	13	100
	12/10/76	Canopy Footing Line	792.0	2.5	113	11.7	13	96
	12/10/76	Canopy Footing Line	7 93. 0	3.5	111	13.2	13	94
	12/15/76	Canopy Footing Line	789.5	1.0	113	12.4	13	96
	12/15/76	Canopy Footing Line	790.5	2.0	119	12.6	13	100
	12/15/76	Canopy Footing Line	790.0	1.5	116	13.0	13	98
50	12/15/76	Canopy Footing Line	791.5	3.0	113	13.2	13	96
	12/15/76	Canopy Footing Line	791.0	2.5	111	13.4	13	94
	12/15/76	Canopy Footing Line	792.0	3.5	107	13.1	13	91 97
163	12/15/76	Canopy Footing Line	792.5	4.0	114	13.9	13	97 92
	12/15/76	Canopy Footing Line	789.0	0.5	109	16.9	13	96
155	12/16/76	Canopy Footing Line	789.0	0.5	113	13.9	13	96 94
166	12/16/76	Canopy Footing Line	789.5	1.0	111	16.0	13	93 1
167	12/16/76	Canopy Footing Line	790.0	1.5	109	13.4	13	97
168	12/16/76	Canopy Footing Line	790.5	2.0	114	14.7	13	95
169	12/16/76	Canopy Footing Line	791.0	2.5	112	14.0	13	1
170	12/16/76	Canopy Footing Line	791.5	3.0	110	16.7	13	93
171	12/16/76	Canopy Footing Line	792.0	3.5	104	12.8	13	88
173A	12/16/76	Canopy Footing Line	792.0	3.5	104	13.8	13	88
174A	12/16/76	Carropy Footing Line	792.0	3.5	114	12.8	13	96
22 172	12/16/76	Canopy Footing	791.0	3.0	118	12.9	13	100
		CONVERSE	DAVIS DIX	ON ASSOCIAT	ES			

ala de la compañía de S IS TELE

Test Date	Test Location	Approx. Test Elevation <u>Feet</u>	Approx- Depth of Fill Below Test Feet	(1) Dry Density <u>p.c.f.</u>	Maisture Content Percent of Dry Wt.	(2) Solit Type	Pere Cor pact
12/16/76	Canopy Footing	793.0	4.5	112	14.2	13	95
12/17/76	Canopy Footing Line	788.0	0.0	111	15.0	13	94
12/17/76	Canopy Footing Line	788.0	0.0	115	14.2	13	97
12/17/76	Canopy Footing Line	789.0	1.0	112	14.6	13	95 98
12/17/76	Canopy Footing Line	788. <i>5</i>	0.5	116	15.2	13	-
12/17/76	Canopy Footing Line	789.5	1.5	117	13.5	13	99
12/17/76	Canopy Footing Lin e	790.0	2.0	113	14.6	13	96
12/17/76	Canopy Footing Line	790.5	2.5	113	14.2	13	96 10
12/17/76	Canopy Footing Line	791.0	3.0	11 8 110	1 2.9 16.3	13 13	93
12/17/76	Canopy Footing Line	791.5	3.5	125	9.3	10	93
1/16/77	Retaining Wall Line	788.0 790.0	1.5 3.5	123	13.3	10	91
1/28/77	Retaining Wall Line	790.0	5.0	115	13.3	9	90
1/31/77 2/2/77	Retaining Wall Line Retaining Wall	795.5	2.0	102	19.0	3	94
2/2/77	Line Retaining Wall	797.5	4.0	100	14.7	3	93
2/4/77	Line Retaining Wall	798.0	4.5	109	17.5	3	10
3/2/77	Line Retaining Wall	799.5	6.0	105	16.9	3	96
	Line Detailing Wall	800 0	6.5	119	12.8	2	92

Density of the compacted fill was determined in the field by the A.S.T.M. D1556-64 sand cone test.

800.0

794.0

802.0

796.0

802.0

119

121

113

113

113

6.5

1.5

7.0

3.0

8.0

12.8

11.2

14.8

12.7

8.7

92

93

93

93

93

2

2

4

4

4

Soil type is given on Table II, Laboratory Maximum Density Tests.

Tests taken to recheck areas of substandard compaction.

Retaining Wall

Retaining Wall

Retaining Wall

Retaining Wall

Retaining Wall

Line

Line

Line

Line

Line

192

193

194

195

196

(1)

(2)

4/27/77

4/27/77

5/17/77

5/17/77

6/6/77

CONVERSE DAVIS DIXON ASSOCIATES

alect No. 75-149-DG


TABLE II LABORATORY MAXIMUM DENSITY TESTS*

<u>Soil</u>	Туре	Soil Description	Maximum Dry Density, p.c.f.	Optimum Moisture Content-Percent
Ха.	1	Black CLAY with Diatomaceous SHALE	110	14.3
	2	Brown SILTY SAND and GRAVEL	130	8.3
	3	Light Brown SANDY SILT	109	16.7
	4	Brown SANDY SILT (Import)	121	10.2
	5	Light Brown SILTSTONE and Dark Brown SILTY CLAY	81	34.0
	6	Dark Brown SILT with Diatomaceous SHALE	102	18.0
444 	7	Dark Red-Brown CLAYEY SAND (Import)	124	12.5
1 13	8	Brown SILTY SAND D.G. (Import)	133	9.6
	9	Brown Fine SANDY SILT with GRAVEL (Import)	1 28 °	9.8
.	10	Red-Brown SILTY SAND (Import)	134	7.5
1	11	Light Brown SILTY SAND with CLAY	116	11.2
**	12	Mixed Brown SILTY CLAY, SILTSTONE, Dark Brown SILT with Diatomaceous SHALE	92	29.0
**	13	Black SANDY CLAY	118	15.0

*A.Ş.T.M. D1557-70 test method. **Field Checkpoint.

CONVERSE DAVIS DIXON ASSOCIATES





11x17

CITY OF LOS ANGELES

JUN 29 1977

DEPARTMENT OF BUILDING AND SAFETY

DEPARTMENT OF BUILDING & SAFETY. ENGINEER'S CERTIFICATE OF COMPLIANCE FOR COMPACTION NEXT DEFISE GRADING DIVISION

LOCATION OF FILL: TRACT NO. LOT NOS. _____ Buckley School Pavilion Building and Passage Structureras shown on Drawing Nos. 1 and 2 of report listed below:

JOB ADDRESS: SOLL TESTING AGENCY: PROPERTY OWNER'S NAME OWNER'S ADDRESS: 3900 Stansbury Avenue, Sherman Oaks, California Convenier David Dixon Associates Buckley School

3900 Stansbury Avenue, Sherman Oaks, California

PER REPORTS ON OUR PROJECT NO. 75-149-DG dated June 8, 1977

DATE OF THIS CERTIFICATE:	June 8, 1977
DATE FILL WAS COMPLETED:	June 6, 1977
DATE WORK STARTED ON PROJECT:	December 15, 1975

TO THE SUPERINTENDENT OF BUILDING:

*I hereby certify that I have personally inspected and tested the placing of compacted earth fill on the above described property, and on the basis of these inspections and tests it is my opinion that the same was placed in conformity with the requirements of the Los Angeles City Building Code.

Civil Engineer Algiras G. Leskys California Certificate No. 21783

*For the purpose of this Certificate, to "have personally inspected and tested" shall include inspection and testing performed by any person responsible to the licensed engineer signing this certificate. Where the inspection and test of all or part of the work above is delegated, full responsibility shall be assumed by the licensed engineer whose signature is affixed thereon.

X B&S G-22 4.67


Melians Melians Winnager	TY OF LOS ANGEL CALLEGRNIA	DEPARTMENT OF BUILDING AND SAFETY 402, CITY HALL LOS ANGELES, CALIF. 90012
	TOM BRADLEY	
Anakley School 100 Stansbury Ave. 100 Stansbury Ave. 100 Stansbury Ave. 11 12 12 12 12 12 12 12 12 12	DAT PER	TE: 53311 MIT: LA 53311 7327
TAL Soil classificatio	on, per Table 28-A: See r	eropt
Lots having compacted f		
described in the compac	compacted fill construct tion report dated	B. 1977 ,
No. 75-119-Da	VIE-DIRON ARABA	Report
A. Footings for one-st Table 17-B without	the area shown in the rep ory wood-frame structures use of the soil bearing v	may be dimensioned from alue.
approved compacted		
 D. Dwelling foundation ground shall meet th E. Slope erosion control runoff control are 	per Code Section 91.3012 s located partially or wh he requirements of Section ol, planting, and irrigat required as per Code Sect	olly upon compacted fill n 91.3012. ing of fill slopes, and ion 91.3007.
of slopes 20 feet of between 1½ horizont Where the vertical 1	re footings shall be set r less in vertical height al to 1 vertical and 2 ho height of slope exceeds 2 ed above, the set back sha	where the slope angle is rizontal to 1 vertical. O feet and the slope
for each additional maximum set back of	5 feet in vertical heigh 10 feet. For slopes exce e set back shall be 40 fee	t over 20 feet to a eeding 100 feet in
· See report dated Jar	nuary 27, 1972.	
R.J. WILLIAMS General Manager By	footing exe they are fo strate befo	ngineer shall inspect the cavations to determine that bunded in the recommended ore calling the Department inspection.
By F.R. Dauer, Greding		
B (S.B-142 R11.74		Tuist Westerneiden ander west

Consulting Engineers and Geologists

REE, DAVIS AND ASSOCIATES

126 West Del Mar Boulevard, Post Office Box 2268D, Pasadena, California 91105 Telephone (213) 681-1121

December 13, 1972



四方:"你们,你们的

P and A Construction Co., Inc. 1200 West 220th Street Torrance, California 90502

DEPARTMENT OF BUILDING & SAFETY VAN NUYS DISTRICT OFFICE GRADING DIVISION

LOTI

Attention: Mr. William N. Weeger

Subject:

ct: Project No. 72-245-DG, Report on Compacted Fill Maintenance Building, The Buckley School 3900 Stansbury Avenue, Sherman Oaks, California

Gentlemen:

TRACT 23823

This is to report the results of tests and observations made during the placement of compacted fill on the subject site.

Periodic tests and inspections were provided by a representative of Converse, Davis and Associates to check the grading contractor on compliance with the drawings and job specifications. The presence of our field representative at the site was to provide to the owner a continuing source of professional advice, opinions and recommendations based upon the field representative's observations of the contractor's work and did not include any superintending, supervision or direction of the actual work of the contractor or the contractor's workmen. The opinions and recommendations presented hereafter are based on our tests and observations of the grading procedures used, and represent our engineering judgment as to the contractor's compliance with the drawings and job specifications.

The grading operation was observed to be performed in the following general manner:

1. Vegetation, surface trash and miscellaneous debris were cleared from the areas to be graded and were hauled off the property.

and the last live of the contained of the second state of the second state of the second state of the second st

Pasadena, Anaheim, Las Vegas

P and A Construction Co., Inc. Project No. 72-245-DG December 13, 1972 Page two

- 2. Unsatisfactory soils were excavated to expose competent materials on which to start the fill. Portions of an existing fill placed in 1965 under engineering inspection by Advanced Foundation Engineering, Incorporated, Consulting Foundation Engineers, were encountered during this excavation. This previously placed fill was inspected and found to be suitable to receive the new fill.
- 3. Approved soils were placed in layers on the prepared surface, and each layer was compacted to the specified density before the next layer was added.
- Placement of the compacted fill was continued to the final grades indicated on Drawing No. 1.
- The minimum acceptable degree of compaction was
 90 percent of the maximum density.
- 6. Maximum density and optimum moisture content were determined by the A.S.T.M. D1557-70 method.
- 7. The soils used in the compacted fill consisted of sandy silt and silty sand with gravel and were classified as nonexpansive with respect to volume-change characteristics. A list of soil types encountered during testing is presented in the "Table of Test Results."

Field density tests were made during the placement of fill to determine the degree of compaction and moisture content. Where tests or field observations indicated insufficient density, additional compaction with adjustment of the moisture content where necessary was performed before the next layer was added. All field density tests are listed in the "Table of Test Results," and their approximate locations are shown on Drawing No. 1. Also shown are the limits and depths of the controlled fill placed during this grading operation.

Undisturbed samples were obtained from the compacted fill. The samples were obtained by hand driving a thin-walled steel sampler. One sample was tested at varying normal loads in a direct shear machine to determine the Coulomb

CONVERSE, DAVIS AND ASSOCIATES

A TANK AND A DESCRIPTION OF A DESCRIPTIO

P and A Construction Co., Inc. Project No. 72-245-DG December 13, 1972 Page three

shear strength parameter. The sample was saturated and drained prior to testing. The result of the shear test is listed in the "Table of Test Results."

CONCLUSIONS AND RECOMMENDATIONS

Based on the final results of the tests, on observation of the construction procedures used in the field and on our experience, it is our opinion that the controlled compacted fill shown on Drawing No. 1 has been placed in accordance with the applicable portions of the job specifications and with the recommendations of Converse, Davis and Associates. The compacted fill discussed in this report will support spread footings, slabs-on-grade, and pavement. Any fill added beyond the limits or above the grades shown should be placed under engineering control and in accordance with the specifications, if it is to be covered by the recommendations of this report.

No warranty concerning the performance of the preexisting fill mentioned above, either express or implied, is made by Converse, Davis and Associates by virtue of this compacted fill report.

Footings should be at least 18 inches in width and bottomed 18 inches below lowest adjacent final surface on controlled compacted fill. The permissible bearing value is 2000 pounds per square foot on the proper bearing soils.

It is recommended that all footing excavations be inspected by Converse, Davis and Associates prior to pouring concrete to see that they are into satisfactory soils and are free of loose and disturbed materials. If conditions are encountered during building construction that appear to be different from those presented in this report, this office should be notified.

Our findings have been obtained in accordance with accepted professional engineering practice in the fields of engineering and soil mechanics. This warranty is in lieu of all other warranties, either express or implied.

are a serie a suite distant he liter and the based of the series and the series and the series are a series after the series and the series are a series and the series of the series are a series and the series of the series are a s

The undersigned licensed Civil Engineer certifies that he has personally inspected the placement of and tested the

CONVERSE, DAVIS AND ASSOCIATES

P and A Construction Co., Inc. Project No. 72-245-DG December 13, 1972 Page four

compacted earth fill being reported, and that in his opinion the same was placed in conformity with the applicable portions of the City of Los Angeles Building Code.*

Respectfully submitted,

CONVERSE, DAVIS AND ASSOCIATES

By ject Engineer

Reviewed and approved; C. R. MacFadyen, Principal Engineer

EJJ/CRM:eg

Encl: Table of Test Results I, II and III, Sheets 1 and 2 Drawing No. 1

Dist: (2) Addressee

(2) City of Los Angeles Department of Building and Safety Grading Division

(2) Ragnar C. Qvale and Associates

*For the purpose of this certificate, to "have personally inspected and tested" shall include inspection and testing performed by any person or persons employed by, and responsible to the licensed Civil Engineer signing this report. Where the inspection and testing of all or part of the work above is delegated, full responsibility shall be assumed by the licensed Civil Engineer whose signature is affixed hereon.

CONVERSE, DAVIS AND ASSOCIATES

A Construction ct. No. 72-245-DG mber 13, 1972

TABLE OF TEST RESULTS

Inc.

TABLE I FIELD DENSITY TESTS

Test No.	Test Date	Test Location	Approx. Test Eleva- tion Feet	Approx. Depth of Fill Below Test Feet	(1) Dry Density p. c. f.	Field Moisture Content Percent of Dry Weight	(2) Soil Type	Percent Com- paction
1	10/25/72	East of	821	2	86	20.3	1	71
2-A		Concrete Apron East of	821	2	112	16.7	1	90
- 3	10/26/72		824	2	104	12.0	2	95
4	10/27/72		827	4	113	12.2	1	91
5	10/27/72		829	4	112	12.6	1	90
6	10/27/72		832	7	112	11.2	1	90
7	10/30/72	Concrete Apron East of Concrete Apron	835	8	113	12.8	1	91
8	10/30/72		838	12	115	11.7	1	92
9	10/30/72	Concrete Apron	834	3	112	10.0	1	90
10		Concrete Apron	836	8	113	10.6	1	91
P 11	10/31/72	Concrete Apron	838	6	113	16.4	1	90
12	10/31/72	Concrete Apron	840	10	105	15.9	2	96
13	11/2/72	Concrete Apron	842	6	105	17.9	2	96
14	11/2/72	Concrete Apron	844	8	104	19.1	2	95
15	11/3/72	Building Area	846	6	116	10.5	1	93
16	11/7/72	Building Area	846	2	91	9.0	2	84 90
17-A	11/7/72	Building Area	846	2	113	9.8	1	90
18	11/7/72	Building Area	848	4 8	107 113	13.4 9.5	2	90
19	11/8/72	Building Area	848	o	212	ليه ک لي		

- (1) Density of the compacted fill was determined in the field by the A.S.T.M. D1556-64 sand cone test. Soil samples obtained from the sand cone tests were oven-dried to obtain the field moisture content.
- (2) Soil Type is given on Table II, Laboratory Maximum Density Tests.

A - Tests taken to recheck areas of substandard compaction.

CONVERSE, DAVIS AND ASSOCIATES

and a second second

TABLE OF TEST RESULTS (Cont'd.)

TABLE IILABORATORY MAXIMUM DENSITY TESTS*

Soil Type	Soil Description	Maximum Dry Density, p.c.f.	Optimum Moisture <u>Content-Percent</u>
1	Brown SILTY SAND and GRAVEL	125	9.3
2	Light Brown SANDY SILT	109	16.7

*A.S.T.M. D1557-70 test method.

-245-00

r 13, 1972


...............................


TABLE III

Sam No		Location	Depth Below Finish Grade (Feet)	c (Pounds Per Square Foot)	ø Degrees
•	1	Maintenance Building	1.5	350	27

CONVERSE, DAVIS AND ASSOCIATES

An and the second s





CONSULTING FOUNDATION ENGINEEDS

2210 AIBEST HAAS 1994/1 BEACH, CALIF MOBOS 1924 2333 A24-7345 578 6438 1960 BEACHD 1175 ANDERED 10000 (10).

The Buckley Schools 3900 Stansbury Avenue Sherman Daks, Californie

PROJECT: DUCKLEY SCHOOL 3190 Stansbury Avanue She'rhn Paks, Callfornia

Lenel Description. Portion of Lot | Tract 23823 SUBJECT: Soll Compaction Tests - Progress Report

This report contains the results of Density Tests Nos. I thru 36 taken on the subject project on Jenuary 15 thru 30, 1968. Refer to the attached plot plan, Plate "A", for the location of tests.

MADING

Pathonk 5 Block Coalde

STATE & F. F. F. STON

NAME OF FRANKS

Electer P. HARRISELLE

February 16, 1968 Project 67-2746

REFER . HAMMERS

HINEERING INCOR

APR 1 9 1950

マルナ

and the free

* 1 * * *

Saulestere.

1.4.45 2.4

PREPARATION OF AREAS TO RECEIVE FILL

Frior to the placing of any fill, the area is being cleared of all organic or deleterious material, scarified to a depth of 6 inches and inspected by this issue atory. The area was then recompacted to provide a bonding between natural softs and the fill material.

The natural ground is considered adequate to safely support the imposed fill. In areas of natural slopes, benches are being out into firm natural material every 5 feet in vertical height of fill placed to provide an interlocking effect between the fill and natural soil.

2、111年11月1日(111日))(111日))(111日))(111日))(111日))(111日))(111日))(111日)(111日))(111日))(111日))(111日))(111日))(111日))(11 111日))第一学校教師(111日)和教師本編編新期期(111日)開始期期部第中的「伊斯斯新聞新聞」「新知事」「新聞」「新聞」「新聞」「「「「「「」」」(111日))(111日))(111日))(111日))(111日)) 111日)(111日)(111日)(111日)(111日)(111日))(111日))(111日))(111日)(111日)(111日)(111日)(111日)(111日)(111日)(111日)(111日))(111日)

Fahrungy 16, 1955 Postart 67-2745

PREPARATION OF AREAD TO RECEIVE FILL . conclosed

The structural area in being excevated to natural call and recompacted to ra-

计总线表

The <u>non-structural</u> area is helog scarified at existing surface and compacting additional fill placed to 903 of relative density.

PLACING OF THE FILL

tm

1 A

0

The fill material was out from the site, placed in d instituyers, watered to approximate Optimum Moleture, and compacted to the specified relative compaction of 90%.

The contractors attention is being called to areas failing below the required relative compaction. These areas are being reworked, recompacted and retested until they meet the specified relative compaction.

Tests are being taken every 1.5 feet in vertical height of fill placed to insure complete control of grading operations.

EQUIPMENT ON JOB

1 - Cet. D-8 Dozer 1 - John Deere TD-24 Dozer 1 - Sual 5 × 5 Sheepsfrot Roller

• Votor Truck • Screper

PROGRESS OF JOH

Structural area tested and approved to Elev. 775t to date.

COMPACTION STANDARD - ASTH DISS7-64T

10 pound hermer, 18 inch drop, 25 blows per layer on each of 5 equal layers of soll in a 1/30 cubic foot mold.

Pebruary 16, 1968 Project 67-2746

COMPACTION STANDARD - continued

Material Classification	Maximum Bensity <u>Lus./Cubic Popt</u>	Optimum Holsturn Per Cont
frown sondy slity sloy w/shale fragments Dark brown fine to coarse candy clay Light brown clay w/distomecous and	113.0	16.5 16.0
shale frequents frown silly clay w/shale	100.0 110.0	21.0 17.0

FILLD DENSITY TESTS

State State

0

Tost No.	Wat Density Lbs./Cu.Ft,	t Field Aplature	Dry Donalty Lbs./Cu.Ft.	1 hondinum	Depth of Test	Depth of Fill
1=15-4	•		and the second second second	and the		
	125.5	17.0	107.2	94.8	-0,31	2.01
2	117.2	16,0	101.0	92.7	-0.51	3.01
1	112.6	25.5	89.6	81.4	-1.0*	4.01
4	122.8	22.6	100.2	92.0	-0.51	5.01
1-16-66						
5 .	124.0	18.3	104.7	92.3	-0.5	5.0'
- 6	122.2	16.5	105.0	93.0	-0.5'	6.51
· · · · · · · · · · · · · · · · · · ·	123.2	17.0	105.3	93.3	Astest /	
8	123.8	18.3	104.5	92.5	-0,5'	2.01
- 9	122.0	17.1	104.2	92.3	-1.0'	8.01
10	124.0	18.3	105.3	93.3	-0.5'	5.0'
11	125.4	19.1	105.3	93.3	-0,5*	5.0'
1-18-68	· • • • •					
12	124.0	18.0	105.0	91.0	-0,5'	4.01
13	123.8	17.0	105.0	92.4	•0,91	7.5'
14	121.1	16.0	104,4	91.3	-0,51	10.01
15	122.6	10.0	103.0	90.1	-0.5"	2.01
1=19=68						
16	124.0	17.0	125.9	54.4	-0.5!	13.01
17	121,4	16.5	104.2	91.0	-0,51	8.5.
18 8 5	107.6	16.5	107.5	94.0	-0.5'	5.0.
1-22-68						
19	128,0	10.0	108,5	94.5	-0.5	15.0'
20	119.0	15.0	103.5	90.)	-0,5'	13.0'
21	170.7	15.0	104.4	91.4	•0.5'	٥, ١, ١, ١, ١, ١, ١, ١, ١, ١, ١, ١, ١, ١,
22	176.4	17.0	100.0	94.3	•0.51	3.0'
1-26-68						
23	119,2	20.5	91.5	91.5	*1.0'	15.0'
24	119.2	20.0	99 . A	90,3	-1,01	12,01
25	115.8	16,0	99.7	90.7	•0.51	19.01
16	120.2	18.0	103.0	98.5	+1.01	17.01
21	121.4	22.0	101,2	92.0	-1,0'	8.0'

•] •

ANVANELD THE ABATTER ENGINEERING INTERPORTED

February 16, 1968 Project 07-2746

 ~ 3.2

in.

Ŷr.

FIELD DENAITY TESTS - contlined

A. A.

Test Liga	Wat Dansley Lie./Cy.Ci.	* Flatd Matsturg	bry Density <u>Lba./Cu.Ft.</u>	3 Montenia Danatev	Depth <u>pf Tent</u>	Depth of Fill
1-29-68 28 29 30 31 1-30-68	100.0 117.4 110.0 116.6	20.5 25.5 21.5 25.5	83.5 93.5 90.5 92.7	83.5 93.5 90.9 92.0	-1.0' -1.0' -1.0' Rotost /	7.0' 20.0' 18.0'
33 33 36 36	1 16 . 4 1 12 . 6 1 17 . 6 1 16 . 4 1 15 . 4	27.4 23.4 85.0 24.0 33.0	91.3 91.0 94.0 93.0 67.0	21.3 1.0 23.0 97.6	-),0* -),0* -),0* -),0*	20.0' 23.0' 6.0' 12.0' 19.0'

ADVANCED FOUNDATION ENGINEERING, INC.

L'annes Calamater

Stanley C. Davidson

SCOIPLBILE

 . #1

1

0

cc: The Buckley Schools/3 R. C. Qvate & Assoc. Otls Moore

lat lay Civil Engineer



À.

13

1744 Call State and a state of the second state of

			tin y		
行行的分子的	ŧ0:+	地合義	軟約約	希知公科博	建築 氯
594	ia k	e	ين 1		

5

調查

¥.

41【争频:青楼先

April 4, 1968 Project 68-2746

St.

A STATE

1

ann an Alina Ann an Alina Ann an Alina

The Buckley Schools 3900 Stansbury Avanua Sharman Daks, California

PROJECT: BUCKLEY SCHOOL - 3190 Stansbury Avenue She - In Joks, California

Leave Description: Portion of Lot | Tract 23823 SUBJECT: Soll Compaction Tests - Progress Report No. 2

This report contains the results of Density Tests Nes. 37 thru 83 taken on the subject project on February 2 thru March 30, 1968. Refer to the attached plot plan, Plate "A", for the location of tests.

PREPARATION OF AREAS TO RECEIVE FILL

Prior to the placing of any fill, the area is baing cleared of all organic or deleterious material, scarified to a depth of 6 inches and inspected by this icpuratory. The area was then recompacted to provide a bonding between netural solis and the fill material.

The natural around is considered adequate to safely support the imposed fill.

in areas of natural slopes, benches are baing out into firm natural material every 5 feet in vertical height of fill placed to provide an interfacking effect between the fill and natural sull.

ê

April 4, 1968 Project 68+2746

STANCTURAL AREA

的なななな、教育の政治学校の教育

1.4

0

The structural area is being excevated to natural solls and recompacted to required relative density of 90%.

NOH-STAUCTURAL AREA

The non-structural area is being scarified at existing surface and compacting additional fill placed to 90% of relative density.

PLACING OF THE FILL

The fill material was aut from the site and imported, placed in 8 inch layars, watered to approximate Optimum Holsture, and compacted to the specified relative compaction of 90%.

The contractor's attention is being called to areas falling below the required relative compaction. These areas are being reworked, recompacted and retested until they meet the specified relative compaction.

Texts are being taken every 1.5 feet in vertical height of fill placed to insure complete control of grading operations.

EQUIPMENT ON JOB

1 - Cat. 0-8 buzar 1 - John Dears TD-24 Dozer

Water Truck

1 - Dual 5 x 5 Sheepsfoot Roller

Scraper

PROGRESS OF JOB

fill tested to finish grade at north and and to 5' balow finish grade at south and on structural area.

Tested to 3' above existing grade on non-structural area shown on plot plan.

ANVANEED FOLVOUTINN ENGINEERING ENCORPORATED

toril 4, 1968 Projact 68-2246

COMPACTION STANDARD - ASTN 01557-641

10 pound hommer, 18 Inch drup, 25 bleam par layor on each of 5 coust layors of soil to a 1/30 cubic foot mold.

Hatoria) Clancification	Maximum Density Lbs./Cubic Foot	Optimum Moleture Per Cent
Dark brown fine to charpe bondy clay Light brown fine clay w/dietomsceous	114.5	16.0
and shalp fragmonts	100.0	21.0
Brown sliky clay w/shate (import)	110.0	17.0
Light brown clayay modium to coarso		•
sand (import)	119.5	13.0
Yellow brown clay w/diatomaceous (impo Reffini brown clayey fine to coarse	rt) 99.5	23.5
sand (Impurs)	125.0	13.5
Light brown clay w/sandstone (import)	116.0	17.0

FIELD DENSITY TESTS

~}

1 1

Tant	Wet Density	% Fleid	Dry Density	1 Haximum	Depth	Depth
NO.	Lbs./Cu.Ft.	Molsture	Ltis. /Cu.Ft.	<u>Density</u>	of Test	of FIII
2-2-68			•			
37	122.4	30.0	94.5	94.5	+1.0 ¹	25.0'
38	118.0	29,0	91.3	91.3	-1.0'	16.0'
19	113.2	25.0	90.7	90.7	Rotost #	36
40	121,8	\$2.7	92.5	92.5	+1.01	5.0'
41	116.8	28.0	91.2	91.2	*0,2'	1.5'
42	115.4	30.0	69.0	89.0	-0.3'	1.51
43	120.6	29.0	93.3	93.3	-0.2'	2.0'
2-5-68			49 P 23	a ² a ² 5 ∪"		€ • ₩
44	116.2	16.0	100,4	91.3	-1.0'	12.0'
100	112.0	22.0	91.7	91.7	-1.0'	26.0'
46	111.4	22.0	91.3	91.3	-1.0'	14.0'
47	120.2	18.0	103.0	92.7	-1.0'	14.0
2-26-68			10.310	24.17		5 3 2 64.
48	125.0	23.5	101.0	92.0	•0.5'	3.51
49	121.0	22.0	99.2	90.2	40.51	19 6 1 19 6 1
10	120.2	20.0	100,1	91.2	•0.5'	1.51
51	122.4	22,0	100.4	91.3	*0.5*	4.5
\$2	117.6	13.6	101.7	91.0	*0.51	5.11
53	123.4	22.0	101,2	92.2	•0.51	6 . CF *
2-27-68			•••••••	್ರಿಕ್ರಾಂಗ ಹ	¥0" k . 1	19 A 51
54	120,4	19.0	101,2	19 9 2 6 1 6	el.6'	8.0'
55	121.0	20.0	100.8	91.5	~1. 0*	27.0'
56	120.2	18.0	102.9	11.U	• 1 . (5 1	22.01

April 4, 1960 Project 68-2766

York t Here	Wet Denally Lbs./Cu.Ft.	2 Flold Molsture	Dry Denulty Lbs./Cu.Pt.	E Maximum Donally	Gepth of Test	Dupth of Fill
3-1-68						
\$7	112,8	13.6	99.9	90,7	-1.01	26.01
复片	11G. U	16,9	101.7	92.4	-1.0+	19.01
J-70-68			•••			1.2.1.1
52	116.4	16.3	100.2	91.0	-1.0'	6.0'
60	124.6	19.1	104.6	91.3	-1.0'	2.01
61	129.6	13.0	114.3	91.4	-1.0'	29.01
62	121.4	11.1	109.0	90	-1.01	27.01
3-27-68			•	•		16 F 1 10
63	125.8	13.5	110.7	92.5	-0.5'	3.0'
64	129.0	13.0	110.8	92.6	-0.5.	6.5'
65	130.0	15.0	113.0	94.5	=0.3'	2.51
3-28-			, ,	• • •		G: 1 27
66	115.6	10.5	104,9	83.7	-0.5'	5.0'
67	135.6	13.0	119.8	95.7	Recest /C	
68	127.0	14.9	110.0	68.2	•0.51	22.01
3-29-68						
69	131.1	14.9	118.0	94.7	·0.5'	8.0'
70	113.0	14.3	.98.8	79.2	-0.5	11.01
71	131.0	14.9	114.0	91.3	Retent #6	
72	116.3	14.9	101,2	01.2	-0.51	8.0'
73	127.0	13.0	112.3	90.0	Notest #7	
J-30-68						•
74	136.2	15.0	118.0	93.4	Retest #7	2
75	12911	14.9	112.3	90.3	*1.0*	28.01
76	127.6	11.0	115.0	92.0	-1.0'	21.01
77	120.2	11.0	108.4	87.0	·1.0*	24.01
78	119.0	10.0	108.3	86.5	.0.5'	18.01
79	108,4	19.1	90.7	90.7	Ratost 67	
80	136.2	19.0	114.5	51.7	Retest #7	
81	134.6	18.0	113.9	91.2	•1.0'	•
82	122.5	12.0	109.2	91.5		10.01
P • • • • • • • • • • • • • • • • • • •	128.8	13.5	19.3	90.7	-1.0' -0.5'	19.0' 22.0'

FILL DEWELTY TIETS - continued

ADVANCED FOUNDATION ENGINEERING, INC.

San Ley C. Devidson

SCD. SZA: Ir

 \square


C.C Buckley Schools/3 R. C. GVAID & ANNOL. Otly Hoorn


Wen 2. Ahman R.C.E. 16621


確認の

ADVANCED FOREPAREN CENTRA LICA É a r

ARVINE FRINK MERRATIR







P. L. DAILEY

CITY OF LOS ANGELES

DEPARTMENT OF BUILDING AND SAFETY

ENGINEER'S CERTIFICATE OF COMPLIANCE FOR CONSOLIDATED EARTH FILLS

LEGAL DESCRIPTION: POPSION OF SOUT, TPARE 25825

SOIL TESTING AGENCY: ARAANCED FOUNDATION ENDINGERING, INC. PROPERTY DANER'S NUME: Buckley School# OWNER'S ADORESS: AREA TESTEC PERMETURe! Areas PER REPORTS ON OUR PROJECT NO.: 68-2746

DATE MORK STARTED ON PROJECT: December 26, 1967 DATE FILL WAS COMPLETED: April 8, 1968 DATE OF THIS CERTIFICATE: April 18, 1968

TO THE SUPERINTENDENT OF BUILDING

*I horsely sertify that I have personally supervised the placing of consolidated or earth fill on the above described property, and that the same was placed in conformity with requirements of the Los Angeles Building Code of the City of Los Angeles.

ALCEIVED offile Cortificato No. APR 1 3 1958

Hy address is:3310 Alrport Way - Long Beach, California 90806

HARRIST & AND BRID HAR

For the purpose of this Certificate, to "have pursonally supervised" shall include supervision purformed by any person or persons employed by, and responsible to, the licensed anginuer signing this ewrifficate. Where the supervision of all or part of the work above is delegated, full responsibility shall be assumed by the licensed ungineer whose signature is affined hereon. **UTING HEALTHAN**

Considering Foundation anotherable

3310 ANRONT WAY (CMO) BEACH, CALIF VINGA A26-3355 A36-7385 A76-0437 ASM 34406 A24 ANSO16 - 3156 CO.1 DIFFICTURE MANNER & BOULT - PRODUCT BIEST & APERAD Apt. NE Proc ULANER C DAVISION - VIG Proc MANTIFE C. CAEAWAU - Recorded I-CT F DARBINGSTON - PRODUCT

April 12, 1968 -Project 68-2746

ENGINEERING INCORPORATED

The Buskley Schools 3900 Stansbury Avanue Sherman Baks, California

PA. Jacil MICHLEY SCHOOL JIDO Stansbury Avenue Sherman Daks, California

Legal Description: Portion of Lot | Tract 23823

SUBJECT: Soll Compaction Tests - Final Report on Structural Areas

This report contains the results of Density Tests Nos. 84 thru 95 taken on the subject project on April 1 thru 8, 1968. Refer to the attached plot plan, Plate "A", for the location of tests. This report should be used in sonjunction with progress reports 1 And 2.

PRETARATION OF AFRAS TO RECEIVE FILL

ຕ ເດ

. 0

0

Prior to the placing of any fill, the area is being cleared of all organic or deleterious material, scarified to a depth of 6 inches and inspected by this laboratory. The area was then recompacted to provide a bonding between natural solis and the fill material.

The natural ground is considered adequate to safely support the imposed fill. In areas of natural slopes, benches are being out into firm natural material

事实的复数事件 网络中国大学家

PREPARATION OF AREAS TO RECEIVE FILL . continued

every 5 foot in vertical holight of fill placed to provide an interfecting effect between the VIII and natural coll.

NON-STRUCTURAL AREA

The non-structural area is being scarified at existing surface and compacting additional fill placed to 302 of rolative density.

PLACING OF THE FILL

The fift wateriel was cut from the site and imported, placed in 8 inch layers, watered to approximate Optimum Moisture, and compacted to the specified relative compaction of 90%.

The contractor's attention was being called to areas failing below the required relative compaction. These areas were reworked, recompacted and retested until they most the specified relative compaction.

Tests wore taken every 1.5 feet in vertical height of fill placed to insure complete control of grading operations.

EQUIPMENT ON JOB

 \bigcirc

- 1 CAL. D=8 Jozar
- 1 John Deere 10-24 Dozer

- Water Truck 1 · Scraper

1 - Dual 5 X 5 Sheepsfoot Rooler

PROGRESS OF JOH

fill tested to finish grade on structural area, additional fill is being placed in non-structural groas.

ADVANCED VOLVDATION ENGINEERING INCORPORATION

HESOMMENDATION

All recommendations contained in our freliminary foundation investigation dated octuber to, 1967 Project 2007-515 has been complied with and Bearing Values and recommendation contained therein should be used.

10111 12, 1968 Project (R-2746

CONFACTION STANDARD - ASTH DISST-64T

to pound hammer, 18 Inch drop, 25 blows per layer on each of 5 equal layers of soll in a 1/30 cubic foot mold.

Material Chapification	Lhs./Cubic Foot	Optimum Molsture Per Cent
Dark brown fine to coarsa sendy clay	114.5	16.9
Light in the clay w/distomaceous		10111
#1317 年。 F唐 「どの身所の約主旨	100.0	21.0
Brown alls ilay w/shale (Import)	110.0	17.0
Light brown clayey medium to coarse		1110
tang (import)	119.5	13.0
Vellow brown clay w/distomaceous (impor	t) 99.5	•
addials brown clayay fine to coarse	*/ /2/2	23.5
sand (import)	125.0	13.5
light brown clay w/sandstone (import)	116.0	
Light brown very fine to medium	110.0	17.0
eandy clay	109.5	18.5

PIELD DENSITY TESTS

Test	Wet Density	2 Field	Dry Density	2 Maximum	Depth	Depth
No.	Lbs./Cu.Ft.	Moleture	Lbs./Cu.Ft.	Dansity	of Test	of Fill
, 1-68					an an an a san	anan tan dan janggi ijing
84 85 86 87 4-4-68	114,3 120,6 116,0 116,0	12,4 14,9 14,3 14,9	101.3 104.9 101.3 101.0	92.4 95.6 92.4 92.2	-0.5' -0.5' -1.0' -1.0'	14.0+ 7.0+ 3.0+ 3.0+
88	115,0	14,0	101.6	92.0	-0,51	21.0+
89	118,0	15,0	102.4	93.6	-1,01	14.0+
90	119,2	18,5	100.5	91.8	-0,51	18.0+
91,	122,8	20,5	101.7	92.7	-0,51	20.0+

April 12, 1968 Project 68-2746

FIELD DENSITY TESTS - continued

Test No. 4-8-68	Vot Donstty Lby./Cu.Ft.	2 Flaid Molsture	Dry Density Lbs./Cu.Ft.	1 Max Insum Dena I ty	Popth p! Test	Depth of Fill
93 93 94 95	117,6 119.0 115.8 118.2	12.0 15.0 14.0 14.0	105.0 103.3 101.6 103.7	95.6 94.5 92.6 94.7	-0.3' -0.2 -0.3'	5.0' 5.0' 4.0'

ADVANCED FOUNDATION ENGINEERING, INC.

Stanley collemit


Stanley C. Davidson

SCDIPLBiam

0

ം ന ന ca: Buckley Schools = 3 R. C. Qvale & Assoc. Otis Noore

Tev Civil Engineer



LOS ANGEL CALIFORNIA

·首州中的南· 新杀妇子公主将 会地公 anna an Anna an Anna an Earth an Anna an Anna an



80.000.00

fierantistist sie BUILDING AND DAPPTY FRIERINGHE BRANSTE

Isabelle Buckley Schools 3190 Stansbury Avenue Sherman Oaks, Gallfornia

TRACTI 2 9 Rona LOT 1 LOCATION: 3900 Stansbury Avenue

DATE: ANTEL 20. 1968

PENTI la 59345

Fill soil classification, per Table 28-A: Bandy Clay

Lote hearing compacted fills

Attended Brundation Protineering, Title , Rabort No. 68-8746


Approval is limited to the area shown in the report and by the following requirements:


- Footings for one-story wood frame structures may be dimensioned Α. from Table 17-B without use of the soil bearing value. Ŋ,
- Footing bearing pressure for all other structures shall not exceed a value of 8200 1bs. per sq. ft. at 1900 inches minimum, below approved compacted surface. Ĉ.
- Continuous footings per Code Section 91.3012 are required. D.
- All rootings supported partly or wholly on compacted fill shall be reinforced continuously with at least one number 4 bar at the top and bottom of the footing. E.
- Blope erosion control, planting, and irrigating of fill slopes, and runoff control are required as per Code Section 91.3007. Building or structure footings shall be set back 5 feet from the face of slopes 20 feet of less in vertical height where the angle of slope is between 15 horizontal to 1 vertical and two borizontal to 1 vertical where the vertical beight of slope F. horizontal to 1 vertical. Where the vertical height of slope exceeds 20 feet and the angle of alope is as described above the set back shall be increased 1 foot for each additional 5 feet in vertical height over 20 feet to a maximum set back of 10 feet. For slopes exceeding 100 feet in vertical height, the set back shall be 40 feet except as parmitted in Code Section 91,3009 (a),


Hefer to above reports for location of non-structural fill press. (). ## Refer to above report, dated April 18, 1968, for additional requirements pertaining to minimum frotting depens.


Buperintendent of Bullding


By___ DM#____ W. HARTYONN PAS B-142 RI. 60 Advanced Presidentics Ingineering, Inc. 696













1461 E. CHEVY CHASE DR. #200, GLENDALE, CA 91206 818•549•9959 TEL 818•543•3747 FAX "Trust the Name You Know"

> October 20, 2006 JB 19376-B

The Buckley School % Jeffrey M. Kalban & Associates 10780 Santa Monica Boulevard, Suite 120 Los Angeles, California 90025-4749

Attention: Susan Oakley

Subject

Addendum Geologic and Soils Engineering Exploration Proposed Addition, Four New Buildings, Retaining Walls, and Swimming Pool The Buckley School Lot 1, Tract 23823 3900 Stansbury Avenue Sherman Oaks, California

References: Report by The J. Byer Group, Inc.:

Geologic and Soils Engineering Exploration, Proposed Addition, Four New Buildings, Retaining Walls, and Swimming Pool, The Buckley School, Lot 1, Tract 23823, 3900 Stansbury Avenue, Sherman Oaks, California, dated June 6, 2006.

Response Letter by City of Los Angeles (LADBS):

Geology and Soils Report Correction Letter, Log # 54269, dated September 1, 2006.

Gentlepersons:

The J. Byer Group, Inc., has completed our addendum report which provides the additional information requested by the City of Los Angeles, Department of Building and Safety,

RESPONSE

1.

Identify the access road from the school entrance to the athletic field and the existing storm drains, on the map and on the appropriate cross-sections. Provide an evaluation of the settlement characteristics of the existing fill and a detailed justification demonstrating that potential future settlement of the fill, will not result in future damage or excessive settlement to the access road surface. Alternatively, revise recommendations for new fill, to be placed in compliance with section 7011.3 of the LA City Building Code and identify details on the map and cross-sections.

Response: The existing access road and the easement for storm drain and sewer purposes have been plotted on the enclosed Geologic Map and cross Sections A, B, C, and D. Cross Section A was used to evaluate future settlement from the proposed fill to be placed over the existing fill. Our calculations indicate that up to five inches of settlement could occur as a result of placing fill over the existing fill. This settlement could affect the existing sewer and storm drain pipes which are shown on Section A. As an alternative to using fill to raise the grades, the proposed access road could be supported on a structural deck which can derive support from the piles for the proposed main academic building and the piles for the academic building to the west. The proposed project as shown on the enclosed Geologic Map is a conceptual master plan drawing which may be revised. The purpose of the report is to submit the master plan to the various agencies for their review and comment. The department will be provided with plan review and update reports as the project is prepared for submittal to the building department.

2. The report indicates (see pages 4 and 12) that the "natural drainages" which enter from the east can be sources of eroded soil material and will carry natural runoff, on to the site. Provide recommendations for mud/debris flow control systems within and at the base of concentrated drainage areas using the minimum design parameters specified in section 7014.3 of the LA City Building Code. The entire contributing watershed area on the slopes above the property shall be identified on the topographic map. If such evaluation is to be performed by a licensed civil engineer, include a wet-signed original and two copies with the addendum.

The J. Byer Group, Inc.

1461 East Chevy Chase Drive • Suite 200 • Glendale, California 91206 • (818) 549-9959 • Fax (818) 543-3747 "Trust the Name You Know"

- Response: The secondary drainages will be captured through the use of debris basins and storm drains. These features will be designed by the project civil engineer. The current report is a planning document with respect to obtaining approval for a master plan. Details of the grading and drainage will be furnished at a later date.
- 3. Explain what the approximately 220-feet long (and about 2-feet-wide) line on the map shown on the slope within the existing natural drainage course (above location TP-3 and the curvilinear structure), represents. Note: A similar line on the map is also shown within the natural drainage area in the southern portion of the site (canyon to the east of locations TP-11 and TP-12). If the line represents an existing pipe or other device that conveys slope drainage, provide recommendations and show on the map how drainage will be conveyed around the buildings in a non-erosive device to a location that is acceptable to the Department.
- Response: The two-foot wide line shown on the map is drafting error. The original survey shows that the bottom of the drainage course in its natural condition. The line shown on the map above the athletic field bleachers is a dirt path. Details of the site drainage plan are not available, but will be provided at a later date. The current map shows the proposed master plan which will require approval at the various agencies. Once approved, detailed plans will be provided the department.
- 4. Provide the test pit logs for exploration conducted at locations TP-11 and TP-12.
- Response: Test Pits 11 and 12 were not excavated and were deleted from the exploration program. Therefore, no logs exist. The Geologic Map has been revised.
- 5. Explain what the two curvilinear structures shown east of the proposed Main Academic Building represent. Indicate if these structures are existing, or proposed. If they are existing, clarify if they will be removed or if they will remain. If they are proposed, explain if they will part of the proposed building or, will be detached from the building.
- Response: The curved structure is a seat wall for the lunch area. The larger structure to the north is also a concrete seat wall.

The J. Byer Group, Inc.

1461 East Chevy Chase Drive • Suite 200 • Glendale, California 91206 • (818) 549-9959 • Fax (818) 543-3747 "Trust the Name You Know"

6. It appears from the recommendations provided on page 20 of the report, that removal of the porous, unsuitable upper portion of the alluvium will be required if the floor slab of the Main Academic Building is to be supported on newly-placed certified compacted fill. Shoring is planned to facilitate removal along the west and south sides. Clarify how any removals for building construction and setback wall/slope protection wall construction, will be achieved along the southeastern portion of the building and along the entire length of the building, on the east side.

Provide additional geologic cross-sections drawn through the proposed building, any setback wall and/or slope protection walls proposed and, the immediate slope located above the walls to illustrate the proposed construction.

- Response: The final design of the Academic Building and the finished floor elevations are not determined. This report is a planning document for approval of the Master Plan. The Department will be furnished with a plan review and update report for each of the structures and developments shown on the Master Plan during the building permit process. All removals, temporary slopes, grading, and structures will conform to the requirements of LADBS. The proposed structure will conform to the Building Setback code as required by LADBS. Additional cross sections are not necessary at this time, but will be provided for the plan review and update report once the formal plans are available.
- 7. Verify using the sections requested, that the entire face of the new Main Academic Building will be provided the required level clearance building setback and, identify the required setback on all cross-sections drawn through the Main Academic Building.
- Response: The proposed academic building is shown on Sections A and C, which indicate adequate setback from the ascending natural slope. Formal plans for the project have not been prepared and await approval of the master plan by the various agencies. The proposed academic building will conform to all applicable codes of the LADBS.

8. It appears from the documented geologic orientation (N88W; 31N) plotted on the map, that the correct location for test pit TP-6 is between the proposed toe of slope wall and the Library Building. A location TP-6 is also shown on the east side of the proposed Main Academic building (east of TP-5). Please explain, verify and correct, as necessary. Provide an exploration log, if applicable.

- Response: Test Pit 6 is on the west side of the project located at the point where the excavation was performed. The bedding plane attitude is shown west of the test pit because of the crowded nature of the lettering on the map. Test Pit 6, shown east of the Academic Building, was deleted and moved to the west side as plotted on the Geologic Map. The bedding plane orientations shown on the Geologic Map are consistent on both the east and west sides of the main canyon and are consistent with trends from north to south. These bedding plane attitudes were obtained from the test pits and are considered more reliable than the regional attitudes shown on the City Map.
- 9. The geologic data on the slope above the proposed Main Academic Building is limited to the one orientation from location TP-5. The mapped strike and dip on the City map page 67, shown on the slope in this area, indicates a near east-west strike and a north dip of 16 degrees. Provide additional data with regard to the bedrock orientation on the slope using additional mapping and/or exploration.
- Response: The geologic data at the site is consistent on both the east and west sides of the central canyon. Bedding plane attitudes measured by The J. Byer Group are consistent with those shown on the Regional Geologic Map prepared by the Dibblee Foundation in 1991.
- 10. It appears that geologic cross-section I-I was not drawn through the slope directly above the proposed Main Academic Building. Provide two additional geologic cross-sections drawn through location TP-5. The sections shall be extended up to show the <u>entire slope</u> both in the north-south direction (general true dip direction) and, along the steepest portion of the slope (perpendicular to contours). Provide stability evaluation along these sections using appropriate strengths and demonstrate that the slope above the proposed building will have the required minimum factor of safety of 1.5 for long-term stability (gross and seismic).


The J. Byer Group, Inc.

¹⁴⁶¹ East Chevy Chase Drive • Suite 200 • Glendale, California 91206 • (818) 549-9959 • Fax (818) 543-3747 "Trust the Name You Know"

Note: The subject property on Plate A of the DMG Open-File Report 95-02 is shown as being in an area of "weak bedrock" which consists of thin-bedded, densely jointed siltstone, platy shale, and fine-grained sandstone units" of the Modelo Formation which was "severely affected" by the Northridge Earthquake.

- Response: Cross Section J has been drawn through the location of Test Pit 5 and includes the top of the ridge. This new section is shown on the enclosed Vicinity Map #2 and was used for the additional slope stability analysis. A north-south cross section was not prepared as the bedding planes within the diatomaceous siltstone bedrock dip to the north and the strike is perpendicular to the slope. The bedding planes are not unsupported in the down dip direction. The calculation indicates that the slope above the proposed academic building is grossly and seismically stable with a factor of safety in excess of the LADBS standard. The geologic and geotechnical conditions are based upon site specific exploration and borings. Exploration and testing was not performed as part of the DMG Open File Report 95-02.
- 11. Revise recommendations as necessary and provide an itemized response to this letter.
- Response: This report contains an itemized response to the correction letter dated September 1, 2006.


Should you have any questions, please feel free to contact the undersigned.





Enc: City of Los Angeles Geology and Soils Report Correction Letter, dated September 1, 2006 (3 Pages)
Revised Sections A, B, C, and D (2 Sheets)
Section J
Vicinity Map #2
Slope Stability Analysis (24 Pages)

In Pocket: Revised Geologic Map


- xc: (4) Addressee
 - (4) Bruce A. Miller & Associates
 - (1) Englekirk & Sabol, Attention: Bill Wallace
 - (1) Project Development Group, Attention: James J. Shelton, Jr.
 - (2) Latham & Watkins, LLP, Attention: David F. Thompson (Include two copies of June 6, 2006)







11x17



LA CITY BLDG & SAFTY Fax:213-482-0497

Sep 11 2006 12:58 P.01

BUILDING AND SAFETY COMMISSIONERS

5

JAVIER NUŇEZ PRESIDENT

MARSHA L. BROWN VICE-PRESIDENT VAN AMBATIELOS

PEDRO BIRBA ELENORE A. WILLIAMS



ANTONIO R. VILLARÁIGOSA MAYOR

BUILDING AND SAFETY

201 NORTH FIGUEROA STREET LOS ANGELES, CA 50012

ANDREW A. ADELMAN, P.E. GENERAL MANAGER

RAYMOND CHAN EXECUTIVE OFFICER

GEOLOGY AND SOILS REPORT CORRECTION LETTER

September 1, 2006

Log # 54269 SOILS/GEOLOGY FILE - 2

The Buckley School 3900 N. Stansbury Avenue Sherman Oaks, CA 91423

TRACT:23823LOT:Lot 1LOCATION:3900 N. Stansbury Avenue

CURRENT REFERENCERÉPORTDATE(S) OFREPORT/LETTER(S)NO.DOCUMENTPREPARED BYGeology/Soils ReportJB 19376-B06/06/2006The J. Byer GroupOversized Document``````

The referenced report concerning the proposed new construction on the subject 2-acre school property has been reviewed by the Grading Division of the Department of Building and Safety.

The following are proposed: (i) a new 4-level Main Academic Building (two stories of classrooms and offices over two levels of partial subterranean parking; (ii) a new 2-story Academic Building West; (iii) a new 2-story Library/Tech. Center Building, with basement; (iii) A 2-story addition to the north side of the existing Academic Building South; (iv) a new Aquatic Center Building and, (v) a new swimming pool.

Re-grading of the access road from the school entrance to the athletic field, is planned. The consultants have indicated that the removal and replacement of the existing uncertified fill is not practical, due to its thickness and the presence of an existing storm drain. The placement of new fill over existing uncertified fill, does not comply with the Code as indicated on page 14 of the report, and is not approved at this time.

The consultants are referred to the following maps, which were also reviewed: (i) map page 67 of the 1960 City Geologic Maps of the Santa Monica Mountains, and (ii) Plate A of DMG Open-File Report 95-02 (Landslide Hazards & Effects of the Northridge Earthquake of January 17, 1994).

The review of the subject report cannot be completed at this time and will be continued upon submittal of an addendum to the report which shall include, but need not be limited to, the following:



Page 2

3900 N. Stansbury Avenue

- 1. Identify the access road from the school entrance to the athletic field and the existing storm drains, on the map and on the appropriate cross-sections. Provide an evaluation of the settlement characteristics of the existing fill and a detailed justification demonstrating that potential future settlement of the fill, will not result in future damage or excessive settlement to the access road surface. Alternatively, revise recommendations for new fill, to be placed in compliance with section 7011.3 of the LA City Building Code and identify details on the map and cross-sections.
- 2. The report indicates (see pages 4 and 12) that the "natural drainages" which enter from the east can be sources of eroded soil material and will carry natural runoff, on to the site. Provide recommendations for mud/debris flow control systems within and at the base of concentrated drainage areas using the minimum design parameters specified in section 7014.3 of the LA City Building Code. The entire contributing watershed area on the slopes above the property shall be identified on the topographic map. If such evaluation is to be performed by a licensed civil engineer, include a wet-signed original and two copies with the addendum.
- 3. Explain what the approximately 220-feet-long (and about 2-feet-wide) line on the map shown on the slope within the existing natural drainage course (above location TP-3 and the curvilinear structure), represents. Note: A similar line on the map is also shown within the natural drainage area in the southern portion of the site (canyon to the east of locations TP-11 and TP-12). If the line represents an existing pipe or other device that conveys slope drainage, provide recommendations and show on the map how drainage will be conveyed around the buildings in a non-erosive device to a location that is acceptable to the Department.
- 4. Provide the test pit logs for exploration conducted at locations TP-11 and TP-12.
- 5. Explain what the two curvilinear structures shown east of the proposed Main Academic Building represent. Indicate if these structures are existing, or proposed. If they are existing, clarify if they will be removed or if they will remain. It they are proposed, explain if they will part of the proposed building or, will be detached from the building.
- 6. It appears from the recommendations provided on page 20 of the report, that removal of the porous, unsuitable upper portion of the alluvium will be required if the floor slab of the Main Academic Building is to be supported on newly-placed certified compacted fill. Shoring is planned to facilitate removal along the west and south sides. Clarify how any removals for building construction and setback wall/slope protection wall construction, will be achieved along the southeastern portion of the building and along the entire length of the building, on the east side.

Provide additional geologic cross-sections drawn through the proposed building, any setback wall and/or slope protection walls proposed and, the immediate slope located above the walls to illustrate the proposed construction.

7. Verify using the sections requested, that the entire face of the new Main Academic Building will be provided the required level clearance building setback and, identify the required setback on all cross-sections drawn through the Main Academic Building. Page 3

3900 N. Stansbury Avenue

- 8. It appears from the documented geologic orientation (N88W; 31N) plotted on the map, that the correct location for test pit TP-6 is between the proposed toe of slope wall and the Library Building. A location TP-6 is also shown on the east side of the proposed Main Academic Building (east of TP-5). Please explain, verify and correct, as necessary. Provide an exploration log, if applicable.
- 9. The geologic data on the slope above the proposed Main Academic Building is limited to the one orientation from location TP-5. The mapped strike and dip on the City map page 67, shown on the slope in this area, indicates a near east-west strike and a north dip of 16 degrees. Provide additional data with regard to the bedrock orientation on the slope using additional mapping and/or exploration.
- 10. It appears that geologic cross-section I-I was not drawn through the slope directly above the proposed Main Academic Building. Provide two additional geologic cross-sections drawn through location TP-5. The sections shall be extended up to show the <u>entire slope</u> both in the north-south direction (general true dip direction) and, along the steepest portion of the slope (perpendicular to contours). Provide stability evaluation along these sections using appropriate strengths and demonstrate that the slope above the proposed building will have the required minimum factor of safety of 1.5 for long-term stability (gross and seismic).

Note: The subject property on Plate A of the DMG Open-File Report 95-02 is shown as being in an area of "weak bedrock" which consists of thin-bedded, densely jointed siltstone, platy shale, and fine-grained sandstone units" of the Modelo Formation which was "severely affected" by the Northridge Earthquake.


11. Revise recommendations as necessary and provide an itemized response to this letter.

STEPHEN DAWSON Engincering Geologist I

PASCAL CHALLITA Geotechnical Engineer II

SD/PC:sd/pc 54269 (213) 482-0480

cc: Bruce A. Miller & Associates (Applicant) The J. Byer Group VN District Office



JB 19876-B BUCKLEY SCHOOL-SECTION J ** PCSTABL6 **

by

Purdue University

modified by Peter J. Bosscher University of Wisconsin-Madison

--Slope Stability Analysis--Simplified Janbu, Simplified Bishop or Spencer`s Method of Slices

PROBLEM DESCRIPTION CALCULATE THE STABILITY OF SECTION J

BOUNDARY COORDINATES

10 Top Boundaries 10 Total Boundaries

Boundary No.	X-Left (ft)	Y-Left (ft)	X-Right (ft)	Y-Right (ft)	Soil Type Below Bnd
1 2 3 4 5 6 7 8 9	$\begin{array}{c} 0.00\\ 80.00\\ 120.00\\ 207.00\\ 305.00\\ 400.00\\ 493.00\\ 590.00\\ 730.00\\ \end{array}$	780.00780.00800.00900.00950.001000.001050.001100.00	$\begin{array}{r} 80.00\\ 120.00\\ 207.00\\ 305.00\\ 400.00\\ 493.00\\ 590.00\\ 730.00\\ 865.00\\ \end{array}$	780.00 800.00 900.00 950.00 1000.00 1050.00 1100.00 1122.00	1 1 1 1 1 1 1 1
10	865.00	1122.00	960.00	1100.00	1

ISOTROPIC SOIL PARAMETERS

1 Type(s) of Soil

Туре	Unit Wt.	Unit Wt.	Cohesion Intercept (psf)	Angle	Pressure	Constant	Surface
1	125.0	125.0	951.0	30.0	0.00	0.0	0

A Critical Failure Surface Searching Method, Using A Random Technique For Generating Circular Surfaces, Has Been Specified.

25000 Trial Surfaces Have Been Generated.

500 Surfaces Initiate From Each Of 50 Points Equally Spaced Along The Ground Surface Between X = 70.00 ft. and X = 80.00 ft. Each Surface Terminates Between X = 100.00 ft. and X = 900.00 ft. Unless Further Limitations Were Imposed, The Minimum Elevation At Which A Surface Extends Is Y = 0.00 ft. 20.00 ft. Line Segments Define Each Trial Failure Surface. Following Are Displayed The Ten Most Critical Of The Trial Page 1 JB 19876-B BUCKLEY SCHOOL-SECTION J Failure Surfaces Examined. They Are Ordered - Most Critical First.

 \ast \ast Safety Factors Are Calculated By The Modified Bishop Method \ast \ast

Failure Surface Specified By 38 Coordinate Points

		(ft)	(ft)		
C	1 2 3 4 5 6 7 8 9 10 11 12 13 14 5 16 17 18 9 20 21 22 23 24 25 27 28 29 30 31 22 23 24 25 27 28 29 30 31 20 31 20 31 20 31 20 31 20 31 20 31 20 31 20 31 20 31 20 31 20 31 20 31 20 31 20 31 32 33 34 35 36 37 8 9 10 11 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 37 38 37 38 37 38 37 38 37 38 37 38 37 38 37 38 38 38 38 38 38 38 38 38 38	80.00 99.81 119.56 139.25 158.87 178.42 197.89 217.28 236.57 255.77 274.85 293.83 312.69 331.43 350.03 386.50 386.50 386.50 423.04 440.90 458.60 476.13 493.48 510.65 527.62 544.41 560.99 577.37 593.53 609.49 625.21 640.72 655.99 671.02 685.82 700.36 714.66 718.18 er At X =	780.00 782.79 785.93 789.43 793.29 797.51 802.08 807.00 812.27 817.89 823.86 830.17 836.83 843.82 851.16 858.83 866.84 875.17 883.84 892.83 902.14 911.78 921.72 931.99 942.56 953.44 964.62 976.09 987.87 999.93 1012.29 1024.92 1037.84 1051.03 1064.49 1078.21 1092.20 1095.78 -63.7 ; Y = 18	73.4 and Radius	, 1102.8
	* * *	1.575	* * *		

Failure Surface Specified By 38 Coordinate Points

Point	X-Surf	Y-Surf
No.	(ft)	(ft)
1	72.65	780.00 Page 2

$\begin{array}{cccccccccccccccccccccccccccccccccccc$	9876-B BUCKLEY SCHOOL-SECTION J 778.23 777.07 776.53 776.60 777.29 778.59 780.50 783.02 786.15 789.89 794.23 799.16 804.69 810.81 817.51 824.79 832.63 841.04 850.00 859.50 869.54 880.11 891.19 902.78 914.87 927.44 940.48 953.98 967.93 982.31 997.11 1012.32 1027.92 1043.90 1060.24 1076.92 1087.61
	= 140.2 ; Y = 1427.4 and Radius, 650.9
*** 1.584	

Failure Surface Specified By 36 Coordinate Points

Point	X-Surf	Y-Surf
NO.	(ft)	(ft)
1	72.86	780.00
2	92.78	778.24
3	112.75	777.14
4	132.75	776.70
5	152.74	776.92
6	172.72	777.80
7	192.67	779.33
8	212.55	781.52
9	232.34	784.37
10	252.03	787.86
11	271.60	792.00
12	291.02	796.79

Page 3

$\begin{array}{cccccccccccccccccccccccccccccccccccc$	76-B BUCKLEY SCHOOL- 802.21 808.26 814.94 822.24 830.14 838.65 847.74 857.42 867.67 878.48 889.84 901.74 914.16 927.09 940.51 954.42 968.79 983.61 998.87 1014.54 1030.62 1047.07 1063.90 1074.40	SECTION J	
Circle Center At X =	136.1 ; Y = 1383.6	and Radius,	607.0
*** 1.585	* * *		

Failure Surface Specified By 37 Coordinate Points

Point No.	X-Surf (ft)	Y-Surf (ft)
1 2 3 4 5 6 7 8 9 0 11 2 3 4 5 6 7 8 9 0 11 2 3 4 5 6 7 8 9 0 11 2 3 4 5 6 7 8 9 0 11 2 3 4 5 6 7 8 9 0 11 2 3 4 5 6 7 8 9 0 21 2 3 4 5 6 7 8 9 0 21 2 3 4 5 6 7 8 9 0 21 2 3 4 5 6 7 8 9 0 21 2 3 4 5 6 7 8 9 0 21 2 3 4 5 6 7 8 9 0 21 2 3 4 5 6 7 8 9 0 21 2 2 3 4 5 6 7 8 9 0 21 2 2 3 4 5 6 7 8 9 0 21 2 2 3 4 5 6 7 8 9 0 21 2 2 3 4 5 8 9 0 21 2 2 3 4 5 8 9 0 21 2 2 3 4 5 8 9 0 21 2 2 3 4 5 8 9 0 21 2 2 3 4 5 8 9 0 21 2 2 3 4 5 8 9 0 21 2 2 3 4 5 1 2 2 3 4 5 8 9 0 2 1 2 2 3 4 5 1 2 2 3 4 5 2 2 3 4 5 2 2 2 2 2 2 3 4 5 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	74.90 94.82 114.78 134.77 154.77 174.76 194.71 214.60 234.41 254.12 273.71 293.16 312.44 331.55 350.45 369.12 387.55 405.72 423.61 441.19 458.46 475.38 491.95 508.14 523.94	780.00 778.18 777.01 776.49 776.63 777.41 778.85 780.94 783.68 787.07 791.09 795.76 801.05 806.98 813.52 820.68 813.52 820.68 813.52 820.68 845.75 855.28 865.38 876.04 887.24 898.98 911.24

26 27 28 29 30 31 32 33 34 35 36 37	JB 1987 539.33 554.30 568.83 582.90 596.49 609.60 622.22 634.31 645.89 656.92 667.40 668.23	76-B BUCKLEY 924.01 937.28 951.02 965.24 979.91 995.01 1010.53 1026.46 1042.77 1059.45 1076.48 1077.94	SCHOOL-S	SECTION	J	
Circle Center	r At X =	140.6 ; Y =	1388.9	and Ra	dius,	612.4
* * *	1.586	* * *				

Failure Surface Specified By 40 Coordinate Points

Point	X-Surf	Y-Surf
No.	(ft)	(ft)
123456789011234567890123456789012345678901234567890123456789012334567890123345678901233456789012334567	78.57 98.50 118.46 138.45 158.45 178.44 198.41 218.33 238.20 257.98 277.67 297.26 316.71 336.02 355.17 374.14 392.92 411.50 429.84 447.95 465.80 483.38 500.67 517.67 534.34 550.69 582.34 597.61 612.51 627.00 641.09 654.75 667.99 680.78 693.11 704.98	780.00 778.26 777.09 776.52 776.52 777.11 778.29 780.05 782.39 785.30 788.80 792.87 797.51 802.71 808.48 814.81 821.68 829.11 837.07 845.56 854.58 864.12 874.17 884.71 895.75 907.28 919.27 931.73 944.64 957.99 971.77 985.97 1000.57 1030.94 1046.69 1062.78 Page

	JB 1987	6-B BUCKLEY	SCHOOL-SECTION	J
38	716.38	1079.22		
39	727.29	1095.98		
40	729.66	1099.88		

Circle Center At X = 148.2; Y = 1460.9 and Radius, 684.4

*** 1.588 ***

Failure Surface Specified By 37 Coordinate Points

Point No.	X-Surf (ft)	Y-Surf (ft)		
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 Circle Cer	78.78 98.69 118.65 138.64 158.64 178.63 198.58 218.49 238.31 258.05 277.67 297.15 316.48 335.64 354.59 373.34 391.85 410.10 428.09 445.78 463.16 480.22 496.93 513.28 529.24 544.82 559.98 574.71 589.00 602.83 616.19 629.06 641.44 653.30 664.64 675.44 683.13	780.00 778.11 776.87 776.27 776.31 777.00 778.33 780.30 782.91 786.16 790.04 794.55 799.69 805.45 811.82 818.79 826.37 834.54 843.29 852.62 862.51 872.95 883.94 895.46 907.51 920.06 933.10 946.63 960.62 975.07 989.95 1005.26 1020.97 1037.07 1037.07 1033.55 1070.38 1083.26 147.3 ; Y = 139	7.4 and Radius,	621.2
* * *	1.588	* * *		

Failure Surface Specified By 41 Coordinate Points Page 6

JB 19876-B BUCKLEY SCHOOL-SECTION J

Point No.	X-Surf (ft)	Y-Surf (ft)			
1 2 3 4 5 6 7 8 9 10 11 2 3 4 5 6 7 8 9 10 11 2 13 14 15 16 7 8 9 10 11 2 2 3 14 15 16 7 8 9 20 12 23 4 5 6 7 8 9 10 11 2 23 4 5 6 7 8 9 10 11 2 13 14 15 16 7 8 9 20 12 23 4 5 6 7 8 9 10 11 2 23 4 5 6 7 8 9 10 11 2 2 3 4 5 6 7 8 9 20 12 2 2 3 4 5 6 7 8 9 20 1 2 2 3 4 5 6 7 8 9 20 1 2 2 2 8 9 20 2 1 2 2 3 4 5 6 7 8 9 20 1 2 2 3 4 5 6 7 8 9 20 1 2 2 3 4 5 6 7 8 9 20 1 2 2 3 4 5 6 7 8 9 20 1 2 2 3 4 5 6 7 8 9 20 1 2 2 3 4 5 6 7 8 9 20 1 2 2 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3	72.65 92.58 112.54 132.53 152.53 172.53 192.50 212.43 232.32 252.13 271.86 291.49 311.01 330.40 349.64 368.72 387.63 406.34 424.85 443.15 461.21 479.02 496.57 513.85 530.83 547.52 563.89 579.93 595.63 610.98 625.96 640.57 654.79 668.61 682.03 695.02 707.58 719.70 731.37 742.58 744.91	780.00 778.25 777.06 776.43 776.36 776.85 777.90 779.51 781.67 784.39 787.66 791.48 795.86 800.77 806.23 812.22 818.74 825.79 833.36 841.44 850.04 859.13 868.72 878.80 889.13 868.72 878.80 889.13 868.72 878.80 889.36 900.38 911.87 923.82 936.21 949.03 962.27 975.93 990.00 1004.45 1019.29 1034.50 1050.06 1065.97 102.43	1401 2	and Radius,	714 0
			1491.2	and Radius,	717.5
***	1.588	* * *			
Failure S	urface Speci	fied By 38 C	oordinat	e Points	

Point	X-Surf	Y-Surf
NO.	(ft)	(ft)
1 2 3	73.67 93.56 113.51	780.00 777.91 776.45 Page 7

$\begin{array}{cccccccccccccccccccccccccccccccccccc$	876-B BUCKLEY 775.62 775.41 775.83 776.87 778.54 780.84 783.76 787.30 791.45 796.22 801.59 807.56 814.13 821.29 829.03 837.35 846.23 855.67 865.66 876.18 887.24 898.81 910.89 923.46 936.52 950.04 964.02 978.44 933.29 1008.55 1024.21 1040.25 1056.66 1073.42 1089.00		
Circle Center At X =	150.1; Y =	1412.9 anu	Radius,

*** 1.591 ***

Failure Surface Specified By 40 Coordinate Points

Point	X-Surf	Y-Surf
No.	(ft)	(ft)
1 2 3 4 5 6 7 8 9 10 11 12 13 14	74.6994.60114.55134.54154.54174.53194.51214.45234.34254.15273.88293.51313.02332.38	780.00 778.05 776.68 775.90 775.69 776.07 777.03 778.69 783.39 786.69 783.39 786.67 790.51 794.93 799.92

637.5

$\begin{array}{cccccccccccccccccccccccccccccccccccc$	76-B BUCKLEY SCHOOL- 805.46 811.57 818.22 825.42 833.16 841.44 850.24 859.56 869.40 879.73 890.56 901.88 913.67 925.92 938.63 951.79 965.38 979.39 993.81 1008.62 1023.82 1039.40 1055.33 1071.61 1088.22 1100.88	SECTION J	
Circle Center At X =	151.6 ; Y = 1462.4	and Radius,	686.8
1.392			

Failure Surface Specified By 36 Coordinate Points


Point	X-Surf	Y-Surf
No.	(ft)	(ft)
1 2 3 4 5 6 7 8 9 0 11 2 3 4 5 6 7 8 9 0 11 2 3 4 5 6 7 8 9 0 11 2 3 4 5 6 7 8 9 0 11 2 3 4 5 6 7 8 9 0 11 2 3 4 5 6 7 8 9 0 11 2 3 4 5 6 7 8 9 0 11 2 3 4 5 6 7 8 9 0 11 2 3 4 5 6 7 8 9 0 11 2 3 4 5 6 7 8 9 0 11 2 3 4 5 6 7 8 9 0 11 2 3 4 5 6 7 8 9 0 11 2 3 4 5 6 7 8 9 0 11 2 3 4 5 6 7 8 9 0 11 2 3 4 5 6 7 8 9 0 11 2 3 4 5 6 7 8 9 0 11 2 3 4 5 8 9 0 11 2 3 4 5 6 7 8 9 0 11 2 2 3 4 5 8 9 0 11 2 2 3 4 5 8 9 0 1 12 2 3 4 5 1 1 2 2 1 2 1 2 2 1 2 2 1 2 2 2 2 2 2	75.71 95.62 115.58 135.57 155.57 175.55 195.50 215.38 235.18 254.87 274.43 293.84 313.07 332.09 350.90 369.46 387.75 405.75 423.44 440.81 457.82 474.46 490.71	780.00 778.02 776.73 776.13 776.21 776.98 778.44 780.58 783.40 786.90 791.07 795.91 801.42 807.58 814.40 821.85 829.94 838.65 847.97 857.90 868.42 879.51 891.17

	24 25 26 27 28 29 30 31 32 33 34 35 36	JB 1987 506.55 521.96 536.92 551.42 565.44 578.96 591.96 604.44 616.37 627.74 638.55 648.76 649.76	90 91 92 94 95 97 98 100	3.38 6.13 9.40 3.18 7.44 2.18 7.37 3.01 9.06 5.51 2.34 9.53	SCHOOL -	-SECTIO	J		
Cir	rcle Cente	r At X =	143.2	; Y =	1358.3	and R	adius,	582	2.3
	* * *	1.592	* * *						
	Y		А	x	I	ς		F	т
V		.00 246					987.3		
Х	0.00	+ - -				.*	т		т
	246.84	 + 				.2*. 21 811* 21. 211 221	 .*. 1		
А	493.68				••	2	2211* .5211 5211. 5221 5221	.* _3. 113	
Х	740.52	- - - -							
I	987.36	- + - -							
S	1234.20	- + - -			10				

			JΒ	19876-в	ΒU
		-			
	1481.04	+			
		~			
		-			
		-			
		-			
F	1727.88	+			
		-			
		-			
		_			
Т	1974.72	+			

JB 19876-B BUCKLEY SCHOOL-SECTION J

.



JB 19876-B BUCKLEY SCHOOL-SECTION J-EQ ** PCSTABL6 **

by

Purdue University

modified by Peter J. Bosscher University of Wisconsin-Madison

--Slope Stability Analysis--Simplified Janbu, Simplified Bishop or Spencer`s Method of Slices

PROBLEM DESCRIPTION CALCULATE THE SEISMIC STABILITY OF SECTION J

BOUNDARY COORDINATES

```
10 Top Boundaries
10 Total Boundaries
```

Boundary No.	X-Left (ft)	Y-Left (ft)	X-Right (ft)	Y-Right (ft)	Soil Type Below Bnd
1 2 3 4 5 6 7 8 9	$\begin{array}{c} 0.00\\ 80.00\\ 120.00\\ 207.00\\ 305.00\\ 400.00\\ 493.00\\ 590.00\\ 730.00\end{array}$	780.00780.00800.00900.00950.001000.001050.001100.00	80.00 120.00 207.00 305.00 400.00 493.00 590.00 730.00 865.00	780.00 800.00 900.00 950.00 1000.00 1050.00 1100.00 1122.00	1 1 1 1 1
10	865.00	1122.00	960.00	1100.00	1

ISOTROPIC SOIL PARAMETERS

1 Type(s) of Soil

Туре	Unit Wt.	Unit Wt.	Cohesion Intercept (psf)	Angle	Pressure	Constant	Surface	
1	125.0	125.0	951.0	30.0	0.00	0.0	0	

A Horizontal Earthquake Loading Coefficient Of0.150 Has Been Assigned

A Vertical Earthquake Loading Coefficient 0f0.000 Has Been Assigned

Cavitation Pressure = 0.0 psf

A Critical Failure Surface Searching Method, Using A Random Technique For Generating Circular Surfaces, Has Been Specified.

25000 Trial Surfaces Have Been Generated.

500 Surfaces Initiate From Each Of 50 Points Equally Spaced Along The Ground Surface Between X = 70.00 ft. and X = 80.00 ft.

Each Surface Terminates Between X = 100.00 ft. Page 1

JB 19876-B BUCKLEY SCHOOL-SECTION J-EQ and X = 900.00 ft.

Unless Further Limitations Were Imposed, The Minimum Elevation At Which A Surface Extends Is $\,Y\,=\,0.00$ ft.

20.00 ft. Line Segments Define Each Trial Failure Surface.

Following Are Displayed The Ten Most Critical Of The Trial Failure Surfaces Examined. They Are Ordered - Most Critical First.

* * Safety Factors Are Calculated By The Modified Bishop Method * *

Failure Surface Specified By 38 Coordinate Points

Poin No.	t	X-Si (f	urf t)		Y	′-S (f	t.	rf)			
12345678901123456789011213415678901222345667890123345667890122334566789012333333333333333333333333333333333333		999991388 1199222222222222222222222222222222222	2572987753933031400038521973912922668	-6	777778888888888888888899999999999999	24 37 51 64 78 95		793391807967326347434829642973924391	18;	73	. 4
			•			-	,			-	ŕ

4 and Radius, 1102.8 C

* * * 1.152 ***

JB 19876-B BUCKLEY SCHOOL-SECTION J-EQ

Failure Surface Specified By 41 Coordinate Points

Point	X-Surf	Y- Sur f
No.	(ft)	(ft)
1 2 3 4 5 6 7 8 9 0 112 13 4 5 6 7 8 9 0 112 13 4 5 6 7 8 9 0 112 13 4 5 6 7 8 9 0 112 13 4 5 6 7 8 9 0 112 13 4 5 6 7 8 9 0 112 13 4 5 6 7 8 9 0 112 13 4 5 6 7 8 9 0 112 13 4 5 6 7 8 9 0 112 13 4 5 6 7 8 9 0 112 13 4 5 6 7 8 9 0 112 13 4 5 6 7 8 9 0 112 13 4 5 6 7 8 9 0 112 13 4 5 6 7 8 9 0 112 13 4 5 6 7 8 9 0 112 13 4 5 6 7 8 9 0 112 13 8 4 5 6 7 8 9 0 12 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2		780.00 783.58 787.42 791.52 795.88 800.51 805.39 810.54 815.94 827.51 833.68 840.10 846.78 853.71 860.89 868.32 875.99 868.32 875.99 868.32 875.99 868.32 875.99 868.32 900.49 909.15 918.04 927.17 936.54 946.15 955.98 966.06 976.36 986.89 997.64 1008.62 1019.83 1031.25 1042.89 1054.75 1066.831 1091.61 1104.31 1109.00

Circle Center At X = -177.5; Y = 2252.5 and Radius, 1494.9

*** 1.158 ***

Failure Surface Specified By 41 Coordinate Points

Point	X-Surf	Y-Surf
No.	(ft)	(ft)
1	72.65	780.00 Page 3

2 3 4 5 6 7 8 9 10 11 12 13 14 5 6 7 8 9 10 11 12 13 14 5 6 7 8 9 10 11 12 13 14 5 6 7 8 9 20 12 23 4 5 6 7 8 9 20 12 23 4 5 6 7 8 9 20 12 23 24 5 26 7 8 9 30 12 23 34 5 6 7 8 9 0 11 12 13 14 5 6 7 8 9 20 12 23 24 5 26 7 8 9 0 11 12 13 14 5 6 7 8 9 20 12 22 3 4 5 26 7 8 9 0 21 22 3 4 5 26 7 8 9 0 21 22 3 4 5 26 7 8 9 0 11 12 13 14 5 6 7 8 9 0 21 22 3 4 5 26 7 8 9 0 21 22 3 4 5 26 7 8 9 0 21 22 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3	$\begin{array}{c} \textbf{JB} & \textbf{19876} - \\ \textbf{92.58} \\ \textbf{112.54} \\ \textbf{132.53} \\ \textbf{152.53} \\ \textbf{152.53} \\ \textbf{172.53} \\ \textbf{192.50} \\ \textbf{212.43} \\ \textbf{232.32} \\ \textbf{252.13} \\ \textbf{271.86} \\ \textbf{291.49} \\ \textbf{311.01} \\ \textbf{330.40} \\ \textbf{349.64} \\ \textbf{368.72} \\ \textbf{368.72} \\ \textbf{387.63} \\ \textbf{406.34} \\ \textbf{424.85} \\ \textbf{461.21} \\ \textbf{479.02} \\ \textbf{496.57} \\ \textbf{513.85} \\ \textbf{530.83} \\ \textbf{547.52} \\ \textbf{530.83} \\ \textbf{547.52} \\ \textbf{563.89} \\ \textbf{579.93} \\ \textbf{595.63} \\ \textbf{640.57} \\ \textbf{654.79} \\ \textbf{668.61} \\ \textbf{682.03} \\ \textbf{695.02} \\ \textbf{707.58} \\ \textbf{719.70} \\ \textbf{731.37} \\ \textbf{742.58} \\ \textbf{744.91} \end{array}$	778.25 777.06 776.43 776.36 776.85 777.90 779.51 781.67 784.39 787.66 791.48 795.86 800.77 806.23 812.22 818.74 825.79 833.36 841.44 850.04 859.13 868.72 878.80 889.36 900.38 911.87 923.82 936.21 949.03 962.27 975.93 990.000 1004.45 1019.29 1034.50 1050.06 1065.97 1082.21 1098.77 1102.43
Circle Cente	r At X = 1	145.0 ; Y = 1491.2 and Radius, 714.9
* * *	1.163	* * *
Failure Surf	ace Specif	ied By 40 Coordinate Points
Point NO.	X-Surf (ft)	Y-Surf (ft)
1 2 3 4 5 6 7 8 9	78.57 98.50 118.46 138.45 158.45 178.44 198.41 218.33 238.20	780.00 778.26 777.09 776.52 776.52 777.11 778.29 780.05 782.39 Page 4

10 2 11 2 12 2 13 14 15 16 17 18 19 2 20 4 22 23 24 25 26 27 28 29 301 6 333 6 37 7 38 7 39 7	257.98 277.67 297.26 316.71 336.02 355.17 374.14 392.92 411.50 429.84 447.95 465.80 483.38 500.67 517.67 534.34 550.69 562.34 57.61 512.51 527.00 554.75 567.99 567.99 567.99 567.99 567.99 567.29	BUCKLEY 785.30 788.80 792.87 797.51 802.71 808.48 814.81 821.68 829.11 837.07 845.56 854.58 864.12 874.17 884.71 895.75 907.28 919.27 931.73 944.64 957.99 971.77 985.97 1000.57 1030.94 1046.69 1062.78 1095.98 1099.88	SCHOOL - SE	CTION	J-EQ	
Circle Center	At $X = 14$	8.2 ; Y	= 1460.9	and I	Radius,	684.4

*** 1.164 ***

Failure Surface Specified By 41 Coordinate Points

Point	X-Surf	Y-Surf
NO.	(ft)	(ft)
$ \begin{array}{c} 1\\ 2\\ 3\\ 4\\ 5\\ 6\\ 7\\ 8\\ 9\\ 10\\ 112\\ 13\\ 14\\ 15\\ 16\\ 1\\ 1\\ 18\\ \end{array} $	$\begin{array}{c} 72.86\\ 92.78\\ 112.73\\ 132.72\\ 152.72\\ 172.72\\ 192.70\\ 212.64\\ 232.54\\ 252.37\\ 272.13\\ 291.79\\ 311.35\\ 330.78\\ 350.08\\ 369.22\\ 388.20\\ 406.99\end{array}$	780.00 778.19 776.92 776.20 776.03 776.41 777.34 778.82 780.84 783.41 786.53 790.18 794.38 799.11 804.37 810.16 816.47 823.31

19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40	JB 19876-B 425.59 443.99 462.16 480.09 497.78 515.20 532.34 549.20 565.75 581.99 597.90 613.48 628.70 643.56 658.05 672.15 685.86 699.16 712.05 724.51 736.54 748.13 757.46	BUCKLEY 830.65 838.51 846.86 855.71 865.06 874.88 885.18 895.94 907.17 918.84 930.96 943.51 956.48 969.87 983.65 997.83 1012.40 1027.33 1012.40 1027.33 1042.62 1058.27 1074.24 1090.55 1104.48	SCHOOL-SE	CTION	J-EQ	
Circle Center	r At X = 14	8.9 ; Y	= 1504.1	and F	adius,	728.1

*** 1.165 ***

Failure Surface Specified By 38 Coordinate Points

Point	X-Surf	Y-Surf
NO.	(ft)	(ft)
1234567890 11234567890 11234567890 1223456 2223456 222222222222222222222222222222222222	72.65 92.58 112.54 132.53 152.53 172.52 192.48 212.39 232.23 251.98 271.63 291.15 310.53 329.76 348.80 367.64 386.27 404.67 422.82 440.70 458.29 475.59 492.57 509.22 525.52 541.45	780.00 778.23 777.07 776.53 776.60 777.29 778.59 780.50 783.02 786.15 789.89 794.23 799.16 804.69 810.81 817.51 824.79 832.63 841.04 850.00 859.50 869.54 880.11 891.19 902.78 914.87

27 28 29 30 31 32 33 34 35 36 37 38	557.01 572.17 586.93 601.26 615.16 628.61 641.60 654.11 666.14 677.68 688.70 695.30	927.44 940.48 953.98 967.93 982.31 997.11 1012.32 1027.92 1043.90 1060.24 1076.92 1087.61				
Circle Cente	r At X =	140.2 ; Y	= 1427.4	and R	adius,	650.9

Failure Surface Specified By 40 Coordinate Points

Point	X-Surf	Y-Surf
NO.	(ft)	(ft)
12345678901123456789011234567890112345678901223456789012334556789012334556789012334556789012334556789012334556789012334556789012334556789012334556789012334556789012334556789012334556789012333333333333333333333333333333333333	74.69 94.60 114.55 134.54 154.54 174.53 194.51 214.45 234.34 254.15 273.88 293.51 313.02 332.38 351.60 370.65 389.51 408.17 426.61 444.81 462.77 480.47 497.88 515.01 531.82 548.31 564.47 580.27 595.71 610.78 625.45 639.73 653.59 667.02 680.02 692.57 704.65	780.00 778.05 776.68 775.69 775.69 775.69 777.03 778.57 780.69 783.39 786.67 790.51 794.93 799.92 805.46 811.57 818.22 825.42 833.16 841.44 850.24 859.56 869.40 879.73 890.56 901.88 913.67 925.92 938.63 951.79 965.38 979.39 993.81 1008.62 1023.82 1039.40 1055.33

JB 19876-B BUCKLEY SCHOOL-SECTION J-EQ 38 716.28 1071.61 39 727.42 1088.22 40 735.39 1100.88 Circle Center At X = 151.6 ; Y = 1462.4 and Radius, 686.8 *** 1.167 ***

Failure Surface Specified By 43 Coordinate Points

Point	X-Surf	Y-Surf
No.	(ft)	(ft)
1234567890123456789012345678901234567890123 1111111122222222223333333333344444	75.51 95.43 115.39 135.38 175.37 195.36 215.31 235.22 255.08 274.87 294.58 314.18 333.69 353.06 372.30 391.40 410.33 429.09 447.65 466.02 484.18 502.11 519.80 537.25 554.43 571.34 587.96 604.29 620.32 636.02 651.40 666.43 681.12 695.45 709.41 722.99 736.18 748.98 761.37 773.34 784.90 785.79	780.00 778.22 776.96 776.22 776.00 776.30 777.13 778.47 780.34 782.73 785.63 789.05 792.98 797.42 802.37 807.83 813.78 820.23 827.18 834.60 842.52 850.91 859.76 869.09 878.87 889.11 899.79 910.91 922.45 934.42 946.81 959.60 972.78 986.36 1000.31 1014.64 1029.32 1044.35 1059.72 1075.42 1091.44 1107.76 1109.09

Circle Center At X = 153.7; Y = 1542.2 and Radius, 766.3

*** 1.169 ***

Failure Surface Specified By 40 Coordinate Points

Poin No.	t X-Surf (ft)	Y-Surf (ft)		
12345678901121341567890112134156178902122345678903323345567890	72.45 92.34 112.28 132.26 152.26 172.25 192.24 212.19 232.08 251.91 271.66 291.30 310.83 330.21 349.45 368.51 387.39 406.06 424.51 442.73 460.70 478.40 495.82 512.95 529.76 546.24 562.38 578.17 593.59 608.62 623.26 637.50 651.31 664.69 677.63 690.11 702.12 713.66 724.71 733.10 Center At X =	780.00 777.89 776.37 775.44 775.10 775.35 776.19 777.62 779.63 782.23 785.41 789.18 793.52 798.43 803.92 809.96 816.57 823.73 831.44 839.69 848.47 857.78 867.61 877.95 888.78 900.11 911.92 924.20 936.93 950.12 963.75 977.80 992.26 1007.13 1022.38 1038.01 1054.00 1054.00 100.51 153.8 ; Y = 1453.5	5 and Radius,	678.4
		,	· ,	

*** 1.169 ***


Failure Surface Specified By 37 Coordinate Points

Point X-Surf Y-Surf

Page 9


No.	JB 1987 (ft)	6-B BUCKLEY (ft)	SCHOO	L-SECTIO	N J-EQ	
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37	74.90 94.82 114.78 134.77 154.77 174.76 194.71 214.60 234.41 254.12 273.71 293.16 312.44 331.55 369.12 387.55 405.72 423.61 441.19 458.46 475.38 491.95 508.14 523.94 539.33 558.83 582.90 509.60 622.22 634.31 645.89 656.92 667.40 668.23	780.00 778.18 777.01 776.49 776.63 777.41 778.85 780.94 783.68 787.07 791.09 795.76 801.05 806.98 813.52 820.68 828.44 836.80 845.75 855.28 865.38 876.04 897.24 994.01 937.28 951.02 965.24 979.91 995.01 1010.53 1026.46 1042.77 1059.45 1076.48 1077.94				
Circle Cente			= 1388	.9 and	Radius, (512.4
***	1.170	***				
Y	/	A X	I	S	F	T T
		6.84 493		740.52		
x 0.00	- -	-+	+	. *		
				.3*. 31. 511	• * •	
246.84	+ -				1.*.	
	_	Page	e 10		-k- = =	


		JB 1	L9876-в	BUCKLEY	SCHOOL-SECTION J-EQ	
	402 69	-				
А	493.68	+				
		-				
		-				
		-				
Х	740.52	+				
		-				
		-			,,	
		-			•••••	
I	987.36	- +			*	
1	907.50	−				
		-				
		-				
		-				
S	1234.20	+				
		-				
		-				
		-				
	1481.04 ·	÷				
		-				
		-				
		-				
F	1727.88 -	 +-				
F	1/2/,00	τ -				
		-				
		-				
Т	1974.72 ·	+				




11x17


		Brush Brook
	1840 Tennis Co	
		Tennis Couri
JUNE 6, 2006	REF.: SM TOPO #67	
THE J. BYER GROUP, INC.	VICINITY MAP	
A GEOTECHNICAL CONSULTING FIRM 1461 E. Chevy Chase Dr Suite 200, Glendale, CA 91206 (818) 549-9959 Tel • (818) 543-3747 Fax	JB: 1937G-B THE BUCKLEY SCHOOLCONSULTANT: JWBSCALE: 1" = 100'	
	SOULE 1-100	








recommendation of the good 10-1-49 This when has been reviewed and cunturns to the recommendation of the geological report. EXPLANATION caf(s) CERTIFIED ARTIFICIAL FILL STRUCTURAL caf(n) CERTIFIED ARTIFICIAL FILL NON-STRUCTURAL C GEOLOGIC CONTACT LINE DASHED WHERE INFERRED B-1 APPROXIMATE LOCATION OF TEST BORING LINE OF CROSS SECTION STANSBURY 21 9-24-94 Moi Yarsburg Aze Lit-jor 1 CENSI M.N. AVENUE 10,0 77:14- 23 Ferry DESIGN ENGINEER: S hereby config that the work shown on this Plan has been Constructed and Conforms to the approved Graphing Plage يريند راهين شا در هين GeoSoils, Inc. Hunnel wed BORING LOCATION MAP 3900 STANSBURY AVE THE BUCKLEY SCHOOL SCALE 1 20 WORK ORDER 4213 VN DATE 3 94 PLATE 1 STALEN OF THE ALL



























SEC	TION J
IB: 19376-B -	THE BUCKLEY SCHOOL
CONSULTANT: JV	VB SCALE. 1" = 100'
	OCTOBER 20, 2006
(960,1100)	т
	- 1100
ONE	
	- 900
	- 800
	J









LEAD-BASED PAINT

INSPECTION

REPORT Report ID #LBP-01

Prepared for:

The Buckley School 3900 Stansbury Road Sherman Oaks, CALIFORNIA 91423

Curtis Covington, Director of Physical Plant (818).783-1610 Office (818).461-6712 Fax

Prepared by:

). 4/28/06

Kenneth Medici Certified Asbestos Consultant California DOSH #92-0007 Lead Inspector/Assessor CA-DHS ID#1629

Site: The Buckley School, Sherman Oaks Campus -Phase One and Phase Two Structures

Dates: April 26, 2006 (On-Site XRF Testing) April 26, 2006 (On-site Assessment) April 28, 2006 (Issue Inspection Report)

Table of Contents

PAGE

LIST OF AP	PENDICES	ii
Section 1.0	Introduction	1
Section 2.0	Summary of all field and observation methods used	2
Section 3.0	Discussion of Findings	4

LIST OF APPENDICES

Appendix 1.0	XRF Lead-Based Paint Testing Report
Appendix 2.0	California Dept of Health Services Form #8552 Kenneth Medici

Lead-Based Paint Inspection & Assessment

The Buckley School 3900 Stansbury Ave Sherman Oaks, CA 91423

EXECUTIVE SUMMARY

The Buckley School conducted XRF Lead-Based Paint Inspection and Assessment on April 26, 2006 at 3900 Stansbury Ave Sherman Oaks, CA 91423. Structures engaged within this investigation include The Robert Young Library, The Main Campus Administration Building, the Upper School North and South Buildings, the Milkhouse, The College Counselors Trailor, and the Merchandise Trailor. Lead-based paint was discovered at a set of restrooms under the breezeway of the upper school, specifically upon the doorframes of these restrooms. Lead in ceramic tiles was also discovered. See Appendix 1 and details of floor plan of the XRF report. Lead-Dust Wipes, Lead-Air Samples, Lead-in soil samples were not collected for analysis because intact paint containing lead was found and the vast majority of painted surfaces were found not to contain lead. The Buckley School campus was deemed in compliance with all laws regarding lead-based paint.

Section 1.0 Introduction

On April 26, 2006 Applied Toxicology conducted an Lead-paint inspection at the above address. The primary objective of the work was to identify the existence and extent of major leadcontaining materials paints utilizing non-destructive investigations. The site construction is believed to have occurred prior to 1970. An XRF machine was used to accomplish nondestructive testings. AllState Services Environmental Company was employed by Applied Toxicology to conduct the XRF testings.

The accessible areas were visually inspected for suspect lead-containing materials. All accessible suspected lead-containing painted materials were tested using and XRF machine. Areas such as behind/within walls, under existing ACM's, linoleum, under the building, within the structure (hidden by known ACM), under concrete, within layered components, attic interstitial spaces, sub-structure areas, etc. were inaccessible within the scope of this investigation.

Section 2.0 Summary of all Field and Observation Methods Used

XRF Tests - Collection

The survey of April 26, 2006 processed approximately 694 tests of individual surfaces resulting in 16 positive findings of lead in material. The survey of homogeneous building material areas was conducted in a manner that minimized damage to the structure and minimized the health hazard to occupants or inspectors. The number of tests conducted from each suspect homogeneous building material area did follow HUD guidelines for Lead-Paint Inspection

See attached XRF Report prepared by AllState Services Environmental for protocols, testing methodology, detailed XRF findings, recommendations.

Analytical Laboratory Analysis

No Atomic Absorption Spectroscopy (AAS) analysis was performed. (No samples collected)

Laboratory Analysis Results

N/A

Conclusions and Recommendations

We conclude that ceramic tile, a water fountain, two door frames as stated in the attached XRF report contain lead above the legal limits and caution must be taken by the owner when disturbing these materials.

Because The Buckley School is planning Demolition of these Buildings which contain the above lead materials, the conclusions and recommendations may be tailored as such. We recommend that the owner not utilize this survey report as a stand alone document for bidding purposes by abatement contractors. We recommend the owner employ a CA Certified Asbestos/Lead Consultant and Lead-Related Construction Inspector Assessor - Project Designer to develop and implement an abatement plan along with air monitoring for community/School safety purposes.

Estimated Costs for Abatement (Removal) of Lead Materials

The costs of the above lead-containing materials will not affect the total budget for abatement of asbestos within the Phase one or Phase Two Structures under the current Modernization Project.

The information presented in this Asbestos Survey is based upon the agreed upon scope of work outlined in the above Report text. This environmental assessment is based mainly upon a limited collection and analysis of a limited number of samples from accessible suspected homogeneous material sampling areas. This report is not a legal opinion. The services performed by Applied Toxicology have been conducted in manner consistent with the level of care ordinarily exercised by members of our profession currently practicing under similar conditions. No warranty, expressed or implied is made. Applied Toxicology is not responsible for any claims or damages associated with interpretation of available information. This assessment should not be regarded as a guarantee that no further lead materials beyond that which was suspected to be present at the property, is present at this property. In the event site changes occur, or additional relevant information about the property is brought to our attention, the recommendations contained in this assessment may not be valid unless these changes and additional relevant information are reviewed and recommendations of this assessment are modified or verified in writing. Draft reports are not to be considered final reports.

4/28/06 =====

Ken Medici Certified Asbestos Consultant Cal-OSHA ID # 92-0007 Certified Lead-related Construction Inspector/Assessor Calif. Dept of Health Services ID#1629

APPENDIX

1.0

XRF REPORT

Professional Environmental Consulting and Training



Working for a clean environment 1826 Pomona Road Corona, California 92880 (951) 340-1717 (800) 320-LEAD Fax (951) 340-1448

LEAD-BASED PAINT TESTING

a

THE BUCKLEY SCHOOL 3900 STANSBURY AVENUE SHERMAN OAKS, CALIFORNIA 917423

PREPARED FOR: KEN MEDICI APPLIED TOXICOLOGY 1450 NORTH SANTA FE, SUITE C, PMB #144 VISTA, CALIFORNIA 92083

<u>PREPARED BY:</u> JAMES HANTGIN & GEORGE MUNOZ INSPECTOR/ASSESSOR CERTIFICATION #I-6259 & I-11268

APRIL 28, 2006

Professional Environmental Consulting and Training



Working for a clean environment 1826 Pomona Road Corona, California 92880 (951) 340-1717 (800) 320-LEAD Fax (951) 340-1448

April 28, 2006

Ken Medici Applied Toxicology 1450 Santa Fe, Suite C, PMB #144 Vista, California 92083

RE: Lead-based paint testing at The Buckley School, 3900 Stansbury Avenue, Sherman Oaks, CA

Dear Mr. Medici:

In accordance with your request and authorization, Allstate Services Environmental, Inc. conducted lead-based paint testing at The Buckley School, 3900 Stansbury Avenue in Sherman Oaks, California on April 26, 2006. The on-site work was conducted by James Hantgin and George Munoz, both California Certified Lead Inspector/Assessors.

If you need any further assistance after reviewing your report, please do not hesitate to contact me. Allstate Services Environmental, Inc. remains available to assist you in anyway possible.

Sincerely,

Stacey J. Phelps President

TABLE OF CONTENTS

-

Description		age
1.0	Testing Methodology ⁻	. 1
2.0	Building Description	. 2
3.0	Lead-Based Paint Findings	. 2
4.0	Federal Requirements	. 2
5.0	California State Requirements	. 3
6.0	Los Angeles County Requirements	3
7.0	Recommendations	3
8.0	OSHA Compliance	4

Appendices

- A. Summary Inspection Notice
- B. Detailed XRF Testing Results
- C. Floor Plan

-

-

- D. Inspector/Assessor Certifications
- E. DHS Form 8552 Lead Hazard Evaluation Report

1.0 TESTING METHODOLOGY

Lead-based paint testing was conducted using portable x-ray fluorescence (XRF) spectrum analyzer, Model MAP-4, Manufactured Keymaster Products Division of Kennewick, Washington. The MAP-4 is calibrated to measure the K-shell and the L-shell x-ray emission lines of lead. During testing, only the K-shell readings were recorded per the recommendation of the HUD Guidelines and the XRF Performance Characteristic Sheet (PCS) for the instrument. The K-shell is normally used for paint analysis because it measures lead in all layers of paint films, including the lower layers where higher concentrations of lead are usually found.

Lead-based paint testing was conducted in accordance with *Title 17, California Code of Regulations, Division 1, Chapter 8, Accreditation, Certification, and Work Practice in Lead Related Construction Section 36000* and the United States Department of Housing and Urban Development's *Guidelines for the Evaluation and Control of Lead-Based Paint Hazards in Housing, Chapter 7 Lead-Based Paint Inspection,* as published in June 1995 and revised in 1997.

The purpose of this inspection is to identify surfaces that contain lead-based paint as per *California* regulations, the HUD Guidelines and section 403 of the Toxic Substances Control Act.

The state of California, HUD and the EPA currently define lead-based paint as a paint or other surface coating which contains lead equal to or greater than 1.0 milligrams of lead per square centimeter of surface area (mg/cm²).

The Los Angeles County Department of Health Services has established a more stringent threshold level of 0.7 mg/cm² for lead in paint for lead poisoning cases (LACC Title 11, Chapter 11.28.010, Section C). Due to fact that the subject property is in the Los Angeles County and for the purpose of this report the more stringent standard of 0.7 mg/cm² would be used as the threshold level for this survey.

XRF readings were taken using the "Unlimited" mode of the MAP-4. "Unlimited" mode measurements have no predetermined testing length, and automatically adjust to account for various types of substrates and material's densities. The precision of the XRF readings is proportional to the square root of the number of x-rays counted by the scanner. The longer the test, the higher the level of precision as compared against the set threshold level of 0.7 mg/cm².

In the "Unlimited" mode, the MAP-4 tests until a K-shell result is indicated as either positive or negative, compared to the threshold level based on the current precision of the test. Correction for paint matrix and substrate effects is performed automatically. The correction function is based on measurements performed by the manufacturer with NIST paint film standards laid over a variety of substrates typically encountered in construction.

Based on the XRF Performance Characteristic Sheet (PCS) jointly released by HUD and EPA (effective June 26, 1996), the inconclusive range of the MAP-4 in the "Unlimited" mode is 0.61 mg/cm² to 0.89 mg/cm². Results are classified as positive if they are greater than the upper limit of the inconclusive range. Results are classified as negative if they are less than the lower limit of the inconclusive range. No substrate correction is required for testing using the "Unlimited" mode.

XRF readings were made on testing combinations in all room equivalents in an effort to test typical materials, which are representative of the room equivalent. Testing combinations were tested nondestructively by holding the MAP-4 against the surface being tested. At each XRF sample location the MAP-4 shutter is opened, and one reading was made using the "Unlimited"-testing testing mode. Results of each test were read from the digital display of the instrument console and recorded on the XRF Detailed Testing Data Sheet attached in Appendix B.

To ensure that the XRF equipment was working properly, various quality control tests were performed before, during and after the on-site work. At the beginning of the workday, three start up validation measurements were made in the "Test" mode, using the calibration check standard associated with the particular MAP-4 that was used. This painted standard contains a known quantity of lead and allows the XRF operator to determine whether the instrument is functioning within acceptable tolerance ranges for accuracy and precision, as determined by the manufacturer.

In addition to the three starts up tests, calibration readings were taken on the red 1.02 mg/cm² Standard Reference Material (SRM) paint film, developed by the National Institute of Standards and Technology (NIST). Results of each reading, along with computed readings averages were recorded on the XRF Calibration Form, and compared against the calibration tolerance range defined the MAP-4 PCS. This calibration check was also performed after four hours and at the end of the day. The quality control tests taken during testing at the subject property were within the acceptable performance range prescribed by the PCS and by the XRF equipment manufacturer. Documentation of the quality control calibration check is included in Appendix A, following the detailed testing data.

2.0 BUILDING DESCRIPTION

The property tested is a school campus with several buildings. The exteriors consist of brick and concrete walls, plaster canopies, brick columns and metal door and window systems. The interiors contain drywall and concrete walls, wood doors with metal frames and metal window systems.

3.0 LEAD-BASED PAINT FINDINGS

Lead-based paint was found at or above the Los Angeles County threshold level of 0.7 mg/cm² on the following components:

• Interior metal door frames

Please see Appendix A - XRF Positive Summary Report for a complete list of positive components and specific locations.

4.0 FEDERAL REQUIREMENTS

A copy of this summary must be provided to new lessees (tenants) and purchaser of this property under federal law (24 CFR part 35 and 40 CFR part 745) before they become obligated under a lease or sales contract. The complete report must also be provided to new purchasers and it must be made available to tenants. Landlord (lessors) and sellers are also required to distribute an educational pamphlet approved by the U. S. Environmental Protection Agency and include standard warning language in their lease or sales contracts to ensure that parents have the information they need to protect their children from lead-based paint hazards.

5.0 CALIFORNIA STATE REQUIREMENTS

Allstate Services Environmental, Inc. is required under California regulations (Title 17, CCR, Division 1, Chapter 8) to notify the California Department of Health Services that a lead hazard evaluation survey was conducted at the subject property.

Please see Appendix E for DHS Form 8552, Lead Hazard Evaluation Report.

6.0 LOS ANGELES COUNTY REQUIREMENTS

Allstate Services Environmental, Inc. hereby calls attention to Los Angeles County Code Title 11, Chapter 11.28 "Lead Hazards." As specified by the above, lead-based paint is defined as at or above the level of 0.7mg/cm². Thus for this report, all paint tested at or above the Los Angeles County level is considered "Positive."

7.0 RECOMMENDATIONS

If this building undergoes renovation in the future, personnel performing the construction work should be properly trained in lead-related construction. California regulations define lead-related construction work as, "Construction, alteration, painting, demolition, salvage, renovation, repair, or maintenance of any residential, public or commercial building, including preparation and cleanup, that, by using or disturbing lead containing material or soil, may result in significant exposure of individuals to lead."

California has a certification process for lead related construction workers. To receive a list of certified individuals, you may contact the Lead Accreditation and Certification Unit Hotline at (800) 597-5323.

There are different methods of addressing lead hazards. These methods include:

- <u>Abatement</u>: A measure or set of measures designed to permanently eliminate lead-based paint hazards or lead-based paint. There are different methods of abatement.
- <u>Replacement</u>: Removing the old component and installing a new non-lead containing component. Replacement is best suited for components that are easily removed. This includes doors, windows, trim, etc.
 - Enclosure: Covering a surface with a durable mechanically affixed, dust tight material, such as drywall, paneling, aluminum siding, etc. Enclosure is best used on walls, ceilings, floors, and some exterior components.

- Removal: Removing the paint from the substrate. This is accomplished by wet scraping, using power tools with special HEPA vacuum attachments, heat guns, and chemical stripping either on or off site. Paint removal is best suited when a component is to be preserved or when a component cannot be easily replaced or enclosed. Lead-based paint encapsulant products must have a minimum of twenty years warranty.
- <u>Encapsulation</u>: The process that makes lead-based paint inaccessible by providing a barrier between the lead-based paint and the environment. This barrier is formed using a liquid applied coating or an adhesive bonded covering material. Encapsulation is best used on walls and ceilings. Please note that ordinary lead-free paint is not considered an encapsulation.
- **Interim Controls** A set of measures designed to temporarily reduce human exposure or likely exposure to lead-based paint hazards. Interim controls include specialized cleaning, repairs, maintenance, painting, temporary containment, ongoing monitoring of lead-based paint hazards or potential hazards and the establishment and operation of management and resident education programs.

Interim controls should be used only if full abatement is not feasible. Reducing the hazards can be accomplished by simply keeping the painted surfaces intact and through specialized cleaning methods. If abatement cannot take place soon, interim controls should be implemented and maintained until full abatement can be made.

As previously stated, any activities involving lead hazard control and/or lead abatement must be performed by certified individuals.

8.0 OSHA COMPLIANCE

OSHA Regulations (Title 8 CCR Section 1532.1 and 29 CFR 1926.62) apply to all construction work where an employee may be occupationally exposed to lead, and therefore may be applicable to renovation or demolition projects involving paints with any concentration of lead.

It should be noted that "Lead-Based Paint Inspection" is a survey to discover the existence of leadbased paint only, which is defined as paint or other coating with lead levels of 1.0 mg/cm² or 0.5%. There are many other building materials, which may contain lead in the average building. When conducting construction activities, which disturb lead in any amount or create an exposure to workers, the employer is required to provide worker protection and conduct exposure assessments. All employers should consult Federal OSHA Regulations at 29 CFR 1926.62 and Cal-OSHA Regulations at Title 8, 1532.1, "Lead in Construction" standards for complete requirements. -

-

-

-

APPENDIX A SUMMARY INSPECTION NOTICE



Working for a clean environment 1826 Pomona Road Corona, California 92880 (951) 340-1717 (800) 320-LEAD Fax (951) 340-1448

Summary Notice of Lead-Based Paint Inspection

Address/location of property or structures(s) this summary notice applies to: The Buckley School 3900 Stansbury Avenue Sherman Oaks, California 91423

Lead-based paint inspection description: Dates(s) of inspection: *April 26, 2006*

Summary of inspection results (check all that apply):

- A. _____ No lead-based paint was found.
- B. ____X___ Lead-based paint was found.
- C. ___X A brief summary of the findings of the inspection is provided below (required if lead-based paint is found)

See positive summary table.

 Prepared by: James Hantgin
 Certification Number: #I-6259

 Signature:
 Image: April 28, 2006

Prepared by: George Munoz

Certification Number: #I-11268

Date: April 28, 2006 Signature:

			0.01		SUNT		(82)				
	1		1	3900 Stansbury Ave	enue, Sherman	Oaks, CA	91423				
		Room	Side				10300mmb	Lead		Quantities	
mple	Area	Equivalent	Tested	Component	Substrate	Color	Condition	(mg/ cm ²)	Results	For Entire Area	Comme
47 159	Interior	MEN'S RESTROOM	A	Door Frame	Metal	White	Intact	1.32	Positive	1 Fa	Comme
08	Interior *** Qu	WOMAN'S RESTROOM Jantity estimations of leaded m	C C	Door Frame	Metal	White	Intact	2.01	Positive	1 Ea.	

1

4 I

APPENDIX B DETAILED XRF TESTING RESULTS

-

-

				ILED XRF	TESTI	NGE	ESULT	18			
		anna an									
				3900 Stansbury Ave	enue, Sherman	Oaks, CA	91423				
		and the second	1					Lead		Quantities	ł
		Room	Side					(mg/			
mple	Area	Equivalent	Tested	Component	Substrate	Calar	0		-	For Entire	
1	Exterior	COLLEGE COUNSELOR I	A	Wall			Condition	cm²)	Results	Area	Commer
2	Exterior	COLLEGE COUNSELOR I	B	Wall	Metal	Tan	Intact	-0.15	Negative	-	
3	Exterior	COLLEGE COUNSELOR I	C	Wall	Metal	Tan	Intact	0.03	Negative		
4	Exterior	, COLLEGE COUNSELOR I	D	Wall	Metal	Tan	Intact	0.09	Negative		
5	Exterior	COLLEGE COUNSELOR I	A	Fascia	Metal	Tan	Intact	0.14	Negative		
6	Exterior	COLLEGE COUNSELOR I	A	Door	Metal	Tan	Intact	0.16	Negative		
7	Exterior	COLLEGE COUNSELOR I	A	Door Frame	Metal	Tan	Intact	0.33	Negative		
8	Exterior	COLLEGE COUNSELOR II	A	Wall	Metal	Tan	Intact	0.22	Negative		
9	Exterior	COLLEGE COUNSELOR II	B	Wall	Metal	Tan	Fair	-0.13	Negative		
10	Exterior	COLLEGE COUNSELOR II		Wall	Metal	Tan	Fair	-0.12	Negative		1
11	Exterior	COLLEGE COUNSELOR II	D	Wall	Metal	Tan	Fair	0.07	Negative		
12	Exterior	COLLEGE COUNSELOR II	A	Fascia	Metal	Tan	Fair	0.10	Negative		
13	Exterior	COLLEGE COUNSELOR II	A	Pascia Door	Metal	Tan	Fair	0.03	Negative		
14	Exterior	COLLEGE COUNSELOR II	A	Door Frame	Metal	Tan	Fair	0.18	Negative		
15	Exterior	MILK HOUSE	A	Wall	Metal	Tan	Fair	0.06	Negative		
16	Exterior	MILK HOUSE	B		Brick	Tan	Fair	0.30	Negative		
17	Exterior	MILK HOUSE	C	Wall Wall	Brick	Tan	Fair	0.20	Negative		and a subscription of the state
18	Exterior	MILK HOUSE	D	Wall	Brick	Tan	Fair	0.04	Negative		
19	Exterior	MILKHOUSE	B		Brick	Tan	Fair	0.18	Negative		
20	Exterior	MILK HOUSE	B	Fascia	Wood	Green	Fair	0.10	Negative		
21	Exterior	MILKHOUSE	C	Overhang	Wood	Tan	Fair	0.30	Negative		1
22	Exterior	MILKHOUSE	c	Door	Metal	White	Fair	-0.07	Negative		
23	Exterior	LIBRARY	A	Door Frame	Metal	White	Fair	-0.14	Negative	and a second	
24	Exterior	LIBRARY	B	Wall	Concrete	Tan	Intact	-0.37	Negative		r 1
25	Exterior	LIBRARY	C	Wall	Concrete	Tan	Intact	-0.26	Negative		
26	Exterior	LIBRARY	D	Wall	Concrete	Tan	Intact	-0.04	Negative	And a second	
27	Exterior	LIBRARY	A	Wall	Concrete	Tan	Intact	-0.39	Negative		1
28	Exterior	LIBRARY	A	Column	Concrete	Tan	Intact	-0.18	Negative		
29	Exterior	LIBRARY	A	Fascia	Wood	Brown	Intact	-0.13	Negative		
30	Exterior	LIBRARY	A	Overhang	Plaster	Tan	Intact	0.22	Negative		
31	Exterior	LIBRARY	B	Gutter	Metal	White	Intact	0.27	Negative	· · · · · · · · · · · · · · · · · · ·	
32	Exterior	LIBRARY	С	Railing	Metal	Green	Intact	0.44	Negative		
33	Exterior	LIBRARY		Boiler Door	Metal	Tan	Fair	0.01	Negative	• •	
34	Exterior	SOUTH CAMPUS BLDG.	C	Boiler Door Frame	Metal	Tan	Fair	0.23	Negative		
35	Exterior	SOUTH CAMPUS BLDG.	A	Wall	Plaster	White	Intact	-0.29	Negative		In the second
36	Exterior	SOUTH CAMPUS BLDG.	B	Wall	Plaster	White	Intact	0.23	Negative		
37	Exterior	SOUTH CAMPUS BLDG.	C D	Wall	Plaster	White	Intact	-0.45	Negative		·····
38	Exterior	SOUTH CAMPUS BLDG.		Wall	Plaster	White	Intact	0.04	Negative		
39	Exterior	SOUTH CAMPUS BLDG.	C	Window Frame	Wood	Brown	Intact	-0.50	Negative		
40	Exterior	SOUTH CAMPUS BLDG.	A	Door Frame	Wood	Tan	Intact	0.17	Negative	· · · · · · · · · · · · · · · · · · ·	
41	Exterior		<u>A</u>	Door	Metal	Tan	Intact	0.04	Negative		
42	Exterior	SOUTH CAMPUS BLDG. SOUTH CAMPUS BLDG.	A	Lower Fascia	Wood	Brown	Intact	0.03	Negative		
		SUBJECT AND A SHORE AND A S	A	Overhang	Plaster	White	Intact	0.26	Contraction of the second s		1

				3900 Stansbury Ave	onuo Shorman		04.402				
	•			Second Stansbury Ave	enue, Sherman	Oaks, CA	N 91423	Land		Ourselles	
		Room	Side					Lead		Quantities	
mule	Area	Equivalent	Tested	Component	Substrate	Color	Condition	(mg/ cm²)	Results	For Entire	
44	Exterior	SOUTH CAMPUS BLDG.	A	Fountain	Ceramic Tile	**************************************				Area	Commer
45	Exterior	SOUTH CAMPUS BLDG.	A	Locker Counter	Wood	Yellow	Intact	31.97	Positive	1 Ea.	Not a pain
46	Exterior	SOUTH CAMPUS BLDG.	A	Locker	and and a second s	White	Intact	0.06	Negative		· · · · · · · · · · · · · · · · · · ·
47	Exterior	SOUTH CAMPUS BLDG.	A		Metal	Gray	Intact	-0.24	Negative		
48	Exterior	NORTH CAMPUS BLDG.	A	Gutter Wall	Metal	White	Intact	-0.03	Negative		
49	Exterior	NORTH CAMPUS BLDG.	B	Wali	Plaster	Tan	Intact	0.01	Negative		
50	Exterior	NORTH CAMPUS BLDG.	C		Plaster	Tan	Intact	0.04	Negative		
51	Exterior	NORTH CAMPUS BLDG.	D	Wall	Plaster	Tan	Intact	0.05	Negative		
52	Exterior	NORTH CAMPUS BLDG.		Wall	Plaster	Tan	Intact	-0.43	Negative		
53	Exterior	NORTH CAMPUS BLDG.	<u> </u>	Fascia	Wood	Brown	Intact	0.03	Negative		
54	Exterior	NORTH CAMPUS BLDG,	<u>C</u>	Overhang	Plaster	Tan	Intact	0.06	Negative		
55	Exterior	NORTH CAMPUS BLDG.	C	Tile	Ceramic Tile	Red	Intact	0.11	Negative		
56	Exterior	NORTH CAMPUS BLDG.	C	Fountain	Ceramic Tile	White	Intact	0.08	Negative		
57	Exterior		C	Door	Wood	White	Intact	-0.76	Negative		
58	Exterior	NORTH CAMPUS BLDG.	C	Door Frame	Metal	White	Intact	0.03	Negative		
59 59	Exterior	NORTH CAMPUS BLDG.	C	Window Frame	Wood	Brown	Intact	0.24	Negative		-
		NORTH CAMPUS BLDG.	В	Lockers	Metal	White	Fair	0.17	Negative		
60	Exterior	NORTH CAMPUS BLDG.	С	Gutter	Metal	White	Intact	0.09	Negative		1
61	Exterior	NORTH CAMPUS BLDG.	C	Lubbers	Metal	White	Fair	0.07	Negative	····	
62	Exterior	NORTH CAMPUS BLDG.	D	Mech. Door	Metal	Tan	Intact	-0.31	Negative	201 - Calendar Samerica - Concerning Samerica - Provide Samerica - Concerning Samerica - Samer	
63	Exterior	ADMINISTRATIVE BLDG.	A	Wall	Plaster	White	Intact	-0.05	Negative		1
64	Exterior	ADMINISTRATIVE BLDG.	В	Wall	Plaster	White	Intact	-0.50	Negative		
65	Exterior	ADMINISTRATIVE BLDG.	С	Wall	Plaster	White	Intact	0.07	Negative	No	1
66	Exterior	ADMINISTRATIVE BLDG.	D	Wali	Plaster	White	Intact	-0.33	Negative	· · · · · · · · · · · · · · · · · · ·	
67	Exterior	ADMINISTRATIVE BLDG.	C	Handrail	Metal	Green	Intact	-0.26	Negative		
68	Exterior	ADMINISTRATIVE BLDG.	C	Gutter	Metal	White	Intact	-0.19	Negative		1
69	Exterior	ADMINISTRATIVE BLDG.	С	Fascia	Wood	Brown	Intact	-0.24	Negative		+
70	Exterior	ADMINISTRATIVE BLDG.		Overhang	Plaster	White	Intact	0.16	Negative		
71	Exterior	ADMINISTRATIVE BLDG.	С	Column	Brick	Brown	Intact	0.03	Negative		+
72	Exterior	ADMINISTRATIVE BLDG.	C	Window Frame	Wood	Brown	Intact	0.13	Negative		+
73	Exterior	ADMINISTRATIVE BLDG.	С	Window Sill	Wood	Brown	Intact	-0.28	Negative	·····	÷
74	Exterior	ADMINISTRATIVE BLDG.	С	Door	Metal	Black	Intact	-0.11	Negative	······································	1
75	Exterior	ADMINISTRATIVE BLDG.	A	Lockers	Metal	Tan	Intact	-0.13	Negative		1
76	Exterior	ADMINISTRATIVE BLDG.		Vent Caps	Metal	Tan	Intact	0.06	Negative		On the Ro
77	Exterior	ADMINISTRATIVE BLDG.		Vent	Metai	Tan	Intact	0.00	Negative		On the Ro

			DETA	ILED XRF	TESTI	NG F	ESUL	rs.			
				3900 Stansbury Ave	enue, Sherman	Oaks, CA	91423				
		Room	Side					Lead		Quantities	1
Sample	Area	Equivalent		Companyant	C		A 20	(mg		For Entire	
78			Tested	Component	Substrate	Color		, cm²)	Results	Area	Comments
78	Interior Interior	COLLEGE COUNSELOR I	A	Wall	Drywall	White	Intact	-0.11	Negative		
80	Interior	COLLEGE COUNSELOR I	B C	Wall	Drywall	White	Intact	-0.08	Negative		
81	Interior	COLLEGE COUNSELOR I	D	Wall	Drywall	White	Intact	-0.02	Negative		
82	Interior	COLLEGE COUNSELOR I	A	Wall	Drywall	White	Intact	-0.14	Negative		
83	Interior	COLLEGE COUNSELOR I	A	Door Door	Metal	White	Intact	0.03	Negative		
84	Interior	COLLEGE COUNSELOR I	<u></u>	Door Frame	Metal	White	Intact	0.04	Negative		
85	Interior	MILK HOUSE	A	Ceiling Wall	Drywall	White	Intact	-0.08	Negative		;
86	Interior	MILK HOUSE	B	Wall	Concrete	White	Intact	-0.07	Negative		1
87	Interior	MILK HOUSE	C	Wall	Concrete Concrete	White White	Intact	0.08	Negative		
88	Interior	MILK HOUSE	D	Wall	Concrete	White	Intact	-0.19	Negative		·
89	Interior	MILK HOUSE	c	Door	Metal	Tan	Intact Poor	0.03	Negative		
90	Interior	MILK HOUSE	c	Door Frame	Metal	Tan	Poor	-0.02	Negative	:	
91	Interior	MILK HOUSE	č	Window Service	Wood	White		-0.06	Negative		
92	Interior	MILK HOUSE	C	Window Frame	Wood	White	intact	0.03	Negative		
93	Interior	MILK HOUSE		Ceiling	Drywall	White	Intact	0.14	Negative		
94	Interior	MILK HOUSE	D	Closet Shelf	Wood		Intact	0.08	Negative	ļ	
95	Interior	UPPER LIBRARY	A	Wall		White	Fair	-0.13	Negative		
96	Interior	UPPER LIBRARY	B	Wall	Drywall Drywall	White White	Intact	-0.03	Negative	· · · · · · · · · · · · · · · · · · ·	
97	Interior	UPPER LIBRARY	C	Wall	Drywall	White	Intact	-0.14	Negative	e De la beneficia de la composition de la La composition de la c	- -
98	Interior	UPPER LIBRARY	D	Wall	Drywall	White	Intact	-0.06	Negative	Na internet and a state of the state of th	
99	Interior	UPPER LIBRARY		Ceiling	Wood	Brown	Intact	-0.11	Negative		· · · · · · · · · · · · · · · · · · ·
100	Interior	UPPER LIBRARY	С	Trim	Wood		Intact	-0.12	Negative		
101	Interior	UPPER LIBRARY		Column	Plaster	Brown White	Intact	-0.30	Negative	*	
102	Interior	LOWER LIBRARY	A	Wall	Drywall	White	Intact	0.12	Negative	-	
103	Interior	LOWER LIBRARY	B	Wall	Drywall	White	Intact	-0.08	Negative		
104	Interior	LOWER LIBRARY	C	Wall	Drywall	White	Intact	-0.14	Negative	, 6	:
105	Interior	LOWER LIBRARY	D	Wall	Drywall	White	Intact	-0.09	Negative	: 	· · · · · · · · · · · · · · · · · · ·
106	Interior	LOWER LIBRARY	A	Door	Metal	White	Intact Intact	-0.25	Negative		
107	Interior	LOWER LIBRARY	A	Door Frame	Metal	White	······································		Negative	/ 	
108	Interior	LOWER LIBRARY		Ceiling	Drywall	White	Intact Intact	0.21	Negative	1 	
109	Interior	LOWER LIBRARY		Stairway Column	Concrete	White	Intact	0.06	Negative		
110	Interior	LOWER LIBRARY		Handrail	Wood	Brown	Intact	0.06	Negative		
111	Interior	ROOM 123	A	Wall	Drywall	White			Negative		
112	Interior	ROOM 123	B	Wall	Drywall	White	Intact Intact	0.06	Negative		
113	Interior	ROOM 123	C	Wall	Drywall	White	Intact	0.04	Negative		
114	Interior	ROOM 123	D	Wall	Drywall	White	Intact	-0.26	Negative	· · · · · · · · · · · · · · · · · · ·	
115	Interior	ROOM 123	C	Door	Metal	White	Intact	-0.26	Negative	· · · · · · · · · · · · · · · · · · ·	
116	Interior	ROOM 123	C	Door Frame	Metal	White	Intact	-0.18	Negative	· · ·	
117	Interior	ROOM 123		Ceiling	Drywall	White	Intact	-0.10	Negative	\ 	
118	Interior	, LIBRARY OFFICE	A	Wall	Drywall	Beige	Intact	0.36	Negative	:	
119	Interior	LIBRARY OFFICE	В	Wall	Drywall	Beige	Intact	0.36	Negative		
120	Interior	LIBRARY OFFICE	C	Wall	Drywall	Beige	Intact	0.02	Negative Negative	1	

1

			DET/	ALED XRF	TESTI	NG F	RESUL	TS			
				3900 Stansbury Ave						-	
				eeee etanobary me	ondo, onorman	ouns, or	(01420	Lead		Quantities	
		Room	Side						1		
÷.				_				(mg/		For Entire	
	Area	Equivalent	Tested	Component	Substrate	Color	Condition	(cm²)	Results	Area	Comme
21	Interior	LIBRARY OFFICE	D	Wall	Drywall	Beige	Intact	0.05	Negative		
22	Interior	LIBRARY OFFICE	С	Door	Metal	White	Intact	0.09	Negative	1	
123	Interior	LIBRARY OFFICE	С	Door Frame	Metal	White	Intact	0.16	Negative		
24	Interior	LIBRARY OFFICE		Ceiling	Drywall	White	Intact	0.03	Negative		
125	Interior	LIBRARY OFFICE	A	Upper-Cabinet	Wood	Brown	Intact	0.00	Negative		
126	Interior	LIBRARY OFFICE	A	Lower-Cabinet	Wood	Brown	Intact	-0.16	Negative		i
127	Interior	CONFERENCE ROOM	<u>A</u>	Wall	Drywall	White	Intact	0.11	Negative	;	
1 <u>28</u> 129	Interior	CONFERENCE ROOM	B	Wali	Drywall	White	Intact	0.09	Negative		
130	Interior Interior	CONFERENCE ROOM	C	Wall	Drywall	White	Intact	0.22	Negative		
130		CONFERENCE ROOM	D	Wall	Drywall	White	Intact	0.13	Negative		
132	Interior	CONFERENCE ROOM	A	Door	Wood	White	Intact	0.03	Negative		
133	Interior	CONFERENCE ROOM	A	Door Frame	Metal	White	Intact	0.22	Negative		
134	Interior Interior	CONFERENCE ROOM		Celling	Drywall	White	Intact	-0.02	Negative		
135		ADMISSIONS BLDG.	<u>A</u>	Wall	Drywall	White	Intact	0.03	Negative	-	
136	Interior Interior	ADMISSIONS BLDG.	B	Wall	Drywall	White	Intact	0.08	Negative		
130	Interior	ADMISSIONS BLDG. ADMISSIONS BLDG.	<u> </u>	Wall	Drywall	White	Intact	0.02	Negative		
138			D	Wall	Drywall	White	Intact	0.14	Negative		:
139	Interior	ADMISSIONS BLDG.	A	Door	Wood	White	Intact	0.00	Negative		
138	Interior Interior	ADMISSIONS BLDG.	Α	Door Frame	Metal	White	Intact	0.01	Negative	I	
141	Interior	ADMISSIONS BLDG.		Ceiling	Drywall	White	Intact	0.08	Negative		
142	Interior	ENGLISH DEPARTMENT ENGLISH DEPARTMENT	<u>A</u>	Wall	Drywall	Green	Intact	0.08	Negative		
143	Interior	ENGLISH DEPARTMENT	B	Wall	Drywall	Green	Intact	-0.06	Negative		
143	Interior	ENGLISH DEPARTMENT	C	Wall	Drywall	Green	Intact	-0.02	Negative	1	
145	Interior		D	Wall	Drywall	Green	Intact	0.01	Negative		
146	Interior	ENGLISH DEPARTMENT ENGLISH DEPARTMENT	A	Door	Wood	Green	Intact	0.08	Negative		
147	Interior	ENGLISH DEPARTMENT	<u>A</u>	Door Frame	Metal	White	Intact	0.16	Negative		
148	Interior	STORAGE CLOSET	A	Ceiling	Drywall	White	Intact	0.07	Negative	· · · · · · · · · · · · · · · · · · ·	
149	Interior	STORAGE CLOSET	B	Wall	Drywall	White	Intact	-0.01	Negative		· · · · · · · · · · · · · · · · · · ·
150	Interior	STORAGE CLOSET	C D	Wall	Drywall	White	Intact	-0.20	Negative		
151	Interior	STORAGE CLOSET		Wall Wall	Concrete	White	Intact	-0.06	Negative		
152	Interior	STORAGE CLOSET	D		Drywall	White	Intact	-0.04	Negative		
153	Interior	STORAGE CLOSET	D	Door	Wood	Green	Intact	0.06	Negative		
154	Interior	STORAGE CLOSET		Door Frame	Metal	White	Intact	0.03	Negative		1
155	Interior	WOMAN'S RESTROOM	· · · · · · · · · · · · · · · · · · ·	Ceiling	Drywall	White	Intact	0.02	Negative		
156	Interior	WOMAN'S RESTROOM	: <u>A</u>	Wall	Ceramic Tile	Yellow	Intact	12.11	Positive		Not a pa
157	Interior	WOMAN'S RESTROOM	B	Wall	Ceramic Tile	Yellow	Intact	13.45	Positive		Not a pa
158	Interior	WOMAN'S RESTROOM	<u>C</u>	Wall	Ceramic Tile	Yellow	Intact	12.22	Positive		Not a pa
159	Interior	WOMAN'S RESTROOM	D	Wall	Ceramic Tile	Yellow	Intact	11.09	Positive		Not a pa
160	Interior	and the second se	<u> </u>	Door	Wood	White	Intact	0.01	Negative		
161	Interior	WOMAN'S RESTROOM	С	Door Frame	Metal	White	Intact	0.16	Negative	1	
162	Interior	WOMAN'S RESTROOM		Ceiling	Plaster	White	Intact	0.12	Negative		i
162		WOMAN'S RESTROOM		Stall	Metal	White	Intact	0.08	Negative	1	
100	Interior	MEN'S RESTROOM	A	Wall	Ceramic Tile	Yellow	Intact	18.26	Positive		Not a pa

			DETA	NLED XRF	- TESTI	NGE	ESHL	PS .			
				3900 Stansbury Av	enue, Sherman	Oaks, CA	91423				
								Lead		Quantities	
		Room	Side					ímg/		For Entire	
enple		Equivalent	Tested	Component	Substrate	Color	Condition	cm ²)	Results	Area	Comment
164	Interior	MEN'S RESTROOM	B	Wall	Ceramic Tile	Yellow	Intact	12.13	Positive		Not a paint
165	Interior	MEN'S RESTROOM	C	Wall	Ceramic Tile	Yellow	Intact	11.06	Positive		Not a paint
166	Interior	MEN'S RESTROOM	D	Wall	Ceramic Tile	Yellow	Intact	14.31	Positive		Not a paint
167	Interior	MEN'S RESTROOM	С	Door	Wood	White	Intact	0.22	Negative		Not a pain
168	Interior	MEN'S RESTROOM	С	Door Frame	Metal	White	Intact	0.01	Negative	and the subscription of th	
169	Interior	MEN'S RESTROOM		Ceiling	Plaster	White	Intact	0.08	Negative		
170	Interior	ROOM 101	A	Wall	Drywall	White	Intact	0.00	Negative		
171	Interior	ROOM 101	В	Wall	Drywall	White	Intact	-0.20	Negative		
172	Interior	ROOM 101	С	Wall	Drywall	White	Intact	0.19	Negative	and a second	
173	Interior	ROOM 101	<u>D</u>	Wall	Drywall	White	Intact	-0.18	Negative		
174	Interior	ROOM 101	A	Door	Wood	White	Intact	0.07	Negative		
175	Interior	ROOM 101	<u>A</u>	Door Frame	Metal	White	Intact	0.15	Negative		<u> </u>
176	Interior	ROOM 101	Α	Window Frame	Wood	White	Intact	0.07	Negative		
177	Interior	ROOM 101	A	Window Sill	Wood	White	Intact	-0.15	Negative		
178	Interior	ROOM 101	C	Window Frame	Metal	White	Intact	0.34	Negative		
179	Interior	ROOM 101		Ceiling	Drywall	White	Intact	0.06	Negative		
180	Interior	ROOM 101	B	Upper-Cabinet	Wood	White	Intact	-0.15	Negative		
181	Interior	ROOM 102	A	Wall	Drywall	White	Intact	0.16	Negative		
182	Interior	ROOM 102	В	Wall	Drywall	White	Intact	0.10	Negative		
183	Interior	ROOM 102	С	Wall	Drywall	White	Intact	-0.02	Negative		
184	Interior	ROOM 102	D	Wall	Drywall	White	Intact	-0.15	Negative	······	
185	Interior	ROOM 102	A	Door	Wood	White	Intact	0.06	Negative		· · · · · · · · · · · · · · · · · · ·
186	Interior	ROOM 102	A	Door Frame	Metal	White	Intact	0.23	Negative		
187	Interior	ROOM 102	A	Window Frame	Wood	White	Intact	0.13	Negative	······	
188	Interior	ROOM 102	A	Window Sill	Wood	White	Intact	0.13	Negative		
189	Interior	ROOM 102		Ceiling	Drywall	White	Intact	0.03			
190	Interior	ROOM 102	В	Upper-Cabinet	Wood	White	Intact	0.03	Negative Negative		
191	Interior	ROOM 103	A	Wall	Drywall	White	Intact	0.00	Negative		
192	Interior	ROOM 103	В	Wall	Drywall	White	Intact	-0.04	Negative		
193	Interior	ROOM 103	С	Wall	Drywall	White	Intact	-0.04	Negative		
194	Interior	ROOM 103	D	Wall	Drywall	White	Intact	0.03			
195	Interior	ROOM 103	A	Door	Wood	White	Intact	0.03	Negative		
196	Interior	ROOM 103	A	Door Frame	Metal	White	Intact	0.04	Negative		
197	Interior	ROOM 103	A	Window Frame	Wood	White	Intact	the second se	Negative		
198	Interior	ROOM 103	A	Window Sill	Wood	White	The second	-0.07	Negative		
199	Interior	ROOM 103		Ceiling	Drywall	White	Intact	0.09	Negative		
200	Interior	ROOM 103	В	Upper-Cabinet	Wood	White	Intact	0.08	Negative		
201	Interior	ROOM 104	A	Wall	Drywall	White	Intact	0.10	Negative		· · · · · · · · · · · · · · · · · · ·
202	Interior	ROOM 104	B	Wall	Drywall	White	Intact	-0.18	Negative		
203	Interior	ROOM 104	C	Wall	Drywall	White	Intact	0.06	Negative		
204	Interior	ROOM 104	D	Wall	Drywall	White	Intact	0.23	Negative		
205	Interior	ROOM 104	Ā	Door	Wood	White	Intact	0.04	Negative	······	,
206	Interior	ROOM 104	A	Door Frame	, wyoda	vvnite	Intact	0.08	Negative		

1 *I*

			DETA	ILED XRF	TEST	NG R	ESUL	TS			
				3900 Stansbury Ave	nue Shermar	Oaks CA	01423				
				eeee etanobary / we	indo, onormai	rouns, or	01420	Lead		Quantities	
		Room	Side			-		(mg/	l	For Entire	
Sample	Area	Equivalent	Tested	Component	Substrate	Color	Condition	cm ²)	Results	Area	Comments
207	Interior	ROOM 104	A	Window Frame	Wood	White	Intact	0.01	Negative		and and the product of the second
208	Interior	ROOM 104	A	Window Sill	Wood	White	Intact	0.12	Negative		· · · · · · · · · · · · · · · · · · ·
209	Interior	ROOM 104		Ceiling	Drywall	White	Intact	0.08	Negative		
210	Interior	ROOM 104	В	Upper-Cabinet	Wood	White	Intact	0.30	Negative		
211	Interior	ROOM 105	A	Wall	Drywall	White	Intact	-0.22	Negative		
212	Interior	ROOM 105	В	Wall	Drywall	White	Intact	-0.42	Negative	«	2
213	Interior	ROOM 105	С	Wall	Drywall	White	Intact	0.23	Negative		1
214	Interior	ROOM 105	D	Wall	Drywall	White	Intact	0.13	Negative		· · · · · · · · · · · · · · · · · · ·
215	Interior	ROOM 105	A	Door	Wood	White	Intact	0.06	Negative		
216	Interior	ROOM 105	A	Door Frame	Metal	White	Intact	0.20	Negative		
217	Interior	ROOM 105	A	Window Frame	Wood	White	Intact	0.06	Negative		i
218	Interior	ROOM 105	A	Window Sill	Wood	White	Intact	0.09	Negative		
219	Interior	ROOM 105		Ceiling	Drywall	White	Intact	0.20	Negative		
220	Interior	ROOM 106	A	Wall	Drywall	White	Intact	0.10	Negative		*
221	Interior	ROQM 106	В	Wall	Drywall	White	intact	0.26	Negative		· · · · · · · · · · · · · · · · · · ·
222	Interior	ROOM 106	C	Wall	Drywall	White	Intact	0.09	Negative		· · · · · · · · · · · · · · · · · · ·
223	Interior	ROOM 106	D	Wall	Drywall	White	Intact	0.07	Negative		
224	Interior	ROOM 106	A	Door	Wood	Red	Intact	0.03	Negative		· · · · · · · · · · · · · · · · · · ·
225	Interior	ROOM 106	A	Door Frame	Metal	Red	Intact	0.43	Negative		
226	Interior	ROOM 106	A	Window Frame	Wood	White	Intact	-0.07	Negative		2
227	Interior	ROOM 106	A	Window Sill	Wood	White	Intact	-0.02	Negative		
228	Interior	ROOM 106		Ceiling	Drywall	White	Intact	0.08	Negative		
229	Interior	ROOM 106 A	A	Wall	Drywall	White	Intact	-0.31	Negative	·····	
230	Interior	ROOM 106 A	В	Wall	Drywall	White	Intact	0.00	Negative		1
231	Interior	ROOM 106 A	С	Wall	Drywall	White	Intact	0.09	Negative		
232	Interior	ROOM 106 A	D	Wall	Drywall	White	Intact	-0.32	Negative		······································
233	Interior	ROOM 106 A	C	Door	Wood	White	Intact	0.22	Negative		
234	Interior	ROOM 106 A	C	Door Frame	Metal	White	Intact	0.26	Negative	· · · · · · · · · · · · · · · · · · ·	
235	Interior	ROOM 106 A		Ceiling	Drywall	White	Intact	-0.27	Negative		
236	Interior	ROOM 106 A	В	Upper-Cabinet	Wood	White	Intact	-0.13	Negative		
237	Interior	ROOM 107	<u>A</u>	Wall	Drywall	White	Intact	0.11	Negative		
238	Interior	ROOM 107	B	Wall	Drywall	White	Intact	-0.62	Negative		
239	Interior	ROOM 107	C	Wall	Drywall	White	Intact	0.31	Negative		· · ·
240		ROOM 107	D	Wall	Drywall	White	Intact	0.20	Negative		
241	Interior	ROOM 107	С	Door	Wood	White	Intact	0.04	Negative		
242	Interior	ROOM 107	C	Door Frame	Metal	White	Intact	0.18	Negative		;
243	Interior	ROOM 107	С	Window Frame	Wood	White	Intact	0.31	Negative	4 8	1
······	Interior	ROOM 107	С	Window Sill	Wood	White	Intact	0.26	Negative		
245 246	Interior	ROOM 107		Ceiling	Drywall	White	Intact	0.03	Negative		
	Interior	ROOM 107	В	Upper-Cabinet	Wood	White	Intact	0.01	Negative		
247	Interior	ROOM 108	<u>A</u>	Wall	Drywall	White	Intact	0.02	Negative		
248	Interior	ROOM 108	В	Wall	Drywall	White	Intact	0.16	Negative		an a
L 249	Interior	ROOM 108	C	Wall	Drywall	White	Intact	0.08	Negative	- "And the second se	

			DETA	ILED XRF	TESTI	NG F	ESUI-	TS .			
								<u> </u>			
				3900 Stansbury Ave	nue, Sherman	Oaks, CA	91423				
		Room	<u> </u>					Lead		Quantities	
Samele	S firms		Side		_			(mg/		For Entire	
250		Equivalent	Tested	Component	Substrate	Color	Condition	cm ²)	Results	Area	Comments
250	Interior	ROOM 108	D	Wall	Drywall	White	Intact	0.19	Negative		1
252	Interior Interior	ROOM 108	C	Door	Wood	White	Intact	0.08	Negative		
253	Interior	ROOM 108 ROOM 108	C	Door Frame	Metal	White	Intact	-0.13	Negative		
254	Interior	ROOM 108	C	Window Frame	Wood	White	Intact	0.03	Negative	······································	
255	Interior	ROOM 108	C	Window Sill	Wood	White	Intact	0.01	Negative		· · · · · · · · · · · · · · · · · · ·
256	Interior	MATHEMATICS OFFICE	 A	Ceiling	Drywall	White	Intact	0.02	Negative		
257	Interior	MATHEMATICS OFFICE	B	Wall	Drywall	White	Intact	0.22	Negative		······································
258	Interior	MATHEMATICS OFFICE	C	Wall Wall	Drywall	White	Intact	0.03	Negative		
259	Interior	MATHEMATICS OFFICE	D +	Wall	Drywall	White	Intact	0.27	Negative		
260	Interior	MATHEMATICS OFFICE	C	Door	Drywall Wood	White	Intact	0.01	Negative		
261	Interior	MATHEMATICS OFFICE	C	Door Frame		Red	Intact	0.08	Negative		
262	Interior	MATHEMATICS OFFICE	C	Window Frame	Metal Wood	Red White	Intact	-0.22	Negative		
263	Interior	MATHEMATICS OFFICE	c	Window Sill	Wood		Intact	-0.30	Negative		-
264	Interior	MATHEMATICS OFFICE		Ceiling		White	Intact	-0.18	Negative		
265	Interior	DEANS OFFICES	A	Wall	Drywall Drywall	White	Intact	-0.01	Negative		
266	Interior	DEANS OFFICES	B	Wall		White	Intact	0.03	Negative		
267	Interior	DEANS OFFICES	c	Wall	Drywall Drywall	White	Intact	0.14	Negative		
268	Interior	DEANS OFFICES	D	Wall	Drywall	White	Intact	0.09	Negative		
269	Interior	DEANS OFFICES	C	Door		White	Intact	0.26	Negative		:
270	Interior	DEANS OFFICES	c	Door Frame	Wood	White	Intact	-0.22	Negative		
271	Interior	DEANS OFFICES	C C	Window Frame	Metal Wood	White	Intact	-0.11	Negative	······································	
272	Interior	DEANS OFFICES	C C	Window Sill		White	Intact	-0.06	Negative		
273	Interior	DEANS OFFICES		Ceiling	Wood Drywall	White	Intact	-0.12	Negative		•
274	Interior	ROOM 109	A	Wall	Drywall	White White	Intact	0.08	Negative		
275	Interior	ROOM 109	B	Wall	Drywall	White	Intact	0.06	Negative		
276	Interior	ROOM 109	C	Wall	Drywall	White	Intact	-0.31	Negative		1
277	Interior	ROOM 109	D	Wall	Drywall	White	Intact	0.20	Negative		·
278	Interior	ROOM 109	В	Door	Wood	White	Intact	0.08	Negative		
279	Interior	ROOM 109	B	Door Frame	Metal	White	Intact Intact	-0.23 -0.15	Negative		
280	Interior	ROOM 109		Ceiling	Drywall	White	Intact	-0.15	Negative		·
281	Interior	FACULTY WORK ROOM	A	Wall	Drywall	White	Intact	-0.22	Negative	······································	
282	Interior	FACULTY WORK ROOM	В	Wall	Drywall	White	Intact	-0.32	Negative		
283	Interior	FACULTY WORK ROOM	С	Wall	Drywall	White	Intact	-0.40	Negative Negative	Contraction of the Contraction o	
284	Interior	FACULTY WORK ROOM	D	Wall	Drywali	White	Intact	0.12	Negative		+
285	Interior	FACULTY WORK ROOM	В	Door	Wood	White	Intact	-0.12	Negative		
286	Interior	FACULTY WORK ROOM	В	Door Frame	Metal	White	Intact	-0.18	Negative		
287	Interior	FACULTY WORK ROOM		Ceiling	Drywall	White	Intact	0.03	Negative		1
288	Interior	FACULTY WORK ROOM	D	Upper-Cabinet	Wood	Tan	Intact	0.32	Negative		
289	Interior	JANITOR CLOSET	A	Wall	Plaster	Tan	Intact	0.32	Negative	· · · ·	
290	Interior	JANITOR CLOSET	В	Wall	Plaster	Tan	Intact	0.32	Negative		
291	Interior	JANITOR CLOSET	С	Wall	Plaster	Tan	Intact	0.32	Negative		
292	Interior	JANITOR CLOSET	D	Wall	Plaster	Tan	Intact	0.18	Negative		

			DETA		STESTI		ESHI	тο		
				3900 Stansbury Av	enue, Sherman	Oaks, CA	91423			
								Lead		Quantities
		Room	Side					ímg/	ł i	For Entire
mpie	e Area	Equivalent	Tested	Component	Substrate	Color	Condition		Results	
293	Interior	JANITOR CLOSET	В	Door	Wood	Orange	Fair			Area Comme
294	Interior	JANITOR CLOSET	В	Door Frame	Metal	Orange	Fair	0.37	Negative	-
295	Interior	JANITOR CLOSET		Ceiling	Plaster	Tan	Intact	0.14	Negative	
296	Interior	JANITOR CLOSET	А	Shelves	Wood	Tan	Fair	0.05	Negative	
297	Interior	ROOM 110	A	Wall	Drywall	White	Intact	0.01	Negative	
298	Interior	ROOM 110	В	Wall	Drywall	White	Intact	0.02	Negative	
299	Interior	ROOM 110	С	Wall	Drywall	White	Intact	-0.30	Negative	
300	Interior	ROOM 110	D	Wall	Drywall	White	Intact	-0.30	Negative	
301	Interior	ROOM 110	A	Door	Wood	White	Intact	0.16	Negative Negative	
302	Interior	ROOM 110	A	Door Frame	Metal	White	Intact	0.18	Negative	
303	Interior	ROOM 110	Α	Window Frame	Wood	White	Intact	-0.13	Negative	
304 305	Interior	ROOM 110	A	Window Sill	Wood	White	Intact	-0.27	Negative	
306	Interior	ROOM 110		Ceiling	Drywall	White	Intact	-0.10	Negative	
307	Interior	ROOM 110	В	Upper-Cabinet	Wood	White	Intact	0.13	Negative	······
307	Interior	ROOM 111	A	Wall	Drywall	White	Intact	0.11	Negative	1
309	Interior	ROOM 111	B	Wall	Drywall	White	Intact	0.10	Negative	
310	Interior	ROOM 111	<u> </u>	Wall	Drywall	White	Intact	-0.04	Negative	
310	Interior	ROOM 111	D	Wall	Drywall	White	Intact	-0.13	Negative	
312	Interior	ROOM 111	A	Door	Wood	White	Intact	0.09	Negative	
312 313	Interior	ROOM 111	A	Door Frame	Metal	White	Intact	0.14	Negative	
314	Interior	ROOM 111	<u>A</u>	Window Frame	Wood	White	Intact	-0.10	Negative	
315	Interior	ROOM 111	<u>A</u>	Window Sill	Wood	White	Intact	-0.01	Negative	· · · · · · · · · · · · · · · · · · ·
	Interior	ROOM 111		Ceiling	Drywall	White	Intact	0.00	Negative	
316	Interior	ROOM 111	Q	Upper-Cabinet	Wood	White	Intact	-0.06	Negative	
317 318		JANITOR CLOSET	<u>A</u>	Wall	Plaster	Tan	Intact	0.04	Negative	
	Interior	JANITOR CLOSET	В	Wall	Plaster	Tan	Intact	0.39	Negative	
319	Interior	JANITOR CLOSET	C	Wall	Plaster	Tan	Intact	0.28	Negative	
320 321		JANITOR CLOSET	D	Wall	Plaster	Tan	Intact	0.26	Negative	
322	Interior	JANITOR CLOSET	<u>A</u>	Door	Wood	Orange	Fair	0.20	Negative	
	Interior	JANITOR CLOSET	A	Door Frame	Metal	Orange	Fair	0.06	Negative	
323	Interior	JANITOR CLOSET		Ceiling	Plaster	Tan	Intact	0.08	Negative	2
324	Interior	ROOM 112	A	Wall	Drywall	White	Intact	0.20	Negative	
325	Interior	ROOM 112	8	Wall	Drywall	White	Intact	0.06	Negative	
326 327	Interior	ROOM 112	C	Wall	Drywall	White	Intact	0.30	Negative	
327 328	Interior	ROOM 112	D	Wall	Drywall	White	Intact	0.14	Negative	
	Interior	ROOM 112	<u>A</u>	Door	Wood	White	Intact	0.14	Negative	-
329	Interior	ROOM 112	A	Door Frame	Metal	White	Intact	0.03	Negative	
330	Interior	ROOM 112	<u>A</u>	Window Frame	Wood	White	Intact	0.03	Negative	:
331	Interior	ROOM 112	A	Window Sill	Wood	White	Intact	-0.26	Negative	
332	Interior	ROOM 112		Ceiling	Drywall	White	Intact	-0.20	Negative	1
333	Interior	ROOM 113-114	A	Wall	Drywall	White	Intact	0.01	Negative	· · · · · · · · · · · · · · · · · · ·
334	Interior	ROOM 113-114	В	Wali	Drywall	White	Intact	0.27		
335	Interior	ROOM 113-114	C	Wall	Drywall	White	Intact	0.14	Negative Negative	

•

.

			DETA	ILED XRF	TEST		PESHI [®]	ΓS			
							· · · · · · · · · · · · · · · · · · ·		······		
				3900 Stansbury Ave	enue, Sherman	Oaks, CA	91423				
								Lead		Quantities	
		Room	Side					(mg/		For Entire	
Sample	Area	Equivalent	Tested	Component	Substrate	Color	Condition		Dessite		<u> </u>
336	Interior	ROOM 113-114	D	Wall	Drywall	White			Results	Area	Comments
337	Interior	ROOM 113-114	D	Door	Wood	White	Intact Intact	0.20	Negative		
338	Interior	ROOM 113-114	D	Door Frame	Metal	White	Intact	-0.03	Negative		
339	Interior	ROOM 113-114	D	Window Frame	Wood	White	Intact	0.19	Negative		
340	Interior	ROOM 113-114	D	Window Sill	Wood	White	Intact	0.20	Negative		
341	Interior	ROOM 113-114		Ceiling	Drywall	White	Intact	0.32	Negative Negative		· · · · · · · · · · · · · · · · · · ·
342	Interior	MEN'S RESTROOM	Α	Wall	Plaster	White	Intact	0.08	Negative		
343	Interior	MEN'S RESTROOM	В	Wall	Plaster	White	Intact	0.03	Negative		
344	Interior	MEN'S RESTROOM	С	Wall	Plaster	White	Intact	0.03	Negative		
345	Interior	MEN'S RESTROOM	D	Wall	Plaster	White	Intact	0.13	Negative		
346	Interior	MEN'S RESTROOM	A	Door	Wood	White	Intact	0.06	Negative		
347	Interior	MEN'S RESTROOM	A	Door Frame	Metal	White	Intact	1.32	Positive	1 Ea.	
348	Interior	MEN'S RESTROOM		Ceiling	Plaster	White	Intact	0.03	Negative) b Q.	
349	Interior	MEN'S RESTROOM		Floor	Ceramic Tile	Brown	Intact	-0.03	Negative		
350	Interior	MEN'S RESTROOM	D	Urinal	Ceramic Tile	White	Intact	0.01	Negative		
351	Interior	MEN'S RESTROOM		Stall	Metal	White	Intact	0.16	Negative	a	
352	Interior	MEN'S RESTROOM		Tile	Ceramic Tile	Brown	Intact	14.12	Positive	300 SF	Not a paint
353	Interior	MEN'S RESTROOM		Sink	Ceramic Tile	White	Intact	-0.17	Negative	7	- Noca paint
354	Interior	WOMAN'S RESTROOM	A	Wall	Plaster	White	Intact	0.02	Negative		
355	Interior	WOMAN'S RESTROOM	8	Wall	Plaster	White	Intact	0.04	Negative		
356	Interior	WOMAN'S RESTROOM	С	Wall	Plaster	White	Intact	0.18	Negative		
357	Interior	WOMAN'S RESTROOM	D	Wall	Plaster	White	Intact	0.09	Negative	and a second	
358	Interior	WOMAN'S RESTROOM	С	Door	Wood	White	Intact	0.28	Negative		
359	Interior	WOMAN'S RESTROOM	С	Door Frame	Metal	White	Intact	2.01	Positive	1 Ea.	
360	Interior	WOMAN'S RESTROOM		Ceiling	Plaster	White	Intact	0.06	Negative		
361	Interior	WOMAN'S RESTROOM		Stall	Metal	White	Intact	0.04	Negative		· · · · · · · · · · · · · · · · · · ·
362	Interior	WOMAN'S RESTROOM		Floor	Ceramic Tile	Brown	Intact	0.28	Negative		
363	Interior	WOMAN'S RESTROOM		Tile	Ceramic Tile	Brown	Intact	10.70	Positive	300 SF	Not a paint
365	Interior	WOMAN'S RESTROOM	<u>A</u>	Sink	Ceramic Tile	White	Intact	0.06	Negative	······································	
366	Interior	PRINCIPLE'S OFFICE	A	Wall	Drywall	White	Intact	0.07	Negative		
367	Interior Interior	PRINCIPLE'S OFFICE	B	Wall	Drywall	White	intact	0.13	Negative		
368		PRINCIPLE'S OFFICE	С	Wall	Drywall	White	Intact	0.24	Negative		
369	Interior Interior	PRINCIPLE'S OFFICE	D	Wall	Drywall	White	Intact	0.05	Negative		
370	Interior	PRINCIPLE'S OFFICE PRINCIPLE'S OFFICE	В	Wall	Wood	Brown	Intact	0.12	Negative		
370	Interior	PRINCIPLE'S OFFICE	<u>A</u>	Crown Molding	Wood	Brown	Intact	0.16	Negative		:
372	Interior	PRINCIPLE'S OFFICE	B	Door	Wood	Brown	Intact	0.03	Negative		
373	Interior	PRINCIPLE'S OFFICE	<u> </u>	Door Frame	Wood	Brown	Intact	0.26	Negative		
374	Interior	PRINCIPLE'S OFFICE	D	Window Frame	Wood	Brown	Intact	0.16	Negative		
375	Interior	PRINCIPLE'S OFFICE	D	Window Sill	Wood	Brown	Intact	0.07	Negative		!
376	Interior	PRINCIPLE'S OFFICE		Ceiling	Drywall	White	Intact	0.05	Negative		
377	Interior	ASSISTANT PRINCIPLE	C	Upper-Cabinet	Wood	Brown	Intact	0.03	Negative		
378	Interior	ASSISTANT PRINCIPLE	A B	Wall	Drywall	White	Intact	0.07	Negative		
8			. D	Wall	Drywall	White	Intact	0.13	Negative		

r.

•

			DETA		TEST		ESHI	TC		
								<u></u>		
				3900 Stansbury Ave	enue, Sherman	Oaks, CA	91423			
								Lead		Quantities
		Room	Side					(mg/		For Entire
~~~~~	Area	Equivalent	Tested	Component	Substrate	Color	Condition	cm ² )	Results	Area Comme
379	Interior	ASSISTANT PRINCIPLE	С	Wall	Drywall	White	Intact	0.25	Negative	An en anterio
380	Interior	ASSISTANT PRINCIPLE	D	Wall	Drywall	White	Intact	0.18	Negative	
381	Interior	ASSISTANT PRINCIPLE	В	Wall	Wood	Brown	Intact	0.03	Negative	
382	Interior	ASSISTANT PRINCIPLE	С	Crown Molding	Wood	Brown	Intact	-0.13	Negative	
383	Interior	ASSISTANT PRINCIPLE	В	Door	Wood	Brown	Intact	0.02	Negative	
384	Interior	ASSISTANT PRINCIPLE	В	Door Frame	Wood	Brown	Intact	-0.15	Negative	
385	Interior	ASSISTANT PRINCIPLE	D	Window Frame	Wood	Brown	Intact	-0.30	Negative	
386	Interior	ASSISTANT PRINCIPLE	D	Window Sill	Wood	Brown	Intact	-0.06	Negative	
387	Interior	ASSISTANT PRINCIPLE		Ceiling	Drywall	White	Intact	0.04	Negative	
388	Interior	ASSISTANT PRINCIPLE	A	Upper-Cabinet	Wood	Brown	Intact	0.17	Negative	
389	Interior	MID. SCHOOL PRINCIPLE	A	Wall	Drywall	White	Intact	0.04	Negative	
390	Interior	MID. SCHOOL PRINCIPLE	В	Wall	Drywall	White	Intact	-0.37	Negative	
391	Interior	MID. SCHOOL PRINCIPLE	C	Wall	Drywall	White	Intact	0.18	Negative	
392	Interior	MID. SCHOOL PRINCIPLE	D	Wall	Drywall	White	Intact	0.09	Negative	
393	Interior	MID. SCHOOL PRINCIPLE	D	Door	Wood	Brown	Intact	0.03	Negative	
394	Interior	MID. SCHOOL PRINCIPLE	D	Door Frame	Metal	White	Intact	-0.32	Negative	
395	Interior	MID. SCHOOL PRINCIPLE		Ceiling	Drywall	White	Intact	0.05	Negative	
396	Interior	MID. SCHOOL PRINCIPLE	A	Door	Wood	White	Intact	-0.12	Negative	
397	Interior	ADMINISTRATIVE OFFICE	A	Wall	Drywall	Tan	Intact	0.01		
398	Interior	ADMINISTRATIVE OFFICE	В	Wall	Drywall	Tan	Intact	0.01	Negative	
399	Interior	ADMINISTRATIVE OFFICE	С	Wall	Drywall	Tan	Intact	-0.22	Negative	
400	Interior	ADMINISTRATIVE OFFICE	D	Wall	Drywall	Tan	Intact	0.22	Negative	
401	Interior	ADMINISTRATIVE OFFICE	С	Door	Metal	Black	Intact		Negative	
402	Interior	ADMINISTRATIVE OFFICE	Ċ	Door Frame	Metal	Black		-0.06	Negative	
403	Interior	ADMINISTRATIVE OFFICE	C	Window Sill	Wood	Tan	Intact Intact	-0.38	Negative	
404	Interior	ADMINISTRATIVE OFFICE		Ceiling	Drywall	White	Intact	-0.13	Negative	2
405	Interior	COLLEGE COUNSELOR	A	Wali	Drywall	White	Intact	0.04	Negative	· · · · · · · · · · · · · · · · · · ·
406	Interior	COLLEGE COUNSELOR	В	Wall	Drywall	White	the set of	0.07	Negative	
407	Interior	COLLEGE COUNSELOR	С	Wall	Drywall	White	Intact	-0.31	Negative	· · · · · · · · · · · · · · · · · · ·
408	Interior	COLLEGE COUNSELOR	D	Wall	Drywall		Intact	-0.26	Negative	· · · · · · · · · · · · · · · · · · ·
409	Interior	COLLEGE COUNSELOR	B	Door	Wood	White Brown	Intact	0.04	Negative	
410	Interior	COLLEGE COUNSELOR	В	Door Frame	Metal	White	Intact	0.16	Negative	2 
411	Interior	COLLEGE COUNSELOR	C	Window Frame	Wood	White	Intact	0.03	Negative	
412	Interior	COLLEGE COUNSELOR	Č	Window Frame Window Sill	Wood	White	Intact	0.13	Negative	
413	Interior	COLLEGE COUNSELOR		Ceiling	Drywall	White	Intact	0.09	Negative	
414	Interior	ADMINISTRATIVE SECRETARY	A	Wall	Drywall		Intact	0.01	Negative	1
415	Interior	ADMINISTRATIVE SECRETARY	B	Wall		Beige	Intact	0.01	Negative	;
416	Interior	ADMINISTRATIVE SECRETARY	C	Wall	Drywall	Beige	Intact	0.03	Negative	
417	Interior	ADMINISTRATIVE SECRETARY	D	Wall	Drywall	Beige	Intact	0.14	Negative	
418	Interior	ADMINISTRATIVE SECRETARY	A	Vvaii Door	Drywall	Beige	Intact	0.32	Negative	
419	Interior	ADMINISTRATIVE SECRETARY	A		Wood	Brown	Intact	0.14	Negative	
420	Interior	ADMINISTRATIVE SECRETARY	Concernance of the concernance of	Door Frame	Metal	White	Intact	0.05	Negative	
421	Interior	ADMINISTRATIVE SECRETARY	D	Window Frame	Wood	White	Intact	0.04	Negative	
	t niteriol	ADMINISTRATIVE SECRETARY	D	Window Sill	Wood	White	Intact	0.11	Negative	

4 J

			DETA		TESTI	NG R	ESULT	-5			
				3900 Stansbury Av	enue Sherman	Oaks CA	01423				
		and a second		eeee etanloydi j / ti	ondo, onorman	Ouns, OA	01420	Lord		A	
		Room	614-					Lead		Quantities	
			Side					(mg/		For Entire	•
ample	· · · ·	Equivalent	Tested	Component	Substrate	Color	Condition	cm ²	Results	Area	Comment
422	Interior	ADMINISTRATIVE SECRETARY		Ceiling	Drywall	White	Intact	0.07	Negative		
423	Interior	BREAK ROOM	A	Wall	Drywall	Beige	Intact	0.03	Negative	· · · · · · · · · · · · · · · · · · ·	+
424	Interior	BREAK ROOM	В	Wall	Drywall	Beige	Intact	0.26	Negative		
425	Interior	BREAK ROOM	С	Wall	Drywall	Beige	Intact	0.17	Negative		
426	Interior	BREAK ROOM	D	Wall	Drywall	Beige	Intact	0.30	Negative		
427	Interior	BREAK ROOM	С	Door	Wood	Brown	Intact	0.17	Negative		
428	Interior	BREAK ROOM	C	Door Frame	Metal	White	Intact	0.39	Negative	· · · · · · · · · · · · · · · · · · ·	
429	Interior	BREAK ROOM	A	Window Frame	Wood	White	Intact	0.70	Negative	1	
430	Interior	BREAK ROOM	A	Window Sill	Wood	White	Intact	0.08	Negative		
431	Interior	BREAK ROOM		Ceiling	Drywall	White	Intact	0.01	Negative		·
432	Interior	HEALTH OFFICE	A	Wall	Drywall	Tan	Intact	0.07	Negative		
433	Interior	HEALTH OFFICE	Β.	Wall	Drywall	Tan	Intact	-0.09	Negative	1	· · · · · · · · · · · · · · · · · · ·
434	Interior	HEALTH OFFICE	С	Wall	Drywall	Tan	Intact	-0.22	Negative		
435	Interior	HEALTH OFFICE	D	Wall	Drywall	Tan	Intact	-0.02	Negative	an denote a ser i se a constante a ser a constante e constante e constante a ser a ser a ser a ser a ser a ser 1	
436	Interior	HEALTH OFFICE	A	Door	Wood	Brown	Intact	-0.10	Negative		
437	Interior	HEALTH OFFICE	A	Door Frame	Wood	Brown	Intact	0.15	Negative		
438	Interior	HEALTH OFFICE		Ceiling	Drywall	White	Intact	0.03	Negative		
439	Interior	INFIRMARY 1	Α	Wall	Drywall	Tan	Intact	0.03	Negative	Ny INSEE dia mampikambana mampikambana amin'ny fisiana amin'ny fisiana amin'ny fisiana amin'ny fisiana amin'ny	
440	Interior	INFIRMARY 1	В	Wall	Drywall	Tan	Intact	0.07	Negative	· · · · · · · · · · · · · · · · · · ·	
441	Interior	INFIRMARY 1	С	Wall	Drywall	Tan	Intact	0.36	Negative		
442	Interior	INFIRMARY 1	D	Wall	Drywall	Tan	Intact	0.04	Negative		
443	Interior	INFIRMARY 1	В	Door	Wood	White	Intact	0.06	Negative	· · · · ·	
444	Interior	INFIRMARY 1	В	Door Frame	Wood	White	Intact	0.03	Negative	· · · · · · · · · · · · · · · · · · ·	
445	Interior	INFIRMARY 1		Ceiling	Drywall	White	Intact	0.08	Negative	· · · · · · · · · · · · · · · · · · ·	
446	Interior	RESTROOM	A	Wall	Drywall	White	Intact	0.07	Negative		
447	Interior	' RESTROOM	В	Wall	Drywall	White	Intact	0.31	Negative	i.	<u>}</u>
448	Interior	RESTROOM	С	Wall	Drywall	White	Intact	0.14	Negative		1
449	Interior	RESTROOM	D	Wall	Drywall	White	Intact	0.05	Negative		
450	Interior	RESTROOM	A	Door	Wood	White	Intact	0.19	Negative		i
451	Interior	RESTROOM	A	Door Frame	Wood	White	Intact	0.26	Negative		
452	Interior	RESTROOM		Ceiling	Drywall	White	Intact	0.02	Negative		
453	Interior	RESTROOM		Tile	Ceramic Tile	Beige	Intact	11.99	Positive	150 SF '	Not a paint
454	Interior	RESTROOM		Floor	Ceramic Tile	Yellow	Intact	0.26	Negative		inor a paini
455	Interior	INFIRMARY 2	A	Wall	Drywall	Pink	Intact	0.20	Negative		
456	Interior	INFIRMARY 2	В	Wall	Drywall	Pink	Intact	0.37	Negative		
457	Interior	INFIRMARY 2	С	Wall	Drywall	Pink	Intact	0.14	Negative		
458	Interior	INFIRMARY 2	D	Wall	Drywall	Pink	Intact	0.05	Negative		
459	Interior	INFIRMARY 2	A	Door	Wood	White	Intact	-0.20	Negative		
460	Interior	INFIRMARY 2	A	Door Frame	Wood	White	Intact	-0.20	Negative		
461	Interior	INFIRMARY 2		Ceilina	Drywall	White	Intact	0.08	Negative		
462	Interior	INFIRMARY 2	В	Upper-Cabinet	Wood	Brown	Intact	0.03	Negative		· · · · · · · · · · · · · · · · · · ·
463	Interior	INFIRMARY 2	B	Lower-Cabinet	Wood	Brown	Intact	0.04			· · · · · · · · · · · · · · · · · · ·
464	Interior	WOMAN'S RESTROOM	: A	Wall	Drywall	Yellow	Intact	0.03	Negative Negative		

.

			DETA	ILED XRI	FTESTI	NGR	ESUL	FS			
		•••••									
				3900 Stansbury Av	enue, Sherman	Oaks, CA	91423				
								Lead		Quantities	
	i.	Room	Side					(mg/		For Entire	
mpie	Area	Equivalent	Tested	Component	Substrate	Cales	C		<b>e</b>		-
165	Interior	WOMAN'S RESTROOM	B	Wall		an a	Candition		Results	Area	Commei
166	Interior	WOMAN'S RESTROOM	<u> </u>	Wall	Drywall	Yellow	Intact	0.07	Negative		
167	Interior	WOMAN'S RESTROOM	D	Wall	Drywall	Yellow	Intact	0.14	Negative		
168	Interior	WOMAN'S RESTROOM	A	Baseboard	Drywall Ceramic Tile	Yellow Tan	Intact	0.09	Negative		
169	Interior	WOMAN'S RESTROOM	C C	Door	Wood	White	Intact	13.37	Positive	50 LF	Not a pair
470	Interior	WOMAN'S RESTROOM	C	Door Frame	Wood	White	Intact Intact	0.06	Negative		·
471	Interior	WOMAN'S RESTROOM		Ceiling	Drywall	Yellow	Intact	0.11	Negative		
472	Interior	WOMAN'S RESTROOM	) waa	Stall	Metal	White	Intact	0.07	Negative Negative		
473	Interior	JANITOR CLOSET	A	Wall	Plaster	Green	Intact	0.31	Negative		
174	Interior	JANITOR CLOSET	В	Wall	Plaster	Green	Intact	0.13	Negative		
175	Interior	JANITOR CLOSET	C	Wall	Plaster	Green	Intact	0.20	Negative	· · · · · · · · · · · · · · · · · · ·	
476	Interior	JANITOR CLOSET	D	Wall	Plaster	Green	Intact	0.07	Negative	·····	
477	Interior	JANITOR CLOSET	В	Door	Wood	Brown	Intact	0.06	Negative		
178	Interior	JANITOR CLOSET	В	Door Frame	Wood	Brown	Intact	0.03	Negative		
479	Interior	JANITOR CLOSET		Ceiling	Plaster	Green	Intact	0.02	Negative		
480	Interior	MEN'S RESTROOM	Α	Wall	Plaster	White	Intact	0.06	Negative		
481	Interior	MEN'S RESTROOM	В	Wall	Plaster	White	Intact	0.03	Negative		
482	Interior	MEN'S RESTROOM	С	Wall	Plaster	White	Intact	0.14	Negative	· · · · · · · · · · · · · · · · · · ·	
483 484	Interior	MEN'S RESTROOM	D	Wall	Plaster	White	Intact	0.26	Negative		
485	Interior	MEN'S RESTROOM	D	Door	Wood	Brown	Intact	0.30	Negative		
486	Interior Interior	MEN'S RESTROOM	D	Door Frame	Wood	Brown	Intact	0.06	Negative		
487	Interior	MEN'S RESTROOM		Ceiling	Drywall	White	Intact	-0.38	Negative		;
488	Interior	MEN'S RESTROOM		Tile	Ceramic Tile	Brown	Intact	13.50	Positive	70 SF	Not a pair
489	Interior	MEN'S RESTROOM		Stall	Metal	White	Intact	0.02	Negative		
490		ADMINISTRATIVE LOBBY	A	Wall	Drywall	Tan	Intact	0.17	Negative		
491	Interior Interior	ADMINISTRATIVE LOBBY	B	Wall	Drywall	Tan	Intact	0.14	Negative		
492	Interior	ADMINISTRATIVE LOBBY	<u> </u>	Wall	Drywall	Tan	Intact	0.00	Negative		
493	Interior	ADMINISTRATIVE LOBBY ADMINISTRATIVE LOBBY	D	Wall	Drywall	Tan	Intact	-0.04	Negative		
494	Interior	ADMINISTRATIVE LOBBY	C C	Door	Metal	Black	Intact	-0.06	Negative		
495	Interior	ADMINISTRATIVE LOBBY		Door Frame	Metal	Black	Intact	-0.13	Negative		
496	Interior	ADMINISTRATIVE LOBBY	<u>A</u>	Window Frame	Metal	Black	Intact	-0.01	Negative		
497	Interior	ADMINISTRATIVE LOBBY	A	Window Sill	Metal	Black	Intact	-0.03	Negative		
498	Interior	ADMINISTRATIVE LOBBY		Ceiling	Drywall	White	Intact	-0.36	Negative		:
499	Interior	ADMINISTRATIVE LOBBY		Rail Stairway Door	Wood	Brown	Intact	-0.30	Negative		
500	Interior	DEVELOPMENT	A	Wall	Metal	Black	Intact	-0.10	Negative		:
501	Interior	DEVELOPMENT	B	Wall	Drywall Drywall	White	Intact	0.20	Negative		
502	Interior	DEVELOPMENT	C	Wall	Drywall	White White	Intact	0.04	Negative		
503	Interior	DEVELOPMENT	D	Wall	Drywall	White	Intact	0.15	Negative		
504	Interior	DEVELOPMENT	A	Door Frame	Metal	White	Intact	0.38	Negative		
505	Interior	DEVELOPMENT		Ceiling	Drywall	White	Intact	0.04	Negative		
506	Interior	ADMISSIONS OFFICE	A	Wall	Drywall	Tan	Intact	0.00	Negative		
507	Interior	ADMISSIONS OFFICE	B	Wall	Drywall	Tan	Intact Intact	-0.33	Negative Negative		

			DETA		- TESTI		ESHI -			
				3900 Stansbury A	enue, Shermar	i Oaks, CA	91423			
								Lead	0	uantities
	1	Room	Side					(mg/	E E	or Entire
nncle	Area	Equivalent	Tested	Component	Substrate	Color	Condition		Results	
508	Interior	ADMISSIONS OFFICE	С	Wall	Drywall	Tan	Intact		•	Area Commer
509	Interior	ADMISSIONS OFFICE	D	Wall	Drywall	Tan	Intact	0.11	Negative	
510	Interior	ADMISSIONS OFFICE	С	Door	Wood	Brown	Intact	0.22	Negative	
511	Interior	ADMISSIONS OFFICE	С	Door Frame	Metal	White	Intact	0.03	Negative Negative	
512	Interior	ADMISSIONS OFFICE	Α	Window Frame	Wood	White	Intact	0.03	Negative	
513	Interior	ADMISSIONS OFFICE	A	Window Sill	Wood	White	Intact	0.05	Negative	i
514	Interior	ADMISSIONS OFFICE		Ceiling	Drywall	White	Intact	-0.10	Negative	j.
515	Interior	ADMISSIONS/DEVELOPMENT	A	Wall	Drywall	White	Intact	0.06	Negative	
516	Interior	ADMISSIONS/DEVELOPMENT	В	Wall	Drywall	White	Intact	0.03	Negative	
517	Interior	ADMISSIONS/DEVELOPMENT	С	Wall	Drywall	White	Intact	-0.41	Negative	
518	Interior	ADMISSIONS/DEVELOPMENT	D	Wall	Drywall	White	Intact	-0.37	Negative	
519	Interior	ADMISSIONS/DEVELOPMENT	A	Door	Wood	Brown	Intact	-0.18	Negative	
520 521	Interior	ADMISSIONS/DEVELOPMENT	A	Door Frame	Metal	White	Intact	-0.20	Negative	
	Interior	ADMISSIONS/DEVELOPMENT	С	Window Frame	Wood	White	Intact	-0.35	Negative	
522	Interior	ADMISSIONS/DEVELOPMENT	C	Window Sill	Wood	White	Intact	-0.26	Negative	
523	Interior	ADMISSIONS/DEVELOPMENT		Ceiling	Drywall	White	Intact	0.08	Negative	
524	Interior	ASSISTANT HEAD OF SCHOOL	A	Wall	Drywall	Tan	Intact	0.09	Negative	
525	Interior	ASSISTANT HEAD OF SCHOOL	В	Wall	Drywall	Tan	Intact	0.10	Negative	
526	Interior	ASSISTANT HEAD OF SCHOOL	i C	Wall	Drywall	Tan	Intact	0.04	Negative	
527	Interior	ASSISTANT HEAD OF SCHOOL	D	Wall	Drywall	Tan	Intact	-0.21	Negative	
<u>528</u> 529	Interior	ASSISTANT HEAD OF SCHOOL	A	Window Frame	Wood	White	Intact	0.03	Negative	
	Interior	ASSISTANT HEAD OF SCHOOL	Α	Window Sill	Wood	White	Intact	0.27	Negative	· · · · · · · · · · · · · · · · · · ·
530 531	Interior	HEAD OF SCHOOL	A	Wall	Drywall	Tan	Intact	0.20	Negative	
532	Interior	HEAD OF SCHOOL	В	Wall	Drywall	Tan	Intact	0.03	Negative	
532 533	Interior	HEAD OF SCHOOL	С	Wall	Drywall	Tan	Intact	0.14	Negative	·
534	Interior	HEAD OF SCHOOL	D	Wall	Drywall	Tan	Intact	0.05	Negative	
535 535	Interior	HEAD OF SCHOOL	D	Door	Wood	Brown	Intact	0.06	Negative	
535 536	Interior	HEAD OF SCHOOL	D	Door Frame	Metal	White	Intact	0.01	Negative	
535 537	Interior	HEAD OF SCHOOL	В	Window Frame	Wood	White	Intact	0.08	Negative	
538	Interior Interior	HEAD OF SCHOOL	В	Window Sill	Wood	White	Intact	0.01	Negative	· · · · · · · · · · · · · · · · · · ·
539		HEAD OF SCHOOL		Ceiling	Drywall	White	Intact	0.07	Negative	-
539 540	Interior	ASSISTANT HEAD OF SCHOOL	<u>A</u>	Wall	Drywall	Tan	Intact	-0.16	Negative	
540 541	Interior Interior	ASSISTANT HEAD OF SCHOOL	В	Wall	Drywall	Tan	Intact	-0.64	Negative	
541 542	Interior	ASSISTANT HEAD OF SCHOOL	C	Wall	Drywall	Tan	Intact	-0.37	Negative	· · · · · · · · · · · · · · · · · · ·
543	Interior	ASSISTANT HEAD OF SCHOOL ASSISTANT HEAD OF SCHOOL	D	Wall	Drywall	Tan	Intact	-0.20	Negative	
544	Interior	ASSISTANT HEAD OF SCHOOL ASSISTANT HEAD OF SCHOOL	D	Door	Wood	Brown	Intact	0.13	Negative	-
545	Interior		D	Door Frame	Metal	White	Intact	0.08	Negative	· · · · · · · · · · · · · · · · · · ·
546	Interior	ASSISTANT HEAD OF SCHOOL	C	Window Frame	Wood	White	Intact	-0.32	Negative	
547	Interior	ASSISTANT HEAD OF SCHOOL	С	Window Sill	Wood	White	Intact	-0.29	Negative	1
548		ASSISTANT HEAD OF SCHOOL		Ceiling	Drywall	White	Intact	0.08	Negative	
	Interior	SERVER ROOM	Α	Wall	Concrete	Pink	Intact	0.30	Negative	
549	Interior	SERVER ROOM	В	Wall	Concrete	Pink	Intact	0.26	Negative	
550	Interior	SERVER ROOM	С	Wall	Drywall	Pink	Intact	0.04	Negative	

			DETA		TESTI	NG R	ESULT	TS .			
				3900 Stansbury Av							
				, , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , , . , , . , , , , , , , , , , , , , . , , , . , , . , . , , . , , . , , . , . , , , , . , , , , , , ,		ound, orr	01-12-0	Lead		Quantities	
		Room	Side					(mg)		For Entire	
Sample	Area	Equivalent	Tested	Component	Substrate	Color	Condition	cm ²	Results	Area	Commente
551	Interior	SERVER ROOM	D	Wall	Drywall	Pink	Intact	0.15		Phi Co	Comments
552	Interior	SERVER ROOM	D	Door	Wood	White	Intact	0.15	Negative Negative		
553	Interior	SERVER ROOM	D	Door Frame	Wood	White	Intact	0.01	Negative		- 
554	Interior	SERVER ROOM		Ceiling	Drywall	White	Intact	0.20	Negative		
555	Interior	ROOM 147	A	Wall	Drywall	Pink	Intact	0.00	Negative		
556	Interior	ROOM 147	B	Wall	Drywall	Pink	Intact	0.27	Negative		
557	Interior	ROOM 147	C	Wall	Drywall	Pink	Intact	0.38	Negative		
558	Interior	ROOM 147	D	Wall	Drywall	Pink	Intact	0.19	Negative		
559	Interior	ROOM 147	C	Door	Wood	White	Intact	0.22	Negative		
560	Interior	ROOM 147	С	Door Frame	Wood	White	Intact	0.06	Negative		
561	Interior	ROOM 147	- 1	Ceiling	Drywall	White	Intact	0.09	Negative		
<u>562</u> 563	Interior	ROOM 141	A	Wall	Drywall	White	Intact	0.26	Negative		
	Interior	ROOM 141	В	Wall	Drywall	White	Intact	0.08	Negative		·
<u>564</u> 565	Interior	ROOM 141	С	Wall	Drywall	White	Intact	0.09	Negative	and the second se	
566	Interior	ROOM 141	D	Wall	Drywall	White	Intact	0.14	Negative	-	
567	Interior	ROOM 141	D	Door	Wood	White	Intact	0.00	Negative		
568	Interior	ROOM 141	D	Door Frame	Metal	White	Intact	0.01	Negative	· · · · · · · · · · · · · · · · · · ·	
569	Interior	ROOM 141		Ceiling	Drywall	White	Intact	0.30	Negative		
570	Interior Interior	ROOM 142	<u>A</u>	Wall	Drywall	White	Intact	-0.20	Negative		
570		ROOM 142	В	Wall	Drywall	White	Intact	-0.37	Negative		
572	Interior	ROOM 142	<u> </u>	Wall	Drywall	White	Intact	0.08	Negative		
572	Interior Interior	ROOM 142	D	Wall	Drywall	White	Intact	0.19	Negative		-
573	Interior	ROOM 142	С	Door	Wood	White	Intact	0.15	Negative		
575	Interior	ROOM 142	C	Door Frame	Metal	White	Intact	0.09	Negative		
576	Interior	ROOM 142	<u>A</u>	Window Frame	Metal	White	Intact	0.06	Negative		
577	Interior	ROOM 142 ROOM 143		Ceiling	Drywall	White	Intact	0.00	Negative		
578	Interior		<u>A</u>	Wall	Drywall	White	Intact	0.06	Negative		
579	Interior	ROOM 143 ROOM 143	B	Wall	Drywall	White	Intact	0.08	Negative		4 -
580	Interior	ROOM 143	<u> </u>	Wall	Drywall	White	Intact	0.31	Negative		
581	Interior	ROOM 143	D	Wall	Drywall	White	Intact	0.24	Negative		
582	Interior	ROOM 143		Door	Wood	White	Intact	0.22	Negative		
583	Interior	ROOM 143	A	Door Frame	Metal	White	Intact	0.06	Negative		
584	Interior		 P3	Ceiling	Drywall	White	Intact	0.08	Negative		
585		LOWER LEVEL MECHANICAL RM.	B	Wall	Plaster	Green	Fair	0.06	Negative		
586	Interior	LOWER LEVEL MECHANICAL RM.	C D	Wall	Plaster	Green	Fair	0.08	Negative		
587	Interior	LOWER LEVEL MECHANICAL RM.	C	Wall	Plaster	Green	Fair	0.09	Negative		
588		LOWER LEVEL MECHANICAL RM.	<u> </u>	Door	Wood	Tan	Fair	0.02	Negative		
589	Interior	LOWER LEVEL MECHANICAL RM.	<u>C</u>	Door Frame	Wood	Tan	Fair	0.22	Negative		
590	Interior	LOWER LEVEL MECHANICAL RM.	B	Closet Wall	Drywall	White	Intact	0.07	Negative	· · · · · · · · · · · · · · · · · · ·	
591	Interior	LOWER LEVEL MECHANICAL RM.		Closet Door	Wood	Green	Fair	0.13	Negative	1	
592	Interior	ROOM 144	 A	Valve Closet	Metal	Green	Intact	0.14	Negative	: ; ;	
593	Interior	ROOM 144 ROOM 144	<u> </u>	Wall	Drywall	White	Intact	0.06	Negative	-	
L	31100101	INCOW 144	D	Wall	Drywall	White	Intact	0.12	Negative	, 	

**1** 

,

			DETA		ПЕСТІ			TO		nan an	an an
						<u>Ne N</u>	EOUL				
				2000 Chanabury Au	0	<u>.</u>					
				3900 Stansbury Ave	enue, Sherman	Oaks, CA	91423				
								Lead		Quantities	
		Room	Side					(mg/		For Entire	
Sample	a Area	Equivalent	Tested	Component	Substrate	Color	Condition		Descrite		0
594	Interior	ROOM 144	С	Wall	Drywall	White	Intact		Results	Area	Comments
595	Interior	ROOM 144	D	Wall	Wood	Brown	Intact	0.31	Negative		
596	Interior	ROOM 144	A	Door	Wood	White	Fair	0.15	Negative Negative		
597	Interior	ROOM 144	A	Door Frame	Metal	White	Fair	0.25			
598	Interior	ROOM 144	С	Window Frame	Metal	Black	Intact	0.04	Negative Negative		
599	Interior	ROOM 144	С	Window Sill	Metal	Black	Intact	0.04	Negative		
600	Interior	ROOM 144		Ceiling	Drywall	White	Intact	0.08	Negative		<u>.</u>
601	Interior	CUSTODIAN	A	Wall	Plaster	Green	Fair	0.14	Negative		1
602	Interior	CUSTODIAN	8	Wall	Plaster	Green	Fair	0.22	Negative		:
603 604	Interior	CUSTODIAN	С	Wall	Plaster	Green	Fair	0.13	Negative	· · · · · · · · · · · · · · · · · · ·	······································
605	Interior	CUSTODIAN	D	Wall	Plaster	Green	Fair	0.20	Negative		
605	Interior Interior	CUSTODIAN	D	Door	Wood	White	Intact	0.09	Negative		÷
607	A	CUSTODIAN	D	Door Frame	Metal	White	Intact	0.11	Negative		
608	Interior Interior	CUSTODIAN		Ceiling	Plaster	Green	Intact	0.00	Negative		
609	Interior	RESTROOM	<u>A</u>	Wall	Drywali	White	Intact	0.04	Negative		
610	Interior	RESTROOM	B	Wall	Drywall	White	Intact	0.05	Negative		
611	Interior	RESTROOM	C	Wall	Drywall	White	Intact	0.12	Negative		
612	Interior	RESTROOM	D	Wall	Drywall	White	Intact	0.08	Negative		1
613	Interior	RESTROOM	D D	Door	Wood	White	Intact	0.13	Negative		}
614	Interior	RESTROOM		Door Frame	Metal	White	Intact	0.08	Negative	······································	
615	Interior	RESTROOM		Ceiling	Drywall	White	Intact	0.15	Negative		
616	Interior	RESTROOM		Tile Floor	Ceramic Tile	White	Intact	0.09	Negative		
617	Interior	RESTROOM	A	Wall	Ceramic Tile	White	Intact	0.13	Negative		
618	Interior	RESTROOM	B	Wall	Drywall	White	Intact	0.13	Negative		
619	Interior	RESTROOM	C C	Wall	Drywall	White	Intact	0.20	Negative		
620	Interior	RESTROOM	D	Wall	Drywall Drywall	White	Intact	0.09	Negative		1
621	Interior	RESTROOM	C	Door	Wood	White White	Intact	0.11	Negative		
622	Interior	RESTROOM	C C	Door Frame	Metal	White	Intact Intact	0.32	Negative		÷
623	Interior	RESTROOM		Ceiling	Drywall	White	Intact	0.21	Negative		
624	Interior	RESTROOM		Tile	Ceramic Tile	White	Intact	0.20	Negative		
625	Interior	RESTROOM	4440	Floor	Ceramic Tile	White	Intact	0.21	Negative		
626	Interior	HALL	A	Wall	Drywall	White	Intact	0.28	Negative		
627	Interior	HALL	В	Wall	Drywall	White	Intact	0.08	Negative		
628	Interior	HALL	С	Wall	Drywall	White	Intact	0.09	Negative		
629	Interior	HALL	D	Wall	Drywall	White	Intact	0.33	Negative Negative		:
630	Interior	HALL	A	Door	Wood	White	Intact	0.28	Negative		
631	Interior	HALL	A	Door Frame	Wood	White	Intact	0.03	Negative		
632	Interior	HALL		Ceiling	Drywall	White	Intact	0.02	Negative		
633	Interior	HALL	В	Closet Door	Wood	White	Intact	0.02	Negative		
634	Interior	ROOM 145	A	Wall	Drywall	White	Intact	0.04	Negative		-
635	Interior	ROOM 145	В	Wall	Wood	Tan	Intact	0.00	Negative		
636	Interior	ROOM 145	C	Wall	Drywall	White	Intact	-0.41	Negative		

**\$77** 

			DETA	<b>ALED XRF</b>	TESTI	NG R	ESUL	TS			
				3900 Stansbury Av							
					onde, onernan	Oaks, OA :	J1420			_	
		Room	Side					Lead		Quantities	
ammic	Area			_				(mg/		For Entire	
637		Equivalent	Tested	Component	Substrate	Color	Condition	1 Cm ² )	Results	Area	Commen
638	Interior Interior	ROOM 145	D	Wall	Drywall	White	Intact	-0.31	Negative	mica	Commen
639	Interior	ROOM 145	Α	Door	Wood	White	Intact	0.06	Negative	·	
640	Interior	ROOM 145	A	Door Frame	Metal	White	Intact	0.00	Negative		
641	Interior	ROOM 145	С	Window Frame	Metal	Black	Intact	-0.09	Negative		
642	Interior	ROOM 145 ROOM 145	С	Window Sill	Metal	Black	Intact	-0.23	Negative	A second size such a local second	
643	Interior			Ceiling	Drywall	White	Intact	-0.34	Negative		
644	Interior	ROOM 146 PUBLICATION ROOM 146 PUBLICATION	<u>A</u>	Wall	Drywall	Tan	Intact	0.07	Negative		
645	Interior	ROOM 146 PUBLICATION	B	Wall	Drywall	Tan	Intact	0.34	Negative		
646	Interior	ROOM 146 PUBLICATION	C	Wall	Drywall	Tan	Intact	0.26	Negative		
647	Interior	ROOM 146 PUBLICATION	D	Wall	Drywall	Tan	Intact	0.04	Negative	······································	
648	Interior	ROOM 146 PUBLICATION	- B	Door	Wood	White	Intact	0.25	Negative		
649	Interior	ROOM 146 PUBLICATION		Door Frame	Metal	White	Intact	0.39	Negative		
650	Interior	ROOM 149 COMPUTER LAB	 A	Ceiling	Drywall	White	Intact	-0.32	Negative		
651	Interior	ROOM 149 COMPUTER LAB	B	Wall	Drywali	Tan	Intact	0.06	Negative		
652	Interior	ROOM 149 COMPUTER LAB	C	Wall	Drywall	Tan	Intact	0.03	Negative		
653	Interior	ROOM 149 COMPUTER LAB	D	Wali	Drywall	Tan	Intact	0.29	Negative		
654	Interior	ROOM 149 COMPUTER LAB	B	Wall	Drywall	Tan	Intact	0.14	Negative		
655	Interior	ROOM 149 COMPUTER LAB	B	Door	Wood	White	Intact	0.11	Negative		
656	Interior	ROOM 149 COMPUTER LAB		Door Frame	Metal	White	Intact	, 0.28	Negative		
857	Interior	COPY ROOM	 A	Ceiling	Drywall	White	Intact	-0.30	Negative		
658	Interior	COPY ROOM	<u>A</u>	Wall	Drywall	White	Intact	0.30	Negative		
659	Interior	COPY ROOM	B	Wall	Drywall	White	Intact	0.16	Negative		
660	Interior	COPY ROOM	<u> </u>	Wall	Drywall	White	Intact	0.04	Negative		
661	Interior	COPY ROOM	D	Wali	Drywall	White	Intact	0.09	Negative		
662	Interior	COPY ROOM	C	Door	Wood	White	Intact	0.02	Negative		
663	Interior	COPY ROOM	С	Door Frame	Metal	White	Intact	0.03	Negative	ł	······
664	Interior	COPY ROOM	A	Ceiling	Drywall	White	Intact	0.08	Negative		
665	Interior	COPY ROOM		Closet Wall	Concrete	Green	Intact	-0.22	Negative		
666	Interior	COPY ROOM	B	Closet Door	Metal	Green	Intact	-0.12	Negative		
667	Interior	DIRECTOR OF TECHNOLOGY	B	Elevator Door	Metal	White	Intact	0.46	Negative		
668	Interior	DIRECTOR OF TECHNOLOGY	<u>A</u>	Wall	Drywall	Tan	Intact	0.16	Negative		
669	Interior	DIRECTOR OF TECHNOLOGY	B	Wall	Drywall	Tan	Intact	0.09	Negative		
670	Interior	DIRECTOR OF TECHNOLOGY	D	Wall	Drywall	Tan	Intact	0.01	Negative	11 ha	
671	Interior	DIRECTOR OF TECHNOLOGY	D B	Wall	Drywall	Tan	Intact	0.26	Negative	······································	
672	Interior	DIRECTOR OF TECHNOLOGY	<u> </u>	Door	Wood	White	Intact	-0.45	Negative	······································	
673	Interior	DIRECTOR OF TECHNOLOGY		Door Frame	Metal	Tan	Intact	0.11	Negative	······································	
674	Interior	SUPPLY ROOM	 A	Ceiling	Drywall	White	Intact	0.14	Negative		
675	Interior	SUPPLY ROOM	<u>A</u> B	Wall	Concrete	Green	Intact	0.15	Negative	· · · · · · · · · · · · · · · · · · ·	
676	Interior	SUPPLY ROOM	states and	Wall	Drywall	Green	Intact	0.26	Negative		
677	Interior	SUPPLY ROOM	<u> </u>	Wall	Drywall	Green	Intact	0.08	Negative		
678	Interior	SUPPLY ROOM	<u>D</u>	Wall	Drywall	Green	Intact	0.13	Negative		
679	Interior		D	Door	Wood	White	Intact	0.00	Negative		
~	NICTION	SUPPLY ROOM	D	Door Frame	Wood	White	Intact	0.03	Negative	······	

.

	90 N		DETA	ILED XRF	TESTI	NG F	RESULT	18			
				3900 Stansbury Ave	enue, Sherman	Oaks, CA	91423				
		Room	Side					Lead		Quantities	
Sample	Area	Equivalent	Tested	Component	Substrate	Color	Condition	(mg/		For Entire	
680	Interior	SUPPLY ROOM	10 North 13 and 14	·····	·	Color		, de la casa de la cas	Results	Area	Commen
681	Interior	TECHNOLOGY ROOM	A	Ceiling Wall	Drywall	Green	Intact	0.01	Negative		
682	Interior	TECHNOLOGY ROOM	B	Wall	Drywall	Tan	Intact	0.20	Negative		
683	Interior	TECHNOLOGY ROOM	C	Wall	Drywall	Tan	Intact	0.16	Negative		
684	Interior	TECHNOLOGY ROOM	D		Drywall	Tan	Intact	0.04	Negative		
685	Interior	TECHNOLOGY ROOM	D	Wall	Drywall	Tan	Intact	0.30	Negative		
686	Interior	TECHNOLOGY ROOM	D	Door Door Frame	Wood	White	Intact	0.07	Negative		
687	Interior	TECHNOLOGY ROOM	U		Wood	White	Intact	0.31	Negative		
688	Interior	LOWER LEVEL HALL	A	Ceiling	Drywall	White	Intact	0.08	Negative		
689	Interior	LOWER LEVEL HALL	B	Wall	Drywall	White	Intact	0.01	Negative		
690	Interior	LOWER LEVEL HALL	C	Wall	Drywall	White	Intact	0.16	Negative		
691	Interior	LOWER LEVEL HALL	D	Wall	Drywall	White	Intact	-0.21	Negative		
692	Interior	LOWER LEVEL HALL	C	Door	Drywall	White	Intact	-0.03	Negative		
693	Interior	LOWER LEVEL HALL	- C	Door Door Frame	Wood	White	Intact	0.16	Negative		3
694	Interior	LOWER LEVEL HALL		the second s	Metal	White	Intact	0.03	Negative		
	to the local data and the local data and the	Contraction of the Contraction of the second state of the second s	1	Ceiling	Drywall	White	Intact	0.08	Negative		

#### <u>ALLSTATE SERVICES ENVIRONMENTAL</u> <u>XRF CALIBRATION FORM</u>

Address/Unit: _The Buckley School, 3900 Stansbury Avenue, Sherman Oaks, CA 91423_

Device: EDAX/MAP-4 M41316

Date: _____ April 26, 2006____

Inspector: James Hantgin & George Munoz

Calibration Check Tolerance Used: <u>0.6 mg/cm² - 1.2 mg/cm² (Inclusive)</u> Use Level III (1.02 mg/cm²) NIST SRM Paint film

**First Calibration Check** 

2nd Reading 3rd Reading 1st Average

1.03

_____

Second Calibration Check

<u>Time: 7:00 pm</u>

1.04

Time: 3:00 pm

1 st Reading	2 nd Reading	3 rd Reading	2 nd Average
1.01	1.05	0.99	1.02

1.03

#### **Third Calibration Check (If Needed)**

1st Reading

1.07

<u>Time: 8:30 pm</u>

1 st Reading	2 nd Reading	3 rd Reading	3 rd Average
1.05	1.01	1.03	1.03

• Use the Test Mode Reading

-

• Tolerance Values for EDAX/MAP-4: 0.6 mg/cm² to 1.2 mg/cm² (Inclusive)


-

~

# APPENDIX C FLOOR PLAN

-


-




-

-

## APPENDIX D INSPECTOR/ASSESSOR CERTIFICATIONS





# APPENDIX E DHS FORM 8552 - LEAD HAZARD EVALUATION REPORT

~

-

### LEAD HAZARD EVALUATION REPORT

Section 1: Date of Lead Hazard Evaluation	······				
Section 2:				<b></b>	
A. Type of Lead Hazard Evaluation (Check One Box	and Mark the Necessar	y Option):			
Lead Inspection	Risk	Assessment		Clearar	nce Inspection
No lead-based paint detected -		No lead hazards detected			No lead hazards detected
Intact lead-based paint detected		Lead hazards detecte	ed		Lead hazards detected
Deteriorated lead-based paint detected					
Environmental Investigation					
No lead hazards detected					
No lead-based paint detected					
Lead hazards detected					
Lead-based paint detected					
B. Method of Lead Hazard Evaluation (Check All The					
Soil Wipe(s) Paint Chips	✓ XRF (Brand and Ser	ial Number) EDAX/	MAP-4 M413	316	
Section 3: Structure Where Lead Hazard Eval	uation Was Conducte	ed			
Name of Structure (if applicable):		Construction Date (Y		ure:	
Buckley School	· · · · · · · · · · · · · · · · · · ·		1/1/60		
Address [number, street, apartment number (if applicable	)]:	City:		unty:	Zip Code:
3900 Stansbury Avenue	·····	Sherman Oaks	Lo	os Angeles	91423
Type of Structure (Check One Box Only):	ool, Day Care, or Other C	Child-Occupied Facility			
Single Family Dwelling Multi-Unit Buildin	ng 🗌 P	ublic Building	Com	mercial Facility	Other
ection 4: Owner of Structure (if business/agen	cy/school, list contact	person)			
Name of Organization (if any):	First Name:		Last Name:	•	Telephone Number:
Applied Toxicology	Ken		Medici		( )(760) 212-885
Address [number, street, apartment number (if any)]:		City:		State:	Zip Code:
1450 North Sants Fe Suite # C, PMB # 144		Vista		California	92083
Section 5: Individual Conducting Lead Hazard	Evaluation				
Last Name:	First Name:		Telep	hone Number:	
Hantgin	James		(	) (951) 340-171	17
Address [number, street, apartment (if applicable)]		City:		State:	Zip Code:
1826 Pomona Road		Corona		California	92880
DHS Certification Number (Required)	Signature:	$\Pi$	i		Date:
I-6259	Jan	- This	$\overline{\gamma}$		4/27/06
Section 6: Attachments (Submit By Request On	ly)				
· · ·					

B. Each testing method, device, and sampling procedures used;

C. All data collected, including quality control data, laboratory results, including laboratory name, address, and phone number.

First copy and attachments retained by inspector Second copy and attachments retained by owner

#### Third copy must be submitted to DHS (NO Attachments)

This form shall be mailed or faxed to: Childhood Lead Poisoning Prevention Branch Reports 850 Marina Bay Parkway, Bldg. P, Third Floor Phone: (510) 620-5600 Fax: (510) 620-5656

### LEAD HAZARD EVALUATION REPORT

Section 1: Date of Lead Hazard Evaluation 4/	26/06				
Section 2:					
A. Type of Lead Hazard Evaluation (Check One Box and	nd Mark the Necessar	y Option):			
Lead Inspection	🗌 Risk	Assessment		Clearan	ce Inspection
No lead-based paint detected	Ē	No lead hazards dete	cted	ז 🗌	No lead hazards detected
Intact lead-based paint detected	C	Lead hazards detecte	d		lead hazards detected
Deteriorated lead-based paint detected					
Environmental Investigation					
No lead hazards detected					
No lead-based paint detected					
Lead hazards detected					
Lead-based paint detected					
1					
B. Method of Lead Hazard Evaluation (Check All That				- 10	
Soil Wipe(s) Paint Chips	XRF (Brand and Ser	ial Number) EDAX/M	/AP-4 M41	316	
Section 3: Structure Where Lead Hazard Evaluation	ation Was Conducte	d			
Name of Structure (if applicable):		Construction Date (Ye		ture:	
Buckley School			1/1/60		
Address [number, street, apartment number (if applicable)]:		City:		ounty:	Zip Code:
3900 Stansbury Avenue		Sherman Oaks	<u>j L</u>	os Angeles	91423
Type of Structure (Check One Box Only):	ol, Day Care, or Other C	hild-Occupied Facility			
Single Family Dwelling Multi-Unit Building	P	ublic Building	Con	nmercial Facility	Other
ection 4: Owner of Structure (if business/agency	/school, list contact	person)			
Name of Organization (if any):	First Name:		Last Name	:	Telephone Number:
Applied Toxicology	Ken		Medici		( )(760) 212-885
Address [number, street, apartment number (if any)]:		City:		State:	Zip Code:
1450 North Sants Fe Suite # C, PMB # 144		Vista		California	92083
ection 5: Individual Conducting Lead Hazard E	Evaluation				
Last Name:	First Name:		Tele	phone Number:	
Munoz	George		(	) (951) 340-171	7
Address [number, street, apartment (if applicable)]		City:		State:	Zip Code:
1826 Pomona Road	<b>A</b>	Corona		California	92880
DHS Certification Number (Required)	Signature:	í.			Date:
-11268 🧠	KID	m	$\sim$		4/27/06
ection 6: Attachments (Submit By Request Only	/)				
· · · · · · · · · · · · · · · · · · ·	· · · · · · · · · · · · · ·			<u> </u>	
<ul> <li>A foundation diagram or sketch of the structure indicat</li> <li>B. Each testing method, device, and sampling procedures</li> </ul>	* •	is of each lead hazard of	r presence o	f lead-based paint;	

C. All data collected, including quality control data, laboratory results, including laboratory name, address, and phone number.

First copy and attachments retained by inspector Second copy and attachments retained by owner

#### Third copy must be submitted to DHS (NO Attachments)

This form shall be mailed or faxed to: Childhood Lead Poisoning Prevention Branch Reports 850 Marina Bay Parkway, Bldg. P, Third Floor Phone: (510) 620-5600 Fax: (510) 620-5656

____

# APPENDIX 2.0

CADHS Form 8552

Kenneth Medici

### LEAD HAZARD EVALUATION REPORT

Section 1: Date of Lead Hazard Evaluation 4/	26/06					
Section 2:						
A. Type of Lead Hazard Evaluation (Check One Box an	nd Mark the Necessa	ry Option):				
Lead Inspection	Risl	k Assessment		Clearance	Inspection	
No lead-based paint detected		No lead hazards detected			lead hazards detected	
Intact lead-based paint detected	[	Lead hazards detecte	d	Lead hazards de		
Deteriorated lead-based paint detected						
Environmental Investigation						
No lead hazards detected						
No lead-based paint detected						
Lead hazards detected						
Lead-based paint detected						
B. Method of Lead Hazard Evaluation (Check All That	Apply):					
	XRF (Brand and Se	erial Number)				
Section 3: Structure Where Lead Hazard Evaluation	ation Was Conduc					
Name of Structure (if applicable):		Construction Date (Y	ear) of Structure: 1/1/60			
The Buckley School Address [number, street, apartment number (if applicable)]		City:	County:		Zip Code:	
3900 Stansbury Ave		Sherman Oaks	Los Angele	s	91423	
Type of Structure (Check One Box Only):	Day Care or Other	Child-Occupied Facility		-		
Single Family Dwelling	· · · _	Public Building	Commercial Fa	cility [	Other	
	-	-				
Section 4: Owner of Structure (if business/agency	y/school, list contac First Name	•	Last Name:		77-1	
Name of Organization (if any): The Buckley School	First Name		Last Name:		Telephone Number: ( )(818) 783-1610	
Address [number, street, apartment number (if any)]:		City:	State:		Zip Code:	
3900 Stansbury Avenue		Sherman Oaks	CA		91423	
Section 5: Individual Conducting Lead Hazard I	Evaluation					
Last Name:	First Name:		Telephone Nun	nber:		
Medici	Kenneth		( ) (760)	212-8857		
Address [number, street, apartment (if applicable)]		City:	State:		Zip Code:	
1450 North Santa Fe Avenue #C-144	<b>a</b>	Vista	CA		92083	
DHS Certification Number (Required) 1629	Signature:				Date:	
Section 6: Attachments (Submit By Request Only	y)					

A. A foundation diagram or sketch of the structure indicating the specific locations of each lead hazard or presence of lead-based paint;


B. Each testing method, device, and sampling procedures used;

C. All data collected, including quality control data, laboratory results, including laboratory name, address, and phone number.

## First copy and attachments retained by inspector Second copy and attachments retained by owner

#### Third copy must be submitted to DHS (NO Attachments)

This form shall be mailed or faxed to: Childhood Lead Poisoning Prevention Branch Reports 850 Marina Bay Parkway, Bldg. P, Third Floor Phone: (510) 620-5600 Fax: (510) 620-5656



### ASBESTOS

ABATEMENT

REPORT

Prepared for:

The Buckley School 3900 Stansbury Road Sherman Oaks, CALIFORNIA 91423

Curtis Covington, Director of Physical Plant (818).783-1610 Office (818).461-6712 Fax

Prepared by:

Kenneth Medici Certified Asbestos Consultant California DOSH #92-0007



Site: The Buckley School, Sherman Oaks Campus -Administration Bldg MR Cleaning (Basement) & Lower School Buildings - O&M Clean-up Work -Assembly Room Boiler Room Attic Work -Attic above Kindergarten Rooms

&

Pavilion Stairwell Flooring Abatement (Stairs located at Stage area up to Mech Rm)

Dates:

June 2001Comprehensive Asbestos SurveyDecember 2005Background air testsDecember 2005Asbestos AbatementDecember 2005TEM Air Clearance Testing(Winter Break 2005)

### TABLE OF CONTENTS

SECTION 1.0 (White Tab)	THE BUCKLEY SC PART 1. PART 2.	HOOL RECORDS Comprehensive Asbestos Survey (On File with Facility Department) Proposal/contracts
SECTION 2.0	ASBESTOS CONSU	LTANT RECORDS
(White Tab)	PART 1.	Overall Work Summary
	PART 2.	Comprehensive Survey
	PART 3.	Abatement Plan
	PART 4.	Construction Bidding Job Walk
	PART 5.	Pre-construction Meeting
	PART 6.	Abatement Oversight Records &
		Field Data
	PART 7.	Analytical Laboratory Results &
		Chain of Custody Forms

SECTION 3.0 ASBESTOS ABATEMENT CONTRACTOR RECORDS

- PART 1. Pre-construction Meeting Submittal
  - PART 2. Post Abatement Submittal

(White Tab)

# The Buckley School Records

# **SECTION 1.0**

Comprehensive Asbestos Survey on file with administration office. Not included in this report.

# SECTION 2.0

## ASBESTOS CONSULTANT RECORDS

## ASBESTOS CONSULTANT RECORDS

# SECTION 2.0

**PART** 1.0

## WORK SUMMARY

### SECTION 2.0 - PART 1.0 (page one of one) SUMMARY OF THE ASBESTOS ABATEMENT WORK

**Background:** The Buckley School continued to conduct O&M work within the Attics of the Lower School Building above Kindergarten rooms and Assembly Boiler room. Also, asbestos abatement of the flooring materials at the Pavilion Stairwell (located at the stage area up to the Mech room) was begun. Also, O&M cleaning of the Main Campus Administration Bldg Mechanical room was begun. The Buckley School contacted Applied Toxicology for management of the asbestos abatement project. Ken Medici, CAC #92-0007 was designated as the primary Asbestos Abatement Consultant for The Buckley School. Subsequently, directives were prepared regarding the asbestos AHERA regulations in which only the most stringent abatement procedures be followed and only the most stringent air clearance tests were to be performed prior to release of the asbestos abatement contractor from his cleaning liability. This school policy would maximize construction safety and minimize asbestos fiber release.

Asbestos Survey: Applied Toxicology conducted a comprehensive asbestos survey of the entire school; this survey is on file with the school at the Superintendents office. Additional samples of attic area stucco-related debris were collected August 2004 which found <1% asbestos ("Trace") Asbestos present. Additional samples of floor glue were collected at the stairwell which found no asbestos detected.

Asbestos Abatement Plan: An abatement plan was prepared and issued by Ken Medici of Applied Toxicology for bidding by California Licensed Contractors, Certified in Asbestos Abatement.

Asbestos Abatement Job Walk/Bid Award: A job walk with Fresh Air Environmental Contractors qualified contractors was performed via telephone December 2005 prior to contract ward. The Buckley School collected quoted labor rates from the bidding contractor and selected Fresh Air for the work.

**Pre-construction meeting:** A meeting was conducted on-site with Romeo Hernandez of Fresh Air. Paperwork submittals were pending for review at this pre-construction meeting. A planned asbestos abatement date was set for December 22, 2005 at 9am.

Abatement & Clearance Work: On Thursday, December 22, 2005 (7am) Applied Toxicology met at Buckley and conducted background air tests. Work began at approximately 9:10am. Fresh Air provided workers for this job and their names are found in the Contractor submittal section of this report. Applied Toxicology provided one worker for this job-Kenneth Medici, CAC #92-0007. Fresh Air Set-up the work area at the Stairs with with plastic sheeting barriers (containment area). After set-up the workers began abating floor tile from the base landing and upper landing and stairwell stairs. Friday December 23, 2005 Fresh Air went into the Boiler room attic adjacent to the Assembly Room and set-up plastic to conduct cleaning at the Admin Bldg Basement Mech Room. Air tests were conducted throughout the project. Air tests were collected from within each work area and outside each work area. Review of the air tests found that all work was conducted safely and in compliance with all laws and regulations regarding asbestos. Other asbestos-related work:

1. PLM Bulk suspect asbestos samples were collected within the Pavilion Building at the stairs for glue found under the floor tile . The Analytical laboratory reported no asbestos found. One sample of the Admin Bldg elevator linoleum found no asbestos detected.

## ASBESTOS CONSULTANT RECORDS

### SECTION 2.0

### **PART** 2.0

## **COMPREHENSIVE ASBESTOS SURVEY**

Comprehensive asbestos survey on file with administration office. Not included in this report.

## ASBESTOS CONSULTANT RECORDS

## SECTION 2.0

## **PART** 3.0

## ABATEMENT PLAN

.

### ASBESTOS

#### ABATEMENT

PROJECT DESIGN PLAN

Prepared for:

### THE BUCKLEY SCHOOL 3900 Stansbury Ave Sherman Oaks, CA 91423-4699

### Curtis Covington, Director of Physical Plant (818).783-1610 Office (818).990-4516 Fax

Kenneth Medici Management Planner for The Buckley School California DOSH #92-0007 1450 North Santa Fe #C-144 Vista, CA 92083 (888).999-7908 toll-free Fax (760).414-1183

Site: THE BUCKLEY SCHOOL SHERMAN OAKS, CALIFORNIA Pavilion Stairwell to upper Mech Rm Associated Floor Tile, Mastic, Baseboards Approx 150 sq ft floor tile and associated black mastic floor adhesive &

Lower School Assembly attic cleaning- O&M work

Planned Abatement

Time Frame: December 22, 23, 26, 27, 28, 2005

### BID FORM

JOB SPECIFICATION REQUIREMENTS - Pavilion Stairwell to Mech room Flooring ABATEMENT: Submit this completed bid form and your work contract to Kenneth Medici, Buckley School Management Planner for written approval. The Buckley School Management Planner will then submit approved contract to The Buckley School - Curtis Covington for final approval and final signature.

(ACM's) Removal and Disposal & Attic cleaning:

- Disposal of floor tile/black mastic: Asbestos Hazardous Waste Disposal only. Contractor to assist owner in obtaining applicable Hazardous Waste Generator ID's Keep all in-place cabinets(if applicable) as original- Sand off mastic from wood stairs! Remove stair metal lips and sidewall baseboard and sidewall mastic with sander.
  - Construct full containment with negative air pressure enclosure-4 or more air changes/hr.
  - Use wet methods, notify applicable agencies and pay applicable permit fees
  - If emergency notification is required, Buckley School will issue a letter confirming such
  - Complete all removal work in two shifts or less, request an air clearance from Applied Toxicology. Asbestos abatement may be monitored during asbestos abatement work. Air Clearance will be performed by Applied Toxicology. If air test fails, re-clean the work area. Applied Toxicology will re-test work area.
  - Within 30 days of demobilization submit copies of Supervisor logs, air testing results, copy of waste manifest that was signed on-site at time of transport, copies of worker and supervisor documentation not obtained by The Buckley School on-site.
- 2. Send a final invoice to The Buckley School, attention Curtis Covington c/o Ken Medici, Applied Toxicology after work and paperwork are complete.
- 3. All of the above flooring removal work must be completed in 1-2 work shift time frame so air clearances can be completed during winter break with enough time for Buckley to install new flooring. Complete removal and disposal with two men and a supervisor in two or less shifts.
- 4. Attic cleaning consists of HEPA vac and wet wiping of walking boards, no air clearance tests planned. Set-up a negative pressure enclosure inside the boiler room with decon unit. Complete cleaning using one man and a supervisor in three or less shifts.

Bid Time and Material Rates:

Bid per hour per worker:Fresh Air - \$55/hr WorkerBid per hour per supervisor:Fresh Air - \$65/hr Supervisorabove labor includes all disposal costs, related mgt costs, transportation costs, materials,Labor Overtime Costs, etc.

Project costs: 5 days two men and one supervisor 10hrs/day = \$3250 -Supervisor plus \$5500 workers Total = \$8750.00

Submitted by:	
Signature:	
Print Name - 🚫	DATE

The Buckley School Approval:

Signed by:

Faxed back:

THE BUCKLEY SCHOOL - Abatement of flooring at the Pavilion Stairs to Mech room & O&M Work at Lower School Attic areas near the Boiler Room of the Assembly Room

UP TO 150 sq ft of floor tile/associated black mastic (layered flooring) Up to 45 ft of attic boards to be cleaning with HEPA Vac/wet wipe

### SUMMARY OF THE ASBESTOS ABATEMENT WORK

### PART 1 GENERAL:

- 1.01 RELATED WORK REQUIREMENTS: Related requirements and conditions required by the Contract Documents include, but are not necessarily limited to the following:
  - A. Drawing and general provisions of Contract Documents, including General and Supplementary and Special Conditions, apply to work of this section.
  - B. Asbestos is a generic term applied to a number of mineral silicates which are separable into fibers. There is evidence to support the fact that the inhaling of the fibers can result in various diseases to those exposed. Some of the diseases that have been associated with exposure to airborne asbestos are: asbestosis; mesothelioma; and cancers of the lung, esophagus, stomach, colon, and other organs. The US EPA and the scientific community believe that any level of exposure to asbestos involves some health risks, although the exact degree of the risk is not readily measurable or known. The Contractor acknowledges the danger and the health risk associated with working in and around asbestos and assumes said risk by entering into the Contract. The Contractor shall secure a copy of and familiarize himself with EPA Document No. 560/5-85-024, published June 1985, titled "Guidance for Controlling Asbestos-Containing Materials in Buildings," and applicable State, Federal, and Local, asbestos rules and regulations.
  - C. The Contractor under this Contract has the care, custody, and control of the premises and is solely responsible for all persons entering the work areas to be attired and protected as specified herein. The Contractor has the option to establish OSHA-defined Regulated Areas or to use glovebags and/or mini-enclosures to contain the work areas where asbestos-containing materials may be disturbed or removed. Regardless of the containment methods used, the Contractor is liable for constructing air-tight containments and for compliance with all current applicable regulations and guidelines relevant to this work.
    - 1. The contractor must remove/dispose and clean areas of asbestos identified above, etc. and allow the asbestos consultant/others to test or inspect for asbestos.
    - 2. This work must be completed within the TIME specified.
    - 3. Work hours are pre-determined by the School.
    - 4. Clearance will be by TEM or PCM by the asbestos consultant as applicable.
    - 5. Include stairs, hallways, mastic on wood within the scope of work at the project location; include walking boards and vertical wood members.

- D. The Contractor shall submit evidence of the following: 1) successful completion of at least three comparable asbestos removal projects accomplished by the firm to perform the work specified herein; 2) Asbestos Certification from the State Contractor's License Board; and 3) registration from Cal-OSHA as an Asbestos Abatement Contractor; 4) Applicable Insurance.
- E. Comply with all Applicable codes and regulations.
- F. Pay for and submit all required Notices and permits (Cal-OSHA and AQMD, etc)
- G. Comply with applicable existing site conditions and restrictions on use of the site.
- H. Patents: of negative air machines.
   Contractor shall either be licensed by GPAC, Inc. for use of the patented Reduced Pressure and Filtration System, or indemnify Owner and Owner's Representative against any and all potential liability from patent infringement or use of this system.

### 1.02 **DEFINITIONS**:

A.	Owner:	The Buckley Sch	ool
B.	Owner's Representative:	Curtis Covington	l
		The Buckley Sch	ool
C.	Asbestos Consultant:	Kenneth Medici	1-888-999-7908
	(Management Planner)	CAC #92-0007	Fax-(760).414-1183

- D. Site Surveillance Technician TBD, if applicable
- E. AIHA Accredited Laboratory Analysis Firm: TBD
- F. Work to be performed at this Facility Address:

The Buckley School

3900 Stansbury Ave

### Sherman Oaks, California 91423

Work Area: The location where asbestos abatement work will occur. The "work area" is considered contaminated during the abatement work and must be isolated from the balance of the building, and decontaminated at the completion of the removal of asbestos. The work area must be isolated from the balance of the building by constructing a negatively pressurized containment around the work area. The containment must be constructed in a manner which prevents dust or debris from passing beyond the work area. Should the area beyond the work area containment become contaminated (as determined by a statistically significant increase in airborne fiber levels measured outside the containment barriers) with ACM dust or debris as a consequence of the work, immediately stop all abatement work. The Contractor shall clean any contaminated areas using wet-wiping and HEPA vacuuming techniques. G. ACM: Asbestos-containing material.

### 1.03 SUMMARY OF WORK:

- A. This abatement plan covers the removal of asbestos-containing materials which have been previously identified and which have not been previously identified. It is the sole responsibility of the Asbestos Abatement Contractor to thoroughly investigate periodically along with the Asbestos Consultant newly discovered suspect building materials not accessible or tested in previous surveys. Applicable change order approvals will be authorized upon completion of a written review by the Asbestos Consultant/Project Management. The contractor must adjust their bid to accommodate all interaction with the asbestos consultant and other project management and assumes risk for estimation of this additional time required to allow for owner's rep. or owner interaction.
- B. All bidders shall attend the pre-bid walk-through inspection and measure amounts of material to be removed and thoroughly familiarize themselves with existing conditions that affect the work.
- C. The objective of the project is to "clean" the areas designated of all asbestoscontaining materials and to provide an atmosphere inside the building that is free from airborne fibers within limits specified in these specifications.
- D. Work specified in this section includes furnishing all labor, equipment, services, insurance, materials, etc., in accordance with the requirements of EPA, OSHA, and other regulatory agencies, to complete removal of designated ACMs at the Owner's facility specified herein.

The asbestos consultant will perform air monitoring within the work area, outside the work area as deemed applicable during asbestos abatement work. The asbestos consultant will perform visual inspections and final visual and clearance inspections and air testing independent of the contractor. Allow two days for lab results as a worst case, if applicable. We anticipate 5 hour lab turnarounds as our goal, if possible!

- 1.04 DESCRIPTION OF WORK: Briefly and without force and effect upon the Contract Documents, the work of the contract can be summarized as follows:
  - A. Upon acceptance of asbestos removal plan and with prior authorization from the Asbestos-Consultant, secure and post areas where asbestos removal will take place.
  - B. Setup negative air system prior to start of cleaning (try to establish negative pressure within the proposed abatement area). Clean each individual designated work space using a high-efficiency particulate air (HEPA) vacuum system and wetwiping techniques prior to beginning removal operations.

- C. Prepare work areas for removal of existing ACMs in accordance with applicable laws.
- D. Remove, clean, and properly package all ACM waste on a daily basis for proper disposal. Transport, prior to the end of each work shift, all packaged ACM waste to a fully enclosed (no open top) locked dumpster for overnight storage or other equivalent. All waste ACM must be disposed of as hazardous waste!
- E. After final air clearance for unrestricted occupancy, dispose of all asbestos waste remaining and other items used in the work as applicable.
- F. Conduct all work otherwise in accordance with these requirements, and, prior to submittal for final payment, deduct all costs due the Owner. Do not submit partial payment final requests.
- 1.05 GENERAL AND ADMINISTRATIVE REQUIREMENTS are set forth by Project Management and by this abatement plan:

CODES AND REGULATIONS: Sets forth governmental regulations and industry standards which are included and incorporated herein by reference and made a part of the Specifications. This section also sets forth those notices and permits which are known to the Owner and which either must be applied for and received, or which must be given to governmental agencies before start of work.

1.06 WORK AREA ACM REMOVAL: Requirements are set forth in the following section, listed here according to the sequence of the work:

A. Prepare a working decontamination unit. 3 stage only with hot running water for the Asbestos Consultant to shower with, every hour. Provide towels, waste bags, non-slip floors outside shower and in clean room. Provide a locked containment, use wood barriers as needed. Contractor may be forced to stop work and pay for the owner to install a locked barrier system if contractor fails to set up a locked regulated area.

B. HEPA vacuum and wet wipe as needed.

C. Prepare a regulated area as applicable.

D. Remove and properly package as ACMs. Dispose of ACM's. The Buckley School Policy is to dispose of all waste generated as Hazardous Material Asbestos waste. 1.07 AIR MONITORING SURVEILLANCE: The protocol for the Site Surveillance Technician or asbestos consultant to use for conducting Baseline, Periodic, and Clearance air monitoring of the work area. Does not include Contractor's employee exposure monitoring.

WORK AREA CLEARANCE: The protocol to determine if the work area has been successfully cleaned of contamination, and is "cleared" for re-entry by building occupants. The asbestos consultant will perform his independent work area clearance as applicable and use PCM or TEM air analysis protocols.

- A. The disturbance or dislocation of ACMs may cause the asbestos fibers to be released. Apprise all workers, supervisory personnel, subcontractors and consultants who will be at the job site of the seriousness of the hazard and of proper work procedures which must be followed.
- B. Whereas in the performance of the work, workers, supervisory personnel, subcontractors, or consultants may encounter, disturb, or otherwise function in the immediate vicinity of any identified ACMs, take appropriate continuous measures as necessary to protect human health and the environment from the potential hazard and exposure to airborne asbestos. Such measures shall include the procedures and methods described herein, and compliance with regulations of applicable federal, state and local agencies.

### 1.08 ASBESTOS-CONTAINING MATERIALS/OTHER HAZARDS:

The following asbestos-containing materials are known to be present at the worksite. If any other materials are found which are suspected of containing asbestos, notify the Owner's representative immediately. These materials are not to be disturbed without prior written authorization from the Owner's Representative. Floor Tile, Black Mastic, Drywall, Stucco, stucco overspray, roofing, attic debris, drywall mud, plaster, TSI elbows, TSI, etc.....

- A. Please see comprehensive asbestos survey for the entire school at Buckley office as a background reference.
- B. The Contractor shall be responsible for removing all ACM as identified in this abatement plan and during the "job walk."
- C. See above addendum work sheet and bid sheet.

### 1.09 CONTRACTOR USE OF PREMISES:

- A. General: The Contractor shall limit his use of the premises to the work indicated, so as to allow for Owner occupancy, and use by the public. (Use of the premises is unrestricted if indicated so by the "Job Walk").
- B. Keep existing driveways and entrances serving the premises available to the Owner and his employees, etc., at all times. Do not use these areas for parking or storage of materials.
- C. Lock automotive-type vehicles, such as passenger cars and trucks and other mechanized or motorized construction equipment, when parked and unattended, so as to prevent unauthorized use. Do not leave such vehicles or equipment unattended with motor running or ignition key in place or accessible to unauthorized persons.

### 1.10 CONTRACTOR'S USE OF THE EXISTING BUILDING:

Maintain existing building in a safe and weather-tight condition throughout the construction period. Take all precautions necessary to protect human health and the environment during the construction period. These protective measures shall be provided by the Contractor 24 hours per day and 7 days per week until the work area or portion of the premises exposed by work under this contract has been deemed safe by the Asbestos Consultant.

PART 2	PRODUCTS	(NOT APPLICABLE)
PART 3	EXECUTION	(NOT APPLICABLE)

# ASBESTOS CONSULTANT RECORDS

# SECTION 2.0

## **PART** 7.0

# ANALYTICAL LABORATORY RESULTS

## CHAIN OF CUSTODY FORMS

### Asbestos Consultant Records - Section 2.0 Analytical Laboratory Results Summary - Part 7.0 Page 1 of 5

### Laboratory Analytical Methods

PLM - Bulk Sample Analysis (Polarized Light Microscopy):

The bulk material samples were submitted to an accredited laboratory in California. Bulk material samples were analyzed using dispersion staining techniques in accordance with the 40 CFR, Part 763, Appendix A, Subpart F, AHERA regulations.

PCM - Air Analysis (Phase Contrast Microscopy):

The air samples were analyzed for airborne fibers by a regular light microscope per NIOSH Method 7400 A (as applicable).

**TEM -** Air Analysis (Transmission Electron Microscopy):

The air samples were analyzed for airborne asbestos by a Transmission Electron Microscope per AHERA protocol .

Sample ID #	t Location/description	<b>Result Summary</b>
0	<b>d Air Tests at Pavilion Stairwell:</b> 2, 2005, Thursday at 6:20am:	=======
1222T-01	Work Area - base of stairs	Pass
1222T-02	Work Area -middle of stairs	Pass
1222T-03	Work Area - Top of Stairs	Pass
1222T-04	Work Area - Stage Corridor	Pass
1222T-05	Work Area - Basketball stage area	Pass
1222T-06	Work Area - Door to stairwell at end of lower corridor	Pass
Bulk Suspe	ct Flooring Glue tests at Pavilion Stairwell: 6 total 2, 2005:	tests:

A-01	Stair mastic, brown mixture, top landing	None detected
A-02	Stair mastic, brown mixture, random stair	None Detected
A-03	Stair mastic, random stair, stair mixture	None Detected
A-03L-2	Layer #2 mastic	None Detected
A-04	Stair Mastic, random stair, stair mixture	None Detected
A-05	Stiar Mastic, random mixture,	None Detected

### (Continued) Asbestos Consultant Records - Section 2.0 Analytical Laboratory Results Summary - Part 7.0 Page 2 of 5

### Laboratory Analytical Methods

**PLM -** Bulk Sample Analysis (Polarized Light Microscopy): The bulk material samples were submitted to an accredited laboratory in California. Bulk material samples were analyzed using dispersion staining techniques in accordance with the 40 CFR, Part 763, Appendix A, Subpart F, AHERA regulations.

**PCM** - Air Analysis (Phase Contrast Microscopy):

The air samples were analyzed for airborne fibers by a regular light microscope per NIOSH Method 7400 A (as applicable).

**TEM** - Air Analysis (Transmission Electron Microscopy):

The air samples were analyzed for airborne asbestos by a Transmission Electron Microscope per AHERA methods.

Sample ID #	t Location/Description	Result Summary
====== PAVILION Thursday, D	STAIRS FLOORING AREA	
1222-1	Stage Corridor Entry area	Pass
1222-2	Stage exit area	Pass
1222-3	Decon Clean Room	Pass
1222-4	Middle Stage Corridor area	Pass
1222-5	Blank Zefon Lot #11292	Pass
1222-6	Stage corridor exit area	Pass
1222-7	Stage exit area	Pass
1222-8	Decon Clean Room	Pass
1222-9	Middle stage corridor area	Pass
1222-10	Stage Corridor Entry area	Pass
1222-11	Stage exit area	Pass
1222-12	Decon Clean Room	Pass
1222-13	Middle of corrdior area	Pass

Contractors abated ACMs and finished by 3pm December 22, 2005.

### (Continued) Asbestos Consultant Records - Section 2.0 Analytical Laboratory Results Summary - Part 7.0 Page 3 of 5

### Laboratory Analytical Methods

**PLM** - Bulk Sample Analysis (Polarized Light Microscopy): The bulk material samples were submitted to an accredited laboratory in California. Bulk material samples were analyzed using dispersion staining techniques in accordance with the 40 CFR, Part 763, Appendix A, Subpart F, AHERA regulations.

**PCM** - Air Analysis (Phase Contrast Microscopy):

The air samples were analyzed for airborne fibers by a regular light microscope per NIOSH Method 7400 A (as applicable).

**TEM -** Air Analysis (Transmission Electron Microscopy):

The air samples were analyzed for airborne asbestos by a Transmission Electron Microscope per AHERA methods.

Sample ID #		Result Summary
=====		
LOWER SC	HOOL ASSEMBLY ROOM AREA	
Thursday	December 22, 2005	
22-01	Lower School Assembly Boiler room	Pass
22-02	Lower School Assembly Room	Pass
22-03	Lower School Assembly Kindergarten Room	Pass
22-04	Blank - Zefon lot #11292	0
22-05	Blank - Zefon Lot #11292	0
	l Assembly Room Area	
Background		
Thursday, D	ecember 22, 2005	
AR-1	<b>Boiler Room adjacent to Assembly Room</b>	pass
AR-2	Assembly Room	Pass
AR-3	Kindergarten Rooms adjacent to Boiler Room	pass
Main Comm	a Administration Duilding	
-	as Administration Building	
•	cember 23, 2005	·
X-01	Elevator Admin Bldg Floor Linoleum	none detected

### (Continued) Asbestos Consultant Records - Section 2.0 Analytical Laboratory Results Summary - Part 7.0 Page 4 of 5

### Laboratory Analytical Methods

**PLM** - Bulk Sample Analysis (Polarized Light Microscopy): The bulk material samples were submitted to an accredited laboratory in California. Bulk material samples were analyzed using dispersion staining techniques in accordance with the 40 CFR, Part 763, Appendix A, Subpart F, AHERA regulations.

PCM - Air Analysis (Phase Contrast Microscopy):

The air samples were analyzed for airborne fibers by a regular light microscope per NIOSH Method 7400 A (as applicable).

**TEM -** Air Analysis (Transmission Electron Microscopy):

The air samples were analyzed for airborne asbestos by a Transmission Electron Microscope per AHERA methods.

Sample ID #	t Location/Description	Result Summary
=====	========	========
PAVILION	STAIRS FLOORING AREA	
Friday, Dece	ember 23, 2005	
AHERA CL	EARANCE TESTING Post Mastic Abatement:	
1223T-01	Pavilion Stairwell up to Mech Room @ top landing	pass
1223T-02	Pavilion Stairwell up to Mech Room @ top stairs	pass
1223T-03	Pavilion Stairwell up to Mech Room @ middle stairs	pass
1223T-04	Pavilion Stairwell up to Mech Room @ base of stairs	pass
Main Camp	us Administration Building	
_	ng of Basement Mechanical Room	
	ember 23, 2005	
Filiday, Dece	ander 25, 2005	
1223-1	Basement at hallway at Mech room	Pass
1223-2	Basement at middle hallway at Mech room	Pass
1223-3	Basement at Mech Room at Stairs	Pass
	(Neg air exhaust area)	
1223-4	Blank - Zef lot #11292	0

### (Continued) Asbestos Consultant Records - Section 2.0 Analytical Laboratory Results Summary - Part 7.0 Page 5 of 5

### Laboratory Analytical Methods

**PLM** - Bulk Sample Analysis (Polarized Light Microscopy): The bulk material samples were submitted to an accredited laboratory in California. Bulk material samples were analyzed using dispersion staining techniques in accordance with the 40 CFR, Part 763, Appendix A, Subpart F, AHERA regulations.

PCM - Air Analysis (Phase Contrast Microscopy):

The air samples were analyzed for airborne fibers by a regular light microscope per NIOSH Method 7400 A (as applicable).

**TEM** - Air Analysis (Transmission Electron Microscopy):

The air samples were analyzed for airborne asbestos by a Transmission Electron Microscope per AHERA methods.

Sample ID #	Location/Description	Result Summary
=====	=======	
Main Camp	pus Mechanical Room - Basement	
O & M Clear	ning of Mech Room	
Tuesday, De	cember 27, 2005	
1227-1	Outside - ambient air at stairs near elevator entry	pass
1227-2	Inside- Top of stairs at elevator	Pass
1227-3	Inside-Top of stairs at Headmaster office hjall	pass
1227-4	Inside- Neg Air exhaust near tube	Pass
1227-5	Inside-Decon Dirty room	Pass
1227-6	Inside-Basement hallway near decon unit	Pass
1227-7	Inside-Basement area at elevator	Pass
1227-8	Outside - ambient air at stairs near elevator entry	pass
1227-9	Inside- Top of stairs at elevator	Pass
1227-10	Inside-Top of stairs at Headmaster office hjall	pass
1227-11	Inside- Neg Air exhaust near tube	Pass
1227-12	Inside-Decon Dirty room	Pass
1227-13	Inside-Basement hallway near decon unit	Pass
1227-14	Inside-Basement area at elevator	Pass
1227-15	Blank - Zefon lot #11292	0
1227-16	Blank - Zefon lot #11292	0
1227-17	Basement near decon	Pass
1227-18	Hallway near decon	Pass

PAGE 04/04

905121623-

1450 North Santa Fe Ave, Suite #C PMB #144 Vista, CA 92083 Kenneth Medici, CAC #92-0007 Office: 1-888-999-7908 Toll-Free RNSH Fax: (760).414-1183 22 DECOSSampler: K. Medici, CAC #92-0007 Date THVRS Client: The Buckley School Site area: Site Address: Sherman Oaks Campus FIELD DATA AND CHAIN OF CUSTODY FORM Please fax lab results to 760.414-1183; call Ken Medici with verbal results at 760-212-8857 and return original chain of custody to Ken Medici at above address. Your laboratory must be NVLAP certified as applicable to complete this work (asbestos, lead or other). If your laboratory is not certified please stop and call Ken Medici at phone #760-212-8857. Sample Description/Location/Condition of Material Sample ID 0 AIR Pould ð 6/ve on stail 7 stain 200 9 mas 10 11 <u>14 66</u> DUN 12 13 14 15 _____ 16 17 <u>18</u> Asbestos or Lead Relinquished by/Date: (PLM + PCM TEM THR 12 23 as 2 Ob'OO+ AA flame for lead Received by / Date

## AmeriSci Los Angeles

24416 SOUTH MAIN STREET • SUITE 308 CARSON, CA 90745 TEL: (310) 834-4868 • FAX: (310) 834-4772

# PLM Bulk Asbestos Report

Attn: Kei		Date Received Date Examined RE The Buckley ID's A-01 Th	12/23/05 School; Sh	P.O. # Page	ci Job No.905121623 The Buckley School 1 of 2 aks Campus / Sample
Client N	o./HGA La	b No.	Asbestos Pi	resent	Total % Asbestos
A-01	905	i121623-01 stic @ Top Landing/Brows	<b>No</b> n Glue		NAD
	Description: Brown, H Asbestos Types: Other Material: Non-fibro	leterogeneous, Non-Fibro ous 100. %	us, Bulk Materi	al	
A-02		5121623-02 stic @ Random Stair/Brov	No vn Glue		NAD
	Description: Brown, H Asbestos Types: Other Material: Non-fibro	leterogeneous, Non-Fibro ous 100. %	us, Bulk Materi	al	
A-03		5121623-03L1 stic @ Random Stair/Brow	No vn Glue		NAD
	Description: Brown, H Asbestos Types: Other Material: Non-fibro	Heterogeneous, Non-Fibro ous 100. %	ous, Mastic		
A-03		5121623-03L2 Istic @ Random Stair/Bro	<b>No</b> wn Glue		NAD
	Description: White, H Asbestos Types: Other Material: Non-fibr	leterogeneous, Non-Fibro ous 100. %	us, Joint Comp	bound	
A-04		5121623-04 astic @ Random Stair/Bro	<b>No</b> wn Glue		NAD
	Description: Brown, I Asbestos Types: Other Material: Non-fibr	Heterogeneous, Non-Fibra ous 100. %	ous, Buik Mater	ial	



AmeriSci Los Angeles 24416 SOUTH MAIN STREET • SUITE 308 CARSON, CA 90745 TEL: (310) 834-4868 • FAX: (310) 834-4772

AmeriSci Job No.905121623

P.O. # The Buckley School

## **PLM Bulk Asbestos Report**

Date Received 12/23/05

Date Examined 12/23/05

Applied Toxicology Attn: Kenneth Medici 1450 North Santa Fe Avenue PMB #144 Vista, CA 92083

Page 2 of 2 RE The Buckley School; Sherman Oaks Campus / Sample ID's A-01 Through A-05

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos
A-05	905121623-05	No	NAD
	on: Stair Mastic @ Random Stai	r/Brown Glue	
Descripti	on: Brown, Heterogeneous, Non	-Fibrous, Bulk Material	

Asbestos Types:

Other Material: Non-fibrous 100. %

### **Reporting Notes:**

**Reviewed By:** 

Analyzed By: David G. Baseman  $\frac{12}{12}$ ; Date Analyzed: <Date Examined>  $\frac{12}{22}$ / $\frac{12}{23}$ "NAD = no asbestos detected; Detection Limit <1%; Reporting Limits: CVES = 1%, 400 Pt Ct = 0.25%, 1000 Pt Ct = 0.1%; "Present" or "NVA" = "No Visible Asbestos" are observations made during a qualitative analysis; NA = not analyzed; NA/PS = not analyzed / positive stop; PLM Bulk Asbestos Analysis by EPA 600/M4-82-020 per 40 CFR 763 (NVLAP Lab #200346-0, CA ELAP lab #2322); Note: PLM is not consistently reliable in detecting asbestos in floor coverings and similar NOB materials. TEM is currently the only method that can be used to determine if this material can be considered or treated as non-asbestos-containing in New York State (also see EPA Advisory for floor tile, FR 59, 146, 38970, 8/1/94). NIST Accreditation requirements mandate that this report must not be reproduced except in full without the approval of the laboratory. This PLM report relates ONLY to the items tested. •

AMERISCILA

. .

905121610

Λ.

Kenneth Medici, CAC #92-0007         1450 North Santa Fe Ave, Suite #C         PMB #144         Vista, CA 92083           Fax: (760).414-1183         Office: 1-888-999-7908         Toll-Free
Client: The Buckley School Date THURS 22 DE 05 Sampler: K. Medici, CAC #92-0007 Site Address: Sherman Oaks Campus Site area: LOWA SCHOOL ASSEMBLY ROOM FIELD DATA AND CHAIN OF CUSTODY FORM
Please fax lab results to 760.414-1183; call Ken Medici with verbal results at 760-212-8857 and return original chain of custody to Ken Medici at above address. Your laboratory must be NVLAP certified as applicable to complete this work (asbestos, lead or other). If your laboratory is not certified please stop and call Ken Medici at phone #760-212-8857.
Sample ID Sample Description/Location/Condition of Material EM
AR-01 BOILER KOOM
2AR-OZ ASSEMBLY ROOM (IDAM/11 AM
3AR-03 KINTYER FARTEN ROOMA ) F= 10 LAM
4
5
BACKFROUND AIR TESTS
8
· Fresh Air plans to clean attic
11
12
13
14
15
16
17
18
Relinquished by/Date HHERH + Notes: + Notes: AHERH + PCM TEM PLM + 24HR
+ POM (IEM) PLIM 24HR
Received by / Date: Cant is lar & Ob'00 + AA flame for lead

### AmeriSci Job #: 905121610 Client Name: Applied Toxicology

### Table I Summary of Transmission Electron Microscopy (TEM) Results for Asbestos (air)

The Buckley school; Sherman Oaks Campus / Lower School Assembly Room

AmeriSci	Client	Air Dilution Filtere		<ul> <li>Analytical</li> <li>Sensitivity</li> </ul>	Asbestos	Structures (Microns)		Struc Den (struc/s	sity	Struc Concen (struc/i	tration	Type of
Sample #	Sample #	Factor (liters	) (sq. mm.)	(struc/cc air)	0.5-5.0	>=5.0	Total	>=5.0	Total	>=5.0	Total	Asbestos
01 inside	AR-01	650	.100	0.0059	0.0	0.0	0.0	<10	<10	<0.0059	<0.0059	NSD
	Boiler Room											
02 inside	AR-02	650	.100	0.0059	0.0	0.0	0.0	<10	<10	<0.0059	<0.0059	NSD
	Assembly Room											
03 inside	AR-03 Kindergaten Room	650	.100	0.0059	0.0	0.0	0.0	<10	<10	<0.0059	<0.0059	NSD

concentration represented by the detection of	1 structure	$\cap$	6	
** not analyzed NSD: No Asbestos Structures Detected	Reviewed By:	 _; Analyzed By:	- Cont	Date: 12/23/2005
		Javier Co	ortes	· ·

12/23/2005

14:10

13108341464

NVLAP#: 200346-0

905121611

1450 North Santa Fe Ave, Suite #C PMB #144 Vista, CA 92083 Kenneth Medici, CAC #92-0007 Office: 1-888-999-7908 Toll-Free Fax: (760).414-1183 Sampler: K. Medici, CAC #92-0007 Date 22 DEC 05 Client: The Buckley School Site area: PAVILION STAIRS (TO UPPR MECHRM Site Address: Sherman Oaks Campus FIELD DATA AND CHAIN OF CUSTODY FORM Please fax lab results to 760.414-1183; call Ken Medici with verbal results at 760-212-8857 and return original chain of custody to Ken Medici at above address. Your laboratory must be NVLAP certified as applicable to complete this work (asbestos, lead or other). If your laboratory is not certified please stop and call Ken Medici at phone #760-212-8857. Sample Description/Location/Condition of Material Sample ID VASE ()になない M LPM 8(7)  $C \cap M$ S ] A RWEL 6122 1.10 7 8 CMS 9 omo 10 11 12 13 14 <u>15</u> 16 17 18 **BAT**ANANANANANANANANANANANANANANA Annungation LIP sbestos br Lead: + PCM (TEM) PLM Relinquished by/Date: A Chico AA flame for lead Received by / Date:

### AmeriSci Job #: 905121611 Client Name: Applied Toxicology

### Table I

Summary of Transmission Electron Microscopy (TEM) Results for Asbestos (air)

The Buckly School; Sherman Oaks Campus / Pavilion Stairs (To Upper Mech Rm)

			Air		<ul> <li>Analytical</li> <li>Sensitivity</li> </ul>	Asbestos	Structures (Microns)		Struc Den:		Struct Concent (struc/c	ration	Type of
AmeriSci	Client Sample #	Dilution Fil Factor (li		(sq. mm.)	(strue/cc air)	0.5-5.0	>=5.0	Total	>=5.0	Total	\suucc	Total	Asbestos
Sample # 01 inside	1222 <b>T</b> -01		1400	.060	0.0046	0.0	0.0	0.0	<16.6	<16.6	<0.0046	<0.0046	NSD
Of Insue	Base Of Stairs											0.001/	NOD
02 inside	1222 <b>T-02</b>	1	1400	.060	0.0046	0.0	0.0	0.0	<16.6	<16.6	<0.0046	<0.0046	NSD
	Middle Stairs		1 100	.060	0.0046	0.0	0.0	0.0	<16.6	<16.6	<0.0046	<0.0046	NSD
03 inside	1222T-03 Top Of Stairs		1400	.000	0.0040	0.0	0.0	010					
04 inside	1222T-04		1400	.060	0.0046	0.0	0.0	0.0	<16.6	<16.6	<0.0046	<0.0046	NSD
	Stage Corridor										-0.0046	<0.0046	NSD
05 inside	1222T-05		1400	.060	0.0046	0.0	0.0	0.0	<16.6	<16.6	<0.0046	<0.0040	NON
06 inside	Basket Ball / Stage Area 1222T-06		1400	.060	0.0046	0.0	0.0	0.0	<16.6	<16.6	<0.0046	<0.0046	NSD
	Door To Stairwell @ Stage												

AMERISCILA

* concentration represented by the detection of 1 structure £ Date: 12/23/2005 ** not analyzed ; Analyzed B Reviewed By: NSD: No Asbestos Structures Detected

NVLAP#: 200346-0

**O**1----

## 905121625-

1450 North Santa Fe Ave, Suite #C PMB #144 Vista, CA 92083 Kenneth Medici, CAC #92-0007 Office: 1-888-999-7908 Toll-Free Fax: (760).414-1183 22 DEC 05 Sampler: K. Medici, CAC #92-0007 Date THURS Client: The Buckley School Site area: Site Address: Sherman Oaks Campus FIELD DATA AND CHAIN OF CUSTODY FORM Please fax lab results to 760.414-1183; call Ken Medici with verbal results at 760-212-8857 and return original chain of custody to Ken Medici at above address. Your laboratory must be NVLAP certified as applicable to complete this work (asbestos, lead or other). If your laboratory is not certified please stop and call Ken Medici at phone #760-212-8857. Sample Description/Location/Condition of Material Sample ID EN るみる 68 RM CORRIDOR ST 90 2 RM CI ON 8 CORRIDO 9100n ENTRY 10/223 6 J R 11/20 29 12 13 <u>14</u> 10:30An 1 15 16 17 18 Notes: Asbestos or Lead: Relinquished by/Date: PCM TEM PLN - do 00 _ + AA flame for lead - @ Received by / Date:

AmeriSci Job #:

ı

905121625

Client Name: Applied Toxicology

## Phase Contrast Microscopy (PCM) Fiber Results

The Buckley School; Sherman Oaks Campus / Sample ID's 1222-1 Through 1222-13

AmeriSci Sample #	•	Date Collected	Flow Rate (liters/min.)	Duration (min.)	Air Filtered (liters)	Fields	Fibers	Fiber Density (Fibers/mm ² )	Fibers Conc. (Fibers/cc)	TWA
01	1222-1	12/22/2005	10	120	1200	100	41	52.23	0.017	
	Stage Corridor Entry									
02	1222-2	12/22/2005	10	120	1200	92	101	139.85	0.045	
	Stage Exit									
03	1222-3	12/22/2005	10	120	1200	100	36	45.86	0.015	
	Decon Clean Rm									
04	1222-4	12/22/2005	10	120	1200	90	103	145.79	0.047	
	Middle Stage Corridor									
05	1222-5	12/22/2005	0	0	0	100	Ð	ND		
	Blank Zefon Lot #11292				•				Footnotes:	- I
06	1222-6	12/22/2005	10	120	1200	100	21	26.75	0.009	
	Stage Corridor Entry									
07	1222-7	12/22/2005	10	120	1200	100	10	12.74	0.004	
	Stage Exit									
08	1222-8	12/22/2005	10	120	1200	100	20	25.48	0.008	
	Decon Clean Rm									
09	1222-9	12/22/2005	10	120	1200	100	12	15.29	0.005	
	Middle Stage Corridor									
10	1222-10	12/22/2005	10	120	1200	100	7	8.92	0.003	
	Stage Corridor Entry									
11	1222-11	12/22/2005	10	120	1200	100	5	6.37	< 0.002	
	Stage Exit									
12	1222-12	12/22/2005	10	120	1200	100	6	7.64	0.002	
	Decon Clean Rm									

See Reporting notes on last page

## AmeriSci Job #: 905121625

Client Name: Applied Toxicology

### Phase Contrast Microscopy (PCM) Fiber Results

The Buckley School; Sherman Oaks Campus / Sample ID's 1222-1 Through 1222-13

AmeriSci Sample #	Client Sample # / Location	Date Collected	Flow Rate (liters/min.)	Duration (min.)	Air Filtered (liters)	Fields	Fibers	Fiber Density (Fibers/mm ² )	Fibers Conc. (Fibers/cc)	TWA	
13	1222-13	12/22/2005	10	120	1200	100	9	11.46	0.004		
	a. a · · · ·										

Middle Stage Corridor

### **Reporting Notes:**

(1) Fibers/cc cannot be calculated for samples (or blanks) with no air volume.

Analyzed By: Javier Cortes

Samples analyzed by NIOSH 7400(A) METHOD, Issue #2, 8/15/94; Limit of Detection = 5.5 fibers per 160 fields or 7 fibers / mun2; This report relates ONLY to the sample analysis expressed as fibers/sq mm of fiber area; ND = no fibers observed; NA = Not Analyzed; Walton - Beckett gradicule field area 0.00785 mm2; Duration in minutes; TWA = 8Hr TWA, calculation assumes zero exposure for remainder of 8 hour period not sampled; Upper 95% Confidence Limit (Employer's Compliance Test) - Calculated as a one sided UCL to determine 95% centainuy of compliance with the 0.01 fiber/ce standard; Estimated relative standard deviation: Intralab Sr = 0.405, Interlab Sr = 0.45.

Reviewed By:_____

Solution (1983) Self Page 2 of 2 se

-

AMERISCILA

•

# 905121624-

Kenneth Medici, CAC #92-0007         1450 North Santa Fe Ave, Suite #C         PMB #144         Vista, CA 92083           Fax: (760).414-1183         Office: 1-888-999-7908         Toll-Free	
Client: The Buckley School Date 22 TEC 05 THURS Sampler: K. Medici, CAC #92-0007	
Site Address: Sherman Qaks Campus She area.	
FIELD DATA AND CHAIN OF CUSTODY FORM	
Please fax lab results to 760.414-1183; call Ken Medici with verbal results at 760-212-8857 and return original chain of custody to Ken Medici at above address. Your laboratory must be NVLAP certified as applicable to complete this work (asbestos, lead	
or other) If your laboratory is not certified please stop and call Ken Medici at phone # $(00-212-000)$	
Sample ID Sample Description/Location/Condition of Material	
122-01 Lwr School- Boiler Rm a Assmbly Hall) 204/00	<b>ł</b> -
222-02 Lur School - Assmbly Room (1) April Apr	h
322-03 Lun School - Kindersanten 10 LPM	
122-04 BLANK Seten (0+#11292	
532-05 BLANK Zetan Jot 7 11292	
6	
7	
8	
9	
10	
11	
12	
13	
<u>14</u>	
15	
16	
17	
Relinquished by/Date: Asbestos or Lead:	
Received by / Date: I a Cont 12/23/05 Q 06:00 + AA flame for lead	

#### 905121624 AmeriSci Job #:

Applied Toxicology Client Name:

## Phase Contrast Microscopy (PCM) Fiber Results

The Buckley School; Sherman Oaks Campus / Sample ID's 22-04 Through 22-05

	Ine Buckie	sy achoor, and			•			Fiber	Fibers
AmeriSci		Date Collected	Flow Rate (liters/min.)	Duration (min.)	Air Filtered (liters)	Fields	Fibers	Density (Fibers/mm ² )	Conc. (Fibers/cc) TWA
Sample #	Sample # / Location	12/22/2005	10	120	1200	100	16	20.38	0.007
01	Lwn School-Boiler Rm @ Assembly Hall		*0	120	1200	100	4	5.10	< 0.002
02	22-02	12/22/2005	10	120	1200				
	Lwn School-Assembly Room	( + 13 P 10 0 0 5	10	120	1200	100	10	12.74	0.004
03	22-03	12/22/2005	10	120		1200			
	Lwn School-Kindergarden		Q	0	0	100	4	5.10	
04	22-04	12/22/2005	U	Ŷ	U				Footnotes: 1
	Blank Zefon Lot #11292			0	0	100	1	1.27	
05	22-05	12/22/2005	0	Ŭ	v				Footnoles: 1
	Blank Zefon Lot #11292								

### **Reporting Notes:**

(1) Fibers/cc cannot be calculated for samples (or blanks) with no air volume.

Samples analyzed by NIOSH 7400(A) METHOD, Issue #2, 8/15/94; Limit of Detection = 5.5 fibers per 100 fields or 7 fibers / num2; This report relates ONLY to the sample analysis expressed as fibers/sq num of filter area; ND = no fibers observed; NA = Not Analyzed; Walton - Beckett gradicule field area 0.00785 mm2; Duration in minutes; TWA = 8Hr TWA, calculation assurbes zero exposure for remainder of 8 hour period nat sampled; Upper 95% Confidence Limit (Employer's Compliance Test) -Calculated as a one wided UCL to determine 95% certainty of compliance with the 0.01 fiber/oc standard; Estimated relative standard deviation: Introlab Sr = 0.405, Interlab Sr = 0.45,

Reviewed By:

12/24/2005

٠

---

AMERISCILA

905121650

Kenneth Medici, CAC #92-0007 1450 North Santa Fe Avc, Suite #C PMB #144 Vista, CA Fax: (760).414-1183 Office: 1-888-999-7908 Toll Free	92083
Client: The Buckley School Date FRI 23 DEC OF Sampler K Medici CAC 400 0000	<u></u>
Site area: ADMIN 8 475	
FIELD DATA AND CHAIN OF CUSTODY FORM lease fax lab results to 760.414-1183; call Ken Medici with verbal results at 760-212-8857 and return original chain of Ken Medici at above address. You labor the Medici with verbal results at 760-212-8857 and return original chain of	
	of custody stos. lead
vertice and call Ken Medici at phone #760-212-8857.	,
Sumple Prescription Execution Condition of Material	
X-01 LINO- ADMIN BLDG	
- Elevator Floor	
* Notre:	
THIS FLOOR HAS BEEN	
THE NEW LINO IS ACM.	
X-01 WILL TEST THIS PARA	<u>n</u> .
	—
	[]]
linquished by/Date: Asbestor or Lead:	<b>S</b> rr
+ PCM TEM(PLM) 4	·0 🖾
ceived by / Date: KUNLAN @D903 12/24/05+ AA flame for lead	
+	

AMERISCILA



AmeriSci Los Angeles 24416 SOUTH MAIN STREET • SUITE 308 CARSON, CA 90745 TEL: (310) 834-4868 • FAX: (310) 834-4772

## PLM Bulk Asbestos Report

Applied Toxicology Attn: Kenneth Medici 1450 North Santa Fe Avenue PMB #144 Vista, CA 92083 Date Received12/24/05AmeriSci Job No.905121650Date Examined12/27/05P.O. # The Buckley SchoolPage1ofRE The Buckley School;Sherman Oaks Campus Admin<br/>Bidg.

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos
X-01	905121650-01	No	NAD
Locatio	n: Lino, -Admin Bldg, Elevator I	Floor	•
Descriptio	n: Beige, Heterogeneous, Fibro	ous, Bulk Material	

Asbestos Types:

Other Material: Cellulose 22. %, Fibrous glass 3. %, Non-fibrous 75. %

#### **Reporting Notes:**

Analyzed By: David G. Baseman  $\frac{12}{22/65}$ ; Date Analyzed: <Date Examined> $\frac{12}{22/65}$ *NAD = no asbestos detected; Detection Limit <1%; Reporting Limits: CVES = 1%, 400 Pt Ct = 0.25%, 1000 Pt Ct = 0.1%; "Present" or "NVA" = "No Visible Asbestos" are observations made during a qualitative analysis; NA = not analyzed; NA/PS = not analyzed / positive stop; PLM Bulk Asbestos Analysis by EPA 600/M4-82-020 per 40 CFR 763 (NVLAP Lab #200346-0, CA ELAP lab #2322); Note: PLM is not consistently reliable in detecting asbestos in floor coverings and similar NOB materials. TEM is currently the only method that can be used to determine if this material can be considered or treated as non-asbestos-containing in New York State (also see EPA Advisory for floor tile, FR 59, 146, 38970, 8/1/94). NIST Accreditation requirements mandate that this report must not be reproduced except in full without the approval of the laboratory. This PLM report relates ONLY to the items tested. Reviewed By:_______

AMERISCILA

905121648

Kenneth Medici, CAC		anta Fe Ave, Suite i	#C PMB #144 Vista 999-7908 Toll-Free	, CA 92083	
Fax: (760). Client: The Buckley School	Dette A 2 DEC 2005	Sampler: k	. Medici, CAC #92-00	07	24
	Sife area	PAVILION		TEM	A
FI	ELD DATA AND CHA	IN OF CUSTO	-8857 and return original of	chain of custody	AHE
				(asbestos, lead	
or other). If your laboratory is r	not certified please stop and call f	Con Medici at phone #	760-212 <b>-</b> 8857. <u>ndition of Material</u>		
Sample ID	Sample Desu	LUILLUIM LUIVONNING VI		AMERY	ЮЛ
1 12237-01	PAVILION	- STAIRWE	UL TO UPPE	KINE CI	20
21223T-02	PAVILION -				
12237-03_	PAVILION -		Y	A	
1223T-04	PAVILION	- DECON	C Base of	ESTAI	es
	723Am/92	3 AM	10-100	2/	
5		004	101=12	Z	
6	F = 10L	PIM			
nution	ACLEAR	ANCE		······	
		( - + 10 ]	T= ARATA	EMT	
8 FOLLO	WINEF	( DOKIN	G AVYIII	• ــــــــــــــــــــــــــــــــــــ	
9					
10					
11					
12		<b> </b>			
10					
13					
14					
15					
16		n an			
17	•				
18					
		4 <i>,</i> 111111111111111111111111111111111111		///////////////////////////////////////	
			+ Notes:		
//////////////////////////////////////			+ Notes: + Asbestosor Lead:	01	מנו
			+ Notes:	01	HR

### AmeriSci Job #: 905121648 Client Name: .Applied Toxicology

Table ISummary of Transmission Electron Microscopy (TEM) Results for Asbestos (air)1223T-

AmeriSci	Client D	ilution	Air Filtered	Area Analyzed		1	Structures (Microns)			sity q. mm.)	Struct Concent (struc/c	ration c air)	Type of Asbestos
Sample #	Sample # F	Factor	(liters)	(sq. mm.)	(struc/cc air)	0.5-5.0	>=5.0	Total	>=5.0	Total	>=5.0	Total	
01	[223T-0]		1200	.060	0.0053	0.0	0.0	0.0	<16.6	<16.6	<0.0053	<0.0053	NSD
02	Pavilion Stairwell To Upper Mech Ro 1223T-02	0-0TD	1200	.060	0.0053	0.0	0.0	0.0	<16.6	<16.6	<0.0053	<0.0053	NSÐ
03	Pavilion Stairwell To Upper Mech Ro 1223T-03	00m	1200	.060	0.0053	0.0	0.0	0.0	<16.6	<16.6	<0.0053	<0.0053	NSD
04	Pavilion Stairwell To Upper Mech Ro 1223T-04 Pavilion Decon @ Base Of Stairs	oom	1200	.060	0.0053	0.0	0.0	0.0	<16.6	<16.6	<0.0053	<0.0053	NSD

* concentration represented by the detection of 1 structure ** not analyzed

NSD: No Asbesticis Structures Detected

Reviewed By: ___

Date: 12/24/2005 ; Analyzed By: //Otr// Rory S/Tabatt

12/24/2005 14:06 13108341464

NVLAP#: 200346-0

-

AMERISCILA

905121649-

Kenneth Medici, CAC #92-0007 1450 North Santa Fe Ave, Suite #C PMB #144 Vista, CA 92083 Fax: (760).414-1183 FE 1 PAY Office: 1 550 022 Field #144 Vista, CA 92083
Client: The Buckley School Date 22 are Charter Conce: 1-888-999-7908 Toll-Free
Site Address: Sherman Oaks Campus Site area:
Please fax lab results to 760 414 1192 and a strip CHAIN OF CUSTODY FORM
to Ken Medici at above address. Your laboratory must be NVLAP certified as applicable to complete this work (asbestos, lead or other). If your laboratory is not certified please stop and call Ken Medici at phone #760-212-8857.
Sample ID Sample Description/Location/Condition of Material
1223-1 Basent OUTSIDE MECH RM ) 05/5
21223-2 1 " " 59Am 11 AM
31223-3 V V C STAIRS JOLPM
1223-4 BLANK 16+ 11292
5
6
7
8
9
10
11
12
13
14
15
16
17
18
Relinquished by/Data
+ PCM TEM PLM & THK
Received by / Date: Aulian o C U903 12/24/05+ AA flame for lead PM

#### AmeriSci Job #: 905121649

Client Name:

Base 1 of

Page  $\Omega^{2}$ i

### Page 1 of

12/26/2005 10:58

13108341464

AMERISCILA

# Phase Contrast Microscopy (PCM) Fiber Results

The Buckley School; Sherman Oaks Campus Admin Bldg.

AmeriSci Sample #	# Sample # / Location	Date Collected	Flow Rate (liters/min.)	Duration (min.)	Air Filtered (liters)	Fields	Fibers	Fiber Density (Fibers/mm ² )	Fibers Conc.	
01	1223-1 Basemt Outside Mech. Rm.	12/23/2005	10	120	1200	100	7	(11033411111 ) 8.92		TWA
02	1223-2 Basemt Outside Mech. Rm.	12/23/2005	10	120	1200	100	6	7.64	0.003 0.002	L O L
03	1223-3 Basemt Outside Mech. Rm.	12/23/2005	10	120	1200	100	9	11.46	0.004	0000 4 1
04	1223-4 Blank Lot 11292	12/23/2005	10	120	1200	100	I	1.27		+ 0 +
Reportir	ng Notes:								< 0.002 Footnotes: /	

(1) Fibers/cc cannot be calculated for samples (or blanks) with no air volume.

Analyzed By: Karrie Chan. sa.

Applied Toxicology

_; Date Analyzed: 12/26/2005

Samples analyzed by NtOSH 7400(A) METHOD, Issue #2, 8/15/94; Limit of Detection = 5.5 fibers per 100 fields or 7 fibers / nom2; This report relates ONLY to the sample analyzis expressed as fibers/sq mm of filter area; ND = no fibers observed; NA = Not Analyzed; Watton - Beckett gradicule field area 0.00785 ours2; Duration in minutes; TWA = 8Hr TWA, calculation assumes zero exposure for remainder of 8 hour period not sampled; Upper 95% Confidence Limit (Employer's Compliance Test) -Calculated as a one sided UCL to determine 95% certainty of compliance with the 0.01 fiber/cc standard; Estimated relative standard deviation: Intralab Sr = 0.405, Intertab Sr = 0.45.

AMERISCI

## 105121507

Kenneth Medici, CAC #92-0007 1450 North Santa Fe Ave, Suite #C PMB #144 Vista, CA 92083 Fax: (760).414-1183 TUES Office: 1-888-999-7908 Toll-Free Client: The Buckley School DEC 2005 Date 2 Sampler: K. Medici, CAC #92-0007 Site Address: Sherman Oaks Campus Site area: FIELD DATA AND CHAIN OF CUSTODY FORM Please fax lab results to 760,414-1183; call Ken Medici with verbal results at 760-212-8857 and return original chain of custody to Ken Medici at above address. Your laboratory must be NVLAP certified as applicable to complete this work (asbestos, lead or other). If your laboratory is not certified please stop and call Ken Medici at phone #760-212-8857. Pm : ID L Sample ID Sample Description/Location/Condition of Material A770 neau 5 Am Vsl= O0 08 0-02 0 Am Q_0~ EGE 15 Ò DEC 29 2005 Q_-01 Q-recon 0 CI 18 linin กิโหนกกิโลกกิโลกกาล huunnan Notes: Relinquished by/Date: Asbestosbor Lead: VI W PCM TEM PLM Received by / Date: + AA flame for lead CONTRACTORS WET-WIPING & HEP ADMIN BUILDING MECHANICAL ROOM.

-

AMERISCI

# 105121507

Kenneth Medici, CAC #92-0007 1450 North Santa Fe Ave, Suite #C PMB #144 Vista, CA 92083 Fax: (760).414-1183 70FS Office: 1-888-999-7908 Toll-Free	
Client: The Buckley School Date 27 DFC 05 Sampler: K. Medici, CAC #92-0007 Site Address: Sherman Oaks Campus Site area: FIELD DATA AND CHAIN OF CUSTODY FORM TEM A;	HR HERA
Please fax lab results to 760.414-1183; call Ken Medici with verbal results at 760-212-8857 and return original chain of custody to Ken Medici at above address. Your laboratory must be NVLAP certified as applicable to complete this work (asbestos, lead or other). If your laboratory is not certified please stop and call Ken Medici at phone #760-212-8857. <u>Sample ID</u>	
2 After PCM awalyses please	
3 VUN ATTERA TEMO ON 1 Samples	
5 6 # 1227-05 ( 5 5 5 5 6 1 5 5 5 5 5 5 5 5 5 5 5 5 5 5	
$\frac{7 \pm 1227 - 12}{8 \pm 1227 - 19}$	
9	
10	
12	
13	
14 15 DECEUVED	
16 DEC 2 9 2005	Ą
17 18	_
Relinquished by/Date: 12/28/05 + <u>Notes:</u> Asbestosor Lead: + PCM TEM PLM AHERA	<b></b>
Received by / Date:	

l

### AmeriSci Job #: 105121507

### Page 1 of 2

Client Name: Applied Toxicology

## Phase Contrast Microscopy (PCM) Fiber Results

CAC#92-0007; The Buckley School; 12/27/2005; 1227-01 thru 1227-19; The Buckley School

AmeriSci Sample #		Date Collected	Flow Rate (liters/min.)	Duration (min.)	Air Filtered (liters)	Fields	Fibers	Fiber Density (Fibers/mm ² )	Fibers Conc. (Fibers/cc)	TWA
01	1227-01	12/27/2005	10	127	1270	100	l	1.27	< 0.002	
	Outside Amhient At Admin Entry									
02	1227-02	12/27/2005	10	127	1270	100	4.5	5.73	< 0.002	
	Inside At Top Of Stairs At Elevator									
03	1227-03	12/27/2005	10	127	1270	100	4	5.10	< 0.002	
	Inside At Top Of Stairs At Head Master Office									
04	1227-04	12/27/2005	10	127	1270	100	2.5	3.18	< 0.002	
	Inside At Neg Air Exhaust Near-03									
05	1227-05	12/27/2005	10	127	1270	100	3.5	4.46	< 0.002	
	Inside At Decon Dirty Room									
06	1227-06	12/27/2005	10	127	1270	100	13.5	17.20	0.005	
	Ioside At Basement Hallway									
07	1227-07	12/27/2005	10	127	1270	100	12	15.29	0.005	
	Inside At Basement Elevator									
08	1227-08	12/27/2005	10	123	1230	100	1.5	1.91	< 0.002	
	At 01									
09	1227-09	12/27/2005	10	123	1230	100	11.5	14. <b>65</b>	0.005	
	At 02									
10	1227-10	12/27/2005	10	123	1230	100	9	11.46	0.004	
	At 03									
11	1227-11	12/27/2005	10	123	1230	100	3	3.82	< 0.002	
	At 04									
12	1227-12	12/27/2005	10	123	1230	100	3	3.82	< 0.000	
	At 05		_							
13	1227-13	12/27/2005	10	123	1230	100	6.5	8.28	0.000	
	At 06									
14	1227-14	12/27/2005	10	123	1230	100	11.5	14.65	0.000	
	At 07									
15	1227-15	12/27/2005	0	0	0	100	0	ND		
	Blank Zefon 11292									

12/29/2005

See Reporting notes on last page

#### 105121507 AmeriSci Job #:

#### Applied Toxicology Client Name:

### Phase Contrast Microscopy (PCM) Fiber Results

CAC#92-0007; The Buckley School; 12/27/2005; 1227-01 thru 1227-19; The Buckley School

AmeriSci Sample #	Client Sample # / Location	Date Collected	Flow Rate (liters/min.)	Duration (min.)	Air Filtered (liters)	Fields	Fibers	Fiber Density (Fibers/mm ² )	Fibers Conc. (Fibers/cc)	TWA
16	1227-16	12/27/2005	0	0	0	100	0	ND		
Blank	Zefon 11292									
17	1227-17	12/27/2005	10	122	1220	100	6.5	8.28	0.000	
Near i	Decon									;
18	1227-18	12/27/2005	10	122	1220	100	5.5	7.01	0.000	
Neari	Neg Air Exhaust Stairs									
19	1227-19	12/27/2005	10	122	1220	100	6	7.64	0.000	
Haliw	vay Near Decon									

### **Reporting Notes:**

Reviewed by: _

Date Analyzed: 12/29/2005 .: Analyzed by: Rebekah J. Swanson,

Samples analyzed by NIOSH 7400(A) METHOD, Issue #2, 8/15/94; Limis of Detection = 5.5 fibers per 100 feeds of 7 libers / nm2; This report relates ONLY to the sample analysis expressed as libers/sq nom of filter area; ND = no fibers observed; NA = Not Analyzed; Walton - Beckett gradicule field area 0.00785 mm2; Duration in minutes; TWA = 8Hr TWA calculated as a one sided UCI. to determine 95% certainty of compliance with the 0.01 fiber/cc standard; Estimated relative standard deviation: Intralab Sr = 1.354, Interlab Sr = 14.688., NYSDOH ELAP Lab#10984

# The Buckley School

## 3-year AHERA Re-inspection for Asbestos

Inspector: Ken Medici, CAC #92-0007 -Phone 1-888-999-7908

27December2005 Tuesday, 1:00pm-3pm

Previous Re-Inspection: 23Dec03 by K. Medici. Areas inspected include all areas of the school accessible at time of survey. Most attic areas were not inspected thoroughly because the original Asbestos Management plan determined that these areas were off limits until proper assessment methods could be performed to determine safety.

The site was inspected on Tuesday, December 27, 2005 between the hours of 1pm and 3 pm by Ken Medici an AHERA Accredited Building Inspector and Management Planner.

### **FIELDHOUSE**

Ceiling material was found to be water damaged in selected areas. Discolorations and warping could best describe the surface appearances. Locations included the Boys locker room and girls locker room approx 30 sq ft may be affected. Attic areas were assumed contaminated with asbestos.

### **LOWER SCIENCE BUILDING ROOMS #115**

Mechanical Room #1:Plaster wall damage, delamination approx 2 sq ft (Elbows assumed ACM)Mechanical Room #2:Same as #1Room #115:Flooring is black mastic only - no floor covering to protect mastic - approx 200sq ft

### **UPPER SCHOOL AREAS & ROBERT YOUNG LIBRARY**

Attic areas may have ACM debris from pipe elbows, etc.,

### LOWER SCHOOL AREA

Room #5:	Delamination of Ceiling Tiles at center room / 3 locations approx 12 sq ft total
Room #24:	Minor damage to ceiling tile 1x1, classrooms B and D
Lwr School Office:	2 sq ft of ceiling tiles delamination/missing at xerox room; water damaged

### **ADMINISTRATION BUILDING**

Attic spaces contain hard elbows and are assumed as ACM. Basement area: at xerox machine in hall-ceiling tile 2 sq ft of water-damage....(found painted upon inspection)

Page One of Two

The Buckley School 3 year Asbestos Program Re-Inspection 12/27/05 Asbestos Inspector K. Medici -Phone 1-888-999-7908 Page two of two

### **RECOMMENDATIONS**

- 1. Follow the AHERA Management Plan, inform LEA Designee Asbestos Program Manager, Ken Medici of any upcoming construction work so that applicable bulk sampling may be performed. Inform Ken Medici of any emergency work or plans to enter attic spaces anywhere on campus. Continue to conduct employee Awareness Training and other formal training as needed. Perform a suspects materials audit and update the AHERA Management Plan. Update the AHERA Management Plan as needed. Send out notifications to PTA members, parents, school employees as per the Management Plan and make available the AHERA Management Plan for review. Keep asbestos abatement records and organize into a readable file. Organize the Management Plan into a readable and user friendly document. The Management Plan is a working document and The Buckley School is required by AHERA to actively work with the asbestos concerns specified by the document.
- 2. The Buckley School should not pull up and replace carpet without the written approval of a Certified Asbestos Consultant even if The Buckley School believes newly installed carpet is free of Asbestos debris. (i.e. Lower school area rooms) nor disturb drywall of stucco matls.
- 3. If air testing is out of compliance with the Education Code, complete air testing to be in compliance with the Education Code. See the State of California internet web page (Education)
- 4. Address the damaged materials identified within the 6 month re-inspection.
- 5. Only AHERA accredited persons can work within the Asbestos Management Program and work within the Asbestos Abatement Program.
- 6. Roof materials should also be included as asbestos-containing materials. Attic areas, as mentioned in the original management plan should remain off limits and be considered as contaminated with asbestos until proven not to be contaminated with asbestos.

### **General Comments**

Extensive air monitoring of all campus rooms and hallways was completed in July 2001. All air samples were analyzed by an AIHA accredited laboratory which reported no asbestos detected. During other asbestos abatement work and clean-up, air monitoring was again performed in which all air samples collected were delivered to an AIHA accredited laboratory which again reported no asbestos detected in the air. Because all inspections are up to date and all previous air testing samples found no asbestos airborne fibers present, we conclude that the Buckley Campus in Sherman Oaks, CA is safe and presently free from any air-borne asbestos fiber hazards.

CERTIFICATION OF ASBESTOS SAFE FACILITY :

Dated: 12/27/05

Kenneth Medici Certified Asbestos Consultant #92-0007

	THE BUCKLEY SCHOOL c/o Kenneth Medici, CAC #92-0007 Fax: (760).414-1183 Office: 1-888-999-7908 Toll-Free
	AHERA FIELD DATA RE-INSPECTION ASSESSMENT FORM
	Type of Material: STUCCO Building Description: UPPER SCHOOL BLDGS Or PACM
	Functional Space: classrooms Office hallway) mech rm Attic Crawl-Space Other Functional Space Description: OUTSIDE FAITIC 5 OVERHANGS Estimated square feet or linear feet of Material: 10K-frz Approx Thickness: 3"
	Homogeneous Area: Surfacing TSI Miscellaneous +++++ Friable (Non-Friable)
	Condition of Material: Good Fair Poor Damaged Significantly Damaged AHERA Category required by 40CFR763.88 :
$\langle$	<ol> <li>Damaged or significantly damaged TSI</li> <li>Damaged friable surfacing</li> <li>Significantly damaged friable surfacing - ATTIC AREA5</li> <li>Damaged or significantly damaged friable miscellaneous</li> <li>Any ACBM with potential for damage</li> <li>Any ACBM with potential for significant damage</li> <li>Any friable ACBM</li> </ol>
	Type of Damage: Greater/Less than 10% Distributed/VGreater/Less than 25% localized Explanation: DUST, DEBRIS FROM ORIGINAL INSTALL
	Cause of Damage: Wear and Tear Mechanical Weather Water Other Explanation: Mech INStall caused Just E Jebris
	Accessibility: Always Periodic Rare Explanation: MAINT & CONSTRUCTION ONLY
	Potential for Disturbance: Potential for significant damage Potential for damage Low Vibration Air Erosion Weather Normal O&M
	Preventative Damage Measures Explanation: A CAC SHOULD DIRECT MANAGE ANY ENTRY INTO ATTIC AREAS.
: [ ]	Date of AHERA Assessment: DECEMBER 27, 2005 Inspector Name: Kenneth Medici Signature: Kenneth Me
-	

c/o Kenneth Medici, CAC #92-0007 Fax: (760).414-1183 Office: 1-888-999-7908 Toll-Free

AHERA FIELD DATA RE-INSPECTION ASSESSMENT FORM

Type of Material: EXTERIOR STUCCO Lab % Asbestos: 2% Building Description: ALL LOWER SCHOOL BLDG& PACM

Functional Space: classrooms Office (hallway) mech rm Attic Crawl-Space Other Functional Space Description: ATTIC OVERSPRAY, EXT WALLS & OVERHANCS Estimated square feet or linear feet of Material: 10K f+2 Approx Thickness: 3", N.

Homogeneous Area: (Surfacing) TSI Miscellaneous +++++ (Friable) (Non-Friable)

**Condition of Material:** Good Fair Poor Damaged Significantly Damaged **AHERA Category required by 40CFR763.88**:

- 1. Damaged or significantly damaged TSI
- 2. Damaged friable surfacing
- 3 Significantly damaged friable surfacing -ATTIC AREAS
- 4. Damaged or significantly damaged friable miscellaneous
- 5. Any ACBM with potential for damage
- 6. Any ACBM with potential for significant damage
- 7. Any friable ACBM

Type of Damage Greater/Less than 10% Distributed//Greater/Less than 25% localized Explanation: DUST, PEBRIS FROM ORIGINAL INSTALLATION Cause of Damage: Wear and Tear Mechanical Weather Water Other Explanation/Mech INStall created US+ & Debris Accessibility: Always Periodic Rare Explanation: MAINT ONLY, CAL & CONTRACTORS

Potential for Disturbance: Potential for significant damage Potential for damage Low Vibration Air Erosion Weather Normal O&M

Preventative Damage Measures Explanation: ENTER UNDER DIRECT SUPERVISION OF CAC WITH PROTECTIVE GEAR

Date of AHERA Assessment: DECEMBER 27, 2005 Inspector Name: Kenneth Medici Signature: Phone: 1-888-999-7908

Inspector Accreditation Information: CAC #92-0007

c/o Kenneth Medici, CAC #92-0007 Fax: (760).414-1183 Office: 1-888-999-7908 Toll-Free

AHERA FIELD DATA RE-INSPECTION ASSESSMENT FORM Type of Material: DRYWALL SYSTEM Building Description: LOWER SCHOOL BLDES OF PACM

Functional Space: classrooms Office hallway (mech rm Attic) Crawl-Space Other Functional Space Description:  $\mathcal{C}_{ASSROW} = \mathcal{O}_{FF} = \mathcal{O}_{F}$ Estimated square feet or linear feet of Material:  $\mathcal{O}_{K} = \mathcal{O}_{F}$ Homogeneous Area: Surfacing TSI Miscellaneous +++++ Friable Non-Friable

**Condition of Material:** Good Fair Poor Damaged Significantly Damaged **AHERA Category required by 40CFR763.88**:

- 1. Damaged or significantly damaged TSI
- 2. Damaged friable surfacing
- 3. Significantly damaged friable surfacing
- 4. Damaged or significantly damaged friable miscellaneous
- 5. Any ACBM with potential for damage
- 6. Any ACBM with potential for significant damage
- 7. Any friable ACBM

Type of Damage: Greater Less than 10% Distributed // Greater/Less than 25% localized Explanation:

Cause of Damage: Wear and Tear Mechanical Weather Water Other Explanation: MINDR H20 STAINS

Accessibility: Always Periodic Rare Explanation:

Potential for Disturbance:Potential for significant damagePotential for damageLowVibrationAir ErosionWeatherNormal O&M

**Preventative Damage Measures Explanation:** 

Date of AHERA Assessment: DECEMBER 27, 2005 KenM.C Inspector Name: Kenneth Medici Signature: Phone: 1-888-999-7908

Inspector Accreditation Information: CAC #92-0007

THE BUCKLEY SCHOOL	
c/o Kenneth Medici, CAC #92-0007	

Fax: (760).414-1183 Office: 1-888-999-7908 Toll-Free AHERA FIELD DATA RE-INSPECTION ASSESSMENT FORM Type of Material: PIPING ELBOWS Lab % Asbestos: 10% Building Description: ALL LOWER SCH. BLDGOr PACM Functional Space: classrooms Office hallway mech rm (Attic) Crawl-Space Other Functional Space Description: ATTIC AREAS Estimated square feet or linear feet of Material: **Approx Thickness: Homogeneous** Area: Surfacing (TSI) Miscellaneous +++++ Friable Non-Friable Condition of Material: Good (Fair) Poor Damaged Significantly Damaged AHERA Category required by 40CFR763.88 : 1. Damaged or significantly damaged TSI 2. Damaged friable surfacing 3. Significantly damaged friable surfacing 4. Damaged or significantly damaged friable miscellaneous 5. · Any ACBM with potential for damage 6. Any ACBM with potential for significant damage 7. Any friable ACBM Type of Damage Greater/Less) than 10% Distributed /// Greater/Less than 25% localized Explanation:SOME ERIORATION-VARIOUS ELBOWS DF^ **Cause of Damages** Wear and Tear Mechanical Weather Water Other **Explanation**: DAI ERIOR Accessibility: Always Periodic Rare Explanation: **Potential for Disturbance:** Potential for significant damage Potential for damage ) Low Weather  $\bigcirc$  Normal  $\bigcirc$  &  $M \bigcirc$ Vibration Air Erosion **Preventative Damage Measures Explanation:** Date of AHERA Assessment: DECEMBER 27, 2005 Inspector Name: Kenneth Medici Signature: Phone: 1-888-999-7908 Inspector Accreditation Information: CAC #92-0007

c/o Kenneth Medici, CAC #92-0007 Fax: (760).414-1183 Office: 1-888-999-7908 Toll-Free

AHERA FIELD DATA RE-INSPECTION ASSESSMENT FORM

Type of Material: LINOLEVM年 FLOOR TILE Lab % Asbestos: 10 思 A 学 B Building Description: ADMINIST. 年 LIBRARY Or PACM

Functional Space: classrooms Office (hallway) mech rm Attic Crawl-Space Other Functional Space Description: ALL ROTASEstimated square feet or linear feet of Material:  $10KAZ_{+}$  Approx Thickness: 1''

Homogeneous Area: Surfacing TSI Miscellaneous +++++ Eriable Non-Friable

**Condition of Material:** <u>Good</u> Fair Poor Damaged Significantly Damaged **AHERA Category required by 40CFR763.88**:

- 1. Damaged or significantly damaged TSI
- 2. Damaged friable surfacing
- 3. Significantly damaged friable surfacing
- 4. Damaged or significantly damaged friable miscellaneous
- 5. Any ACBM with potential for damage
- 6. Any ACBM with potential for significant damage
- 7. Any friable ACBM

**Type of Damage: Greater/Less than 10% Distributed///Greater/Less than 25% localized** Explanation:

**Cause of Damage: Wear and Tear Mechanical Weather Water Other** Explanation:

Accessibility: Always Periodic Rare

Explanation:

Potential for Disturbance: Potential for significant damage Rotential for damage Low Vibration Air Erosion Weather Normal O&M

**Preventative Damage Measures Explanation:** 

Date of AHERA Assessment: DECEMBER 27, 2005 Inspector Name: Kenneth Medici Signature: Phone: 1-888-999-7908

Inspector Accreditation Information: CAC #92-0007

c/o Kennetl	h Medici, (	CAC #92-0007	
Fax: (760).414-1183	Office:	1-888-999-7908	<b>Toll-Free</b>

## AHERA FIELD DATA RE-INSPECTION ASSESSMENT FORM

Type of Material: WALL SYSTEMS - DRYUALLab % Asbestos: TRAGE Building Description: UPPER SCHOOL BLDES Or PACM

Functional Space: <u>classrooms</u> Office hallway mech rm Attic Crawl-Space Other Functional Space Description: ALL AREAS-ALL ROOMS Estimated square feet or linear feet of Material: 10K fr2(+) Approx Thickness: 578
Homogeneous Area: Surfacing TSI Miscellaneous +++++ Friable Non-Friable
<b>Condition of Material:</b> Good Fair Poor Damaged Significantly Damaged <b>AHERA Category required by 40CFR763.88 :</b>
<ol> <li>Damaged or significantly damaged TSI</li> <li>Damaged friable surfacing</li> <li>Significantly damaged friable surfacing</li> <li>Damaged or significantly damaged friable miscellaneous</li> <li>Any ACBM with potential for damage</li> <li>Any ACBM with potential for significant damage</li> <li>Any friable ACBM</li> </ol> Type of Damage: Greater/Less than 10% Distributed///Greater/Less than 25% localized Explanation:
<b>Cause of Damage: Wear and Tear Mechanical Weather Water Other</b> Explanation:
Accessibility: Always Periodic Rare Explanation:
Potential for Disturbance: Potential for significant damage Potential for damage Low Vibration Air Erosion Weather Normal O&M
Preventative Damage Measures Explanation: Follow AHERA MGT PLAN Date of AHERA Assessment: DECEMBER 27, 2005
Inspector Name: Kenneth Medici Signature: Kon Maline Maline Signature: Kon Maline Signature: Kon Maline Signature Si

THE BUCKLEY SCHOOL	
c/o Kenneth Medici, CAC #92-0007	
Fax: (760).414-1183 Office: 1-888-999-7908 Toll-Free	
AHERA FIELD DATA RE-INSPECTION ASSESSMENT FORM	
Type of Material: STUCCO Building Description: FIELDHOUSE Dr PACM	B
Functional Space: classrooms Office hallway mech rm Attic? Crawl-Space Other Functional Space Description: ATTIC AREAS $\neq$ OFFICE Estimated square feet or linear feet of Material: $3000$ $f_{+2}$ Approx Thickness: $3''$	
Homogeneous Area: Surfacing TSI Miscellaneous +++++ Friable Non-Friable	
Condition of Material: Good Fair Poor Damaged Significantly Damaged AHERA Category required by 40CFR763.88 :	•
<ol> <li>Damaged friable surfacing</li> <li>Significantly damaged friable surfacing - ATTIC</li> <li>Damaged or significantly damaged friable miscellaneous</li> <li>Any ACBM with potential for damage</li> <li>Any ACBM with potential for significant damage</li> <li>Any ACBM with potential for significant damage</li> <li>Any friable ACBM</li> </ol> Type of Damage: Greater/Less than 10% Distributed//Greater/Less than 25% localized Explanation:	
Cause of Damage: Wear and Tear Mechanical Weather Water Other Explanation: ORIGINAL APPLICATION	
Accessibility: Always Periodic Rare Explanation: $O+M$	
Potential for Disturbance: Potential for significant damage Potential for damage Low Vibration Air Erosion Weather Normal O&M	
Preventative Damage Measures Explanation: ENTER ATTIC ONLY	
UNDER DIRECT SUPERVISION OF A CAC.	
Date of AHERA Assessment: DECEMBER 27, 2005 Inspector Name: Kenneth Medici Signature: Kan Marchine Signature: Kan Marchine Signature: Inspector Accreditation Information: CAC #92-0007	

	c/o Kennet	h Medici, CAC #92	-0007
AI	Fax: (760).414-1183 IERA FIELD DATA RE		99-7908 Toll-Free N ASSESSMENT FORM
	aterial: BLACK MASTIC escription: ALL BUILI		Lab % Asbestos: 10% aslestos Or PACM
Functional Functional Estimated	Space: classrooms Office Space Description: Glue Un square feet or linear feet of M	hallway) mech der carpe aterial: 120 K	hrm Attic Crawl-Space Other Tor linderms, etc f.Z Approx Thickness: Vg ¹¹
Homogene	ous Area: Surfacing TSI	Miscellaneous	)+++++ Friable Non-Friable
	of Material: Good Fair 1 ategory required by 40CFR76		l Significantly Damaged
<ol> <li>Dan</li> <li>Sign</li> <li>Sign</li> <li>Dan</li> <li>Dan</li> <li>Sign</li> <li>Dan</li> <li>Any</li> <li>Any</li> <li>Any</li> <li>Any</li> </ol>	haged or significantly damage haged friable surfacing dificantly damaged friable sur haged or significantly damage ACBM with potential for dat ACBM with potential for sig friable ACBM mage: Greater/Less than 10%	facing d friable miscel nage nificant damage	
Cause of D Explanation	amage: Wear and Tear M	echanical We	ather Water Other
Accessibilit Explanation			
<b>Potential fo</b> Vibration	r Disturbance: Potential for Air Erosion Weather Norr	significant dama nal O&M	ge Potential for damage Low
Preventativ	e Damage Measures Explana	tion: FOLLC	OW AHERA MET PLAN
DO NOT	DISTURB FLOOR	TILE, L	IND OR MASTICS
Inspector N Phone: 1-88	<b>ERA Assessment: DECEM</b> ame: Kenneth Medici Sigr 8-999-7908 ccreditation Information: CA	ature:	a Mali

c/o Kenneth Medici, CAC #92-0007

Fax: (760).414-1183 Office: 1-888-999-7908 Toll-Free

### AHERA FIELD DATA RE-INSPECTION ASSESSMENT FORM

Type of Material: ROOF CAP SHEETS, MASTAB % Asbestos: Building Description: ALL BUILDINGS Or PACM

Functional Space: classrooms Office hallway mech rm Attic Crawl-Space Other ROOF Functional Space Description: Estimated square feet or linear feet of Material: 120K ft² Approx Thickness: Layevel

Homogeneous Area: Surfacing TSI Miscellaneous +++++ Friable (Non-Friable)

**Condition of Material:** Good Fair Poor Damaged Significantly Damaged **AHERA Category required by 40CFR763.88**:

- 1. Damaged or significantly damaged TSI
- 2. Damaged friable surfacing
- 3. Significantly damaged friable surfacing
- 4. Damaged or significantly damaged friable miscellaneous
- 5. Any ACBM with potential for damage
- 6. Any ACBM with potential for significant damage
- 7. Any friable ACBM

**Type of Damage: Greater/Less than 10% Distributed///Greater/Less than 25% localized** Explanation:

**Cause of Damage: Wear and Tear Mechanical Weather Water Other** Explanation:

Accessibility: Always Periodic (Rare) ROOF AREAS NORMALLY NOT ACCESSIBLE Explanation:

Potential for Disturbance:Potential for significant damagePotential for damageLowVibrationAir ErosionWeatherNormal O&M

**Preventative Damage Measures Explanation:** 

PER APPLICABLE LAWS TAKE ALL

Date of AHERA Assessment: DECEMBER 27, 2005 Inspector Name: Kenneth Medici Signature: Phone: 1-888-999-7908

Inspector Accreditation Information: CAC #92-0007

c/o Kenneth Medici, CAC #92-0007

Fax: (760).414-1183 Office: 1-888-999-7908 Toll-Free

## AHERA FIELD DATA RE-INSPECTION ASSESSMENT FORM

Type of Material: Building Description:

_____

Lab % Asbestos: Or PACM

Functional Space: classroomsOffice hallway mech rmAttic Crawl-Space OtherFunctional Space Description:Estimated square feet or linear feet of Material:Approx Thickness:
Homogeneous Area: Surfacing TSI Miscellaneous +++++ Friable Non-Friable
Condition of Material: Good Fair Poor Damaged Significantly Damaged AHERA Category required by 40CFR763.88 :
<ol> <li>Damaged or significantly damaged TSI</li> <li>Damaged friable surfacing</li> <li>Significantly damaged friable surfacing</li> <li>Damaged or significantly damaged friable miscellaneous</li> <li>Any ACBM with potential for damage</li> <li>Any ACBM with potential for significant damage</li> <li>Any friable ACBM</li> </ol> Type of Damage: Greater/Less than 10% Distributed///Greater/Less than 25% localized Explanation:
<b>Cause of Damage: Wear and Tear Mechanical Weather Water Other</b> Explanation:
Accessibility: Always Periodic Rare Explanation:
Potential for Disturbance: Potential for significant damage Potential for damage Low Vibration Air Erosion Weather Normal O&M
Preventative Damage Measures Explanation:
Date of AHERA Assessment: DECEMBER 27, 2005 Inspector Name: Kenneth Medici Signature: Phone: 1-888-999-7908

Inspector Accreditation Information: CAC #92-0007

Appendix I	H:
Phase I Environmental Site Assessment	ΝT

# Phase I and Phase II Environmental Site Assessment

Buckley School 3900 Stansbury Avenue Sherman Oaks, California

> Prepared for: Latham and Watkins LLP

> > Prepared by:

Rincon Consultants, Inc. March 25, 2005

Environmental Scientists Planners Engineer



Rincon Consultants, Inc.

790 East Santa Clara Street Ventura, California 93001

8056411000 FAX6411072

info@rinconconsultants.com www.rinconconsultants.com

March 25, 2005 Project Numbers 04-17840 and 04-17841

Maria Hoye Latham & Watkins LLP 633 West Fifth Street, Suite 4000 Los Angeles, California 90071

### Phase I and Phase II Environmental Site Assessment Buckley School 3900 Stansbury Avenue Sherman Oaks, California

Dear Ms. Hoye:

This report presents the findings of a Phase I and Phase II Environmental Site Assessment (ESA) completed by Rincon Consultants, Inc. (Rincon) for the Buckley School, located at 3900 Stansbury Avenue, Sherman Oaks.. The assessment was performed in accordance with our proposals and contracts dated November 3, 2004 and December 20, 2004.

If you have any questions or if we can be of any future assistance, please contact us.

Sincerely, RINCON CONSULTANTS, INC.

Vocia Cluse

Tricia Ainsworth, REA I Associate, Environmental Engineer

Walter Hamann RG, CEG, REA II Vice President, Environmental Services



## **EXECUTIVE SUMMARY**

This report presents the findings of a Phase I and Phase II Environmental Site Assessment (ESA) for an irregular shaped, approximately 18-acre property located at 3900 Stansbury Avenue in Sherman Oaks, California (Figure 1, Vicinity Map). The site is currently developed with educational and recreational facilities comprising approximately 16 structures. The site was previously used as a golf course and country club.

The current educational and recreational facilities include a two-story administration building, two-story library, two-story gym and performing arts building (including two basement levels with a swimming pool on the lowest level), a two-story art and science building, several single-story classroom structures, a one-story athletic field house, two-story maintenance building, several paved parking lots, a baseball field, a basketball court, and tennis courts. Several storage sheds, used for storing electrical, mechanical, and janitorial supplies, paints, groundskeeping equipment, fertilizer and earthquake supplies are located south of the baseball field. The storage sheds are used to store small quantities of the following hazardous substances: gasoline tiesel fuel, paint, spray paint, adhesives, coatings, stains, seals, compressed gases, and fertilize. Two 55-gallon drums of waste oil and two 30-gallon drums of waste paint are stored on second. / containment pallets outside the paint shed. Small quantities of various chemicals, glazes and stains are stored in the science and art classrooms. Chlorine and other pool chemicals are stored in the swimming pool maintenance area. The print shop contains small quantities of printing chemicals. Slight staining was observed on the wood floor beneath a small diesel can in the groundskeeping shed.

A bus maintenance garage was formerly located in the vicinity of the current print shop. An underground storage tank (UST) was formerly located in the trash compactor/parking lot area southwest of the science building. According to Curtis Covington, Director of Facilities, the UST was removed in the 1980s. Mr. Covington also indicated that the hydraulic lift in the former bus maintenance garage was removed, a clarifier was abandoned in place, and there is the potential that a UST is still located outside the former garage.

The project site is located in an area that is primarily comprend of residential land uses and open space. Surrounding properties in the vicinity of the site include single-family homes and undeveloped land preserved by the Santa Monica Mountains Conservancy.

Review of an environmental database records search (EDR) indicated that a release from a UST had occurred on the site. Files maintained by Los Angeles City Fire Department (LAFD) and Los Angeles Regional Water Quality Control Board (RWQCB) indicate that a 10,000-gallon gasoline UST was removed from the subject property in 1988, after a leak was detected. Soil and groundwater were reportedly impacted with total petroleum hydrocarbons (TPH), based on soil and soil gas samples collected from the base of the excavation pit and surrounding areas and gasoline observed in the groundwater in the downgradient swimming pool sump pump. According to an Engineering Report on Soil Gas Investigation, prepared by Enviropro Inc., TPH was detected at a concentration of 46,600 milligrams per kilogram (mg/kg) in a soil sample collected from UST excavation pit. The LAFD and RWQCB files did not have any information regarding any soil or groundwater remediation at the site. Additionally, there is no indication

that the soil samples were analyzed for methyl tertiary butyl ether (MTBE). The RWQCB granted case closure for the UST release and removal in 1996.

Historical sources reviewed as part of the Phase I include aerial photographs (1928, 1940, 1952, 1960, 1971, 1982, and 1994) and topographic maps (1898, 1902, 1913, 1921, 1926, 1932, 1953, 1966, and 1972). The photos and maps reviewed indicate the site was undeveloped from 1898 through 1921, developed with a few structures between 1926 and 1932, developed with a golf course and country club in 1940, developed with a few structures from 1952 through 1966, and developed as a school from 1971 through 1994.

Based on the findings of the Phase I ESA, two recognized environmental conditions were identified for the project site: the former presence of a UST and associated gasoline release on the project site, and the former presence of a bus maintenance garage on the project site.

To evaluate the potential site impact associated with the recognized environmental conditions identified in this Phase I ESA, a Phase II ESA was conducted at the site. The Phase II included the completion of a geophysical survey to investigate the potential presence of a UST at the former bus maintenance garage, the collection of subsurface soil samples from ten boring locations in the vicinity of the former UST, clarifier, and hydraulic hoist, and the collection of groundwater from the pool sump pump. Select soil samples were analyzed for the presence of total petroleum hydrocarbons (TPH), volatile organic compounds (VOCs), lead, metals, and polychlorinated biphenyls (PCBs). The groundwater sample from the sump pump was analyzed for hydrocarbons and VOCs. The Phase II geophysical survey was conducted on December 21, 2004. The results of the geophysical survey indicate that a small UST remains in the vicinity of the observed tank vent and covered tank fill access. Based on the dimensions of the detected anomaly, the tank is believed to be a waste oil tank. The Phase II soil sampling was conducted on December 27 and 30, 2004 (Figure 4, Soil Sampling Location Map). The results of laboratory analyses of these samples are presented in Tables 3 through 5.

The laboratory data indicate that TPH – gasoline (TPH-g), VOCs, oxygenates and metals were detected in the soil samples. None of the soil samples tested for TPH-diesel range organics (DRO), TPH-oil range organics (ORO), and PCBs had detectable levels of these constituents. Metals were detected at varying concentrations in the soil samples collected and analyzed for metals. A maximum concentration of 1,080 mg/kg TPH-g was detected in B1 at 25 feet below grade. Maximum concentrations of 8.4 mg/kg benzene, 31 mg/kg toluene, 13.7 mg/kg ethylbenzene and 104.2 mg/kg total xylenes were detected in B1 at 25 feet below grade. A maximum concentration of 0.798 mg/kg tert-butyl alcohol (TBA) was detected in B1 at 20 feet below grade and a maximum concentration of 6.95 mg/kg MTBE was detected in B4 at 20 feet below grade. A maximum concentration of 0.12 mg/kg acetone and 0.27 mg/kg tetrachloroethylene (PCE) was detected in B6 at a depth of 5 feet below grade. Various metal compounds were detected in B1 through B3, B5 through B7, B9 and B10.

To evaluate the significance of the reported hydrocarbon and VOC levels in the soil samples, we compared these levels to threshold levels established by RWQCB. TPH-g and benzene were detected at concentrations exceeding the RWQCB maximum soil screening levels (SSLs) in sample B1 at 25 feet below grade. BTEX and MTBE were detected in soil samples collected at various depths in borings B1, B3, and B4 at concentrations that could potentially exceed the

#### Phase I and II Environmental Site Assessment Buckley School, 3900 Stansbury Avenue, Sherman Oaks, California

RWQCB SSLs. Without actual depth to groundwater data for these locations, exact SSLs cannot be calculated to determine whether these thresholds have been exceeded. TBA was detected in several samples in the former UST area. The SSL for TBA could not be determined as there is no Maximum Contaminant Level (MCL) for this constituent. Low concentrations of PCE and acetone were detected near the waste oil tank in soil samples B5 and B6 at 5 feet below grade. However, based on the shallow depth of the detected PCE, it is not likely that the PCE SSL would be exceeded for this location. The acetone SSL could not be determined as there is no MCL for this constituent.

The metals concentrations were compared to the United States Environmental Protection Agency (USEPA) soil cleanup thresholds and the State of California Department of Toxic Substances Control (DTSC) hazardous waste thresholds. The metal concentrations detected in the soil samples tested for these constituents did not exceed total threshold limit concentration (TTLC) levels or ten times soluble threshold limit concentration (STLC) levels. Therefore, if soil were to be excavated from this location, the metals content in the resulting soil would be considered non-hazardous for disposal purposes. With the exception of arsenic, metals were well below their respective PRGs. Although the levels of arsenic detected in the soil samples analyzed during this assessment exceed the arsenic PRGs, they were within the published ranges for arsenic in soils in the Western United States (Shacklette, H.T. and Boerngen, J.G., 1984) and appear to be within normal background levels. As discussed in the Shacklette and Boerngen report, the range of arsenic observed in background soil in the Western United States was between 0.10 mg/kg and 97 mg/kg. Overall, the levels of metals detected in the soil samples were low and likely represent naturally occurring background concentrations of metals in soil.

## PHASE I ENVIRONMENTAL SITE ASSESSMENT

### INTRODUCTION

This report presents the findings of a Phase I ESA conducted for the property located at 3900 Stansbury Avenue, Sherman Oaks, California, APN 2274-027-003. The Phase I ESA was performed by Rincon Consultants, Inc. (Rincon) for Latham & Watkins LLP in general conformance with ASTM E 1527-00 and our proposal and contract dated November 3, 2004. The following sections present our findings and provide our opinion as to the potential presence and impact of environmental site conditions.

### PURPOSE

The purpose of this Phase I ESA was to identify the possible presence of recognized environmental conditions (RECs) associated with possible soil and groundwater contamination at the site.

A REC is defined pursuant to ASTM E 1527-00 as the presence or likely presence of any hazardous substances or petroleum products on a property under conditions that indicate an existing release, a past release, or a material threat of a release of any hazardous substances or petroleum products into structures on the property or into the ground, groundwater, or surface water of the property. The term includes hazardous substances or petroleum products even under

conditions in compliance with laws. The term is not intended to include de minimis conditions that generally do not present a material risk of harm to public health or the environment and that generally would not be the subject of an enforcement action if brought to the attention of appropriate governmental agencies.

### SCOPE OF SERVICES

The scope of services conducted for this study is outlined below:

- Perform an on-site reconnaissance to identify obvious indicators of the existence of hazardous materials.
- Observe adjacent or nearby properties from public thoroughfares in an attempt to see if such properties are likely to use, store, generate, or dispose of hazardous materials.
- Obtain and review an environmental records database search from Environmental Data Resources (EDR), Inc. to obtain information about the potential for hazardous materials to exist at the site or at properties located in the vicinity of the site.
- Review files for the subject site as identified in the EDR report.
- Review the current U.S. Geological Survey (USGS) topographic map to obtain information about the site's topography and uses of the site and properties in the vicinity of the site.
- Review historic aerial photographs and topographic maps to obtain information about historic uses of the subject property and adjacent properties.
- Review California Division of Oil and Gas records to obtain information about historic oil and gas activity in the vicinity of the site.
- Provide an interview questionnaire to the designated site representative identified to Rincon by Latham & Watkins LLP.
- Conduct a site interview with the designated representative.

Our scope of services, pursuant to ASTM E 1527 practice, did not include any inquiries with respect to asbestos, lead-based paint, lead in drinking water, wetlands, regulatory compliance, cultural and historic resources, industrial hygiene, health and safety, ecological resources, endangered species, indoor air quality, or high voltage power lines.

### LIMITATIONS, ASSUMPTIONS AND USER RELIANCE

This Phase I ESA was prepared for use solely and exclusively by Latham & Watkins LLP and the Buckley School. This report shall not be relied upon by or transferred to any other party without the express written authorization of Rincon Consultants.

Latham & Watkins LLP has requested this assessment and will use the assessment for the purposes of a facilities modernization project. No other use or disclosure is intended or authorized by Rincon. Also, this report is issued with the understanding that it is to be used only in its entirety. It is intended for use only by the client, and no other person or entity may rely upon the report without the express written consent of Rincon.

This work has been performed in accordance with good commercial, customary, and generally accepted environmental investigation practices for similar investigations conducted at this time and in this geographic area. No other guarantee or warranties, expressed or implied are provided.

The findings and opinions conveyed in this report are based on findings derived from a site reconnaissance, review of an environmental database report, specified regulatory records and historical sources, and comments made by interviewees. This report is not intended as a comprehensive site characterization and should not be construed as such. Standard data sources relied upon during the completion of Phase I ESAs may vary with regard to accuracy and completeness. Although Rincon believes the data sources are reasonably reliable, Rincon cannot and does not guarantee the authenticity or reliability of the data sources it has used. Additionally, pursuant to our contract, the data sources reviewed included only those that are practically reviewable without the need for extraordinary analysis.

Rincon has identified evidence that suggests that petroleum products exist at the site at levels that could require mitigation. In accordance with our authorized work scope and contract and the general provisions of ASTM E1527-00, no attempt was made to check for the presence of asbestos, lead-based paint, lead in drinking water, wetlands, regulatory compliance, cultural and historic resources, industrial hygiene, health and safety, ecological resources, endangered species, indoor air quality, or high voltage power lines.

## SITE DESCRIPTION

### LOCATION AND LEGAL DESCRIPTION

The site is an approximately 18-acre property located at 3900 Stansbury Avenue, Sherman Oaks, California (Figure 2, Site and Adjacent Land Use Map). The site is located at the south end of Stansbury Avenue, adjacent to the east of Camino De La Cumbre. The property is identified as APN 2274-027-003.

### SITE AND VICINITY GENERAL CHARACTERISTICS

The site is located in an area that is comprised of residential land uses and open space. Properties north and west of the site include single-family homes. Properties east and south are generally open space.

### CURRENT USES OF THE PROPERTY

The site is currently developed with the Buckley School, a private school (elementary through high school).

# DESCRIPTIONS OF STRUCTURES, ROADS AND OTHER IMPROVEMENTS ON THE SITE

The Buckley School campus is currently developed with approximately 16 structures, including a two-story administration building, two-story library, two-story gym and performing arts building (Pavilion), a two-story art and science building, and several single-story classroom structures. A large paved parking lot is located on the northern end of the property, near the entrance gate. Smaller paved parking areas are located throughout campus. A baseball field is located on the southern end of the property. A basketball court is located along the southeast boundary of the property, adjacent to the baseball field. Several storage sheds, used for storing electrical, mechanical, and janitorial supplies, paints, groundskeeping equipment, fertilizer and earthquake supplies are located adjacent to the south of the baseball field. According to Curtis Covington, Director of Facilities, most facility structures are about 35 years old, with the exception of the gymnasium (pavilion), which is about 32 years old.

Access to the site is available through a guard kiosk entrance located at the southern end of Stansbury Avenue. Water service is provided by Los Angeles Department of Water and Power (LADWP) and sewer service is provided by City of Los Angeles. Los Angeles Department of Water and Power (LADWP) provides electrical service and the Southern California Gas Company provides natural gas service. Solid waste collection and disposal services are provided by Crown Disposal.

### CURRENT USES OF THE ADJACENT PROPERTIES

Current adjacent land uses are described in Table 1 and depicted on Figure 2, Site and Adjacent Land Use Map.

Area	Use
Northern Property	residential
Eastern Property	open space (Santa Monica Mountains Conservancy)
Western Property	Camino de la Cumbre/then residential
Southern Property	open space (Santa Monica Mountains Conservancy)

**Table 1 - Current Uses of Adjacent Properties** 

### **USER PROVIDED INFORMATION**

### TITLE RECORDS

Latham & Watkins LLP and the Buckley School did not provide Rincon with a copy of title records for the subject site.

### ENVIRONMENTAL LIENS OR ACTIVITY AND USE LIMITATIONS

Latham & Watkins LLP and the Buckley School did not provide Rincon with any information pertaining to environmental liens or activity and use limitations for the subject site.

### SPECIALIZED KNOWLEDGE

Latham & Watkins LLP and the Buckley School did not provide Rincon with any specialized knowledge that would be material to recognized environmental conditions in connection with the property.

### VALUATION REDUCTION FOR ENVIRONMENTAL ISSUES

Latham & Watkins LLP and the Buckley School did not provide Rincon with any information pertaining to a valuation reduction for the subject site relative to any known environmental issues.

### **OWNER, PROPERTY MANAGER, AND OCCUPANT INFORMATION**

The school Director of Facilities was interviewed regarding the current and former uses of the site. The information obtained from this interview is described in the Site Reconnaissance and Interviews section of this report.

## **RECORDS REVIEW**

### PHYSICAL SETTING SOURCES

### Topography

The current USGS topographic map (Van Nuys Quadrangle, 1966, photorevised 1972) indicates that the site is situated at an elevation ranging from about 800 to 900 feet above mean sea level with topography sloping generally to the west-northwest on the eastern portion of the site and to the east-southeast on the western portion of the site.

### Geology and Hydrogeology

### <u>Geology</u>

The project area is near the southern boundary of the San Fernando Valley alluvial basin. The sediments in this area are erosional remnants of the sedimentary rocks found along the southern boundary of the Santa Monica Mountains. These sedimentary rocks consist of claystones and siltstones. Erosion of these sediments generally results in fine-grained alluvial deposits.

According to the Geologic Map of the Beverly Hills and Van Nuys (South 1/2) Quadrangles (Dibblee, 1991), the site is underlain by Quaternary-age alluvium and Miocene-age unnamed shale and Monterey Formation. The alluvium is comprised of unconsolidated deposits of gravel,

sand and silt-clay, derived mostly from Santa Monica Mountains and including gravel and sand from stream channels. The unnamed shale is comprised of soft, white-weathering diatomaceous shale to diatomite. The Monterey Formation is comprised of white-weathering, thin bedded, moderately hard, dark siliceous shale and tan to light gray semi-friable bedded sandstone.

The GeoCheck summary report provided in the attached EDR report (Appendix 1, page A-4) indicates that the site is underlain by Tertiary age stratified sequence. The USDA soil survey for the general area of the property indicates that the soil types present in the site vicinity are primarily gravelly loam.

### <u>Hydrogeology</u>

The site is located in the southern portion of the Los Angeles River Watershed. In the San Fernando Valley area, groundwater depths range from near land surface to 100 feet below ground surface. According to the October 1988 Engineering Report on Soil Gas Investigation prepared by Enviropro Inc., groundwater is reportedly at about 35 feet below grade at the Pavilion building (gym), where the sump pump is used to protect the structural integrity of the swimming pool. Based on the Enviropro report, the ground surface drops in elevation by about 40 feet from the former UST area/trash compactor/parking lot to the Pavilion building. Therefore, the estimated depth to groundwater beneath the former UST area is between 60 and 90 feet below grade. As the subject site has a wide range of hillside elevations, the groundwater depths will vary beneath the site. Groundwater flow direction has not been established for this site. However, based on the assumption that the groundwater flow directions near the subject site would be to the west-northwest on the eastern portion of the site and to the east-southeast on the western portion of the site.

### STANDARD ENVIRONMENTAL RECORDS SOURCES

Environmental Data Resources, Inc. (EDR) was contracted to provide a database search of public lists of sites that generate, store, treat or dispose of hazardous materials or sites for which a release or incident has occurred. The EDR search was conducted for the subject site and included data from surrounding sites within a specified radius of the property. A copy of the EDR report, which specifies the ASTM search distance for each public list, is included as Appendix 1. As shown on the attached EDR report, Federal, State and County lists were reviewed as part of the research effort. The subject site was listed as a RCRIS-SQG, FINDS, HAZNET, CA FID UST, LUST, Cortese and ERNS site in the EDR database.

Sites that were identified within a one-mile radius of the subject site are listed in Table 2, EDR Listing Summary of Sites Within One Mile of the Subject Property (see Appendix 1 for a complete listing of sites reported by EDR) and include sites that appear in the following databases:

**FINDS**: Facility Index System. Contains both facility information and pointers to other sources that contain more detail.

**LUST**: LUST records contain an inventory of reported leaking underground storage tank incidents. This database is maintained by the State Water Resources Control Board.

**RCRIS-(TSD, LQG, SQG)**: Resource Conservation and Recovery Information System. The RCRIS database includes selected information on sites that generate, store, treat, or dispose of hazardous waste as defined by the Resource Conservation and Recovery Act. TSD refers to transfer, storage or disposal facility. LQG refers to large quantity generator. SQG refers to small quantity generator. The source of this database is the U.S. EPA.

**CORTESE**: Identified Hazardous Waste and Substance Sites. This database (from the CAL EPA/Office of Emergency Information) identifies public drinking water wells with detectable levels of contamination, hazardous substance sites selected for remedial action, sites with known toxic material identified through the abandoned site assessment program, sites with USTs having a reportable release and all solid waste disposal facilities from which there is known migration.

**Ca. FID**: California Facilities Inventory Database contains active and inactive underground storage tank locations as provided by the California State Water Resources Control Board.

**HistUST**: The Hazardous Substance Storage Container Database is a historical listing of UST sites. This database is maintained by the State Water Resources Control Board.

**ERNS**: Emergency Response Notification System. This database records and stores information on reported releases of oil and hazardous substances.

**NOTIFY 65**: Proposition 65 notification reports. Notify 65 contains facility notifications about any release which could impact drinking water and thereby expose the public to a potential health risk (information is provided by the State Water Resources Control Board).

**HAZNET**: Hazardous Waste Information System. Data that is extracted from the copies of hazardous waste manifests received each year by the DTSC (information is provided by the Department of Toxic Substances Control).

Site Name	Site Address	Distance from Subject Site (miles)	Database Reference
Buckley School Bus Garage / Buckley School	3900 Stansbury Ave.	Subject Site	RCRIS-SQG, FINDS, HAZNET, CA FID UST, LUST, Cortese, ERNS
Service Station	14478 Ventura Blvd.	1/2 – 1 mile	Notify 65, HAZNET, LUST, Cortese, CA FID UST, HIST UST

# Table 2 - EDR Listing Summary of SitesWithin One Mile of the Subject Site

The RCRIS-SQG listing for the subject site indicates that small quantities (more than 100 and less than 1,000 kilograms per calendar month) of unspecified solvent mixture waste, unspecified organic liquid mixture, oil/water separation sludge, organic liquids (nonsolvents) with halogens. laboratory waste chemicals, asbestos containing waste and aqueous waste with less than 10%

total organic residues are generated onsite. There is no indication of any unauthorized release regarding the wastes generated by the subject site. The LUST and Cortese listings for the subject site indicate that there was a gasoline release due to leaking piping in 1988. The EDR indicates the release was to soil only, the site was not tested for MTBE and the case was closed in 1996.

### **REVIEW OF AGENCY FILES**

As a follow-up to the database search and the site reconnaissance, we filed a request with Los Angeles City Fire Department (LAFD) and Los Angeles Regional Water Quality Control Board (RWQCB) to review documents and obtain copies of documents pertaining to the subject site. Rincon reviewed UST files at LAFD and RWQCB for the subject site on December 2, 2004.

### **Review of LAFD Files**

According to an LAFD Fire/Life Safety Violation notice, dated May 27, 1988, Buckley School was directed to remove product from the leaking UST, monitor the groundwater sump (located beneath the swimming pool, downgradient of the UST area) for flammable vapors, provide an integrity test of the UST, and provide the LAFD with a report of analysis from soil borings to determine whether or not an unauthorized release has occurred.

According to a June 2, 1988 LAFD Fire/Life Safety Violation notice, Buckley School was required to provide a site assessment including the extent of contamination, location of groundwater, groundwater flow direction and cleanup recommendations.

According to an Engineering Report on Soil Gas Investigation, prepared by Enviropro Inc. on October 31, 1988, one 10,000-gallon gasoline tank was removed in July of 1988. During the excavation of the tank, two soil samples were collected and analyzed for total petroleum hydrocarbons (TPH) during the tank removal (July 1998). TPH was detected at a concentration of 46,600 mg/kg in the soil sample collected from the north end of the excavation (Sample #1). Hydrocarbon contamination was observed in the groundwater being pumped from a sump near the swimming pool located on the basement floor of the Pavilion building. A preliminary soil gas investigation was conducted by Enviropro Inc. on August 11, 1988 using a photoionization detector (PID). A total of 29 boreholes were drilled to depths from 1 to 1.5 feet below grade. The boreholes were covered with a plastic film and vapors were allowed to collect in the borehole. PID readings were collected from the boreholes by penetrating the plastic film with the PID sampling probe. The report states that the results of the soil gas investigation are only qualitative, because no direct measurement of soil or groundwater contamination has been provided. The report proposes that a subsequent detailed remedial investigation be conducted. including the installation of three groundwater monitoring wells. PID readings collected from various locations near the tank excavation area and the Pavilion area, downgradient of the former tank area, indicate the highest volatile organic compound concentration was detected near the tank excavation to the east. A copy of the soil gas investigation report is included in Appendix 2.

An LAFD letter, dated April 12, 1989, states that groundwater beneath the site has been impacted and the case has been referred to the State Regional Water Quality Control Board (SRWQCB).

### **Review of RWQCB Files**

A May 27, 1988 State of California Hazardous Substance Spill Report indicates that the LAFD notified the state of the gasoline UST release. The spill report indicates that the UST leaked an unknown quantity of gasoline into the swimming pool and school grounds sump pump, causing fuel to be pumped into a drainage ditch, which flows to the Los Angeles River.

According to a June 2, 1988 Underground Storage Tank Unauthorized Release (Leak) / Contamination Site Report, an unknown quantity of gasoline was released from the UST. The leak was discovered on May 27, 1988 during a tank test. The discharge was reportedly stopped by removal of tank contents. A piping leak was the determined source of discharge of the 10,000-gallon, 16 year-old steel tank.

A RWQCB case closure letter, dated July 22, 1996, indicates site closure was granted and no further action was required related to the UST release. Copies of the RWQCB files are included in Appendix 2.

### ADDITIONAL ENVIRONMENTAL RECORDS SOURCES

### State of California Division of Oil and Gas Records

A review of the Division of Oil and Gas Munger Map Book (2001) indicates that no oil or gas wells are or have been located on or within at least two miles of the subject site.

### HISTORICAL USE INFORMATION

### **Review of Historic Aerial Photographs**

Copies of aerial photographs were obtained from UCSB Map and Imagery Department's aerial photograph collection and reviewed. Copies of the aerial photographs are included in Appendix 3 (Historical Documents).

- **1928, Fairchild (Scale:** 1" = 600') The subject site appears to have graded areas and structures or foundations surrounded by undeveloped property. Camino De La Cumbre is depicted as a dirt road adjacent to the west. Beverly Glen Boulevard and Mulholland Highway are depicted to the south. The adjacent properties are depicted as undeveloped. Several surrounding properties are depicted as residential.
- 1940, Fairchild (Scale: 1" = 600") –The subject site appears to be developed as a country club and golf course. The adjacent property to the north, wrapping around to the east and then south, is depicted as the remainder of the golf course. With the exception of the golf course, the adjacent properties are depicted similar to the 1928 photograph. Substantial residential development is depicted in the surrounding properties to the north.

- 1952, ASCS-USDA (Scale: 1" = 600') The subject site appears to be graded and under development, with several smaller structures or trailers onsite. The former adjacent golf course property to the north (wrapping around to the east and south) now appears to be depicted as residential. Additional residential development is depicted in surrounding properties to the north and south.
- **1960, Fairchild (Scale: 1" = 600')** The subject site and adjacent properties are depicted similar to the 1952 photograph. Additional residential development is depicted in surrounding properties in all directions.
- 1971, Teledyne (Scale: 1" = 600') The subject site appears to be developed with three large classroom buildings, paved parking lots, and graded areas under development. Adjacent properties are depicted similar to the 1960 photograph. Additional residential development is depicted in surrounding properties in all directions.
- 1982, Aerial Map Industries (Scale: 1'' = 600') The subject site appears to be developed with approximately thirteen educational facility structures and a sports field and track. Adjacent and surrounding properties are depicted similar to the 1971 photograph.
- **1994, USGS (Scale:** 1" = 600') The subject site and adjacent properties are depicted similar to the 1982 photograph. A large residential development is depicted on a nearby property to the east.

### **Review of Historic Topographic Maps**

Historic topographic maps from the UCSB Map and Imagery Department map collection were reviewed. Copies of the historic topographic maps are included in Appendix 3 (Historical Documents). Following is a summary of our review of these maps.

- **1898 Santa Monica Quadrangle Map** The map depicts the subject site and adjacent properties as being undeveloped. A road (currently Ventura Boulevard) and the Los Angeles River appear to the north of the subject property. The Southern Pacific Railroad is depicted further to the north.
- *1902 Santa Monica Quadrangle Map* The subject site and adjacent properties are depicted similar to the 1898 map.
- 1902, reprinted 1913, Santa Monica Quadrangle Map The subject site and adjacent properties are depicted similar to the 1902 map.
- **1921 Santa Monica Quadrangle Map** The subject site and adjacent properties are depicted similar to the 1913 map.
- **1926** Van Nuys Quadrangle Map The subject site is depicted as being developed with one structure. A road (currently Stansbury Avenue) is depicted on the subject property, connecting to Mulholland Highway further south.

- 1926, reprinted 1932, Van Nuys Quadrangle Map The subject site and adjacent properties are depicted similar to the 1926 map.
- **1953** Van Nuys Quadrangle Map The subject site is depicted as being developed with two structures. A road (currently Camino De La Cumbre) is depicted adjacent to the west.
- **1966** Van Nuys Quadrangle Map The subject site and adjacent properties are depicted similar to the 1953 map. Highway 101 (Ventura Freeway) is depicted north of Ventura Boulevard.
- 1966, photorevised 1972, Van Nuys Quadrangle Map The subject site is depicted as Buckley School, with several structures shown.

### SITE RECONNAISSANCE AND INTERVIEWS

Rincon Consultants performed a reconnaissance of the site on November 22, 2004 accompanied by Curtis Covington, Director of Facilities with the Buckley School. The purpose of the reconnaissance was to observe existing site conditions and to identify obvious indicators of hazardous materials that could affect the subject site. An interview questionnaire was provided to Mr. Covington prior to the site reconnaissance. A copy of the completed questionnaire is included in Appendix 4.

The following information is based on observations noted or information obtained during the November 22, 2004 site reconnaissance and our review of the completed questionnaire.

### HISTORICAL USE INFORMATION

Mr. Covington indicated that the on-site structures are about 35 years old, with the exception of the gymnasium (Pavilion), which is about 32 years old. The Buckley School reportedly obtained ownership of the site in 1968. He did not know who owned or leased the site property prior to the Buckley School. However, Mr. Covington indicated that the subject property was previously used as a golf course and country club.

Mr. Covington indicated a UST was formerly located onsite, in the trash compactor/parking lot area southwest of the science building. He indicated the tank had been removed in the 1980s, however, he was not aware of the details of any unauthorized releases associated with the tank. Mr. Covington indicated that the print shop was formerly a bus maintenance garage, with an abandoned three-stage clarifier, former hydraulic lift, and possible underground storage tank. The three-stage clarifier located in the former bus garage was pumped out, abandoned and filled with sand less than 2 years ago. The hydraulic lift was removed more than 5 years ago. A possible tank vent and tank fill access observed near the bus garage indicate the possible current presence of an underground storage tank in the former bus garage vicinity. Mr. Covington was not aware of any hazardous materials releases or other environmental liabilities associated with the site or surrounding properties.

### **CURRENT USES OF THE PROPERTY**

Mr. Covington indicated that the current operation on the site involves uses that are typical of an educational facility and includes operation and maintenance of buildings, surrounding landscape, tennis courts, basketball court, baseball fields and swimming pool. Maintenance and storage sheds/containers located on the subject site are used to store electrical, mechanical, and janitorial supplies, paints, groundskeeping equipment, fertilizer and earthquake supplies. Site photographs are provided as Figure 3.

### STORAGE TANKS

During the site reconnaissance, Rincon did not observe above-ground tanks. A possible underground tank vent and covered tank fill access were observed near the print shop (former bus garage). Mr. Covington had no knowledge of the status of this possible tank. Mr. Covington indicated on his questionnaire, Appendix 4, that former underground storage tank has been removed.

### HAZARDOUS SUBSTANCES AND PETROLEUM PRODUCTS IN CONNECTION WITH IDENTIFIED USES

- The art classroom contains small quantities of lead-free glazes (i.e., iron oxide and copper carbonate) and stains in the supply cabinet.
- The chemistry supply room contains a 1-gallon container of kerosene, a 16-ounce container of linseed oil, and several small containers of various laboratory chemicals (i.e., phosphorous pentoxide, sodium dithionite, sodium peroxide, acids, and nitrates).
- The pool maintenance area contains various pool chemicals including muriatic acid, Alkalinity Up, a 55-gallon plastic drum of chlorine in secondary containment and a small quantity of boxes of liquid chlorine.
- The print shop contains two 3-gallon containers of blanket wash, one 3-gallon container of Rubber Rejuvenator, one 5-gallon hazardous waste container serviced by Safety Kleen, and small quantities of WD40, spray adhesive, and other print products.
- The athletic office and associated storage shed contain small quantities of rubbing alcohol, hydrogen peroxide, disinfectant, cleaning products, and chlorine for the whirlpool.
- The electrical storage shed contains two 5-gallon containers of gasoline for the two generators stored in the shed.
- The paint storage shed contains approximately fifty 1-gallon cans of paint, fifteen 5-gallon buckets of paint, and small quantities of adhesive and coating.
- Outside of the paint shed, two 55-gallon waste oil drums and two 30-gallon waste paint drums are stored on secondary containment pallets. No staining was observed in the waste drum area.
- The air compressor shed contains compressed acetylene and oxygen tanks and torches, and an air compressor. About thirty 12 and 15-ounce cans of spray paint, ten 1-quart containers of stains and seals, and one gallon of contact cement are stored in a flammables cabinet.

- The parts shed stores small containers of WD40, liquid nails, caulk, spackling paste, primer, and PVC pipe cement.
- The groundskeeping shed contains one 30-gallon diesel drum, two 5-gallon and two 3-gallon containers of gasoline, two 2.5-gallon containers of diesel. Slight staining was observed on the wood floor beneath on the small diesel containers, however, the shed sits atop a concrete pad.
- The fertilizer shed contains about forty 50-pound bags of Nitrex (nitrate and iron mixture).
- The field maintenance shed contains about ten 5-gallon buckets of athletic field striping paint.

### UNIDENTIFIED HAZARDOUS SUBSTANCE AND PETROLEUM PRODUCT CONTAINERS

Unidentified hazardous substance containers or unidentified containers that might contain hazardous substances were not observed during the site reconnaissance. The possible tank vent and covered fill access were the only visible components of the possible petroleum product tank near the bus garage. Therefore, Rincon could not observe indications of potential releases from the possible tank.

Rincon observed two 55-gallon waste oil drums stored on secondary containment pallets outside paint shed, one 30-gallon diesel drum in the groundskeeping shed, and several small containers storing gasoline and diesel in storage sheds. Slight staining was observed on the wood floor beneath the small diesel containers, however, the shed sits atop a concrete pad.

### INDICATIONS OF POLYCHLORINATED BIPHENYLS (PCBs)

Curtis Covington, the Director of Facilities, indicated that there are 13 transformers onsite. During the site reconnaissance, Rincon observed several of the transformers located inside and outside campus buildings. There was no indication of a release in the vicinity of the transformers observed. With the exception of the main high voltage transformer, the onsite transformers are owned by the Buckley School and are maintained as necessary by private contractors. The main transformer on campus is owned and maintained by LADWP.

The hydraulic equipment for one elevator and one dumb waiter were identified during the site reconnaissance. These hydraulic systems are maintained under a private service contract. The elevator equipment is located in the basement of the administration building and the dumbwaiter equipment is located on the bottom floor of the library. An oil leak was observed beneath the hydraulic equipment for the elevator. However, the concrete floor appeared to be in good condition (i.e., no apparent cracking) in the vicinity of the oil leak. No indications of recent spills or leaks were observed beneath the library's dumbwaiter equipment.

### **OTHER CONDITIONS OF CONCERN**

During the site reconnaissance, Rincon did not observe or note any of the following possible indicators of a hazardous materials release:

- stressed vegetation
- solid waste/debris
- odors

However, during the site reconnaissance, Rincon observed the following possible indicators of a hazardous materials release or the presence of the following indicators of such a release: small pool of liquid beneath the elevator equipment and slight staining of wood floor in the groundskeeping shed.

A small pool of oil was observed beneath the hydraulic equipment for the elevator in the administrative building. However, the concrete floor did not appear to be cracked in the vicinity of the oil leak.

Slight staining was observed on the wood floor in the groundskeeping shed beneath two small containers of diesel fuel. However, this shed sits atop a concrete pad.

### FINDINGS OF PHASE I ESA

Known or suspect environmental conditions associated with the property include the following:

- Former presence of UST and associated gasoline release on the subject site.
- Former presence of an onsite bus maintenance garage, with a former hydraulic lift, abandoned clarifier, and possible underground storage tank.
- Former use of subject site as golf course.
- Slight staining of wood floor in the groundskeeping shed on the subject site.
- Presence of leaking elevator equipment on the subject site.

### **OPINIONS AND CONCLUSIONS OF PHASE I ESA**

It is our opinion that the former UST and associated gasoline release is a recognized environmental condition (REC). Although the UST was removed and site closure was granted by the RWQCB, TPH was detected in the soil at the base of the excavation and files reviewed at the LAFD and RWQCB do not indicate that any soil remediation was conducted. Contaminated groundwater was reportedly observed in the nearby sump for the swimming pool and case closure was granted before a groundwater assessment was conducted. Additionally, there is no indication that the soil samples were analyzed for MTBE.

It is our opinion that the former presence of a bus maintenance garage is a REC because of the potential for soil or groundwater to be impacted with hydrocarbons, solvents, and other chemicals in the vicinity of the former hydraulic lift, abandoned clarifier, or possible underground storage tank.

It is our opinion that the former use of the subject property as a golf course is a de minimis condition. The potential for fertilizers and pesticides to impact the underlying soil or groundwater should be considered low.

Based on the minimal amount of staining of the wood floor in the groundskeeping shed set atop a concrete pad, the potential to impact the underlying soil should be considered low. It is our opinion that the slight staining beneath the small diesel containers is a de minimis condition.

It is our opinion that the small pool of oil beneath elevator equipment is a de minimis condition. As the concrete floor appeared to be in good condition, the potential to impact the underlying soil should be considered low.

Rincon has performed a Phase I ESA in general conformance with the scope and limitations of ASTM Practice E 1527 of 3900 Stansbury Avenue, Sherman Oaks. This assessment has revealed evidence of the following recognized environmental conditions in connection with the property: the former presence of a UST and associated gasoline release on the subject site and the former presence of a bus maintenance garage on the subject site.

### PHASE II ENVIRONMENTAL SITE ASSESSMENT

To evaluate the potential site impact associated with the former UST release and the former presence of a bus maintenance garage, a geophysical survey was conducted in the vicinity of the former garage and a Geoprobe drill rig was used to collect soil samples in the vicinity of the former UST, clarifier, and hydraulic hoist (Figure 4). Select soil samples were analyzed for the presence of hydrocarbons, volatile organic compounds (VOCs, EPA 8260B), oxygenates, and PCBs (see Table 3) and metals (see Table 4). A sample was also collected from the pool sump pump groundwater and analyzed for hydrocarbons and VOCs (see Table 5).

### PHASE II METHODOLOGY

### **GEOPHYSICAL SURVEY**

A geophysical survey was conducted in the vicinity of the former bus maintenance garage on December 21, 2004 by GeoVision Geophysical Services. The purpose of the geophysical survey was to determine if there is a UST present in this area. The survey included investigation in the vicinity of the observed tank vent and covered tank fill access near the former bus garage using a ground-penetrating radar (GPR) instrument. Additionally, GPR profiles were collected at 5-foot intervals in both the north-south and east-west directions in the parking lot area adjacent to the former bus garage. See Appendix 5 for a copy of the documentation provided by GeoVision.

### **GEOPROBE SAMPLING**

A Geoprobe sampling rig was used to collect soil samples from ten locations at the subject site (samples B1 through B10; see Figure 4 for sample locations). The Geoprobes were drilled by Core Probe International, Inc. of Irwindale, California on December 27 and 30, 2005 under the responsible oversight of a California registered geologist.

The probes were advanced by hydraulically driving a two-inch diameter rod equipped with a soil sampling tool. The Geoprobe borings were advanced to depths of between 8 and 30 feet below grade. Where possible, soil samples were collected from each probe at 5-foot intervals. When the target sampling depth was reached, a decontaminated, stainless steel soil sampler was attached to the end of the rod. The soil sampler was comprised of a one-inch diameter tube containing four 6-inch long brass sample liners. By advancing this sampler into the soil, soil was forced into the opening of the sampling tube and a sample was obtained. Once the sampler was filled, it was retrieved and the brass sample liners were removed. The bottom brass liners were retained for laboratory analysis and preserved onsite using EPA method 5035. Soil was collected from the bottom brass liner using a disposable EnCore sampling device. The EnCore soil sample was then placed into 40-milliliter (ml) VOA vials containing either sodium bisulfate preservative or a methanol preservative. The remaining soil from the bottom brass liner was sealed with Teflon, capped, labeled. All samples were stored in a cooler with blue ice pending delivery to the analytical laboratory. A total of 33 soil samples were collected from the Geoprobe borings during this assessment. Soil within the sampling tip and the other liners was used for soil classification and to screen for volatile organics using a photoionization detector (PID). Copies of the soil boring logs are included in Appendix 6.

Upon completion of the sampling program, all probe holes were backfilled with bentonite chips. Sampling equipment was decontaminated between use by washing with a non-phosphate detergent solution followed by a potable water rinse.

### POOL SUMP PUMP GROUNDWATER SAMPLING

On December 27, 2005, a groundwater grab sample was collected from the pool sump pump using a disposable bailer. The groundwater collected was placed in a one-liter glass amber bottle and three 40- ml glass vials. Care was taken to ensure no headspace or bubbles were created within the vials. The groundwater sample containers were sealed, placed on ice, and delivered under chain of custody documentation to a state certified laboratory via courier.

### LABORATORY ANALYSIS

The soil and groundwater samples were transported to American Scientific Laboratories of Los Angeles, California under chain-of-custody documentation. The following analyses were performed:

Sampling Area	TPH- a ¹	TPH-DRO/ TPH-ORO ²	VOCs ¹	BTEX only ¹	Oxygenates ¹	PCBs ³	Lead ⁴	Metals⁵
Former UST	14	7		14	14		5	
Area								
Waste Oil Tank		6	6	····				6
Hoist Area		3			······································	2		3
Clarifier		2	2					······································
Pool Sump	1	1	1			·····		

1 - EPA Method 8260B

2 - EPA Method 8015M

3 - EPA Method 8082

4 - EPA Method 6010B

5 - EPA Method 6010B/7471A

### PHASE II RESULTS

### **GEOPHYSICAL SURVEY**

The results of the geophysical survey conducted on December 21, 2004 indicate that a small UST remains in the vicinity of the observed tank vent and covered tank fill access. GeoVision Geophysical Services marked the outline of the UST with marking paint. However, the entire outline of the tank was not identified due to a large storage pile of school equipment. Based on the identified tank dimensions and the location of the tank vent, the tank dimensions are assumed to be about 10 feet long by 4 feet wide. Therefore, based on the size and location of the identified UST, this was assumed to be a waste oil tank.

A copy of the geophysical survey documentation is included in Appendix 5.

### SOIL SAMPLING

Soil discoloration and elevated PID readings were noted in soil samples collected from B1 at a depth of 20 feet below grade and B3 at depths of 15, 20, and 25 feet below grade. A gasoline odor was noted in soil samples collected from B1 at a depth of 25 feet below grade and B3 at depths of 20, 25, and 30 feet below grade. A sweet chemical odor was noted in soil samples collected from B1, B2, and B4 at 20 feet below grade and in B3 at 15 feet below grade. The maximum PID reading of 985 was measured in the soil sample collected from B1 at 25 feet below grade. Soil was comprised primarily of sandy, silty clay mixtures and siltstone. Groundwater was not encountered in the Geoprobe borings. Copies of the soil boring logs are included in Appendix 6.

A summary of the soil analytical testing program is included in Tables 3 and 4. Copies of the laboratory analytical reports are included in Appendix 7. A maximum concentration of 1,080 mg/kg TPH-g was detected in B1 at 25 feet below grade. Maximum concentrations of 8.4 mg/kg benzene, 31 mg/kg toluene, 13.7 mg/kg ethylbenzene and 104.2 mg/kg total xylenes were detected in B1 at 25 feet below grade. A maximum concentration of 0.798 mg/kg tert-butyl alcohol (TBA) was detected in B1 at 20 feet below grade and a maximum concentration of 6.95 mg/kg MTBE was detected in B4 at 20 feet below grade. A maximum concentration of 0.12 mg/kg acetone and 0.27 mg/kg tetrachloroethylene (PCE) was detected in B6 at a depth of 5 feet below grade. None of the soil samples tested for TPH-DRO, TPH-ORO, and PCBs had detectable levels of these constituents. Metals were detected at varying concentrations in the soil samples collected and analyzed for metals.

### **GROUNDWATER SAMPLING**

A summary of the pool sump water analytical testing program is included in Table 5. Copies of the laboratory analytical reports are included in Appendix 7. The water sample had no detectable levels of TPH-g, TPH-DRO, TPH-ORO, and VOCs.

### DISCUSSION

To evaluate the significance of the reported contaminant levels in the soil samples, we compared these levels to threshold levels established by RWQCB, the United States Environmental Protection Agency (USEPA), and the State of California Department of Toxic Substances Control (DTSC). The TPH, BTEX, MTBE and PCE concentrations were compared to the RWQCB thresholds. The metals concentrations were compared to the USEPA soil cleanup thresholds and DTSC hazardous waste thresholds.

### HYDROCARBONS IN SOIL

The RWQCB maximum soil screening level (SSL) for TPH-g ranges from 100 to 1,000 mg/kg, depending on distance above groundwater. Assuming that the depth to groundwater beneath the former UST area is between 60 and 90 feet below grade (based on the 1988 Enviropro, Inc. report), the soil samples collected from the former UST area would be in the range of 30 to 85 feet above groundwater. The RWQCB SSL for TPH-g detected in the soil from 20 to 150 feet above groundwater is 500 mg/kg. Of the 14 soil samples tested for TPH-g, the RWQCB SSL was exceeded in one sample. TPH-g was detected in B1 at a concentration of 1,080 mg/kg at a depth of 25 feet below grade (approximately 35 to 65 feet above groundwater).

### VOLATILE ORGANIC COMPOUNDS IN SOIL

The RWQCB SSLs for BTEX are determined using site-specific distance above groundwater and lithology. Without specific depth to groundwater data for the site, we cannot calculate specific SSLs for BTEX. However, the ranges of BTEX SSLs for various soil types and distances above groundwater are provided below:

	Benzene	Toluene	Ethylbenzene	Xylenes
SSL	0.011-0.8	0.15-43	0.7-170	1.75-465
JOL	mg/kg	mg/kg	mg/kg	mg/kg

Using the above SSL ranges as a guideline, concentrations of BTEX detected in soil beneath the site could potentially exceed these levels in the following samples: B1-20, B3-20, B3-25 and B4-20. The benzene concentration detected in B1-25 exceeds the highest SSL range value for benzene. Therefore, regardless of soil type or distance above groundwater, the concentration of benzene at this location exceeds the RWQCB SSL.

The RWQCB SSL for MTBE is calculated using the California drinking water Maximum Contaminant Level (MCL) level and site-specific distance above groundwater and lithology. For various soil types and distances above groundwater, the MTBE SSL ranges from 0.013 mg/kg to 3.315 mg/kg. Using the SSL range as a guideline, concentrations of MTBE detected in soil beneath the site could potentially exceed these levels in the following samples: B1-20, B1-25, B3-15, B3-20, B3-25, B3-30, B4-10, B4-15 and B4-20. The calculated SSL for PCE ranges from 0.005 to 1.275 mg/kg for various soil types and distances above groundwater. Low concentrations of PCE were detected near the waste oil tank in soil samples B5 and B6 at 5 feet below grade. Based on the shallow depth of the detected PCE, it would not be likely that the

PCE SSL would be exceeded in the B5 and B6 boring locations. SSL ranges for acetone and TBA could not be determined as there are no MCLs for these constituents.

### **METALS IN SOIL**

The levels of metals detected were compared to soluble threshold limit concentration (STLC) levels and total threshold limit concentration (TTLC) levels established by the State of California DTSC. The STLC and the TTLC are used to determine whether soil or other solid waste would be classified as a hazardous or non-hazardous waste for disposal purposes. STLC and TTLC levels for metals are listed in Table 4. The metal concentrations detected in the soil samples tested for these constituents did not exceed TTLC levels or ten times STLC levels (Table 4). Therefore, if soil were to be excavated from this location, the metals content in the resulting soil would be considered non-hazardous for disposal purposes.

In addition to TTLC/STLC values, the metals concentrations in the soil sample were compared to USEPA PRGs. The PRG-R and PRG-I values for metals are listed in Table 4. With the exception of arsenic, the detected concentrations of metals were all below their respective PRG-R and PRG-I values.

For arsenic, normal background concentrations found in California soils are typically above the USEPA PRGs for both residential and industrial settings. The PRGs for residential and industrial settings for arsenic are 0.062 and 0.25 mg/kg, respectively. The USEPA states that generally they do not require cleanup below natural background levels. In light of this fact and in our experience, regulatory agencies typically consider the use of local or regional background concentrations as the threshold concentration. Although the levels of arsenic detected in the soil samples analyzed during this assessment exceed the arsenic PRGs, they were within the published ranges for arsenic in soils in the Western United States (Shacklette, H.T. and Boerngen, J.G., 1984) and appear to be within normal background levels. As discussed in the Shacklette and Boerngen report, the range of arsenic observed in background soil in the Western United States was between 0.10 mg/kg and 97 mg/kg. Overall, the levels of metals detected in the soil samples were low and likely represent naturally occurring background concentrations of metals in soil.

### PHASE II CONCLUSIONS

The following conclusions are based on the geophysical survey and soil and groundwater sampling and analysis for this assessment:

- The results of the geophysical survey conducted on December 21, 2004 indicate that a small UST remains in the vicinity of the observed tank vent and covered tank fill access in the former bus garage area. Based on the size and location of the identified UST, this was assumed to be a waste oil tank.
- The non-detectable levels of TPH-DRO, TPH-ORO, and PCBs in the soil samples collected from beneath the subject property indicate that soil at the locations tested have not been impacted by these contaminants.

- TPH-g and benzene were detected at concentrations exceeding the RWQCB SSL in sample B1 at 25 feet below grade (former UST area). As drilling refusal was encountered at 25 feet below grade, no deeper soil samples were collected from this boring, and the vertical extent of the contamination was not determined.
- BTEX was detected at concentrations that could potentially exceed the RWQCB SSLs in samples B1-20, B3-20, B3-25 and B4-20 (former UST area). MTBE was detected at concentrations that could potentially exceed the RWQCB SSLs in samples B1-20, B1-25, B3-15, B3-20, B3-25, B3-30, B4-10, B4-15 and B4-20. Actual depth to groundwater data is needed to calculate exact SSLs to determine whether SSLs have been exceeded in these samples.
- TBA was detected in several samples in the former UST area. The SSL for TBA could not be determined as there is no MCL for this constituent.
- Low concentrations of PCE and acetone were detected near the waste oil tank in soil samples B5 and B6 at 5 feet below grade. However, based on the shallow depth of the detected PCE, it is not likely that the PCE SSL would be exceeded at these locations. However, it is possible that the low concentrations of PCE detected could be an indication of potentially higher concentrations of PCE existing in the vicinity. The acetone SSL could not be determined as there is no MCL for this constituent.
- The metal concentrations detected in the soil samples tested for these constituents did not exceed TTLC levels or ten times STLC levels. Therefore, if soil were to be excavated from this location, the metals content in the resulting soil would be considered non-hazardous for disposal purposes. With the exception of arsenic, metals were well below their respective PRGs. Although the levels of arsenic detected in the soil samples analyzed during this assessment exceed the arsenic PRGs, they were within the published ranges for arsenic in soils in the Western United States (Shacklette, H.T. and Boerngen, J.G., 1984) and appear to be within normal background levels. We also believe that the other metals are within naturally occurring background concentrations for metals in soil.
- The pool sump groundwater sample had no detectable levels of TPH-g, TPH-DRO, TPH-ORO, and VOCs.

### LIMITATIONS

This Phase II ESA has been prepared for and is intended for the exclusive use of Latham & Watkins LLP and the Buckley School. The contents of this report should not be relied upon by any other party without the written consent of Rincon Consultants, Inc.

Our conclusions regarding the site are based on the results of a limited subsurface sampling program. The results of this evaluation are qualified by the fact that only limited sampling and analytical testing was conducted during this assessment.

This scope was not intended to completely establish the quantities and distribution of contaminants present at the site or to determine the cost to remediate the site. The concentrations of contaminants measured at any given location may not be representative of conditions at other locations. Further, conditions may change at any particular location as a function of time in response to natural conditions, chemical reactions and other events. Conclusions regarding the condition of the site do not represent a warranty that all areas within the site are similar to those sampled.

### REFERENCES

The following published reference materials were used in preparation of this Phase I and Phase II ESA:

Environmental database: Environmental Data Resources (EDR) report dated November 23, 2004.

<u>Geology</u>: Geologic Map of the Beverly Hills and Van Nuys (South 1/2) Quadrangles (Dibblee 1991) and EDR report.

<u>Groundwater</u>: Engineering Report on Soil Gas Investigation at Buckley School, Enviropro Inc., October 31, 1988.

<u>Topography</u>: USGS topographic map, Van Nuys Quadrangle (1966, photorevised 1972) <u>Oil and gas records</u>: Division of Oil and Gas Munger Map Book (2001)


<u>Aerial photographs</u>: Photos maintained by UCSB Map and Imagery Department <u>Historic topographic maps</u>: Maps maintained by UCSB Map and Imagery Department <u>Other</u>:

- Engineering Report on Soil Gas Investigation at Buckley School, Enviropro Inc., October 31, 1988.
- Background Concentrations of Trace and Major Elements in California Soils, Kearney Foundation Special Report, UC-Riverside and CAL-EPA DTSC, Bradford et al, March 1996

### QUALIFICATIONS


The environmental professionals responsible for conducting this Phase I ESA and preparing the report include Tricia Bartholome and Walt Hamann. Their qualifications are summarized below.

**Walt Hamann**, RG, CEG, CHG, REA II, is a Principal and Senior Geologist with Rincon Consultants. He holds a Bachelor of Science degree in geology from the University of California, Santa Barbara and a Master of Science degree in geology from the University of California, Los Angeles. He has over 17 years of experience conducting assessment and remediation projects and has prepared or overseen the preparation of hundreds of Phase I and Phase II Environmental Site Assessments throughout California. Mr. Hamann is a Registered Geologist (#4742), Certified Engineering Geologist (#1635), Certified Hydrogeologist (#208) and Registered Environmental Assessor II (#20063) with the State of California. **Tricia Ainsworth**, REA I, is an Associate Environmental Engineer with Rincon Consultants. She holds a Bachelor of Science degree in environmental engineering from California Polytechnic State University, San Luis Obispo. Ms. Bartholome has experience with regulatory compliance and reporting in the fields of air, water, and hazardous waste management, as well as environmental assessment and remediation of soil and groundwater. Ms. Bartholome's responsibilities at Rincon include implementation of site assessments and development of site remediation programs within the Environmental Site Assessment and Remediation Group. Ms. Bartholome is a certified Engineer-in-Training (#XE105131) with the State of California.



Phase I and Phase II Environmental Site Assessment Buckley School, 3900 Stansbury Avenue, Sherman Oaks, California





Site & Adjacent Land Use Map

Rincon Consultants

uð . J

J

# Phase I and Phase II Environmental Site Assessment Buckley School, 3900 Stansbury Avenue, Sherman Oaks, California



Photo 1 - View of entrance to subject property at the south end of Stansbury Avenue.




Photo 3 - View of 55-gallon waste paint and waste oil drums in the storage shed area.





Photo 2 - Laboratory chemicals stored in the chemistry supply room.



**Photo 4** - View of swiming pool chemicals stored in the basement of the Pavilion building.

Figure 3

Site Photographs

**Rincon Consultants** 

## Phase I and Phase II Environmental Site Assessment Buckley School, 3900 Stansbury Avenue, Sherman Oaks, California



Photo 5 - View of leaking elevator equipment in the Administration building.



Photo 7 - View of possible underground storage tank vent near the former bus maintenance garage.



Photo 6 - View of 30-gallon diesel drum and small containers of gasoline.




Photo 8 - View of possible tank fill access located near possible tank vent.

Site Photographs

Figure 3 Rincon Consultants

			TPH (mg/kg	)		1	Ethyl-	Total	Other		
	Depth	Gasoline	DRO	ORO	Benzene	Toluene	benzene	Xylenes	VOCs	Oxygenates	PCBs
Boring	(feet)	(C4-C12)	(C13-C22)	(C22+)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)
					Decembe	r 27, 2004 Sa	mpling Event				
Former L	JST Area								····		·······
	5	-	-	_	-	-	-	-			
	10	ND	ND	ND	0.002	0.002	ND	ND	-	ND	
B1	15	ND	ND	ND	ND	ND	ND	ND	-	ND	-
	20	2.05	-	-	0.032	0.09	0.024	0.195	-	MTBE - 0.816 TBA - 0.798	
	25	1,080	ND	ND	8.4	31	13.7	104.2	-	MTBE - 3.13	
	5			-	-	-	_	-	-	-	-
B2	10	-	-	-	-	-	-	-	-		-
	15	ND	-	-	0.002	ND	ND	ND	_	ND	-
	20	ND	-	-	ND	ND	ND	ND	-	ND	-
	5		-	-	-	-	-	-	-	-	-
	10	93.4	ND	ND	ND	ND	ND	ND	-	ND	-
50	15	0.646	ND	ND	0.007	0.003	ND	ND	-	MTBE - 0.206 TBA - 0.32	
B3	20	2.55	ND	ND	0.07	ND	0.019	ND	-	MTBE - 1.05 TBA - 0.792	
1	25	28.5	ND	ND	0.295	1.98	0.67	3.79	-	MTBE - 2.74	
	30	1.93	-	-	0.013	ND	0.053	0.054	_	MTBE - 1.05 TBA - 0.302	
	5		-	-	-	-	-	-	-	-	
B4	10	0.55		-	ND	0.002	ND	ND	-	MTBE - 0.129 TBA - 0.392	-
	15	2.02	-	-	0.004	0.002	ND	ND	-	MTBE - 1.27 TBA - 0.346	
	20	10.2		-	0.027	0.054	0.053	0.245	-	MTBE - 6.95	_
Detection	Limit	0.5-50	10	50	0.002-0.2	0.002-0.2	0.002-0.2	varies	varies	varies	varies

### Table 3 - Analytical Testing Summary - TPH, VOCs, Oxygenates and PCBsDecember 27 and 30, 2004

			TPH (mg/kg	)			Ethyl-	Total	Other		
Boring	Depth (feet)	Gasoline (C4-C12)		ORO (C22+)	Benzene (mg/kg)	Toluene (mg/kg)	benzene (mg/kg)	Xylenes (mg/kg)	VOCs (mg/kg)	Oxygenates (mg/kg)	PCBs (mg/kg)
					Decembe	r 27, 2004 Sa	mpling Event				
Waste O	il Tank										
B5	5	-	ND	ND	ND	ND	ND	ND	acetone - 0.106 PCE - 0.018	-	-
	10	-	ND	ND	ND	ND	ND	ND	ND	-	-
	15	~	ND	ND	ND	ND	ND	ND	ND	-	-
B6	5	-	ND	ND	ND	ND	ND	ND	acetone - 0.12 PCE - 0.027		-
	10	-	ND	ND	ND	ND	ND	ND	ND	-	-
	15	-	ND	ND	ND	ND	ND	ND	ND	-	
Hoist Ar											
B7	5	-	ND	ND	-	-	-	-	-	- 1	-
	10	-	ND	ND	-	-	-	-	-	-	ND
					December	r 30, 2004 Sa	mpling Event				
Hoist Ar	ea			·····							
B8	5	-	-	-	-	-	-	_	- 1	- 1	<u> </u>
	9	-	ND	ND	-	-	-	-	-		ND
Clarifier					•	·····					
B9	8	-	-	-	-	-	-	_	T	-	<u> </u>
	10	-	ND	ND	ND	ND	0.004	ND	ND		
B10	5	-	-	-	-	-	_	-	-	-	
	10	-	ND	ND	ND	ND	0.003	ND	ND	-	
Detection	n Limit	0.5-50	10	50	0.002-0.2	0.002-0.2	0.002-0.2	varies	varies	varies	varies

### Table 3 - Analytical Testing Summary - TPH, VOCs, Oxygenates and PCBs December 27 and 30, 2004

- Not analyzed

ND - Not detected

mg/kg - milligrams per kilogram (parts per million)

PCE - tetrachloroethylene

Analyses:

TPH-G (total petroleum hydrocarbons, gasoline range) by EPA Method 8260B

TPH-DRO / TPH-ORO (total petroleum hydrocarbons, diesel range organics / oil range organics) by EPA Method 8015M BTEX and Oxygenates by EPA Method 8260B

VOCs (volatile organic compounds) by EPA Method 8260B (see attached laboratory report for complete listing of VOCs) PCBs (Polychlorinated Biphenyls) by EPA Method 8082

								17 CCR									
Boring/	Results in milligrams per kilogram (mg/kg)																
Depth (ft)	Antimony	Arsenic	Barium	Beryllium	Cadmium	Chromium	Cobalt	Copper	Lead	Mercury	Molyb	Nickel	Selenium	Silver	Thallium	Vanadium	Zinc
						De	cember 27	7, 2004 Sa	mpling Ev	ent							
Former UST A	rea												T T		1		
B1-15	-	-	-	-	-	-	-	-	1.40	-	-	_			<u> </u>	_	-
B1-20	-	-	-	-	-	-		-	2.14		-		+	_	-		_
B1-25	-	-	-	-	-	-	-	-	ND	- 1	-	-	- 1	-	-		-
B3-20	-	*	-	-	-	-	-	-	1.40	-	-	-	-		-		
B3-25	-	-	-	-	-	-	-	-	1.91		-	-	-		-	_	-
Waste Oil Tanl	(												11				
B5-5	1.03	11.8	155	ND	0.50	34.5	10.3	24.0	4.63	ND	0.68	25.6	ND	ND	ND	60.1	55.9
B5-10	ND	3.14	72.1	ND	0.91	16.2	4.73	29.1	0.74	ND	3.00	38.9	ND	ND	ND	66.5	69.3
B5-15	0.51	6.45	138	ND	1.88	12.2	3.40	15.5	ND	ND	5.14	22.3	ND	ND	ND	66.6	47.3
B6-5	0.90	12.2	178	ND	0.57	35.0	13.7	26.5	4.25	ND	0.74	28.6	ND	ND	ND	62.4	61.0
B6-10	1.03	9.51	222	ND	1.72	27.5	7.87	23.7	2.31	ND	1.06	26.6	ND	ND	ND	57.6	57.7
B6-15	0.64	6.67	113	ND	2.76	23.9	2.48	20.0	ND	ND	5.61	29.7	ND	ND	ND	76.6	60.4
Hoist Area													1				
B <u>7</u> -10	ND	14.1	50.8	ND	1.24	11.3	4.26	17.5	0.58	ND	3.82	24.2	ND	ND	ND	71.5	36.0
1						De	cember 30	), 2004 Sa	mpling Ev	ent		<u> </u>	-t	······	4		
B9-10	0.63	0.90	64.1	ND	2.87	10.7	3.23	19.8	0.38	ND	1.92	22.8	ND	0.84	ND	40.1	55.5
B10-10	0.75	3.57	125	ND	0.81	10.4	4.31	20.0	2.18	ND	1.58	19.4	ND	0.70	ND	44.6	51.8
Detection Limit	0.50	0.25	0.50	0.50	0.50	0.50	0.50	0.50	0.25	0.20	0.50	0.50	0.50	0.50	0.50	0.50	0.50
STLC	15	5	100	0.75	1	5 or 560^	80	25	5	0.2	350	20		5	7	24	250
TTLC	500	500	10,000	75	100	500 or 2500	8,000	2,500	1,000	20	3,500	2,000	100	500	700	2,400	5,000
PRG-R	31	0.062	5,400	150	37	210	900	3,100	150	23	390	1.600	390	390	5.2	78	23,000
PRG-I	410	0.25	67,000	1,900	450	450	1,900	41,000	800	310	5,100	20,000	5,100	5,100	67	1,000	100,000

### Table 4 - Analytical Testing Summary - 17 CCR MetalsDecember 27 and 30, 2004

- Not analyzed

ND - Not detected

STLC - Soluble threshold limit concentration

TTLC - Total threshold limit concentration

PRG - United States Environmental Protection Agency Region 9 Preliminary Remediation Goal for residential (R) and industrial (I) sites (October 2004)

^ - STLC for Cr 3+ is 560 mg/L; STLC for Cr 6+ (Hexavalent Chromium) is 5 mg/L

### Table 5 - Pool Sump Water Analytical Testing Summary - TPH and VOCsDecember 27, 2004

Sample Designation	TPH-g (C4-C12) (µg/L)	ТРН-DRO (C13-C22) (µg/L)	TPH-ORO (C22+) (μg/L)	Benzene (μg/L)	Toluene (μg/L)	Ethyl- benzene (µg/L)	Total Xylenes (µg/L)	Other VOCs (µg/L)
Pool Sump*	ND	ND	ND	ND	ND	ND	ND	ND
Detection Limit	50	500	500	1.0	1.0	1.0	varies	varies

µg/L - milligrams per liter

ND - not detected at or above detection limit

TPH-g (total petroleum hydrocarbons, gasoline range)

TPH-DRO / TPH-ORO (total petroleum hydrocarbons, diesel range organics / oil range organics)

* Pool sump water sample collected using a disposable bailer

Analyses:

TPH-g and VOCs by EPA Method 8260B TPH-DRO / TPH-ORO by EPA Method 8015M

Appendix 1 Environmental Database Search Report

### The EDR Radius Map with GeoCheck[®]

Buckley School 3900 Stansbury Avenue Sherman Oaks, CA 91423

Inquiry Number: 01313273.1r

November 23, 2004

### EDF

**EDR**[™] Environmental Data Resources Inc

### The Standard in Environmental Risk Management Information

440 Wheelers Farms Road Milford, Connecticut 06460

### **Nationwide Customer Service**

 Telephone:
 1-800-352-0050

 Fax:
 1-800-231-6802

 Internet:
 www.edrnet.com

### TABLE OF CONTENTS

### SECTION

### PAGE

Executive Summary	ES1
Overview Map	2
Detail Map	3
Map Findings Summary	4
Map Findings	6
Orphan Summary	16
Government Records Searched/Data Currency Tracking	GR-1

### **GEOCHECK ADDENDUM**

Physical Setting Source Addendum	A-1
Physical Setting Source Summary	A-2
Physical Setting Source Map	A-7
Physical Setting Source Map Findings	A-8
Physical Setting Source Records Searched	A-9

*Thank you for your business.* Please contact EDR at 1-800-352-0050 with any questions or comments.

### **Disclaimer - Copyright and Trademark Notice**

This report contains information obtained from a variety of public and other sources. NO WARRANTY EXPRESSED OR IMPLIED, IS MADE WHATSOEVER IN CONNECTION WITH THIS REPORT. ENVIRONMENTAL DATA RESOURCES, INC. SPECIFICALLY DISCLAIMS THE MAKING OF ANY SUCH WARRANTIES, INCLUDING WITHOUT LIMITATION, MERCHANTABILITY OR FITNESS FOR A PARTICULAR USE OR PURPOSE. ALL RISK IS ASSUMED BY THE USER. IN NO EVENT SHALL EDR BE LIABLE TO ANYONE, WHETHER ARISING OUT OF ERRORS OR OMISSIONS, NEGLIGENCE, ACCIDENT OR ANY OTHER CAUSE, FOR ANY LOSS OR DAMAGE, INCLUDING, WITHOUT LIMITATION, SPECIAL, INCIDENTAL, CONSEQUENTIAL, OR EXEMPLARY DAMAGES. It can not be concluded from this report that coverage information for the target and surrounding properties does not exist from other sources. Any analyses, estimates, ratings or risk codes provided in this report are provided for illustrative purposes only, and are not intended to provide, nor should they be interpreted as providing any facts regarding, or prediction or forecast of, any environmental risk for any property. Only a Phase I Environmental Site Assessment performed by an environmental professional can provide information regarding the environmental risk for any property. Any liability on the part of EDR is strictly limited to a refund of the amount paid for this report.

Copyright 2004 by Environmental Data Resources, Inc. All rights reserved. Reproduction in any media or format, in whole or in part, of any report or map of Environmental Data Resources, Inc., or its affiliates, is prohibited without prior written permission.

EDR and its logos (including Sanborn and Sanborn Map) are trademarks of Environmental Data Resources, Inc. or its affiliates. All other trademarks used herein are the property of their respective owners.

A search of available environmental records was conducted by Environmental Data Resources, Inc. (EDR). The report meets the government records search requirements of ASTM Standard Practice for Environmental Site Assessments, E 1527-00. Search distances are per ASTM standard or custom distances requested by the user.

### TARGET PROPERTY INFORMATION

### ADDRESS

3900 STANSBURY AVENUE SHERMAN OAKS, CA 91423

### COORDINATES

Latitude (North):	34.139600 - 34° 8' 22.6"
Longitude (West):	118.443600 - 118° 26' 37.0"
Universal Tranverse Mercator:	Zone 11
UTM X (Meters):	366896.9
UTM Y (Meters):	3778381.0
Elevation:	797 ft. above sea level

### USGS TOPOGRAPHIC MAP ASSOCIATED WITH TARGET PROPERTY

Target	Property:
Source	:

34118-B4 VAN NUYS, CA USGS 7.5 min quad index

### TARGET PROPERTY SEARCH RESULTS

The target property was identified in the following government records. For more information on this property see page 6 of the attached EDR Radius Map report:

Site	Database(s)	EPA ID
BUCKLEY SCHOOL BUS GARAGE 3900 STANSBURY AVE SHERMAN OAKS, CA 91423	RCRIS-SQG FINDS HAZNET	CAD077262558
THE BUCKLEY SCHOOL 3900 STANSBURY AVE SHERMAN OAKS, CA 91403	CA FID UST	N/A
BUCKLEY SCHOOL 3900 STANSBURY AVE SHERMAN OAKS, CA 91423	LUST Cortese	N/A

### DATABASES WITH NO MAPPED SITES

No mapped sites were found in EDR's search of available ( "reasonably ascertainable ") government records either on the target property or within the ASTM E 1527-00 search radius around the target property for the following databases:

### FEDERAL ASTM STANDARD

NPL..... National Priority List

Proposed NPL	. Proposed National Priority List Sites
CERCLIS	Comprehensive Environmental Response, Compensation, and Liability Information
	System
CERC-NFRAP	CERCLIS No Further Remedial Action Planned
CORRACTS	Corrective Action Report
RCRIS-TSD	RCRAInfo
RCRIS-LQG	RCRAInfo
ERNS	. Emergency Response Notification System

### STATE ASTM STANDARD

AWP	. Annual Workplan Sites
Cal-Sites	Calsites Database
CHMIRS	California Hazardous Material Incident Report System
Toxic Pits	
SWF/LF	Solid Waste Information System
WMUDS/SWAT	Waste Management Unit Database
CA BOND EXP. PLAN	Bond Expenditure Plan
UST	List of Underground Storage Tank Facilities
VCP	Voluntary Cleanup Program Properties
INDIAN UST	Underground Storage Tanks on Indian Land
INDIAN LUST	Leaking Underground Storage Tanks on Indian Land
HIST UST	Hazardous Substance Storage Container Database

FEDERAL ASTM SUPPLEMENTAL

CONSENT	
ROD	
	- National Priority List Deletions
HMIRS	- Hazardous Materials Information Reporting System
	Material Licensing Tracking System
MINES	
NPL Liens	
	. PCB Activity Database System
	Uranium Mill Tailings Sites
ODI.	
FUDS	. Formerly Used Defense Sites
DOD	_ Department of Defense Sites
INDIAN RESERV	_ Indian Reservations
RAATS	RCRA Administrative Action Tracking System
TRIS	Toxic Chemical Release Inventory System
TSCA.	Toxic Substances Control Act
SSTS	_ Section 7 Tracking Systems
FTTS INSP	_ FIFRA/ TSCA Tracking System - FIFRA (Federal Insecticide, Fungicide, &
	Rodenticide Act)/TSCA (Toxic Substances Control Act)

### STATE OR LOCAL ASTM SUPPLEMENTAL

AST	Aboveground Petroleum Storage Tank Facilities
CLEANERS	Cleaner Facilities
CA WDS	Waste Discharge System
DEED	
NFE	Properties Needing Further Evaluation
SCH	School Property Evaluation Program

۳.

おうこう

2

ŝ

EMI	Emissions Inventory Data
	Unconfirmed Properties Referred to Another Agency
	No Further Action Determination
CA SLIC	Statewide SLIC Cases
LOS ANGELES CO. HMS	HMS: Street Number List
LA Co. Site Mitigation	Site Mitigation List
AOCONCERN	San Gabriel Valley Areas of Concern

### EDR PROPRIETARY HISTORICAL DATABASES

Coal Gas...... Former Manufactured Gas (Coal Gas) Sites

### **BROWNFIELDS DATABASES**

US BROWNFIELDS...... A Listing of Brownfields Sites VCP...... Voluntary Cleanup Program Properties

### SURROUNDING SITES: SEARCH RESULTS

Surrounding sites were identified.

Elevations have been determined from the USGS Digital Elevation Model and should be evaluated on a relative (not an absolute) basis. Relative elevation information between sites of close proximity should be field verified. Sites with an elevation equal to or higher than the target property have been differentiated below from sites with an elevation lower than the target property. Page numbers and map identification numbers refer to the EDR Radius Map report where detailed data on individual sites can be reviewed.

Sites listed in **bold italics** are in multiple databases.

Unmappable (orphan) sites are not considered in the foregoing analysis.

### STATE ASTM STANDARD

**NOTIFY 65:** Notify 65 records contain facility notifications about any release that could impact drinking water and thereby expose the public to a potential health risk. The data come from the State Water Resources Control Board's Proposition 65 database.

A review of the Notify 65 list, as provided by EDR, has revealed that there is 1 Notify 65 site within approximately 1 mile of the target property.

Lower Elevation	Address	Dist / Dir Map IC	Page
SERVICE STATION	14478 VENTURA BLVD	1/2-1 NNW 4	10

Due to poor or inadequate address information, the following sites were not mapped:

Site Name


BUILDING #8 LONG BEACH NAVAL BUCKLEY SCHOOL


.

Database(s) LUST, CHMIRS ERNS

5

(a., 10-12) 4





 Sherman Oaks CA 91423
 INQUIRY #:
 01313273.1r

 34.1396 / 118.4436
 DATE:
 November 23, 2004 12:39 pm

LAT/LONG:

Copyright # 2004 EDR, Inc. # 2003 GDT, Inc. Rel. 07/2003. All Rights Reserved.

### MAP FINDINGS SUMMARY

Database	Target Property	Search Distance (Miles)	< 1/8	<u>1/8 - 1/4</u>	1/4 - 1/2	<u>1/2 - 1</u>	> 1	Total Plotted
FEDERAL ASTM STANDAR	D							
NPL Proposed NPL CERCLIS CERC-NFRAP CORRACTS RCRA TSD RCRA Lg. Quan. Gen. RCRA Sm. Quan. Gen. ERNS STATE ASTM STANDARD	x	1.000 1.000 0.500 0.250 1.000 0.500 0.250 0.250 TP	0 0 0 0 0 0 0 NR	0 0 0 0 0 0 0 0 NR	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0 NR NR 0 NR NR NR NR	NR NR NR NR NR NR NR NR	
AWP Cal-Sites CHMIRS Cortese Notify 65 Toxic Pits State Landfill WMUDS/SWAT LUST CA Bond Exp. Plan UST VCP INDIAN UST INDIAN UST INDIAN LUST CA FID UST HIST UST	x x x	1.000 1.000 TP 0.500 1.000 0.500 0.500 0.500 0.500 0.250 0.250 0.250 0.250 0.250	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0 0 NR 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0 NR 0 0 0 0 0 0 0 NR 0 R 0 R 0 R 0 R 0	0 0 R R 1 0 R R R 0 R R R R R R R R R R	NR NR NR NR NR NR NR NR NR NR NR NR NR N	0 0 0 1 0 0 0 0 0 0 0 0 0 0 0 0 0 0
FEDERAL ASTM SUPPLEMI CONSENT ROD Delisted NPL FINDS HMIRS MLTS MINES NPL Liens PADS UMTRA ODI FUDS DOD INDIAN RESERV RAATS TRIS	X	1.000 1.000 TP TP TP 0.250 TP TP 0.500 0.500 1.000 1.000 TP TP	0 0 0 R NR 0 R N 0 0 0 0 0 0 0 R N 0 0 0 0 0 0 R N 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0 0 0 NR N 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0 0 NR NR NR NR NR 0 0 0 0 R NR	0 0 0 R R R R R R R R O 0 0 R R N N N N N N N N N N N N N N N N	NR R R R R R R R R R R R R R R R R R R	

### MAP FINDINGS SUMMARY

Database	Target Property	Search Distance (Miles)	< 1/8	1/8 - 1/4	1/4 - 1/2	1/2 - 1	> 1	Total Plotted
TSCA		TP	NR	NR	NR	NR	NR	0
SSTS FTTS		TP TP	NR NR	NR NR	NR NR	NR NR	NR NR	0 0
STATE OR LOCAL ASTM SL	IPPLEMENTAI							-
AST		TP	NR	NR	NR	NR	NR	0
CLEANERS CA WDS		0.250 TP	0 NR	0 NR	NR NR	NR NR	NR NR	0 0
DEED		TP	NR	NR	NR	NR	NR	ŏ
NFE		0.250	0	0	NR	NR	NR	0
SCH		0.250	0	0	NR	NR	NR	0
EMI		TP	NR	NR	NR NR	NR	NR	0
REF NFA		0.250 0.250	0 0	0 0	NR	NR NR	NR NR	0 0
SLIC		0.500	0	0	0	NR	NR	ŏ
HAZNET	х	TP	NR	NR	NR	NR	NR	Õ
Los Angeles Co. HMS		TP	NR	NR	NR	NR	NR	0
LA Co. Site Mitigation		TP	NR	NR	NR	NR	NR	0
AOCONCERN		1.000	0	0	0	0	NR	0
EDR PROPRIETARY HISTORICAL DATABASES								
Coal Gas		1.000	0	0	0	0	NR	0
BROWNFIELDS DATABASES								
US BROWNFIELDS		0.500	0	0	0	NR	NR	0
VCP		0.500	0	0	0	NR	NR	0

### NOTES:

AQUIFLOW - see EDR Physical Setting Source Addendum

TP = Target Property

NR = Not Requested at this Search Distance

Sites may be listed in more than one database

Map ID		MAP FINDINGS		
Direction				
Distance				
Distance (ft	.)			EDR ID Number
Elevation	Site		Database(s)	EPA ID Number
<u></u>			·	

Coal Gas Site Search: No site was found in a search of Real Property Scan's ENVIROHAZ database.

A1 Target Property	BUCKLEY SCHOOL 1 3900 STANSBURY A SHERMAN OAKS, CA	VE	RCRIS-SQG FINDS HAZNET	1000591085 CAD077262558
	Site 1 of 3 in cluster	<b>д</b>		
Actual: 792 ft.	RCRIS:			
		THE BUCKLEY SCHOOL DIST (818) 783-1613 CAD077262558		
		RAY GOURVTAN (818) 783-1613		
	Classification: TSDF Activities:	Small Quantity Generator Not reported		
	Violation Status:	No violations found		
	National Com	invironmental Activity Identified at Site: pliance Data Base servation and Recovery Act Information system		
	HAZNET:			
	Gepaid:	CAD077262558		
	TSD EPA ID:	CAD093459485		
	Gen County:	Los Angeles		
	Tsd County:	Fresno		
	Tons:	.0665		
	•••	Unspecified solvent mixture Waste		
	Disposal Method:			
	Contact:	NON-PROFIT SCHOOL OPERATED UND		
	Telephone:	(818) 783-1610		
	Mailing Address:	3900 STANSBURY AVE		
	County	SHERMAN OAKS, CA 91423 - 4618 Los Angeles		
	•	•		
	Gepaid:	CAD077262558		
	TSD EPA ID:	CAT000613893		
	Gen County:	Los Angeles		
	Tsd County:	Los Angeles		
	Tons:	.2400		
•		Unspecified organic liquid mixture		
	Disposal Method:			
	Contact:	NON-PROFIT SCHOOL OPERATED UND		
	Telephone:	(818) 783-1610 2000 STANSBURY AVE		
	waning Address:	3900 STANSBURY AVE		
	County	SHERMAN OAKS, CA 91423 - 4618		
	County	Los Angeles		

MAP FINDINGS

Map ID Direction Distance Distance (ft.) Elevation Site

Database(s)

EDR ID Number EPA ID Number

ŝ.

ŝ

1

10 V 10

1000591085

### BUCKLEY SCHOOL BUS GARAGE (Continued)

Gepaid: CAD077262558 TSD EPA ID: CAD981696420 Gen County: Los Angeles Tsd County: Los Angeles 5.8380 Tons: Waste Category: Oil/water separation sludge **Disposal Method: Transfer Station** NON-PROFIT SCHOOL OPERATED UND Contact: (818) 783-1610 Telephone: Mailing Address: 3900 STANSBURY AVE SHERMAN OAKS, CA 91423 - 4618 County Los Angeles CAD077262558 Gepaid: TSD EPA ID: CAT000613893 Gen County: Los Angeles Tsd County: Los Angeles .1940 Tons: Waste Category: Unspecified organic liquid mixture **Disposal Method: Transfer Station** Contact: NON-PROFIT SCHOOL OPERATED UND Telephone: (818) 783-1610 3900 STANSBURY AVE Mailing Address: SHERMAN OAKS, CA 91423 - 4618 County Los Angeles Gepaid: CAD077262558 TSD EPA ID: CAT000613893 Gen County: Los Angeles Tsd County: Los Angeles Tons: .2400 Waste Category: Organic liquids (nonsolvents) with halogens Disposal Method: Transfer Station Contact: NON-PROFIT SCHOOL OPERATED UND (818) 783-1610 Telephone: Mailing Address: 3900 STANSBURY AVE SHERMAN OAKS, CA 91423 - 4618 County Los Angeles

<u>Click this hyperlink</u> while viewing on your computer to access 6 additional CA HAZNET record(s) in the EDR Site Report.

### A2 THE BUCKLEY SCHOOL Target 3900 STANSBURY AVE Property SHERMAN OAKS, CA 91403

CA FID UST S101582919 N/A

Site 2 of 3 in cluster A

Actual: 792 ft. MAP FINDINGS

Map ID Direction Distance Distance (ft.) Elevation Site

Database(s)

### EDR ID Number EPA ID Number

S101582919

### THE BUCKLEY SCHOOL (Continued)

FID:

Facility ID:	19001850	Regulate ID:	Not reported
Reg By:	Inactive Underground Storage Tank L	ocation	
Cortese Code:	Not reported	SIC Code:	Not reported
Status:	Inactive	Facility Tel:	(818) 783-1610
Mail To:	Not reported	-	
	3900 STANSBURY AVE		
	SHERMAN OAKS, CA 91403		
Contact:	Not reported	Contact Tel:	Not reported
DUNs No:	Not reported	NPDES No:	Not reported
Creation:	10/22/93	Modified:	00/00/00
EPA ID:	Not reported		
Comments:	Not reported		
	·		

### A3 BUCKLEY SCHOOL 3900 STANSBURY AVE SHERMAN OAKS, CA 91423 Target Property

Sit

Actual: 792 ft.

HERMAN OAKS, CA	91423		
ite 3 of 3 in cluster A	N N		
State LUST:			
Cross Street:	Not reported		
Qty Leaked:	Not reported		
Case Number	9160615		
Reg Board:	Los Angeles Region		
Chemical:	Gasoline		
Lead Agency:	Regional Board		
Local Agency :	19050		
Case Type:	Soil only		
Status:	Case Closed		
Review Date:	Not reported	Confirm Leak:	Not reported
Workplan:	Not reported	Prelim Assess:	Not reported
Pollution Char:	Not reported	Remed Plan:	Not reported
Remed Action:	Not reported		
Monitoring:	Not reported		
Close Date:	1996-07-22 00:00:00		
Release Date:	1988-06-02 00:00:00		
Cleanup Fund Id			
Discover Date :	1988-05-27 00:00:00		÷
Enforcement Dt :	•		
Enf Type:	Not reported		
Enter Date :	1988-09-16 00:00:00		
Funding:	Not reported		
Staff Initials:	PEJ		
	Nuisance Conditions		
How Stopped:	Not reported		
Interim : Leak Cause:	Not reported Structure Failure		
Leak Source:	Piping		
MTBE Date :	Not reported		
Max MTBE GW :	Not reported		
MTBE Tested:	Site NOT Tested for MTBE.Includes Uni	nown and Not Anali	ന്മറ്
Priority:	Not reported	nown and reor Analy	1200.
Local Case # :	Not reported		
Beneficial:	Not reported		
Staff :	UNK		
GW Qualifier :	Not reported		
Max MTBE Soil :	,		
	· · · · - F · · · · · · ·		

LUST 1006890270 Cortese N/A

MAP FINDINGS

Map ID Direction Distance Distance (ft.) Elevation Site

Database(s)

EDR ID Number EPA ID Number

### **BUCKLEY SCHOOL (Continued)**

£

Soil Qualifier : Not reported Hydr Basin #: UNNAMED BASIN BAUMHOFF Operator : Oversight Prgm: LUST 1988-09-21 00:00:00 Review Date : Stop Date : Not reported Work Suspended :Not reported Responsible PartyBUCKLEY SCHOOL **RP** Address: 3900 STANSBURY AVE, SHERMAN Global Id: T0603702598 Org Name: Not reported Contact Person: Not reported MTBE Conc: 0 Mtbe Fuel: 1 Water System Name: Not reported Well Name: Not reported Distance To Lust: 0 Waste Discharge Global ID: Not reported Waste Disch Assigned Name: Not reported LUST Region 4: 6/2/1988 Report Date: Lead Agency: Regional Board 19050 Local Agency: Gasoline Substance: Case Type: Soil Case Closed Status: Region: 4 Staff: UNK Date Case Last Changed on Database: 9/21/1988 Date Leak Record Entered: 9/16/1988 Historical Max MTBE Date: Not reported GW Qualifier: Not reported Soil Qualifier: Not reported Hist Max MTBE Conc in Groundwater: Not reported Hist Max MTBE Conc in Soil : County: Organization : Regional Board: 04 Owner Contact: Responsible Party: **RP** Address: Significant Interim Remedial Action Taken: Program : LUST Lat / Long : Local Agency Staff: PEJ Beneficial Use : Priority : Cleanup Fund Id : Suspended : Local Case No : Substance Quantity : Abatement Method Used at the Site: Operator : Water System : Well Name : Approx. Dist To Production Well (ft) : Assigned Name :

Not reported Los Angeles Not reported Not reported BUCKLEY SCHOOL 3900 STANSBURY AVE, SHERMAN OAKS CA 91423 Not reported 34.1417876 / -1 Not reported BAUMHOFF, WALTER Not reported Not reported 20003.840185590122796404012591 Not reported

1006890270

5

Map ID Direction Distance Distance (ft.) Elevation Site MAP FINDINGS

EDR ID Number Database(s) **EPA ID Number** 

### **BUCKLEY SCHOOL (Continued)**

W Global ID :	Not reported
Source of Cleanup Funding:	Not reported
Date the Leak was Discovered:	5/27/1988
How the Leak was Discovered:	Nuisance Conditions
How the Leak was Stopped:	Not reported
Cause of Leak:	Structure Failure
Leak Source:	Piping
Date The Leak was Stopped:	Not reported
Date Confirmation Leak Began:	Not reported
Preliminary Site Assessment Workplan Submitted:	Not reported
Preliminary Site Assessment Began:	Not reported
Pollution Characterization Began:	9/21/1988
Remediation Plan Submitted:	Not reported
Remedial Action Underway:	Not reported
Post Remedial Action Monitoring Began:	Not reported
Date the Case was Closed:	7/22/1996
Enforcement Action Date:	Not reported
Date Leak First Reported:	6/2/1988
Enforcement Type:	Not reported
Global ID :	T0603702598
Cross Street:	Not reported
Summary : ENVIROPRO HAS SENT WORK	PLAN
CORTESE:	
Region: CORTESE	

Fac Address 2: 3900 STANSBURY AVE

### SERVICE STATION NNW 14478 VENTURA BLVD 1/2-1 SHERMAN OAKS, CA 91423

4304 ft. **Relative:** 

4

Lower

Actual: 662 ft.

State LUST: Cross Street: VAN NUYS BLVD Qty Leaked: Not reported Case Number 9142303 Reg Board: Los Angeles Region Gasoline Chemical: Lead Agency: Regional Board 19050 Local Agency : Case Type: Other ground water affected Status: Pollution Characterization Review Date: Not reported Workplan: Not reported Pollution Char: Not reported Remed Action: Not reported Monitoring: Not reported Close Date: Not reported Release Date: 1988-04-14 00:00:00 Cleanup Fund Id : Not reported Discover Date : 1988-04-12 00:00:00 Enforcement Dt: Not reported DLSEL Enf Type: Enter Date : 1988-04-21 00:00:00 Funding: Not reported Staff Initials: PEJ How Discovered: OM

Confirm Leak:
Prelim Assess:
Remed Plan:

Not reported Not reported Not reported

Notify 65

HAZNET

Cortese CA FID UST

HIST UST

LUST

1000166679

N/A

TC01313273.1r Page 10

MAP FINDINGS

Map ID Direction Distance Distance (ft.) Elevation Site

Database(s)

EDR ID Number EPA ID Number

# SERVICE STATION (Continued)

1000166679

÷.

with the

÷

÷

 $(\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{i},\gamma_{$ 

How Stopped:		
	Not reported	
Interim :	Not reported	
Leak Cause:	Other Cause	
Leak Source:	Piping	
MTBE Date :	2000-04-06 00:0	
	50000 Parts per Billion	
MTBE Tested:	MTBE Detected. Site tested f	or MTRE & MTRE dotoctod
		OF MTBE & MTBE delected
Priority:	Not reported	
Local Case # :	Not reported	
Beneficial:	Not reported	
Staff :	AT	
GW Qualifier :	Not reported	
Max MTBE Soil :	-	
Soil Qualifier :	Not reported	
Hydr Basin #:	SAN FERNANDO VALLEY	
Operator :	NAMSON,	
Oversight Prgm:		
Review Date :	2002-07-15 00:00:00	
Stop Date :	1988-04-12	
Work Suspended	i :Not reported	
Responsible Parl	tySHARI LONDON	
RP Address:	3611 HARBOR BLVD., SUIT	E #20
Global Id:	T0603702483	
Org Name:	Not reported	
Contact Person:	Not reported	
MTBE Conc:	1	
Mtbe Fuel:	1	
Water System Na	ame: Not reported	
Well Name:	Not reported	
•	Not reported	
Well Name: Distance To Lust	: 0	
Well Name: Distance To Lust Waste Discharge	:: 0 Global ID: Not reported	
Well Name: Distance To Lust Waste Discharge Waste Disch Ass	: 0	
Well Name: Distance To Lust Waste Discharge Waste Disch Ass LUST Region 4:	:: 0 Global ID: Not reported igned Name: Not reported	
Well Name: Distance To Lust Waste Discharge Waste Disch Ass LUST Region 4: Report Date:	:: 0 Global ID: Not reported signed Name: Not reported 4/14/1988	
Well Name: Distance To Lust Waste Discharge Waste Disch Ass LUST Region 4: Report Date: Lead Agency:	:: 0 Global ID: Not reported signed Name: Not reported 4/14/1988 Regional Board	
Well Name: Distance To Lust Waste Discharge Waste Disch Ass LUST Region 4: Report Date: Lead Agency: Local Agency:	:: 0 Global ID: Not reported igned Name: Not reported 4/14/1988 Regional Board 19050	
Well Name: Distance To Lust Waste Discharge Waste Disch Ass LUST Region 4: Report Date: Lead Agency:	:: 0 Global ID: Not reported signed Name: Not reported 4/14/1988 Regional Board	
Well Name: Distance To Lust Waste Discharge Waste Disch Ass LUST Region 4: Report Date: Lead Agency: Local Agency:	:: 0 Global ID: Not reported igned Name: Not reported 4/14/1988 Regional Board 19050	
Well Name: Distance To Lust Waste Discharge Waste Disch Ass LUST Region 4: Report Date: Lead Agency: Local Agency: Substance:	:: 0 Global ID: Not reported igned Name: Not reported 4/14/1988 Regional Board 19050 Gasoline	
Well Name: Distance To Lust Waste Discharge Waste Disch Ass LUST Region 4: Report Date: Lead Agency: Local Agency: Substance: Case Type:	:: 0 Global ID: Not reported igned Name: Not reported 4/14/1988 Regional Board 19050 Gasoline Groundwater	
Well Name: Distance To Lust Waste Discharge Waste Disch Ass LUST Region 4: Report Date: Lead Agency: Local Agency: Substance: Case Type: Status:	:: 0 Global ID: Not reported igned Name: Not reported 4/14/1988 Regional Board 19050 Gasoline Groundwater Pollution Characterization	
Well Name: Distance To Lust Waste Discharge Waste Disch Ass LUST Region 4: Report Date: Lead Agency: Local Agency: Substance: Case Type: Status: Region: Staff:	:: 0 Global ID: Not reported signed Name: Not reported 4/14/1988 Regional Board 19050 Gasoline Groundwater Pollution Characterization 4	7/15/2002
Well Name: Distance To Lust Waste Discharge Waste Disch Ass LUST Region 4: Report Date: Lead Agency: Local Agency: Substance: Case Type: Status: Region: Staff:	:: 0 Global ID: Not reported signed Name: Not reported 4/14/1988 Regional Board 19050 Gasoline Groundwater Pollution Characterization 4 AT Changed on Database:	7/15/2002 4/21/1988
Well Name: Distance To Lust Waste Discharge Waste Disch Ass LUST Region 4: Report Date: Lead Agency: Local Agency: Substance: Case Type: Status: Region: Staff: Date Case Last (	O Global ID: Not reported Global ID: Not reported Global ID: Not reported      4/14/1988     Regional Board     19050     Gasoline     Groundwater     Pollution Characterization     4     AT Changed on Database:     d Entered:	
Well Name: Distance To Lust Waste Discharge Waste Disch Ass LUST Region 4: Report Date: Lead Agency: Local Agency: Substance: Case Type: Status: Region: Staff: Date Case Last O Date Leak Recor	O Global ID: Not reported Global ID: Not reported Global ID: Not reported      4/14/1988     Regional Board     19050     Gasoline     Groundwater     Pollution Characterization     4     AT Changed on Database:     d Entered:	4/21/1988
Well Name: Distance To Lust Waste Discharge Waste Disch Ass LUST Region 4: Report Date: Lead Agency: Local Agency: Substance: Case Type: Status: Region: Staff: Date Case Last C Date Leak Recor Historical Max M	O Global ID: Not reported Global ID: Not reported Global ID: Not reported      4/14/1988     Regional Board     19050     Gasoline     Groundwater     Pollution Characterization     4     AT Changed on Database:     d Entered:	4/21/1988 4/6/2000
Well Name: Distance To Lust Waste Discharge Waste Disch Ass LUST Region 4: Report Date: Lead Agency: Local Agency: Substance: Case Type: Status: Region: Staff: Date Case Last O Date Leak Recor Historical Max M GW Qualifier: Soil Qualifier:	O Global ID: Not reported Global ID: Not reported Global ID: Not reported      4/14/1988     Regional Board     19050     Gasoline     Groundwater     Pollution Characterization     4     AT Changed on Database:     d Entered:	4/21/1988 4/6/2000 Not reported Not reported
Well Name: Distance To Lust Waste Discharge Waste Disch Ass LUST Region 4: Report Date: Lead Agency: Local Agency: Substance: Case Type: Status: Region: Staff: Date Case Last O Date Leak Recor Historical Max M GW Qualifier: Soil Qualifier:	: 0 Global ID: Not reported igned Name: Not reported 4/14/1988 Regional Board 19050 Gasoline Groundwater Pollution Characterization 4 AT Changed on Database: d Entered: TBE Date: Conc in Groundwater:	4/21/1988 4/6/2000 Not reported Not reported 50000
Well Name: Distance To Lust Waste Discharge Waste Disch Ass LUST Region 4: Report Date: Lead Agency: Local Agency: Substance: Case Type: Status: Region: Staff: Date Case Last ( Date Leak Recorn Historical Max M GW Qualifier: Soil Qualifier: Hist Max MTBE ( Hist Max MTBE (	: 0 Global ID: Not reported igned Name: Not reported 4/14/1988 Regional Board 19050 Gasoline Groundwater Pollution Characterization 4 AT Changed on Database: d Entered: TBE Date: Conc in Groundwater:	4/21/1988 4/6/2000 Not reported Not reported 50000 Not reported
Well Name: Distance To Lust Waste Discharge Waste Disch Ass LUST Region 4: Report Date: Lead Agency: Local Agency: Substance: Case Type: Status: Region: Staff: Date Case Last O Date Leak Recorn Historical Max M GW Qualifier: Hist Max MTBE O Hist Max MTBE O County:	: 0 Global ID: Not reported igned Name: Not reported 4/14/1988 Regional Board 19050 Gasoline Groundwater Pollution Characterization 4 AT Changed on Database: d Entered: TBE Date: Conc in Groundwater:	4/21/1988 4/6/2000 Not reported Not reported 50000 Not reported Los Angeles
Well Name: Distance To Lust Waste Discharge Waste Disch Ass LUST Region 4: Report Date: Lead Agency: Local Agency: Substance: Case Type: Status: Region: Staff: Date Case Last O Date Leak Recor Historical Max M GW Qualifier: Soil Qualifier: Hist Max MTBE O County: Organization :	: 0 Global ID: Not reported igned Name: Not reported 4/14/1988 Regional Board 19050 Gasoline Groundwater Pollution Characterization 4 AT Changed on Database: d Entered: TBE Date: Conc in Groundwater:	4/21/1988 4/6/2000 Not reported Not reported 50000 Not reported Los Angeles Not reported
Well Name: Distance To Lust Waste Discharge Waste Disch Ass LUST Region 4: Report Date: Lead Agency: Local Agency: Substance: Case Type: Status: Region: Staff: Date Case Last O Date Leak Recor Historical Max M GW Qualifier: Soil Qualifier: Hist Max MTBE O County: Organization : Regional Board:	: 0 Global ID: Not reported igned Name: Not reported 4/14/1988 Regional Board 19050 Gasoline Groundwater Pollution Characterization 4 AT Changed on Database: d Entered: TBE Date: Conc in Groundwater:	4/21/1988 4/6/2000 Not reported Not reported 50000 Not reported Los Angeles Not reported 04
Well Name: Distance To Lust Waste Discharge Waste Disch Ass LUST Region 4: Report Date: Lead Agency: Local Agency: Substance: Case Type: Status: Region: Staff: Date Case Last O Date Leak Recor Historical Max M GW Qualifier: Hist Max MTBE O County: Organization : Regional Board: Owner Contact:	: 0 Global ID: Not reported signed Name: Not reported 4/14/1988 Regional Board 19050 Gasoline Groundwater Pollution Characterization 4 AT Changed on Database: d Entered: TBE Date: Conc in Groundwater: Conc in Soil :	4/21/1988 4/6/2000 Not reported 50000 Not reported Los Angeles Not reported 04 Not reported
Well Name: Distance To Lust Waste Discharge Waste Disch Ass LUST Region 4: Report Date: Lead Agency: Local Agency: Substance: Case Type: Status: Region: Staff: Date Case Last 0 Date Leak Recorn Historical Max M GW Qualifier: Hist Max MTBE 0 Hist Max MTBE 0 County: Organization : Regional Board: Owner Contact: Responsible Part	: 0 Global ID: Not reported signed Name: Not reported 4/14/1988 Regional Board 19050 Gasoline Groundwater Pollution Characterization 4 AT Changed on Database: d Entered: TBE Date: Conc in Groundwater: Conc in Soil :	4/21/1988 4/6/2000 Not reported 50000 Not reported Los Angeles Not reported 04 Not reported SHARI LONDON
Well Name: Distance To Lust Waste Discharge Waste Disch Ass LUST Region 4: Report Date: Lead Agency: Local Agency: Substance: Case Type: Status: Region: Staff: Date Case Last 0 Date Leak Recor Historical Max M GW Qualifier: Hist Max MTBE 0 County: Organization : Regional Board: Owner Contact: Responsible Part	O Global ID: Not reported	4/21/1988 4/6/2000 Not reported 50000 Not reported Los Angeles Not reported 04 Not reported SHARI LONDON 3611 HARBOR BLVD., SUITE #200
Well Name: Distance To Lust Waste Discharge Waste Disch Ass LUST Region 4: Report Date: Lead Agency: Local Agency: Substance: Case Type: Status: Region: Staff: Date Case Last ( Date Leak Recor Historical Max M GW Qualifier: Hist Max MTBE ( Hist Max MTBE ( County: Organization : Regional Board: Owner Contact: Responsible Part RP Address: Significant Interir	: 0 Global ID: Not reported signed Name: Not reported 4/14/1988 Regional Board 19050 Gasoline Groundwater Pollution Characterization 4 AT Changed on Database: d Entered: TBE Date: Conc in Groundwater: Conc in Soil :	4/21/1988 4/6/2000 Not reported 50000 Not reported Los Angeles Not reported 04 Not reported SHARI LONDON 3611 HARBOR BLVD., SUITE #200 Not reported
Well Name: Distance To Lust Waste Discharge Waste Disch Ass LUST Region 4: Report Date: Lead Agency: Local Agency: Substance: Case Type: Status: Region: Staff: Date Case Last 0 Date Leak Recor Historical Max M GW Qualifier: Hist Max MTBE 0 County: Organization : Regional Board: Owner Contact: Responsible Part	O Global ID: Not reported	4/21/1988 4/6/2000 Not reported 50000 Not reported Los Angeles Not reported 04 Not reported SHARI LONDON 3611 HARBOR BLVD., SUITE #200

Map ID Direction Distance Distance (ft.) Elevation Site MAP FINDINGS

Database(s)

EDR ID Number EPA ID Number

1000166679

#### SERVICE STATION (Continued)

Local Agency Staff: PEJ Beneficial Use : Not reported Not reported Priority : Cleanup Fund Id : Not reported Suspended : Not reported Local Case No : Not reported Substance Quantity : Not reported Abatement Method Used at the Site: Not reported Operator : NAMSON, JOSEPH N. Water System : Not reported Well Name : Not reported Approx. Dist To Production Well (ft) : 17639.953186757741589545141318 Assigned Name : Not reported W Global ID : Not reported Source of Cleanup Funding: Not reported Date the Leak was Discovered: 4/12/1988 How the Leak was Discovered: OM How the Leak was Stopped: Not reported Cause of Leak: Other Causes Leak Source: Piping Date The Leak was Stopped: 4/12/1988 Date Confirmation Leak Began: Not reported Preliminary Site Assessment Workplan Submitted: 3/1/1999 Preliminary Site Assessment Began: Not reported Pollution Characterization Began: 7/25/2000 Remediation Plan Submitted: Not reported Remedial Action Underway: Not reported Post Remedial Action Monitoring Began: Not reported Date the Case was Closed: Not reported Enforcement Action Date: Not reported Date Leak First Reported: 4/14/1988 Enforcement Type: DLSEL Global ID : T0603702483 Cross Street: VAN NUYS BLVD ABANDONED PIPE CONNECTED TO OLD PUMP ISLAND WAS NOT CAPPED. CONTRACTOR Summary : DISCOVERED LEAKING UG PIPE.; 7/14/00 2ND QTR GW MON RPT; 10/30/00 SUPPLE. SITE ASESSM. RPT AND REMED. TESTING PROPOSAL; 12/31/00 4TH QTR GW MON RPT 2000

HAZNET:

Gepaid: CAD981645377 TSD EPA ID: CAD050099696 Gen County: Los Angeles Tsd County: Los Angeles Tons: .4170 Waste Category: Aqueous solution with less than 10% total organic residues **Disposal Method: Recycler** Contact: UNION OIL COMPANY OF CALIFORNI Telephone: (714) 428-6560 Mailing Address: PO BOX 25376 SANTA ANA, CA 92799 - 5376

Los Angeles

County

MAP FINDINGS

Map ID Direction Distance Distance (ft.) Elevation Site

Database(s)

EDR ID Number EPA ID Number

ę

è

0.00

2

3

1

1000166679

#### SERVICE STATION (Continued)

CAD981645377 Gepaid: TSD EPA ID: CAT080011059 Gen County: Los Angeles Tsd County: Los Angeles 1.6680 Tons: Waste Category: Waste oil and mixed oil Disposal Method: Recycler UNION OIL COMPANY OF CALIFORNI Contact: Telephone: (714) 428-6560 Mailing Address: PO BOX 25376 SANTA ANA, CA 92799 - 5376 County Los Angeles Gepaid: CAD981645377 TSD EPA ID: CAT080011059 Gen County: Los Angeles Tsd County: Los Angeles .3085 Tons: Waste Category: Aqueous solution with 10% or more total organic residues Disposal Method: Recycler Contact: UNION OIL COMPANY OF CALIFORNI Telephone: (714) 428-6560 Mailing Address: PO BOX 25376 SANTA ANA, CA 92799 - 5376 County Los Angeles Gepaid: CAD981645377 TSD EPA ID: CAD099452708 Gen County: Los Angeles Tsd County: Los Angeles Tons: 4.3785 Waste Category: Waste oil and mixed oil Disposal Method: Recycler Contact: UNION OIL COMPANY OF CALIFORNI Telephone: (714) 428-6560 Mailing Address: PO BOX 25376 SANTA ANA, CA 92799 - 5376 County Los Angeles Gepaid: CAD981645377 TSD EPA ID: CAD028409019 Gen County: Los Angeles Tsd County: Los Angeles Tons: 3.7862 Waste Category: Aqueous solution with less than 10% total organic residues Disposal Method: Treatment, Tank UNION OIL COMPANY OF CALIFORNI Contact: Telephone: (714) 428-6560 Mailing Address: PO BOX 25376 SANTA ANA, CA 92799 - 5376 County Los Angeles

<u>Click this hyperlink</u> while viewing on your computer to access 7 additional CA HAZNET record(s) in the EDR Site Report.

Map ID Direction		MAP FINDING	S		
Distance Distance (ft Elevation	.) Site			Database(s)	EDR ID Number EPA ID Number
	SERVICE STATION (	Continued)			1000166679
	NOTIFY 65: Date Reported: Board File Numb Facility Type: Discharge Date: Incident Descripti	Not reported Not reported	orted		
,	CORTESE: Region: Fac Address 2:	CORTESE 14478 VENTURA BLVD			
	FID: Facility ID:	19001622	Regulate ID:	00029443	
	Reg By: Cortese Code: Status: Mail To:	Active Underground Storage Tank Local Not reported Active Not reported 3701 WILSHIRE BLVD	SIC Code: Facility Tel:	Not reported (818) 784-2275	
	Contact: DUNs No: Creation: EPA ID: Comments:	SHERMAN OAKS, CA 91403 Not reported Not reported 10/22/93 Not reported Not reported	Contact Tel: NPDES No: Modified:	Not reported Not reported 00/00/00	
	UST HIST: Facility ID: Total Tanks: Owner Address:	29443 3 3701 WILSHIRE BOULEVARD-SUITE LOS ANGELES, CA 90010	Owner Name: Region:	UNION OIL COMPANY STATE	OF CALIFORNI
	Tank Used for: Tank Num: Tank Capacity: Type of Fuel: Leak Detection: Contact Name:	PRODUCT 1 00009950 UNLEADED Stock Inventor, Pressure Test JOSEPH N NAMSON	Container Num: Year Installed: Tank Construction: Telephone:	2421-1 1967 Not Reported (818) 784-2275	
	Facility Type: Facility ID:	Gas Station	Other Type: Owner Name:	Not reported	
	Total Tanks: Owner Address: Tank Used for:	3 3701 WILSHIRE BOULEVARD-SUITE LOS ANGELES, CA 90010 PRODUCT	Region:	STATE	
	Tank Num: Tank Capacity: Type of Fuel: Leak Detection:	2 00009950 PREMIUM Stock Inventor, Pressure Test	Container Num: Year Installed: Tank Construction:	2421-2 1967 Not Reported	
	Contact Name: Facility Type:	JOSEPH N NAMSON Gas Station	Telephone: Other Type:	(818) 784-2275 Not reported	
	Facility ID: Total Tanks: Owner Address: Tank Head for:	29443 3 3701 WILSHIRE BOULEVARD-SUITE LOS ANGELES, CA 90010 PRODUCT	Owner Name: Region:	UNION OIL COMPANY STATE	OF CALIFORNI
	Tank Used for: Tank Num: Tank Capacity: Type of Fuel:	PRODUCT 3 00000550 WASTE OIL	Container Num: Year Installed: Tank Construction:	2421-4 1967 Not Reported	

Map ID Direction	MAP FINDINGS		
Distance			
Distance (ft.)			EDR ID Nu
Elevation Site		Database(s)	EPA ID Nu

# SERVICE STATION (Continued)

Telephone: Other Type:

(818) 784-2275 Not reported

1000166679

, , ;;

.

ORPHAN SUMMARY

	City	EDR ID	Sile Name	Site Address	Zip	Database(s)
۰.	LOS ANGELES COUNTY SHERMAN OAKS	S105632075 8872808	BUCKLEY SCHOOL	BUILDING #8 LONG BEACH NAVAL BUCKLEY SCHOOL		LUST, CHMIRS ERNS

.

To maintain currency of the following federal and state databases, EDR contacts the appropriate governmental agency on a monthly or quarterly basis, as required.

Elapsed ASTM days: Provides confirmation that this EDR report meets or exceeds the 90-day updating requirement of the ASTM standard.

#### FEDERAL ASTM STANDARD RECORDS

NPL: National Priority List

Source: EPA

Telephone: N/A

National Priorities List (Superfund). The NPL is a subset of CERCLIS and identifies over 1,200 sites for priority cleanup under the Superfund Program. NPL sites may encompass relatively large areas. As such, EDR provides polygon coverage for over 1,000 NPL site boundaries produced by EPA's Environmental Photographic Interpretation Center (EPIC) and regional EPA offices.

Date of Government Version: 07/30/04 Date Made Active at EDR: 09/09/04 Database Release Frequency: Semi-Annually Date of Data Arrival at EDR: 08/03/04 Elapsed ASTM days: 37 Date of Last EDR Contact: 11/02/04

#### **NPL Site Boundaries**

Sources:

EPA's Environmental Photographic Interpretation Center (EPIC) Telephone: 202-564-7333

EPA Region 1 Telephone 617-918-1143

EPA Region 3 Telephone 215-814-5418

EPA Region 4 Telephone 404-562-8033

Proposed NPL: Proposed National Priority List Sites Source: EPA

Telephone: N/A

Date of Government Version: 07/22/04 Date Made Active at EDR: 09/09/04 Database Release Frequency: Semi-Annually EPA Region 6 Telephone: 214-655-6659 EPA Region 8 Telephone: 303-312-6774

> Date of Data Arrival at EDR: 08/03/04 Elapsed ASTM days: 37 Date of Last EDR Contact: 11/02/04

CERCLIS: Comprehensive Environmental Response, Compensation, and Liability Information System Source: EPA

Telephone: 703-413-0223

CERCLIS contains data on potentially hazardous waste sites that have been reported to the USEPA by states, municipalities, private companies and private persons, pursuant to Section 103 of the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA). CERCLIS contains sites which are either proposed to or on the National Priorities List (NPL) and sites which are in the screening and assessment phase for possible inclusion on the NPL.

Date of Government Version: 08/10/04 Date Made Active at EDR: 10/27/04 Database Release Frequency: Quarterly Date of Data Arrival at EDR: 09/21/04 Elapsed ASTM days: 36 Date of Last EDR Contact: 09/21/04

CERCLIS-NFRAP: CERCLIS No Further Remedial Action Planned

#### Source: EPA

Telephone: 703-413-0223

As of February 1995, CERCLIS sites designated "No Further Remedial Action Planned" (NFRAP) have been removed from CERCLIS. NFRAP sites may be sites where, following an initial investigation, no contamination was found, contamination was removed quickly without the need for the site to be placed on the NPL, or the contamination was not serious enough to require Federal Superfund action or NPL consideration. EPA has removed approximately 25,000 NFRAP sites to lift the unintended barriers to the redevelopment of these properties and has archived them as historical records so EPA does not needlessly repeat the investigations in the future. This policy change is part of the EPA's Brownfields Redevelopment Program to help cities, states, private investors and affected citizens to promote economic redevelopment of unproductive urban sites.

Date of Government Version: 08/10/04 Date Made Active at EDR: 10/27/04 Database Release Frequency: Quarterly

CORRACTS: Corrective Action Report

Source: EPA Telephone: 800-424-9346

CORRACTS identifies hazardous waste handlers with RCRA corrective action activity.

Date of Government Version: 09/23/04 Date Made Active at EDR: 11/18/04 Database Release Frequency: Semi-Annually Date of Data Arrival at EDR: 09/21/04 Elapsed ASTM days: 36 Date of Last EDR Contact: 09/21/04

Date of Data Arrival at EDR: 10/07/04 Elapsed ASTM days: 42 Date of Last EDR Contact: 09/07/04

RCRIS: RCRAInfo

Source: EPA

Telephone: 800-424-9346

RCRAInfo is EPA's comprehensive information system, providing access to data supporting the Resource Conservation and Recovery Act (RCRA) of 1976 and the Hazardous and Solid Waste Amendments (HSWA) of 1984. RCRAInfo replaces the data recording and reporting abilities of the Resource Conservation and Recovery Information System (RCRIS). The database includes selective information on sites which generate, transport, store, treat and/or dispose of hazardous waste as defined by the Resource Conservation and Recovery Act (RCRA). Conditionally exempt small quantity generators (CESQGs): generate less than 100 kg of hazardous waste, or less than 1 kg of acutely hazardous waste per month. Small quantity generators (SQGs): generate between 100 kg and 1,000 kg of hazardous waste per month. Large quantity generators (LQGs): generate over 1,000 kilograms (kg) of hazardous waste, or over 1 kg of acutely hazardous waste per month. Transporters are individuals or entities that move hazardous waste from the generator off-site to a facility that can recycle, treat, store, or dispose of the waste. TSDFs treat, store, or dispose of the waste.

Date of Government Version: 08/10/04 Date Made Active at EDR: 10/11/04 Database Release Frequency: Varies Date of Data Arrival at EDR: 08/24/04 Elapsed ASTM days: 48 Date of Last EDR Contact: 08/24/04

Date of Data Arrival at EDR: 01/26/04

Date of Last EDR Contact: 10/25/04

Elapsed ASTM days: 46

ERNS: Emergency Response Notification System

Source: National Response Center, United States Coast Guard Telephone: 202-260-2342 Emergency Response Notification System ERNS records and store

Emergency Response Notification System. ERNS records and stores information on reported releases of oil and hazardous substances.

Date of Government Version: 12/31/03 Date Made Active at EDR: 03/12/04 Database Release Frequency: Annually

#### FEDERAL ASTM SUPPLEMENTAL RECORDS

BRS: Biennial Reporting System

Source: EPA/NTIS

Telephone: 800-424-9346

The Biennial Reporting System is a national system administered by the EPA that collects data on the generation and management of hazardous waste. BRS captures detailed data from two groups: Large Quantity Generators (LQG) and Treatment, Storage, and Disposal Facilities.

Date of Government Version: 12/01/01 Database Release Frequency: Biennially Date of Last EDR Contact: 09/20/04 Date of Next Scheduled EDR Contact: 12/13/04

**CONSENT:** Superfund (CERCLA) Consent Decrees Source: Department of Justice, Consent Decree Library Telephone: Varies

Major legal settlements that establish responsibility and standards for cleanup at NPL (Superfund) sites. Released periodically by United States District Courts after settlement by parties to litigation matters.

Date of Government Version: 03/05/04 Database Release Frequency: Varies	Date of Last EDR Contact: 10/25/04 Date of Next Scheduled EDR Contact: 01/24/0
ROD: Records Of Decision Source: EPA Telephone: 703-416-0223 Record of Decision. ROD documents mandate a permanent rem and health information to aid in the cleanup.	nedy at an NPL (Superfund) site containing technical
Date of Government Version: 09/09/04 Database Release Frequency: Annually	Date of Last EDR Contact: 10/06/04 Date of Next Scheduled EDR Contact: 01/03/0
DELISTED NPL: National Priority List Deletions Source: EPA Telephone: N/A The National Oil and Hazardous Substances Pollution Contingen EPA uses to delete sites from the NPL. In accordance with 40 NPL where no further response is appropriate.	
Date of Government Version: 07/30/04 Database Release Frequency: Quarterly	Date of Last EDR Contact: 11/02/04 Date of Next Scheduled EDR Contact: 01/31/0
Telephone: N/A Easility Index System EINDS contains both facility information a	nd 'naintara' to other apurage that contain more
Facility Index System. FINDS contains both facility information a detail. EDR includes the following FINDS databases in this re information Retrieval System), DOCKET (Enforcement Docke enforcement cases for all environmental statutes), FURS (Fee Docket System used to track criminal enforcement actions for Information System), STATE (State Environmental Laws and Date of Government Version: 09/09/04	port: PCS (Permit Compliance System), AIRS (Aerometric et used to manage and track information on civil judicial deral Underground Injection Control), C-DOCKET (Criminal all environmental statutes), FFIS (Federal Facilities Statutes), and PADS (PCB Activity Data System). Date of Last EDR Contact: 09/08/04
Facility Index System. FINDS contains both facility information a detail. EDR includes the following FINDS databases in this re Information Retrieval System), DOCKET (Enforcement Docke enforcement cases for all environmental statutes), FURS (Fee Docket System used to track criminal enforcement actions for Information System), STATE (State Environmental Laws and Date of Government Version: 09/09/04 Database Release Frequency: Quarterly	port: PCS (Permit Compliance System), AIRS (Aerometric at used to manage and track information on civil judicial deral Underground Injection Control), C-DOCKET (Criminal all environmental statutes), FFIS (Federal Facilities Statutes), and PADS (PCB Activity Data System). Date of Last EDR Contact: 09/08/04 Date of Next Scheduled EDR Contact: 01/03/0
<ul> <li>Facility Index System. FINDS contains both facility information a detail. EDR includes the following FINDS databases in this re Information Retrieval System), DOCKET (Enforcement Docke enforcement cases for all environmental statutes), FURS (Fee Docket System used to track criminal enforcement actions for Information System), STATE (State Environmental Laws and Date of Government Version: 09/09/04 Database Release Frequency: Quarterly</li> <li>HMIRS: Hazardous Materials Information Reporting System Source: U.S. Department of Transportation Telephone: 202-366-4555</li> </ul>	port: PCS (Permit Compliance System), AIRS (Aerometric at used to manage and track information on civil judicial deral Underground Injection Control), C-DOCKET (Criminal all environmental statutes), FFIS (Federal Facilities Statutes), and PADS (PCB Activity Data System). Date of Last EDR Contact: 09/08/04 Date of Next Scheduled EDR Contact: 01/03/0
<ul> <li>Facility Index System. FINDS contains both facility information a detail. EDR includes the following FINDS databases in this re information Retrieval System), DOCKET (Enforcement Docke enforcement cases for all environmental statutes), FURS (Fee Docket System used to track criminal enforcement actions for Information System), STATE (State Environmental Laws and Date of Government Version: 09/09/04 Database Release Frequency: Quarterly</li> <li>HMIRS: Hazardous Materials Information Reporting System Source: U.S. Department of Transportation Telephone: 202-366-4555 Hazardous Materials Incident Report System. HMIRS contains h Date of Government Version: 02/17/04</li> </ul>	port: PCS (Permit Compliance System), AIRS (Aerometric et used to manage and track information on civil judicial deral Underground Injection Control), C-DOCKET (Criminal all environmental statutes), FFIS (Federal Facilities Statutes), and PADS (PCB Activity Data System). Date of Last EDR Contact: 09/08/04 Date of Next Scheduled EDR Contact: 01/03/0 azardous material spill incidents reported to DOT. Date of Last EDR Contact: 04/20/04 Date of Next Scheduled EDR Contact: 07/19/0 contains a list of approximately 8,100 sites which
<ul> <li>Facility Index System. FINDS contains both facility information a detail. EDR includes the following FINDS databases in this re information Retrieval System), DOCKET (Enforcement Docke enforcement cases for all environmental statutes), FURS (Fee Docket System used to track criminal enforcement actions for Information System), STATE (State Environmental Laws and Date of Government Version: 09/09/04 Database Release Frequency: Quarterly</li> <li>HMIRS: Hazardous Materials Information Reporting System Source: U.S. Department of Transportation Telephone: 202-366-4555</li> <li>Hazardous Materials Incident Report System. HMIRS contains h Date of Government Version: 02/17/04 Database Release Frequency: Annually</li> <li>MLTS: Material Licensing Tracking System Source: Nuclear Regulatory Commission Telephone: 301-415-7169</li> <li>MLTS is maintained by the Nuclear Regulatory Commission and possess or use radioactive materials and which are subject to</li> </ul>	port: PCS (Permit Compliance System), AIRS (Aerometric et used to manage and track information on civil judicial deral Underground Injection Control), C-DOCKET (Criminal all environmental statutes), FFIS (Federal Facilities Statutes), and PADS (PCB Activity Data System). Date of Last EDR Contact: 09/08/04 Date of Next Scheduled EDR Contact: 01/03/0 azardous material spill incidents reported to DOT. Date of Last EDR Contact: 04/20/04 Date of Next Scheduled EDR Contact: 07/19/0 contains a list of approximately 8,100 sites which
<ul> <li>Facility Index System. FINDS contains both facility information a detail. EDR includes the following FINDS databases in this reinformation Retrieval System), DOCKET (Enforcement Docke enforcement cases for all environmental statutes), FURS (Fee Docket System used to track criminal enforcement actions for Information System), STATE (State Environmental Laws and Date of Government Version: 09/09/04 Database Release Frequency: Quarterly</li> <li>HMIRS: Hazardous Materials Information Reporting System Source: U.S. Department of Transportation Telephone: 202-366-4555</li> <li>Hazardous Materials Incident Report System. HMIRS contains h Date of Government Version: 02/17/04 Database Release Frequency: Annually</li> <li>MLTS: Material Licensing Tracking System Source: Nuclear Regulatory Commission and possess or use radioactive materials and which are subject to EDR contacts the Agency on a quarterly basis. Date of Government Version: 07/15/04</li> </ul>	port: PCS (Permit Compliance System), AIRS (Aerometric et used to manage and track information on civil judicial deral Underground Injection Control), C-DOCKET (Criminal all environmental statutes), FFIS (Federal Facilities Statutes), and PADS (PCB Activity Data System). Date of Last EDR Contact: 09/08/04 Date of Next Scheduled EDR Contact: 01/03/0 azardous material spill incidents reported to DOT. Date of Last EDR Contact: 04/20/04 Date of Next Scheduled EDR Contact: 07/19/0 contains a list of approximately 8,100 sites which NRC licensing requirements. To maintain currency, Date of Last EDR Contact: 10/04/04 Date of Next Scheduled EDR Contact: 01/03/0

7

20

Ν.

87.00 M

ter contra

 $\tilde{\gamma}_{i}^{k}$ 

Source: EPA Telephone: 202-564-4267 Federal Superfund Liens. Under the authority granted the USEPA by and Liability Act (CERCLA) of 1980, the USEPA has the authority to recover remedial action expenditures or when the property own USEPA compiles a listing of filed notices of Superfund Liens.	to file liens against real property in order
Date of Government Version: 10/15/91 Database Release Frequency: No Update Planned	Date of Last EDR Contact: 08/23/04 Date of Next Scheduled EDR Contact: 11/22/
<ul> <li>PADS: PCB Activity Database System</li> <li>Source: EPA</li> <li>Telephone: 202-564-3887</li> <li>PCB Activity Database. PADS Identifies generators, transporters, co of PCB's who are required to notify the EPA of such activities.</li> </ul>	mmercial storers and/or brokers and disposers
Date of Government Version: 06/29/04 Database Release Frequency: Annually	Date of Last EDR Contact: 08/10/04 Date of Next Scheduled EDR Contact: 11/08/
DOD: Department of Defense Sites Source: USGS Telephone: 703-692-8801 This data set consists of federally owned or administered lands, adm have any area equal to or greater than 640 acres of the United St	• •
Date of Government Version: 10/01/03	Date of Last EDR Contact: 08/12/04
Database Release Frequency: Semi-Annually UMTRA: Uranium Mill Tailings Sites Source: Department of Energy Telephone: 505-845-0011 Uranium ore was mined by private companies for federal governmer	Date of Next Scheduled EDR Contact: 11/08/0
Database Release Frequency: Semi-Annually UMTRA: Uranium Mill Tailings Sites Source: Department of Energy Telephone: 505-845-0011	It use in national defense programs. When the mills in after uranium has been extracted from the piles are low; however, in some cases tailings azards of the tailings were recognized. In 1978, Utah, Colorado, New Mexico, Texas, North Dakota,
Database Release Frequency: Semi-Annually UMTRA: Uranium Mill Tailings Sites Source: Department of Energy Telephone: 505-845-0011 Uranium ore was mined by private companies for federal governmer shut down, large piles of the sand-like material (mill tailings) rema the ore. Levels of human exposure to radioactive materials from were used as construction materials before the potential health ha 24 inactive uranium mill tailings sites in Oregon, Idaho, Wyoming, South Dakota, Pennsylvania, and on Navajo and Hopi tribal lands	It use in national defense programs. When the mills in after uranium has been extracted from the piles are low; however, in some cases tailings azards of the tailings were recognized. In 1978, Utah, Colorado, New Mexico, Texas, North Dakota,
<ul> <li>Database Release Frequency: Semi-Annually</li> <li>UMTRA: Uranium Mill Tailings Sites</li> <li>Source: Department of Energy</li> <li>Telephone: 505-845-0011</li> <li>Uranium ore was mined by private companies for federal governmer shut down, large piles of the sand-like material (mill tailings) rema the ore. Levels of human exposure to radioactive materials from were used as construction materials before the potential health ha 24 inactive uranium mill tailings sites in Oregon, Idaho, Wyoming, South Dakota, Pennsylvania, and on Navajo and Hopi tribal lands Energy.</li> <li>Date of Government Version: 04/22/04 Database Release Frequency: Varies</li> </ul>	at use in national defense programs. When the mills in after uranium has been extracted from the piles are low; however, in some cases tailings azards of the tailings were recognized. In 1978, Utah, Colorado, New Mexico, Texas, North Dakota, , were targeted for cleanup by the Department of Date of Last EDR Contact: 09/20/04 Date of Next Scheduled EDR Contact: 12/20/0
<ul> <li>Database Release Frequency: Semi-Annually</li> <li>UMTRA: Uranium Mill Tailings Sites <ul> <li>Source: Department of Energy</li> <li>Telephone: 505-845-0011</li> </ul> </li> <li>Uranium ore was mined by private companies for federal governmer shut down, large piles of the sand-like material (mill tailings) rema the ore. Levels of human exposure to radioactive materials from were used as construction materials before the potential health ha 24 inactive uranium mill tailings sites in Oregon, Idaho, Wyoming, South Dakota, Pennsylvania, and on Navajo and Hopi tribal lands Energy.</li> <li>Date of Government Version: 04/22/04</li> <li>Database Release Frequency: Varies</li> </ul> ODI: Open Dump Inventory Source: Environmental Protection Agency Telephone: 800-424-9346 An open dump is defined as a disposal facility that does not comply to the semicondent of the semico	at use in national defense programs. When the mills in after uranium has been extracted from the piles are low; however, in some cases tailings azards of the tailings were recognized. In 1978, Utah, Colorado, New Mexico, Texas, North Dakota, , were targeted for cleanup by the Department of Date of Last EDR Contact: 09/20/04 Date of Next Scheduled EDR Contact: 12/20/0
<ul> <li>Database Release Frequency: Semi-Annually</li> <li>UMTRA: Uranium Mill Tailings Sites <ul> <li>Source: Department of Energy</li> <li>Telephone: 505-845-0011</li> </ul> </li> <li>Uranium ore was mined by private companies for federal governmers shut down, large piles of the sand-like material (mill tailings) remains the ore. Levels of human exposure to radioactive materials from were used as construction materials before the potential health has 24 inactive uranium mill tailings sites in Oregon, Idaho, Wyoming, South Dakota, Pennsylvania, and on Navajo and Hopi tribal lands Energy.</li> <li>Date of Government Version: 04/22/04</li> <li>Database Release Frequency: Varies</li> </ul> ODI: Open Dump Inventory Source: Environmental Protection Agency Telephone: 800-424-9346 An open dump is defined as a disposal facility that does not comply of Subtitle D Criteria. Date of Government Version: 06/30/85	at use in national defense programs. When the mills in after uranium has been extracted from the piles are low; however, in some cases tailings azards of the tailings were recognized. In 1978, Utah, Colorado, New Mexico, Texas, North Dakota, , were targeted for cleanup by the Department of Date of Last EDR Contact: 09/20/04 Date of Next Scheduled EDR Contact: 12/20/04 Date of Next Scheduled EDR Contact: 12/20/04 with one or more of the Part 257 or Part 258 Date of Last EDR Contact: 05/23/95 Date of Next Scheduled EDR Contact: N/A

. .

INDIAN RESERV: Indian Reservations Source: USGS Telephone: 202-208-3710 This map layer portrays Indian administered lands of the United States that have a than 640 acres.	any area equal to or greater
Date of Government Version: 10/01/03 Database Release Frequency: Semi-Annually	Date of Last EDR Contact: 08/12/04 Date of Next Scheduled EDR Contact: 11/08/04
<ul> <li>RAATS: RCRA Administrative Action Tracking System</li> <li>Source: EPA</li> <li>Telephone: 202-564-4104</li> <li>RCRA Administration Action Tracking System. RAATS contains records based on pertaining to major violators and includes administrative and civil actions brougl actions after September 30, 1995, data entry in the RAATS database was discord the database for historical records. It was necessary to terminate RAATS becaumade it impossible to continue to update the information contained in the database</li> </ul>	ht by the EPA. For administration ontinued. EPA will retain a copy of use a decrease in agency resources
Date of Government Version: 04/17/95 Database Release Frequency: No Update Planned	Date of Last EDR Contact: 09/07/04 Date of Next Scheduled EDR Contact: 12/06/04
<ul> <li>TRIS: Toxic Chemical Release Inventory System</li> <li>Source: EPA</li> <li>Telephone: 202-566-0250</li> <li>Toxic Release Inventory System. TRIS identifies facilities which release toxic chemiland in reportable quantities under SARA Title III Section 313.</li> </ul>	nicals to the air, water and
Date of Government Version: 12/31/02 Database Release Frequency: Annually	Date of Last EDR Contact: 09/20/04 Date of Next Scheduled EDR Contact: 12/20/04
TSCA: Toxic Substances Control Act Source: EPA Telephone: 202-260-5521 Toxic Substances Control Act. TSCA identifies manufacturers and importers of che TSCA Chemical Substance Inventory list. It includes data on the production volu site.	
Date of Government Version: 12/31/02 Database Release Frequency: Every 4 Years	Date of Last EDR Contact: 09/07/04 Date of Next Scheduled EDR Contact: 12/06/04
FTTS INSP: FIFRA/ TSCA Tracking System - FIFRA (Federal Insecticide, Fungicide, Source: EPA Telephone: 202-564-2501	, & Rodenticide Act)/TSCA (Toxic Substances Control Act)
Date of Government Version: 04/13/04 Database Release Frequency: Quarterly	Date of Last EDR Contact: 09/07/04 Date of Next Scheduled EDR Contact: 12/20/04
<ul> <li>SSTS: Section 7 Tracking Systems</li> <li>Source: EPA</li> <li>Telephone: 202-564-5008</li> <li>Section 7 of the Federal Insecticide, Fungicide and Rodenticide Act, as amended ( registered pesticide-producing establishments to submit a report to the Environm 1st each year. Each establishment must report the types and amounts of pestici being produced, and those having been produced and sold or distributed in the</li> </ul>	nental Protection Agency by March ides, active ingredients and devices
Date of Government Version: 12/31/01 Database Release Frequency: Annually	Date of Last EDR Contact: 10/18/04 Date of Next Scheduled EDR Contact: 01/17/05
<ul> <li>FTTS: FIFRA/ TSCA Tracking System - FIFRA (Federal Insecticide, Fungicide, &amp; Rot Source: EPA/Office of Prevention, Pesticides and Toxic Substances Telephone: 202-564-2501</li> <li>FTTS tracks administrative cases and pesticide enforcement actions and complian TSCA and EPCRA (Emergency Planning and Community Right-to-Know Act). T Agency on a quarterly basis.</li> </ul>	ce activities related to FIFRA,

**X**22. 11.

Ś

transfer south

 $\{g_{1}, \dots, g_{n}\}$ 

 $\sum_{i=1}^{n} (1-i) \sum_{i=1}^{n} (1-i) \sum_{i=1}^{n$ 

18 J. 1988

ż

kelo, orto

4

5

.

Date of Government Version: 09/13/04 Database Release Frequency: Quarterly

Date of Last EDR Contact: 09/07/04 Date of Next Scheduled EDR Contact: 12/20/04

### STATE OF CALIFORNIA ASTM STANDARD RECORDS

AWP: Annual Workplan Sites Source: California Environmental Protection Agency Telephone: 916-323-3400 Known Hazardous Waste Sites. California DTSC's Annual Workplan (AWP), formerly BEP, identifies known hazardous substance sites targeted for cleanup. Date of Government Version: 10/05/04 Date of Data Arrival at EDR: 10/15/04 Date Made Active at EDR: 11/03/04 Elapsed ASTM days: 19 Database Release Frequency: Annually Date of Last EDR Contact: 09/16/04 CAL-SITES: Calsites Database Source: Department of Toxic Substance Control Telephone: 916-323-3400 The Calsites database contains potential or confirmed hazardous substance release properties. In 1996, California EPA reevaluated and significantly reduced the number of sites in the Calsites database. Date of Government Version: 10/05/04 Date of Data Arrival at EDR: 10/15/04 Date Made Active at EDR: 11/03/04 Elapsed ASTM days: 19 Database Release Frequency: Quarterly Date of Last EDR Contact: 09/16/04 CHMIRS: California Hazardous Material Incident Report System Source: Office of Emergency Services Telephone: 916-845-8400 California Hazardous Material Incident Reporting System. CHMIRS contains information on reported hazardous material incidents (accidental releases or spills). Date of Government Version: 12/31/03 Date of Data Arrival at EDR: 05/18/04 Date Made Active at EDR: 06/25/04 Elapsed ASTM days: 38 Database Release Frequency: Varies Date of Last EDR Contact: 08/23/04 CORTESE: "Cortese" Hazardous Waste & Substances Sites List Source: CAL EPA/Office of Emergency Information Telephone: 916-323-9100 The sites for the list are designated by the State Water Resource Control Board (LUST), the Integrated Waste Board (SWF/LS), and the Department of Toxic Substances Control (Cal-Sites). This listing is no longer updated by the state agency. Date of Government Version: 04/01/01 Date of Data Arrival at EDR: 05/29/01 Date Made Active at EDR: 07/26/01 Elapsed ASTM days: 58 Database Release Frequency: No Update Planned Date of Last EDR Contact: 10/28/04 NOTIFY 65: Proposition 65 Records Source: State Water Resources Control Board Telephone: 916-445-3846 Proposition 65 Notification Records. NOTIFY 65 contains facility notifications about any release which could impact drinking water and thereby expose the public to a potential health risk. Date of Government Version: 10/21/93 Date of Data Arrival at EDR: 11/01/93 Date Made Active at EDR: 11/19/93 Elapsed ASTM days: 18 Database Release Frequency: No Update Planned Date of Last EDR Contact: 10/18/04 TOXIC PITS: Toxic Pits Cleanup Act Sites Source: State Water Resources Control Board Telephone: 916-227-4364

Toxic PITS Cleanup Act Sites. TOXIC PITS identifies sites suspected of containing hazardous substances where cleanup has not yet been completed.

Date of Government Version: 07/01/95 Date of Data Arrival at EDR: 08/30/95 Date Made Active at EDR: 09/26/95 Elapsed ASTM days: 27 Database Release Frequency: No Update Planned Date of Last EDR Contact: 11/01/04 SWF/LF (SWIS): Solid Waste Information System Source: Integrated Waste Management Board Telephone: 916-341-6320 Active, Closed and Inactive Landfills. SWF/LF records typically contain an inventory of solid waste disposal facilities or landfills. These may be active or i nactive facilities or open dumps that failed to meet RCRA Section 4004 criteria for solid waste landfills or disposal sites. Date of Government Version: 09/13/04 Date of Data Arrival at EDR: 09/14/04 Date Made Active at EDR: 10/12/04 Elapsed ASTM days: 28 Database Release Frequency: Quarterly Date of Last EDR Contact: 09/14/04 WMUDS/SWAT: Waste Management Unit Database Source: State Water Resources Control Board Telephone: 916-227-4448 Waste Management Unit Database System. WMUDS is used by the State Water Resources Control Board staff and the Regional Water Quality Control Boards for program tracking and inventory of waste management units. WMUDS is composed of the following databases: Facility Information, Scheduled Inspections Information, Waste Management Unit Information, SWAT Program Information, SWAT Report Summary Information, SWAT Report Summary Data, Chapter 15 (formerly Subchapter 15) Information, Chapter 15 Monitoring Parameters, TPCA Program Information, RCRA Program Information, Closure Information, and Interested Parties Information. Date of Government Version: 04/01/00 Date of Data Arrival at EDR: 04/10/00 Elapsed ASTM days: 30 Date Made Active at EDR: 05/10/00 Database Release Frequency: Quarterly Date of Last EDR Contact: 09/08/04 LUST: Leaking Underground Storage Tank Information System Source: State Water Resources Control Board Telephone: 916-341-5752 Leaking Underground Storage Tank Incident Reports. LUST records contain an inventory of reported leaking underground storage tank incidents. Not all states maintain these records, and the information stored varies by state. Date of Data Arrival at EDR: 10/13/04 Date of Government Version: 10/13/04 Date Made Active at EDR: 11/03/04 Elapsed ASTM days: 21 Database Release Frequency: Quarterly Date of Last EDR Contact: 10/13/04 CA BOND EXP. PLAN: Bond Expenditure Plan Source: Department of Health Services Telephone: 916-255-2118 Department of Health Services developed a site-specific expenditure plan as the basis for an appropriation of Hazardous Substance Cleanup Bond Act funds. It is not updated. Date of Government Version: 01/01/89 Date of Data Arrival at EDR: 07/27/94 Date Made Active at EDR: 08/02/94 Elapsed ASTM days: 6 Database Release Frequency: No Update Planned Date of Last EDR Contact: 05/31/94 CA UST: UST: Active UST Facilities Source: SWRCB Telephone: 916-341-5752 Active UST facilities gathered from the local regulatory agencies Date of Government Version: 10/13/04 Date of Data Arrival at EDR: 10/13/04 Date Made Active at EDR: 11/03/04 Elapsed ASTM days: 21 Database Release Frequency: Semi-Annually Date of Last EDR Contact: 10/13/04

į,

Ţ

<u>نې</u>

2

5

÷,

VCP: Voluntary Cleanup Program Properties Source: Department of Toxic Substances Control Telephone: 916-323-3400 Contains low threat level properties with either confirmed or unconfirmed releases and the project proponents have request that DTSC oversee investigation and/or cleanup activities and have agreed to provide coverage for DTSC's costs. Date of Government Version: 10/05/04 Date of Data Arrival at EDR: 10/15/04 Date Made Active at EDR: 11/03/04 Elapsed ASTM days: 19 Database Release Frequency: Quarterly Date of Last EDR Contact: 09/16/04 INDIAN LUST: Leaking Underground Storage Tanks on Indian Land Source: Environmental Protection Agency Telephone: 415-972-3372 LUSTs on Indian land in Arizona, California, New Mexico and Nevada Date of Government Version: 10/03/04 Date of Data Arrival at EDR: 10/06/04 Date Made Active at EDR: 11/03/04 Elapsed ASTM days: 28 Database Release Frequency: Varies Date of Last EDR Contact: 08/23/04 INDIAN LUST: Leaking Underground Storage Tanks on Indian Land Source: EPA Region 10 Telephone: 206-553-2857 LUSTs on Indian land in Alaska, Idaho, Oregon and Washington. Date of Government Version: 09/29/04 Date of Data Arrival at EDR: 10/01/04 Date Made Active at EDR: 10/22/04 Elapsed ASTM days: 21 **Database Release Frequency: Varies** Date of Last EDR Contact: 08/23/04 INDIAN UST: Underground Storage Tanks on Indian Land Source: EPA Region 9 Telephone: 415-972-3368 Date of Government Version: 06/18/04 Date of Data Arrival at EDR: 06/21/04 Date Made Active at EDR: 07/26/04 Elapsed ASTM days: 35 **Database Release Frequency: Varies** Date of Last EDR Contact: 08/23/04 CA FID UST: Facility Inventory Database Source: California Environmental Protection Agency Telephone: 916-445-6532 The Facility Inventory Database (FID) contains a historical listing of active and inactive underground storage tank locations from the State Water Resource Control Board. Refer to local/county source for current data. Date of Government Version: 10/31/94 Date of Data Arrival at EDR: 09/05/95 Date Made Active at EDR: 09/29/95 Elapsed ASTM days: 24 Database Release Frequency: No Update Planned Date of Last EDR Contact: 12/28/98 HIST UST: Hazardous Substance Storage Container Database Source: State Water Resources Control Board Telephone: 916-341-5700 The Hazardous Substance Storage Container Database is a historical listing of UST sites. Refer to local/county source for current data. Date of Government Version: 10/15/90 Date of Data Arrival at EDR: 01/25/91 Date Made Active at EDR: 02/12/91 Elapsed ASTM days: 18 Database Release Frequency: No Update Planned Date of Last EDR Contact: 07/26/01

#### STATE OF CALIFORNIA ASTM SUPPLEMENTAL RECORDS AST: Aboveground Petroleum Storage Tank Facilities Source: State Water Resources Control Board Telephone: 916-341-5712 Registered Aboveground Storage Tanks. Date of Government Version: 12/01/03 Date of Last EDR Contact: 11/01/04 Date of Next Scheduled EDR Contact: 01/31/05 **Database Release Frequency: Quarterly CLEANERS:** Cleaner Facilities Source: Department of Toxic Substance Control Telephone: 916-225-0873 A list of drycleaner related facilities that have EPA ID numbers. These are facilities with certain SIC codes: power laundries, family and commercial; garment pressing and cleaner's agents; linen supply; coin-operated laundries and cleaning; drycleaning plants, except rugs; carpet and upholster cleaning; industrial launderers; laundry and garment services. Date of Government Version: 04/21/04 Date of Last EDR Contact: 11/01/04 Database Release Frequency: Annually Date of Next Scheduled EDR Contact: 01/03/05 CA WDS: Waste Discharge System Source: State Water Resources Control Board Telephone: 916-341-5227 Sites which have been issued waste discharge requirements. Date of Government Version: 10/11/04 Date of Last EDR Contact: 09/21/04 Database Release Frequency: Quarterly Date of Next Scheduled EDR Contact: 12/20/04 **DEED:** List of Deed Restrictions Source: Department of Toxic Substances Control Telephone: 916-323-3400 The use of recorded land use restrictions is one of the methods the DTSC uses to protect the public from unsafe exposures to hazardous substances and wastes. Date of Government Version: 10/04/04 Date of Last EDR Contact: 10/04/04 Database Release Frequency: Semi-Annually Date of Next Scheduled EDR Contact: 01/03/05 NFA: No Further Action Determination Source: Department of Toxic Substances Control Telephone: 916-323-3400 This category contains properties at which DTSC has made a clear determination that the property does not pose a problem to the environment or to public health. Date of Government Version: 10/05/04 Date of Last EDR Contact: 09/16/04 Database Release Frequency: Quarterly Date of Next Scheduled EDR Contact: 11/29/04 EMI: Emissions Inventory Data Source: California Air Resources Board Telephone: 916-322-2990 Toxics and criteria pollutant emissions data collected by the ARB and local air pollution agencies. Date of Government Version: 12/31/02 Date of Last EDR Contact: 10/22/04 **Database Release Frequency: Varies** Date of Next Scheduled EDR Contact: 01/17/05 REF: Unconfirmed Properties Referred to Another Agency Source: Department of Toxic Substances Control Telephone: 916-323-3400

This category contains properties where contamination has not been confirmed and which were determined as not requiring direct DTSC Site Mitigation Program action or oversight. Accordingly, these sites have been referred

3

3

1

to another state or local regulatory agency.

Date of Government Version: 10/05/04 Date of Last EDR Contact: 09/16/04 Database Release Frequency: Quarterly Date of Next Scheduled EDR Contact: 11/29/04 SCH: School Property Evaluation Program Source: Department of Toxic Substances Control Telephone: 916-323-3400 This category contains proposed and existing school sites that are being evaluated by DTSC for possible hazardous materials contamination. In some cases, these properties may be listed in the CalSites category depending on the level of threat to public health and safety or the environment they pose. Date of Government Version: 10/05/04 Date of Last EDR Contact: 09/16/04 Database Release Frequency: Quarterly Date of Next Scheduled EDR Contact: 11/29/04 NFE: Properties Needing Further Evaluation Source: Department of Toxic Substances Control Telephone: 916-323-3400 This category contains properties that are suspected of being contaminated. These are unconfirmed contaminated properties that need to be assessed using the PEA process. PEA in Progress indicates properties where DTSC is currently conducting a PEA. PEA Required indicates properties where DTSC has determined a PEA is required, but not currently underway. Date of Government Version: 10/05/04 Date of Last EDR Contact: 09/16/04 Database Release Frequency: Quarterly Date of Next Scheduled EDR Contact: 11/29/04 SLIC: Statewide SLIC Cases Source: State Water Resources Control Board Telephone: 916-341-5752 The Spills, Leaks, Investigations, and Cleanups (SLIC) listings includes unauthorized discharges from spills and leaks, other than from underground storage tanks or other regulated sites. Date of Government Version: 10/13/04 Date of Last EDR Contact: 10/13/04 Database Release Frequency: Varies Date of Next Scheduled EDR Contact: 01/10/05 HAZNET: Facility and Manifest Data Source: California Environmental Protection Agency Telephone: 916-255-1136 Facility and Manifest Data. The data is extracted from the copies of hazardous waste manifests received each year by the DTSC. The annual volume of manifests is typically 700,000 - 1,000,000 annually, representing approximately 350,000 - 500,000 shipments. Data are from the manifests submitted without correction, and therefore many contain some invalid values for data elements such as generator ID, TSD ID, waste category, and disposal method. Date of Government Version: 12/31/02 Date of Last EDR Contact: 08/09/04 Database Release Frequency: Annually Date of Next Scheduled EDR Contact: 11/08/04 LOCAL RECORDS ALAMEDA COUNTY: Local Oversight Program Listing of UGT Cleanup Sites Source: Alameda County Environmental Health Services Telephone: 510-567-6700

Date of Government Version: 08/17/04 Database Release Frequency: Semi-Annually

**Underground Tanks** 

Source: Alameda County Environmental Health Services Telephone: 510-567-6700 Date of Last EDR Contact: 10/25/04 Date of Next Scheduled EDR Contact: 01/24/05

Date of Government Version: 08/17/04 Database Release Frequency: Semi-Annually Date of Last EDR Contact: 10/25/04 Date of Next Scheduled EDR Contact: 01/24/05

### CONTRA COSTA COUNTY:

#### Site List

Source: Contra Costa Health Services Department Telephone: 925-646-2286 List includes sites from the underground tank, hazardous waste generator and business plan/2185 programs.

Date of Government Version: 08/30/04 Database Release Frequency: Semi-Annually Date of Last EDR Contact: 08/30/04 Date of Next Scheduled EDR Contact: 11/29/04

### FRESNO COUNTY:

**CUPA Resources List** 

Source: Dept. of Community Health

Telephone: 559-445-3271

Certified Unified Program Agency. CUPA's are responsible for implementing a unified hazardous materials and hazardous waste management regulatory program. The agency provides oversight of businesses that deal with hazardous materials, operate underground storage tanks or aboveground storage tanks.

Date of Government Version: 07/21/04 Database Release Frequency: Semi-Annually

#### **KERN COUNTY:**

### Underground Storage Tank Sites & Tank Listing

Source: Kern County Environment Health Services Department Telephone: 661-862-8700 Kern County Sites and Tanks Listing.

Date of Government Version: 09/14/04 Database Release Frequency: Quarterly

#### LOS ANGELES COUNTY:

### List of Solid Waste Facilities

Source: La County Department of Public Works Telephone: 818-458-5185

Date of Government Version: 06/03/03 Database Release Frequency: Varies

- City of El Segundo Underground Storage Tank Source: City of El Segundo Fire Department Telephone: 310-524-2236
  - Date of Government Version: 09/07/04 Database Release Frequency: Semi-Annually
- City of Long Beach Underground Storage Tank Source: City of Long Beach Fire Department Telephone: 562-570-2543

Date of Next Scheduled EDR Contact: 11/08/04

Date of Last EDR Contact: 08/09/04

Date of Last EDR Contact: 09/07/04 Date of Next Scheduled EDR Contact: 12/06/04

Date of Last EDR Contact: 08/19/04 Date of Next Scheduled EDR Contact: 11/15/04

Date of Last EDR Contact: 08/30/04 Date of Next Scheduled EDR Contact: 11/15/04 ý

Date of Government Version: 03/28/03 Database Release Frequency: Annually

#### City of Torrance Underground Storage Tank Source: City of Torrance Fire Department Telephone: 310-618-2973

Date of Government Version: 08/16/04 Database Release Frequency: Semi-Annually

#### **City of Los Angeles Landfills**

Source: Engineering & Construction Division Telephone: 213-473-7869

Date of Government Version: 03/01/04 Database Release Frequency: Varies

#### HMS: Street Number List

Source: Department of Public Works Telephone: 626-458-3517 Industrial Waste and Underground Storage Tank Sites.

Date of Government Version: 04/29/04 Database Release Frequency: Semi-Annually

#### Site Mitigation List

Source: Community Health Services Telephone: 323-890-7806 Industrial sites that have had some sort of spill or complaint.

Date of Government Version: 02/26/04 Database Release Frequency: Annually

### San Gabriel Valley Areas of Concern

Source: EPA Region 9 Telephone: 415-972-3178 San Gabriel Valley areas where VOC contamination is at or above the MCL as designated by region 9 EPA office.

Date of Government Version: 12/31/98 Database Release Frequency: No Update Planned

### MARIN COUNTY:

## Underground Storage Tank Sites

Source: Public Works Department Waste Management Telephone: 415-499-6647 Currently permitted USTs in Marin County.

Date of Government Version: 08/18/04 Database Release Frequency: Semi-Annually

#### NAPA COUNTY:

Sites With Reported Contamination

Source: Napa County Department of Environmental Management Telephone: 707-253-4269

Date of Government Version: 09/29/04 Database Release Frequency: Semi-Annually Date of Last EDR Contact: 08/27/04 Date of Next Scheduled EDR Contact: 11/22/04

Date of Last EDR Contact: 06/16/04 Date of Next Scheduled EDR Contact: 11/15/04

Date of Last EDR Contact: 09/14/04 Date of Next Scheduled EDR Contact: 12/13/04

Date of Last EDR Contact: 08/16/04 Date of Next Scheduled EDR Contact: 11/15/04

Date of Last EDR Contact: 08/16/04 Date of Next Scheduled EDR Contact: 11/15/04

Date of Next Scheduled EDR Contact: N/A

Date of Last EDR Contact: 07/06/99

Date of Last EDR Contact: 11/01/04 Date of Next Scheduled EDR Contact: 01/31/05

Date of Last EDR Contact: 09/27/04 Date of Next Scheduled EDR Contact: 12/27/04

### Closed and Operating Underground Storage Tank Sites

Source: Napa County Department of Environmental Management Telephone: 707-253-4269

Date of Government Version: 09/29/04 Database Release Frequency: Annually

### ORANGE COUNTY:

#### List of Underground Storage Tank Cleanups

Source: Health Care Agency Telephone: 714-834-3446 Orange County Underground Storage Tank Cleanups (LUST).

Date of Government Version: 10/14/04 Database Release Frequency: Quarterly

#### List of Underground Storage Tank Facilities

Source: Health Care Agency Telephone: 714-834-3446 Orange County Underground Storage Tank Facilities (UST).

Date of Government Version: 09/01/04 Database Release Frequency: Quarterly

#### List of Industrial Site Cleanups

Source: Health Care Agency Telephone: 714-834-3446 Petroleum and non-petroleum spills.

Date of Government Version: 09/01/04 Database Release Frequency: Annually

#### PLACER COUNTY:

Master List of Facilities

Source: Placer County Health and Human Services Telephone: 530-889-7312 List includes aboveground tanks, underground tanks and cleanup sites.

Date of Government Version: 10/04/04 Database Release Frequency: Semi-Annually

#### RIVERSIDE COUNTY:

#### Listing of Underground Tank Cleanup Sites Source: Department of Public Health Telephone: 909-358-5055 Riverside County Underground Storage Tank Cleanup Sites (LUST).

Date of Government Version: 06/21/04 Database Release Frequency: Quarterly

Underground Storage Tank Tank List Source: Health Services Agency Telephone: 909-358-5055 Date of Last EDR Contact: 09/27/04 Date of Next Scheduled EDR Contact: 12/27/04 ÷

2

è

2

1000

Date of Last EDR Contact: 09/09/04 Date of Next Scheduled EDR Contact: 12/06/04

Date of Last EDR Contact: 09/09/04 Date of Next Scheduled EDR Contact: 12/06/04

#### Date of Last EDR Contact: 09/09/04 Date of Next Scheduled EDR Contact: 12/06/04

Date of Last EDR Contact: 09/20/04 Date of Next Scheduled EDR Contact: 12/20/04

Date of Last EDR Contact: 10/18/04 Date of Next Scheduled EDR Contact: 01/17/05

Date of Government Version: 06/21/04 Database Release Frequency: Quarterly

#### SACRAMENTO COUNTY:

#### **CS** - Contaminated Sites

Source: Sacramento County Environmental Management Telephone: 916-875-8406

Date of Government Version: 08/28/04 Database Release Frequency: Quarterly

### ML - Regulatory Compliance Master List

Source: Sacramento County Environmental Management Telephone: 916-875-8406

Any business that has hazardous materials on site - hazardous material storage sites, underground storage tanks, waste generators.

Date of Government Version: 09/02/04 Database Release Frequency: Quarterly

Date of Last EDR Contact: 11/02/04 Date of Next Scheduled EDR Contact: 01/31/05

Date of Next Scheduled EDR Contact: 01/31/05

Date of Last EDR Contact: 10/18/04

Date of Last EDR Contact: 10/13/04

Date of Next Scheduled EDR Contact: 01/17/05

## SAN BERNARDINO COUNTY:

### **Hazardous Material Permits**

Source: San Bernardino County Fire Department Hazardous Materials Division

Telephone: 909-387-3041

This listing includes underground storage tanks, medical waste handlers/generators, hazardous materials handlers, hazardous waste generators, and waste oil generators/handlers.

Date of Government Version: 09/17/04 Database Release Frequency: Quarterly

Date of Last EDR Contact: 09/07/04 Date of Next Scheduled EDR Contact: 12/06/04

#### SAN DIEGO COUNTY:

### **Solid Waste Facilities**

Source: Department of Health Services Telephone: 619-338-2209 San Diego County Solid Waste Facilities.

Date of Government Version: 08/01/00 Database Release Frequency: Varies

Date of Last EDR Contact: 08/23/04 Date of Next Scheduled EDR Contact: 11/22/04

## Hazardous Materials Management Division Database

Source: Hazardous Materials Management Division

Telephone: 619-338-2268

The database includes: HE58 - This report contains the business name, site address, business phone number, establishment 'H' permit number, type of permit, and the business status. HE17 - In addition to providing the same information provided in the HE58 listing, HE17 provides inspection dates, violations received by the establishment, hazardous waste generated, the quantity, method of storage, treatment/disposal of waste and the hauler, and information on underground storage tanks. Unauthorized Release List - Includes a summary of environmental contamination cases in San Diego County (underground tank cases, non-tank cases, groundwater contamination, and soil contamination are included.)

Date of Government Version: 06/29/04 Database Release Frequency: Quarterly

Date of Last EDR Contact: 10/08/04 Date of Next Scheduled EDR Contact: 01/03/05

#### SAN FRANCISCO COUNTY:

#### Local Oversite Facilities

Source: Department Of Public Health San Francisco County Telephone: 415-252-3920

Date of Government Version: 09/15/04 Database Release Frequency: Quarterly

#### Underground Storage Tank Information

Source: Department of Public Health Telephone: 415-252-3920

Date of Government Version: 09/15/04 Database Release Frequency: Quarterly

#### SAN MATEO COUNTY:

#### Fuel Leak List

Source: San Mateo County Environmental Health Services Division Telephone: 650-363-1921

Date of Government Version: 10/27/04 Database Release Frequency: Semi-Annually

#### **Business Inventory**

Source: San Mateo County Environmental Health Services Division Telephone: 650-363-1921 List includes Hazardous Materials Business Plan, hazardous waste generators, and underground storage tanks.

Date of Government Version: 08/19/04 Database Release Frequency: Annually

#### SANTA CLARA COUNTY:

#### Fuel Leak Site Activity Report

Source: Santa Clara Valley Water District Telephone: 408-265-2600

Date of Government Version: 06/30/04 Database Release Frequency: Semi-Annually

#### Hazardous Material Facilities

Source: City of San Jose Fire Department Telephone: 408-277-4659

Date of Government Version: 10/01/03 Database Release Frequency: Annually

#### SOLANO COUNTY:

#### Leaking Underground Storage Tanks

Source: Solano County Department of Environmental Management Telephone: 707-421-6770

Date of Government Version: 09/20/04 Database Release Frequency: Quarterly Date of Last EDR Contact: 09/20/04 Date of Next Scheduled EDR Contact: 12/06/04

Date of Last EDR Contact: 09/20/04 Date of Next Scheduled EDR Contact: 12/26/04 1

ż,

5

Ð

5

.

Date of Last EDR Contact: 10/12/04 Date of Next Scheduled EDR Contact: 01/10/05

Date of Next Scheduled EDR Contact: 01/10/05

Date of Last EDR Contact: 10/12/04

Date of Last EDR Contact: 09/27/04 Date of Next Scheduled EDR Contact: 12/27/04

Date of Last EDR Contact: 09/07/04 Date of Next Scheduled EDR Contact: 12/06/04

Date of Last EDR Contact: 09/13/04 Date of Next Scheduled EDR Contact: 12/13/04

#### Underground Storage Tanks

Source: Solano County Department of Environmental Management Telephone: 707-421-6770

Date of Government Version: 09/20/04 Database Release Frequency: Quarterly

#### SONOMA COUNTY:

Leaking Underground Storage Tank Sites Source: Department of Health Services Telephone: 707-565-6565

> Date of Government Version: 10/25/04 Database Release Frequency: Quarterly

#### SUTTER COUNTY:

Underground Storage Tanks

Source: Sutter County Department of Agriculture Telephone: 530-822-7500

Date of Government Version: 01/29/04 Database Release Frequency: Semi-Annually

#### **VENTURA COUNTY:**

# Inventory of Illegal Abandoned and Inactive Sites

Source: Environmental Health Division Telephone: 805-654-2813 Ventura County Inventory of Closed, Illegal Abandoned, and Inactive Sites.

Date of Government Version: 08/01/04 Database Release Frequency: Annually

### Listing of Underground Tank Cleanup Sites

Source: Environmental Health Division Telephone: 805-654-2813 Ventura County Underground Storage Tank Cleanup Sites (LUST).

Date of Government Version: 09/02/04 Database Release Frequency: Quarterly

### **Underground Tank Closed Sites List**

Source: Environmental Health Division Telephone: 805-654-2813 Ventura County Operating Underground Storage Tank Sites (UST)/Underground Tank Closed Sites List.

Date of Government Version: 09/29/04 Database Release Frequency: Quarterly

Business Plan, Hazardous Waste Producers, and Operating Underground Tanks

Source: Ventura County Environmental Health Division

Telephone: 805-654-2813

The BWT list indicates by site address whether the Environmental Health Division has Business Plan (B), Waste Producer (W), and/or Underground Tank (T) information.

Date of Last EDR Contact: 09/13/04 Date of Next Scheduled EDR Contact: 12/13/04

Date of Last EDR Contact: 10/25/04 Date of Next Scheduled EDR Contact: 01/24/05

Date of Last EDR Contact: 10/18/04 Date of Next Scheduled EDR Contact: 01/03/05

Date of Last EDR Contact: 08/25/04 Date of Next Scheduled EDR Contact: 11/22/04

Date of Last EDR Contact: 09/14/04 Date of Next Scheduled EDR Contact: 12/13/04

Date of Next Scheduled EDR Contact: 01/10/05

Date of Last EDR Contact: 10/13/04

Date of Government Version: 09/02/04 Database Release Frequency: Quarterly Date of Last EDR Contact: 09/14/04 Date of Next Scheduled EDR Contact: 12/13/04

•

1. . . . .

tion at state

9

i. Bartonina B

Vic. 17 003

### YOLO COUNTY:

Underground Storage Tank Comprehensive Facility Report	
Source: Yolo County Department of Health Telephone: 530-666-8646	
Date of Government Version: 06/02/04 Database Release Frequency: Annually	Date of Last EDR Contact: 10/18/04 Date of Next Scheduled EDR Contact: 01/17/05
California Regional Water Quality Control Board (RWQCB) LUST	Records
LUST REG 1: Active Toxic Site Investigation Source: California Regional Water Quality Control Board North Coast (1) Telephone: 707-576-2220 Del Norte, Humboldt, Lake, Mendocino, Modoc, Siskiyou, Sonoma, Trinity counties please refer to the State Water Resources Control Board's LUST database.	. For more current information,
Date of Government Version: 02/01/01 Database Release Frequency: No Update Planned	Date of Last EDR Contact: 08/23/04 Date of Next Scheduled EDR Contact: 11/22/04
LUST REG 2: Fuel Leak List Source: California Regional Water Quality Control Board San Francisco Bay Regio Telephone: 510-286-0457	n (2)
Date of Government Version: 09/30/04 Database Release Frequency: Quarterly	Date of Last EDR Contact: 10/13/04 Date of Next Scheduled EDR Contact: 01/10/05
LUST REG 3: Leaking Underground Storage Tank Database Source: California Regional Water Quality Control Board Central Coast Region (3) Telephone: 805-549-3147	
Date of Government Version: 05/19/03 Database Release Frequency: Varies	Date of Last EDR Contact: 08/17/04 Date of Next Scheduled EDR Contact: 11/15/04
LUST REG 4: Underground Storage Tank Leak List Source: California Regional Water Quality Control Board Los Angeles Region (4) Telephone: 213-576-6600	
Los Angeles, Ventura counties. For more current information, please refer to the Sta Board's LUST database.	ate Water Resources Control
Date of Government Version: 09/07/04 Database Release Frequency: No Update Planned	Date of Last EDR Contact: 08/16/04 Date of Next Scheduled EDR Contact: 12/27/04
LUST REG 5: Leaking Underground Storage Tank Database Source: California Regional Water Quality Control Board Central Valley Region (5) Telephone: 916-464-3291	
Date of Government Version: 10/01/04 Database Release Frequency: Quarterly	Date of Last EDR Contact: 10/22/04 Date of Next Scheduled EDR Contact: 01/30/05
LUST REG 6L: Leaking Underground Storage Tank Case Listing Source: California Regional Water Quality Control Board Lahontan Region (6) Telephone: 916-542-5424 For more current information, please refer to the State Water Resources Control Bo	pard's LUST database.

Date of Government Version: 09/09/03 Database Release Frequency: No Update Planned	Date of Last EDR Contact: 09/08/04 Date of Next Scheduled EDR Contact: 12/06/04
LUST REG 6V: Leaking Underground Storage Tank Case Listing Source: California Regional Water Quality Control Board Victorville Branch Office Telephone: 760-346-7491	e (6)
Date of Government Version: 08/09/04 Database Release Frequency: Quarterly	Date of Last EDR Contact: 10/04/04 Date of Next Scheduled EDR Contact: 01/03/05
LUST REG 7: Leaking Underground Storage Tank Case Listing Source: California Regional Water Quality Control Board Colorado River Basin R Telephone: 760-346-7491	Region (7)
Date of Government Version: 02/26/04 Database Release Frequency: Semi-Annually	Date of Last EDR Contact: 09/27/04 Date of Next Scheduled EDR Contact: 12/27/04
LUST REG 8: Leaking Underground Storage Tanks Source: California Regional Water Quality Control Board Santa Ana Region (8) Telephone: 951-782-4130 California Regional Water Quality Control Board Santa Ana Region (8). For more	current information, please refer
to the State Water Resources Control Board's LUST database.	
Date of Government Version: 07/01/04 Database Release Frequency: No Update Planned	Date of Last EDR Contact: 08/09/04 Date of Next Scheduled EDR Contact: 11/08/04
LUST REG 9: Leaking Underground Storage Tank Report Source: California Regional Water Quality Control Board San Diego Region (9) Telephone: 858-467-2980 Orange, Riverside, San Diego counties. For more current information, please refe Control Board's LUST database.	r to the State Water Resources
Date of Government Version: 03/01/01 Database Release Frequency: No Update Planned	Date of Last EDR Contact: 10/18/04 Date of Next Scheduled EDR Contact: 01/17/05
California Regional Water Quality Control Board (RWQCB) SLIC	C Records
SLIC REG 1: Active Toxic Site Investigations Source: California Regional Water Quality Control Board, North Coast Region (1) Telephone: 707-576-2220	
Date of Government Version: 04/03/03 Database Release Frequency: Semi-Annually	Date of Last EDR Contact: 08/23/04 Date of Next Scheduled EDR Contact: 11/22/04
<ul> <li>SLIC REG 2: Spills, Leaks, Investigation &amp; Cleanup Cost Recovery Listing Source: Regional Water Quality Control Board San Francisco Bay Region (2) Telephone: 510-286-0457</li> <li>Any contaminated site that impacts groundwater or has the potential to impact group</li> </ul>	undwater.
Date of Government Version: 09/30/04 Database Release Frequency: Quarterly	Date of Last EDR Contact: 10/13/04 Date of Next Scheduled EDR Contact: 01/10/05
SLIC REG 3: Spills, Leaks, Investigation & Cleanup Cost Recovery Listing Source: California Regional Water Quality Control Board Central Coast Region (3) Telephone: 805-549-3147 Any contaminated site that impacts groundwater or has the potential to impact group of the second sec	
Date of Government Version: 08/20/04 Database Release Frequency: Semi-Annually	Date of Last EDR Contact: 08/16/04 Date of Next Scheduled EDR Contact: 11/15/04

Telephone: 213-576-6600 Any contaminated site that impacts groundwater or has the potential to	impact groundwater.
Date of Government Version: 07/08/04	Date of Last EDR Contact: 10/25/04
Database Release Frequency: Quarterly	Date of Next Scheduled EDR Contact: 01/24/0
SLIC REG 5: Spills, Leaks, Investigation & Cleanup Cost Recovery Listin Source: Regional Water Quality Control Board Central Valley Region ( Telephone: 916-464-3291 Unregulated sites that impact groundwater or have the potential to imp	(5)
Date of Government Version: 04/01/04	Date of Last EDR Contact: 10/06/04
Database Release Frequency: Semi-Annually	Date of Next Scheduled EDR Contact: 01/03/0
SLIC REG 6L: SLIC Sites Source: California Regional Water Quality Control Board, Lahontan Re Telephone: 530-542-5574	egion
Date of Government Version: 09/07/04	Date of Last EDR Contact: 09/07/04
Database Release Frequency: Varies	Date of Next Scheduled EDR Contact: 12/06/0
SLIC REG 6V: Spills, Leaks, Investigation & Cleanup Cost Recovery List Source: Regional Water Quality Control Board, Victorville Branch Telephone: 619-241-6583	ing
Date of Government Version: 04/01/04	Date of Last EDR Contact: 10/04/04
Database Release Frequency: Semi-Annually	Date of Next Scheduled EDR Contact: 01/03/0
SLIC REG 7: SLIC List Source: California Regional Quality Control Board, Colorado River Bas Telephone: 760-346-7491	sin Region
Date of Government Version: 08/25/04	Date of Last EDR Contact: 08/23/04
Database Release Frequency: Varies	Date of Next Scheduled EDR Contact: 11/22/0
SLIC REG 8: Spills, Leaks, Investigation & Cleanup Cost Recovery Listin Source: California Region Water Quality Control Board Santa Ana Reg Telephone: 951-782-3298	ig jion (8)
Date of Government Version: 07/01/04	Date of Last EDR Contact: 10/08/04
Database Release Frequency: Semi-Annually	Date of Next Scheduled EDR Contact: 01/03/0
SLIC REG 9: Spills, Leaks, Investigation & Cleanup Cost Recovery Listin Source: California Regional Water Quality Control Board San Diego R Telephone: 858-467-2980	
Date of Government Version: 09/10/04	Date of Last EDR Contact: 08/30/04
Database Release Frequency: Annually	Date of Next Scheduled EDR Contact: 11/29/04

Former Manufactured Gas (Coal Gas) Sites: The existence and location of Coal Gas sites is provided exclusively to EDR by Real Property Scan, Inc. ©Copyright 1993 Real Property Scan, Inc. For a technical description of the types of hazards which may be found at such sites, contact your EDR customer service representative.

.

#### Disclaimer Provided by Real Property Scan, Inc.

The information contained in this report has predominantly been obtained from publicly available sources produced by entities other than Real Property Scan. While reasonable steps have been taken to insure the accuracy of this report, Real Property Scan does not guarantee the accuracy of this report. Any liability on the part of Real Property Scan is strictly limited to a refund of the amount paid. No claim is made for the actual existence of toxins at any site. This report does not constitute a legal opinion.

## BROWNFIELDS DATABASES

VCP: Voluntary Cleanup Program Properties Source: Department of Toxic Substances Control

Telephone: 916-323-3400

Contained law the at law

Contains low threat level properties with either confirmed or unconfirmed releases and the project proponents have request that DTSC oversee investigation and/or cleanup activities and have agreed to provide coverage for DTSC's costs.

Date of Government Version: 10/05/04 Database Release Frequency: Quarterly

Date of Last EDR Contact: 09/16/04 Date of Next Scheduled EDR Contact: 11/29/04

US BROWNFIELDS: A Listing of Brownfields Sites

Source: Environmental Protection Agency

Telephone: 202-566-2777

Included in the listing are brownfields properties addresses by Cooperative Agreement Recipients and brownfields properties addressed by Targeted Brownfields Assessments. Targeted Brownfields Assessments-EPA's Targeted Brownfields Assessments (TBA) program is designed to help states, tribes, and municipalities—especially those without EPA Brownfields Assessment Demonstration Pilots—minimize the uncertainties of contamination often associated with brownfields. Under the TBA program, EPA provides funding and/or technical assistance for environmental assessments at brownfields initiative to country. Targeted Brownfields Assessments supplement and work with other efforts under EPA's Brownfields Initiative to promote cleanup and redevelopment of brownfields. Cooperative Agreement Recipients-States, political subdivisions, territories, and Indian tribes become Brownfields Cleanup Revolving Loan Fund (BCRLF) cooperative agreement recipients when they enter into BCRLF cooperative agreements with the U.S. EPA. EPA selects BCRLF cooperative agreement recipients based on a proposal and application process. BCRLF cooperative agreement recipients must use EPA funds provided through BCRLF cooperative agreement for specified brownfields-related cleanup activities.

Date of Government Version: N/A Database Release Frequency: Semi-Annually

Date of Last EDR Contact: N/A Date of Next Scheduled EDR Contact: N/A

#### **OTHER DATABASE(S)**

Depending on the geographic area covered by this report, the data provided in these specialty databases may or may not be complete. For example, the existence of wetlands information data in a specific report does not mean that all wetlands in the area covered by the report are included. Moreover, the absence of any reported wetlands information does not necessarily mean that wetlands do not exist in the area covered by the report.

**Oil/Gas Pipelines:** This data was obtained by EDR from the USGS in 1994. It is referred to by USGS as GeoData Digital Line Graphs from 1:100,000-Scale Maps. It was extracted from the transportation category including some oil, but primarily gas pipelines.

#### **Electric Power Transmission Line Data**

Source: PennWell Corporation

Telephone: (800) 823-6277

This map includes information copyrighted by PennWell Corporation. This information is provided

on a best effort basis and PennWell Corporation does not guarantee its accuracy nor warrant its

fitness for any particular purpose. Such information has been reprinted with the permission of PennWell.

Sensitive Receptors: There are individuals deemed sensitive receptors due to their fragile immune systems and special sensitivity to environmental discharges. These sensitive receptors typically include the elderly, the sick, and children. While the location of all sensitive receptors cannot be determined, EDR indicates those buildings and facilities - schools, daycares, hospitals, medical centers, and nursing homes - where individuals who are sensitive receptors are likely to be located.

#### AHA Hospitals:

Source: American Hospital Association, Inc.

Telephone: 312-280-5991

The database includes a listing of hospitals based on the American Hospital Association's annual survey of hospitals.

Medical Centers: Provider of Services Listing

Source: Centers for Medicare & Medicaid Services

Telephone: 410-786-3000

A listing of hospitals with Medicare provider number, produced by Centers of Medicare & Medicaid Services,

a federal agency within the U.S. Department of Health and Human Services.

•

#### Nursing Homes

Source: National Institutes of Health

Telephone: 301-594-6248 Information on Medicare and Medicaid certified nursing homes in the United States.

#### Public Schools

Source: National Center for Education Statistics

Telephone: 202-502-7300

The National Center for Education Statistics' primary database on elementary

and secondary public education in the United States. It is a comprehensive, annual, national statistical database of all public elementary and secondary schools and school districts, which contains data that are

comparable across all states.

#### Private Schools

Source: National Center for Education Statistics Telephone: 202-502-7300

The National Center for Education Statistics' primary database on private school locations in the United States.

**Daycare Centers: Licensed Facilities** 

Source: Department of Social Services Telephone: 916-657-4041

**Flood Zone Data:** This data, available in select counties across the country, was obtained by EDR in 1999 from the Federal Emergency Management Agency (FEMA). Data depicts 100-year and 500-year flood zones as defined by FEMA.

NWI: National Wetlands Inventory. This data, available in select counties across the country, was obtained by EDR in 2002 from the U.S. Fish and Wildlife Service.

#### STREET AND ADDRESS INFORMATION

© 2003 Geographic Data Technology, Inc., Rel. 07/2003. This product contains proprietary and confidential property of Geographic Data Technology, Inc. Unauthorized use, including copying for other than testing and standard backup procedures, of this product is expressly prohibited.

1

Q,

2

# **GEOCHECK ®- PHYSICAL SETTING SOURCE ADDENDUM**

#### TARGET PROPERTY ADDRESS

BUCKLEY SCHOOL 3900 STANSBURY AVENUE SHERMAN OAKS, CA 91423

#### TARGET PROPERTY COORDINATES

 Latitude (North):
 34.139599 - 34* 8' 22.6"

 Longitude (West):
 118.443604 - 118* 26' 37.0"

 Universal Tranverse Mercator:
 Zone 11

 UTM X (Meters):
 366896.9

 UTM Y (Meters):
 3778381.0

 Elevation:
 797 ft. above sea level

EDR's GeoCheck Physical Setting Source Addendum has been developed to assist the environmental professional with the collection of physical setting source information in accordance with ASTM 1527-00, Section 7.2.3. Section 7.2.3 requires that a current USGS 7.5 Minute Topographic Map (or equivalent, such as the USGS Digital Elevation Model) be reviewed. It also requires that one or more additional physical setting sources be sought when (1) conditions have been identified in which hazardous substances or petroleum products are likely to migrate to or from the property, and (2) more information than is provided in the current USGS 7.5 Minute Topographic Map (or equivalent) is generally obtained, pursuant to local good commercial or customary practice, to assess the impact of migration of recognized environmental conditions in connection with the property. Such additional physical setting sources generally include information about the topographic, hydrologic, hydrogeologic, and geologic characteristics of a site, and wells in the area.

Assessment of the impact of contaminant migration generally has two principle investigative components:

1. Groundwater flow direction, and

2. Groundwater flow velocity.

Groundwater flow direction may be impacted by surface topography, hydrology, hydrogeology, characteristics of the soil, and nearby wells. Groundwater flow velocity is generally impacted by the nature of the geologic strata. EDR's GeoCheck Physical Setting Source Addendum is provided to assist the environmental professional in forming an opinion about the impact of potential contaminant migration.

### **GROUNDWATER FLOW DIRECTION INFORMATION**

Groundwater flow direction for a particular site is best determined by a qualified environmental professional using site-specific well data. If such data is not reasonably ascertainable, it may be necessary to rely on other sources of information, such as surface topographic information, hydrologic information, hydrogeologic data collected on nearby properties, and regional groundwater flow information (from deep aquifers).


#### TOPOGRAPHIC INFORMATION

Surface topography may be indicative of the direction of surficial groundwater flow. This information can be used to assist the environmental professional in forming an opinion about the impact of nearby contaminated properties or, should contamination exist on the target property, what downgradient sites might be impacted.

#### TARGET PROPERTY TOPOGRAPHY

USGS Topographic Map:	34118-B4 VAN NUYS, CA
General Topographic Gradient:	General NNE
Source:	USGS 7.5 min quad index

#### SURROUNDING TOPOGRAPHY: ELEVATION PROFILES



Source: Topography has been determined from the USGS 7.5' Digital Elevation Model and should be evaluated on a relative (not an absolute) basis. Relative elevation information between sites of close proximity should be field verified.

# **GEOCHECK® - PHYSICAL SETTING SOURCE SUMMARY**

### HYDROLOGIC INFORMATION

Surface water can act as a hydrologic barrier to groundwater flow. Such hydrologic information can be used to assist the environmental professional in forming an opinion about the impact of nearby contaminated properties or, should contamination exist on the target property, what downgradient sites might be impacted.

Refer to the Physical Setting Source Map following this summary for hydrologic information (major waterways and bodies of water).

#### FEMA FLOOD ZONE

Target Property County LOS ANGELES, CA	FEMA Flood Electronic Data YES - refer to the Overview Map and Detail Map
Flood Plain Panel at Target Property:	0601370045C
Additional Panels in search area:	0601370044C 0601370053C 0601370052C
NATIONAL WETLAND INVENTORY	
NWI Quad at Target Property VAN NUYS	NWI Electronic <u>Data Coverage</u> YES - refer to the Overview Map and Detail Map

### HYDROGEOLOGIC INFORMATION

Hydrogeologic information obtained by installation of wells on a specific site can often be an indicator of groundwater flow direction in the immediate area. Such hydrogeologic information can be used to assist the environmental professional in forming an opinion about the impact of nearby contaminated properties or, should contamination exist on the target property, what downgradient sites might be impacted.

Site-Specific Hydrogeological Data*:			
Search Radius:	1.25 miles		
Status:	Not found		

#### **AQUIFLOW®**

Search Radius: 1.000 Mile.

EDR has developed the AQUIFLOW Information System to provide data on the general direction of groundwater flow at specific points. EDR has reviewed reports submitted by environmental professionals to regulatory authorities at select sites and has extracted the date of the report, groundwater flow direction as determined hydrogeologically, and the depth to water table.

MAP ID Not Reported LOCATION FROM TP GENERAL DIRECTION GROUNDWATER FLOW

### **GROUNDWATER FLOW VELOCITY INFORMATION**

Groundwater flow velocity information for a particular site is best determined by a qualified environmental professional using site specific geologic and soil strata data. If such data are not reasonably ascertainable, it may be necessary to rely on other sources of information, including geologic age identification, rock stratigraphic unit and soil characteristics data collected on nearby properties and regional soil information. In general, contaminant plumes move more quickly through sandy-gravelly types of soils than silty-clayey types of soils.

### **GEOLOGIC INFORMATION IN GENERAL AREA OF TARGET PROPERTY**

Geologic information can be used by the environmental professional in forming an opinion about the relative speed at which contaminant migration may be occurring.

#### ROCK STRATIGRAPHIC UNIT

**GEOLOGIC AGE IDENTIFICATION** 

r,

ŝ,

P

3

E. S. S. S.

Era:	Cenozoic Categ	ory:	Stratified Sequence
System:	Tertiary		
Series:	Miocene		
Code:	Tm (decoded above as Era, System & Series)		

Geologic Age and Rock Stratigraphic Unit Source: P.G. Schruben, R.E. Arndt and W.J. Bawiec, Geology of the Conterminous U.S. at 1:2,500,000 Scale - a digital representation of the 1974 P.B. King and H.M. Beikman Map, USGS Digital Data Series DDS - 11 (1994).

### DOMINANT SOIL COMPOSITION IN GENERAL AREA OF TARGET PROPERTY

The U.S. Department of Agriculture's (USDA) Soil Conservation Service (SCS) leads the National Cooperative Soil Survey (NCSS) and is responsible for collecting, storing, maintaining and distributing soil survey information for privately owned lands in the United States. A soil map in a soil survey is a representation of soil patterns in a landscape. Soil maps for STATSGO are compiled by generalizing more detailed (SSURGO) soil survey maps. The following information is based on Soil Conservation Service STATSGO data.

Soil Component Name:	HAMBRIGHT		
Soil Surface Texture:	gravelly - loam		
Hydrologic Group:	Class D - Very slow infiltration rates. Soils are clayey, have a high water table, or are shallow to an impervious layer.		
Soil Drainage Class:	Well drained. Soils have intermediate water holding capacity. Depth to water table is more than 6 feet.		
Hydric Status: Soil does not meet the requirements for a hydric soil.			

Corrosion Potential - Uncoated Steel: MODERATE

Depth to Bedrock Min:	> 10 inches
-----------------------	-------------

Depth to Bedrock Max: > 20 inches

. -

	Soil Layer Information						
	Βοι	undary	1	Classification			
Layer	Upper	Lower	Soil Texture Class	AASHTO Group	Unified Soil	Permeability Rate (in/hr)	Soil Reaction (pH)
1	0 inches	7 inches	gravelly - loam	Silt-Clay Materials (more than 35 pct. passing No. 200), Silty Soils.	COARSE-GRAINED SOILS, Gravels, Gravels with fines, Silty Grave!	Max: 2.00 Min: 0.60	Max: 7.30 Min: 6.10
2	7 inches	16 inches	very gravelly - loam	Granular materials (35 pct. or less passing No. 200), Silty, or Clayey Gravel and Sand.	COARSE-GRAINED SOILS, Gravels, Gravels with fines, Silty Gravel. COARSE-GRAINED SOILS, Gravels, Gravels with fines, Clayey Gravel.	Max: 2.00 Min: 0.60	Max: 7.30 Min: 6.10
3	16 inches	20 inches	unweathered bedrock	Not reported	Not reported	Max: 0.00 Min: 0.00	Max: 0.00 Min: 0.00

## OTHER SOIL TYPES IN AREA

Based on Soil Conservation Service STATSGO data, the following additional subordinant soil types may appear within the general area of target property.

Soil Surface Textures:	loam silty clay loam shaly - clay loam sandy loam loamy sand clay clay loam
Surficial Soil Types:	loam silty clay loam shaly - clay loam sandy loam loamy sand clay clay loam
Shallow Soil Types:	silty clay
Deeper Soil Types:	weathered bedrock clay loam

#### ADDITIONAL ENVIRONMENTAL RECORD SOURCES

According to ASTM E 1527-00, Section 7.2.2, "one or more additional state or local sources of environmental records may be checked, in the discretion of the environmental professional, to enhance and supplement federal and state sources... Factors to consider in determining which local or additional state records, if any, should be checked include (1) whether they are reasonably ascertainable, (2) whether they are sufficiently useful, accurate, and complete in light of the objective of the records review (see 7.1.1), and (3) whether they are obtained, pursuant to local, good commercial or customary practice." One of the record sources listed in Section 7.2.2 is water well information. Water well information can be used to assist the environmental professional in assessing sources that may impact groundwater flow direction, and in forming an opinion about the impact of contaminant migration on nearby drinking water wells.

#### WELL SEARCH DISTANCE INFORMATION

DATABASE	SEARCH DISTANCE (miles)		
Federal USGS	1.000		
Federal FRDS PWS	Nearest PWS within 1 mile		
State Database	1.000		

#### FEDERAL USGS WELL INFORMATION

		LOCATION
MAP ID	WELL ID	FROM TP
No Wells Found		·

#### FEDERAL FRDS PUBLIC WATER SUPPLY SYSTEM INFORMATION

MAP ID	WELL ID

No PWS System Found


Note: PWS System location is not always the same as well location.

### STATE DATABASE WELL INFORMATION

MAP ID No Wells Found WELL ID

LOCATION FROM TP

LOCATION FROM TP .



Copyright © 2004 EDR. Inc. ⊕ 2003 GDT, Inc. Ret. 07/2003. All Rights Reserved.

# GEOCHECK® - PHYSICAL SETTING SOURCE MAP FINDINGS RADON

# AREA RADON INFORMATION

State Database: CA Radon

Radon Test Results

Zip	Total Sites	> 4 Pci/L	Pct. > 4 Pci/L
91423	102	14	13.73

Federal EPA Radon Zone for LOS ANGELES County: 2

Note: Zone 1 indoor average level > 4 pCi/L.

: Zone 2 indoor average level >= 2 pCi/L and <= 4 pCi/L. : Zone 3 indoor average level < 2 pCi/L.

Federal Area Radon Information for Zip Code: 91423

Number of sites tested: 1

Area	Average Activity	% <4 pCi/L	% 4-20 pCi/L	% >20 pCi/L
Living Area - 1st Floor	0.500 pCi/L	100%	0%	0%
Living Area - 2nd Floor	Not Reported	Not Reported	Not Reported	Not Reported
Basement	Not Reported	Not Reported	Not Reported	Not Reported

# PHYSICAL SETTING SOURCE RECORDS SEARCHED

#### TOPOGRAPHIC INFORMATION

### USGS 7.5' Digital Elevation Model (DEM)

Source: United States Geologic Survey

EDR acquired the USGS 7.5' Digital Elevation Model in 2002. 7.5-Minute DEMs correspond to the USGS 1:24,000- and 1:25,000-scale topographic quadrangle maps.

#### HYDROLOGIC INFORMATION

Flood Zone Data: This data, available in select counties across the country, was obtained by EDR in 1999 from the Federal Emergency Management Agency (FEMA). Data depicts 100-year and 500-year flood zones as defined by FEMA.

NWI: National Wetlands Inventory. This data, available in select counties across the country, was obtained by EDR in 2002 from the U.S. Fish and Wildlife Service.

#### HYDROGEOLOGIC INFORMATION

#### AQUIFLOW^R Information System

Source: EDR proprietary database of groundwater flow information

EDR has developed the AQUIFLOW Information System (AIS) to provide data on the general direction of groundwater flow at specific points. EDR has reviewed reports submitted to regulatory authorities at select sites and has extracted the date of the report, hydrogeologically determined groundwater flow direction and depth to water table information.

#### **GEOLOGIC INFORMATION**

#### Geologic Age and Rock Stratigraphic Unit

Source: P.G. Schruben, R.E. Arndt and W.J. Bawiec, Geology of the Conterminous U.S. at 1:2,500,000 Scale - A digital representation of the 1974 P.B. King and H.M. Beikman Map, USGS Digital Data Series DDS - 11 (1994).

#### STATSGO: State Soil Geographic Database

Source: Department of Agriculture, Natural Resources Conservation Services

The U.S. Department of Agriculture's (USDA) Natural Resources Conservation Service (NRCS) leads the national Conservation Soil Survey (NCSS) and is responsible for collecting, storing, maintaining and distributing soil survey information for privately owned lands in the United States. A soil map in a soil survey is a representation of soil patterns in a landscape. Soil maps for STATSGO are compiled by generalizing more detailed (SSURGO) soil survey maps.

#### ADDITIONAL ENVIRONMENTAL RECORD SOURCES

#### FEDERAL WATER WELLS

PWS: Public Water Systems

Source: EPA/Office of Drinking Water

Telephone: 202-564-3750

Public Water System data from the Federal Reporting Data System. A PWS is any water system which provides water to at least 25 people for at least 60 days annually. PWSs provide water from wells, rivers and other sources.

PWS ENF: Public Water Systems Violation and Enforcement Data

Source: EPA/Office of Drinking Water

Telephone: 202-564-3750

Violation and Enforcement data for Public Water Systems from the Safe Drinking Water Information System (SDWIS) after August 1995. Prior to August 1995, the data came from the Federal Reporting Data System (FRDS).

USGS Water Wells: USGS National Water Inventory System (NWIS)

This database contains descriptive information on sites where the USGS collects or has collected data on surface water and/or groundwater. The groundwater data includes information on wells, springs, and other sources of groundwater.

# PHYSICAL SETTING SOURCE RECORDS SEARCHED

#### STATE RECORDS

#### California Drinking Water Quality Database

Source: Department of Health Services

Telephone: 916-324-2319

The database includes all drinking water compliance and special studies monitoring for the state of California since 1984. It consists of over 3,200,000 individual analyses along with well and water system information.

#### California Oil and Gas Well Locations for District 2, 3, 5 and 6

Source: Department of Conservation Telephone: 916-323-1779

#### RADON

#### State Database: CA Radon

Source: Department of Health Services Telephone: 916-324-2208 Radon Database for California

#### Area Radon Information

Source: USGS

Telephone: 703-356-4020

The National Radon Database has been developed by the U.S. Environmental Protection Agency (USEPA) and is a compilation of the EPA/State Residential Radon Survey and the National Residential Radon Survey. The study covers the years 1986 - 1992. Where necessary data has been supplemented by information collected at private sources such as universities and research institutions.

#### EPA Radon Zones

Source: EPA Telephone: 703-356-4020 Sections 307 & 309 of IRAA directed EPA to list and identify areas of U.S. with the potential for elevated indoor radon levels.

#### OTHER

Airport Landing Facilities: Private and public use landing facilities Source: Federal Aviation Administration, 800-457-6656

**Epicenters:** World earthquake epicenters, Richter 5 or greater Source: Department of Commerce, National Oceanic and Atmospheric Administration

**California Earthquake Fault Lines:** The fault lines displayed on EDR's Topographic map are digitized quaternary fault lines, prepared in 1975 by the United State Geological Survey. Additional information (also from 1975) regarding activity at specific fault lines comes from California's Preliminary Fault Activity Map prepared by the California Division of Mines and Geology.

# Appendix 2 Agency File Review Records

# LAFD Files

### 1. <u>SUMMARY OF SOIL GAS ANALYSIS</u>

- 1.1 <u>Date</u>: August 11, 1988 1.2 <u>Project No.</u>: 33501
- 1.3 Job Location:

3900 Stansbury Road, Sherman Oaks, California

### 1.4 Current Status of the Job Site:

- A. Currently operating school and related facilities.
- B. One 10,000 gallon gasoline tank removed in July 1988.
- C. High concentration of hydrocarbons found at the bottom of tank excavation.

### 1.5 <u>Reason for Conducting Soil Gas Analysis:</u>

Preliminary investigation of subsurface soil contamination.

1.6 Detector Unit Used: Photovac TIP II

Photoionization Detector With Detection Limit of 50 ppb (for Benzene) and a Performance Range of Up to 2,000 ppm

1.7 <u>Total No. of Vapor Concentration Readings:</u> 29

### 1.8 <u>Summary of Results</u>:

Soil gas analysis detected a localized area of potential subsurface contamination near the tank excavation. The soil gas survey did not detect <u>extensive</u> contamination, but the high level of contamination found at the north end of the tank excavation and the hydrocarbon odors detected in the ground water being pumped from the sump beneath the Pavilion building strongly suggests that fuel from the tank and/or piping has migrated downward to the underlying ground water table.

### 2. TESTING PROCEDURE AND METHODOLOGY

At the site, half-inch diameter boreholes were established throughout the area by drilling through the overlying pavement to a depth of one (1) to one and a half (1.5) feet. However, somewhat more emphasis was placed on certain locations where leakage typically occurs (e.g., around the tank and piping excavation). Boreholes located in areas other than these strategic points were established to detect possible or unexpected subsurface pollution owing to the migration of released fuel, or organic vapor, and to obtain representative background values for comparison purposes. After each boring was drilled, a thin plastic film was placed over each hole to allow vapors to diffuse into and equilibrate within each borehole. After drilling was completed, vapor samples were withdrawn from each borehole in the same order as they were drilled. All samples were obtained by carefully penetrating the plastic film with the detector's sampling probe.


sensing instrument used in this project The is a photoionization detector manufactured by Photovac, Inc. (Photovac TIP II). This unit has a detection limit of 50 ppb (for benzene) and a performance range of up to 2,000 ppm for total ionizable hydrocarbons at 10.6 eV. As recommended by the manufacturer, the span control adjusted to give the Photovac TIP II a mid-range sensitivity. The calibration of Photovac TIP II, and the calculation of approximate actual vapor concentration based on the field Photovac readings, are discussed in Appendix A. The TIP II reading was adjusted to zero with respect to ambient air before taking vapor readings from each borehole.


It important to recognize that is the "soil gas" technique applied here is not a direct measurement of soil and ground water pollution. These results should be used qualitatively to show probable contamination and tendencies of possible leakage and subsurface migration. In addition, they will be useful in the planning of subsequent detailed remedial investigation, which will include soil borings and direct soil sampling at several locations and depths, and chemical analysis of soil and ground water samples. Final decisions should be based on complete remedial а investigation, which will delineate more accurately the nature and extent of subsurface contamination.

#### 3. **DISCUSSION OF RESULTS**

A total of 29 boreholes were drilled at the site for the soil gas investigation. Drawing 1T shows the locations of the 16 boreholes drilled around the tank excavation area; Drawing 1P shows the locations of the 13 boreholes around the Pavilion (gym). Table 1 and Drawings 2T and 2P present the soil gas sampling data for these areas. Drawings 3T and 3P are the contour maps generated on the basis of field TIP II readings.

2







# TABLE 1 Soil Gas Sampling Data Buckley School


Project No.:	33501
Job Location:	3900 Stansbury Road, Sherman Oaks, CA
Detector Unit:	Photovac TIP II
Date of Sampling:	August 11, 1988
PID Span Setting:	1.0

Boring <u>No.</u>	Field PID <u>Reading</u>	Approximate Isobutylene Equivalent <u>Conc. (ppm)</u>
	Pavilion Area	······································
P-1	12.6	3.92
P-2	46.2	14.37
P-3	3.0	0.89
P4	20.0	6.22
P-5	9.2	2.86
P-6	5.9	1.83
P-7	0.0	0.00
P-8	0.4	0.12
P-9	6.1	1.90
P-10	5.4	1.68
P-11	11.4	3.55
P-12	6.1	1.90
P-13	0.7	0.22
	Tank Excavation Are	a
A <u></u>		
T-1	77.7	24.16
T-2	28.9	8.99
T-3	27.0	8.40
Т-4	20.4	6.34
T-5	38.8	12.07
T-6	17.6	5.47
T-7	57.6	17.91
T-8	33.6	10.45
<b>T-9</b>	20.2	6.28
T-10	1071.0	333.05
T-11	76.1	23.67
T-12	65.1	20.24
T-13	16.9	5.26
T-14	30.8	9.58
T-15	22.3	6.93
T-16	14.6	4.54




് പ്രവാനം പ്രതികള് പ്രതിന്റെ പ്രതിന്റെ പ്രതിന്റെ പ്രതിന്റെ പ്രതിന്റെ പ്രതിന്റെ പ്രതിന്റെ പ്രതിന്റെ പ്രതിന്റെ പ പ്രതിന്റെ പ





stature da



The area between the parking lot where the tank was located (Drawing 3T) and the Pavilion building (Drawing 3P) is a steep hillside, dropping roughly 40 feet in elevation in a lateral distance of 150 feet.

soil gas survey was proposed an initial The as investigation of hydrocarbon contamination discovered in the tank excavation as well as in the ground water being pumped from a sump near the swimming pool located on the lower basement floor of the Pavilion building. Based on pumping records, the ground water level is approximately The 35 feet below the ground surface at this building. pumping is used to keep the buoyant force of the water from structurally damaging the pool by depressing the water table at that location. The water level is depressed at least 8-10 feet at that location due to This water level drawdown and the this activity. resulting cone of depression in the water surface may be locally altering the ground water flow direction and effectively drawing contaminated water from the area beneath the tank excavation.

At the tank excavation area, background vapor readings were in the approximate range of 4 to 10 ppm. A single highly elevated reading of 333 ppm was obtained from Boring T-10 close to the tank excavation. Borings T-1, T-5, T-7, T-11, and T-12 registered slightly elevated readings of 10 to 25 ppm. (See Drawings No. 1T and 2T.)

At the Pavilion building, all soil gas borings registered generally low readings, with Borings T-2, T-3, and T-4 at the west corner of the building registering readings of 14.4 ppm, 5.2 ppm, and 6.22 ppm respectively, which may be slightly above background levels. (See Drawings No. 1P and 2P.)

Although the soil gas survey did not detect extensive contamination, the high level of contamination found at the north end of the tank excavation and the hydrocarbon odors detected in the ground water being pumped from the sump beneath the Pavilion building strongly suggest that fuel from the tank and/or piping has migrated downward to the underlying ground water. Based on the depth to water beneath the Pavilion building, the depth to ground water from the tank area and hence the possible vertical extent of soil contamination is estimated to be 60 to 90 feet.

The single highly elevated reading near the tank excavation (Boring T-14) combined with the lower vapor readings obtained in that same area, suggest that the lateral extent of soil contamination <u>may</u> be limited. However, because of the shallow borings used for soil

. -

1.000

100 C

ana manananya.

3

gas surveys, the permeability of the underlying soils can strongly affect the vapor readings by influencing the upward migration of volatile gases.

A foundation investigation conducted by Converse, Davis and Associates (Appendix B) indicates layers of silts and clayey silts beneath the area of the Science and Pavilion buildings. These layers may be impeding the upward migration of the vapors from the ground water beneath the Pavilion building, which is known to be The low vapor readings collected at the contaminated. west corner of the Pavilion building may be due to contamination migrating via the ground water table from the tank excavation area. Further investigation will be required to determine the nature and extent of the subsurface contamination at this facility. The following section describes the proposed investigative site assessment work.

#### 4. PROPOSAL FOR FURTHER INVESTIGATION


#### 4.1 Introduction

The objective of the proposed work is to investigate and further identify the extent of subsurface soil and ground water contamination previously identified at the site. The work proposed is designed to satisfy Los Angeles City Fire Department requirements for an initial site assessment.

#### 4.2 Monitoring Well Location and Drilling

Three ground water wells (M1, M2, and M3) are proposed for installation at locations shown on Drawing 4. Well M1 will be drilled near the north end of the tank excavation where the previous chemical analysis following tank removal showed the highest concentration of contaminants. (See Table 2.) Well M2 will be located near the perimeter of the Pavilion building, where hydrocarbon odors had been detected in the ground water being pumped. Well M3 will be positioned appropriately to allow a determination of the ground water direction and further define the extent of possible ground water contamination.

A review of the foundation investigation conducted by Converse, Davis & Associates (Appendix B) indicates that bedrock may be encountered during this work. The site also has steep, possibly unstable hillsides and limited access to suitable drilling areas. For these reasons, the most



appropriate drilling technique and exact well placement will be determined after further review of the conditions at the site.

#### TABLE 2

#### Results of Chemical Analysis on Soil Samples Taken During Tank Removal (July 1988)

<u>Sample No.</u>	Depth	<u>Test</u>	Analytical Results
1*	14' B.G. 2' B.I.	8015 M	46,600 mg/kg
2*	14' B.G. 2' B.I.	8015 M	144 mg/kg

B. G. = Below Grade

B. I. = Below Invert

. -

* Sample #1 taken from north end of tank excavation. Sample #2 taken from south end of tank excavation.

#### 4.3 Soil Sampling Procedures

Soil samples will be obtained during the drilling operation with a split spoon sampler and a standard 140 pound hammer using a 30-inch drop. After each soil sample is obtained the sampler and liner tubes will be cleaned using high pressure steam at 300° F to eliminate the possibility of cross-contamination between samping intervals. After each borehole is drilled, all augers, samplers and liner tubes will be steam cleaned as described above to prevent cross-contamination between borings.

At each prescribed sampling depth, soil samples will be collected in the liner tubes of the split spoon sampler. The sample in the lower liner at each depth will be retained for possible chemical analysis. All soil samples designated for chemical analysis will be kept inside the stainless steel sampling tubes during retrieval. The tubes will be tightly wrapped in aluminum foil, capped and placed inside a ziplock plastic bag. A soil sampling label will be placed on the outside of each bag and the bagged samples with labels will be placed inside a second ziplock plastic bag.

The soil from the remaining upper sample liner will used for on-site geological tubes be classification and organic vapor testing using a Photovac TIP II photoionization detector (PID). The soil will be placed into a ziplock bag and The soil will be kneaded inside the bag to sealed. allow potential vapors to collect in the headspace above the soil. The bagged sample will be kept sealed for five (5) minutes prior to testing. Testing will be accomplished by carefully inserting the sampling probe of the TIP II into the sealed The highest reading obtained will then be baq. noted onto the field boring log. Field PID readings will be obtained at every sampling depth and will be included on the final test boring logs in the final report. Sampling will be conducted at depths of 5, 10, 15, 20, 25, and 30 feet and at 10 foot intervals thereafter until ground water is reached during the well drilling.

It is estimated that 4-5 soil samples obtained during the drilling of M1 (near the tank excavation) will be selected for chemical analysis. This is based upon an estimated ground water depth of 70 feet. The field PID readings obtained will be used to aid in the selection of the most appropriate samples for analysis. Because of the lateral distance of wells M2 and M3 from the previous tank location, analysis of water samples only is proposed unless field PID readings from these borings indicate that soil contamination is present.

All prepared soil and water samples (see section 4) will be immediately placed on ice inside a styrofoam cooler and stored in a refrigerated state for delivery to American Analytics of Chatsworth, California, a California State DOHS certified laboratory, for chemical analysis. All drilling cuttings will be retained on-site until the laboratory analysis work has been completed.

#### 4.4 Monitoring Well Construction

Prior to the drilling for the monitoring wells, well permits will be obtained from the Los Angeles County Department of Health Services, Environmental Management Section.

Based on the field observation of water levels in the sump beneath the Pavilion building, ground water appears to exist at a depth of 30 to 80 feet below the ground surface, depending on the 3

Ę

14

8. . . . . . . . 8

PP-02-5-07

Sec. 1. 1. 1.12

\$

(1998) 1997 - 1998 1997 - 1998

8

ŝ

elevation of the well locations (the previous tank area is about 40 feet higher than the Pavilion area). Based upon this depth, soil borings will have to be drilled to a depth of about 40-100 feet to provide for a 10-20 foot deep well screen below the water surface.

If a competent clay layer is encountered (minimum five (5) feet thick) below ground water, drilling will be stopped and the existing borehole will be converted to a ground water monitoring well using the following construction mterials and procedures.

A 4-inch diameter slotted schedule 40 PVC casing with a bottom cap will be installed from the bottom of the borehole to a depth at least 5 feet above the saturated zone. A blank 4-inch casing shall be extended from the upper end of the slotted casing to 4 inches below grade level.

The annular space around the casings will be backfilled with a filter pack of No. 3 Monterey Sand. The filter pack will extend from the well bottom to a distance of 3 feet above the uppermost slots. A 2-foot bentonite seal will be installed above the gravel pack followed by an annular seal of cement grout to fill the remaining annular region.

A watertight, lockable well cover will be installed to protect the wellhead and will be clearly marked with the well identificationn number. The well will be described by well identification number, depth of well and the depths of the perforated interval.

After the construction of each well is complete, well development will be performed to remove sediment collected in the well from the drilling operation. A minimum of eight (8) well volumes will be removed using a Q.E.D. systems ejection pump. The ground water removed will be stored in DOT-approved 55-gallon drums on-site until laboratory analysis of the ground water samples is complete.

Ground water samples will be collected using a clean (previously steam cleaned) teflon bailer. Samples will be put into appropriately sized (per EPA protocol) glass bottles equipped with teflonlined lids. Each bottle will be filled with the water samples such that all headspace is eliminated.

#### 4.5 <u>Methods of Chemical Analysis</u>

Outlined below in Table 2.4.1 are the methods of chemical analysis that will be performed on the collected ground water and soil samples.

#### TABLE 2.4.1

#### EPA Test Methods for Soil and Ground Water Analysis at Buckley School

Sample Type	<u>Locations</u>	Test Method
Water	M1,M2&M3	EPA 602 for Volatile Organics, EPA 8015 for Total Petroleum Hydrocarbons
Soil	M1,M2*,M3*	EPA 8015 Modified for Total Petroleum Hydrocarbons, EPA 8020 for Aromatic Volatile Organics

* A limited number of soil samples will be analyzed based on field PID readings.

#### 4.6 Ground Water Gradient

The existing ground water gradient beneath the site will be determined by measuring the distances from the top of each well casing to the surface of the water table. An arbitrary reference elevation will be established at the site in the vicinity of the wells. The elevation difference between the top of each well casing and the reference elevation will be added to the distance measured from the top of the well casings to the water table.

The distances from the reference elevation to the water table will determine the slope of the water surface and thus the ground water flow direction. Conventional surveying equipment capable of measuring to the nearest 1/10 of an inch will be used to obtain the necessary elevation differences. 1000 C 100

1.522.63

ģ.

1

#### 5. FINAL REPORT

, ,

Upon approval of this work plan, Enviropro, Inc. will implement the work discussed herein. After completion of the field work and receipt of the laboratory analysis, a final report will be prepared for the Los Angeles City Fire Department that will contain the following data/information.

- 5.1 A plot plan showing final well locations and description of the drilling technique(s) used.
- 5.2 Chemical analysis results for the three (3) ground water wells M1, M2, and M3 and for at least two (2) soil samples obtained from the drilling of M1.
- 5.3 Soil boring logs signed by a California Registered Engineering Geologist for each well drilled.
- 5.4 All field data collected during soil sample collection.
- 5.5 Ground water monitoring well completion diagrams.
- 5.6 Ground water monitoring well surveying data and estimate of ground water flow direction.
- 5.7 Well development information.
- 5.8 Conclusions and recommendations for further study or remedial action (if necessary).

# **RWQCB** Files

#### STATE OF CALIFORNIA-ENVIRONMENTAL PROTECTION AGENCY

CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD LOS ANGELES REGION 101 CENTRE PLAZA DRIVE MONTEREY PARK, CA 91754-2156

(213) 266-7500 FAX: (213) 266-7600

July 22, 1996

Mr.Walter Baumhoff **Buckley School** 3900 Stansbury Avenue Sherman Oaks, CA 91423

## UNDERGROUND STORAGE TANK CASE CLOSURE **BUCKLEY SCHOOL** 3900 STANSBURY AVENUE, SHERMAN OAKS (ID #916061598)

Dear Mr. Baumhoff

This letter confirms the completion of the site investigation and remedial action for the underground storage tank(s) formerly located at the above-described location.

Based on the available information and with the provision that the information provided to this agency was accurate and representative of site conditions, no further action related to the underground storage tank release is required.

This notice is issued pursuant to a regulation contained in Title 23, California Code of Regulations, Division 3, Chapter 16, Section 2721(e).

Please contact our office if you have any questions regarding this matter.

Sincerely,

ROBERT P. GHIRELLI, D. Env. **Executive Officer** 

DAVE DEANER Acting Assistant Executive Officer Underground Tanks

Mr. Allan Patton, State Water Resources Control Board, Underground Storage Tank cc: Program Captain Jesse Pasos, Los Angeles City Fire Department, Underground Tanks

Pan,



RECEIVED JUL 30 1995

UNDERGROUND TANK

BUCKLEY SCHOOL

111 17050

88 01589 CM


DTG 1627 27 4 STATE OF CALIFORNIA HAZARDOUS SUBSTANCE SPILL REPORT COUNTY File Deat PHONE 2/3 NOTIFIED DES__O REPORTED BY. PHONE enknown SUBSTANCE GASALINE QTY. SPILL SITE: P/L__SHP__RD__O/F_REF_R/R_S/S_IND PLT_DTG OCC (FND) LOCATION 3900 Ut CrAINA WHAT HAPPENED Sums Jumping the CONTAINMENT/CLEANUP/WATER INVOLVED FD SO PD CO DOH/HW CO DES AIR/Q NRC_ LCL AGENCIES ON SCENE (NTFD) REC'D BY_ NOTIFIED NAME TIME DFG FED R/R CC CO OES RWQCB CHP FRESNO CO EPA CALTRANS HUMBOLDT CO SFM P/L F & A LA CO F/C DOG CDF SBDO CO USCG DPR SF F/D LANDS USFWS SOLANO CO DOH/ST E B PARKS VENTURA CO DOH/CO UC S BARB. FEMA 9 OES 27 (1/88)


	RI 190	50	ANN	UNC, ty
UNDERGROUND STORAGE TA	NK UNAUTHORIZEI	D RELEASE (LEAK) / CO	NTAMINATIC	N SITE REPORT
EMERGENCY     HAS STATE OFFICE OF REPORT BEEN FILED ?       YES     NO       REPORT DATE     CASE #       OM     ON       OM     ON	EMERGENCY SERVICES	FOR LOCAL AGENCY USE ONLY I HEREBY CERTIFY THAT I AM A DE REPORTED THIS INFORMATION TO THE HEALTH AND SAFTY CODE SIGNED	ignated governm .ocal officials pi	ENT EMPLOYEE AND THAT I HAVE IRSUANT TO SECTION 25180.7 OF DATE
AME OF INDIVIDUAL FILING REPORT		989 83-61 SIGNATUR	iduu M .ce Dei	1 Meterson DT.
NAME BUCHLEY SOUDD ADDRESS 3400 STANS BUNY	$\overline{(})$	CONTACT PERSON NA. TEN BAUMA MERMAN OAKS	10FF Ou	TATE $7/67$ ZIP $7/72$ PHONE 7/3 - 16/0 TATE $7/67$ $6$ THE $7/67$ $6$ $7$ THE $7/67$ $6$ THE $7/67$ $6$ $7$ THE $7/67$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $6$ $7$ $7$ $6$ $7$ $6$ $7$ $7$ $6$ $7$ $7$ $7$ $7$ $7$ $7$ $7$ $7$ $7$ $7$
FACILITY NAME (IF APPLICABLE) SAME AS A ADDRESS CROSS STREET	30 VE	OPERATOR		PHONE ( )
CROSS STREET	TYPE OF AREA COMME			OUNTY ZP SS RETAIL FUEL STATION OTHER SE NON
SI La Arrap les Fire Arot Fire	e Proventin Bue	CONTACT PERSON BAN Andrew MGU JOSH WORKMAN	Tiersez 1	PHONE (8/8)989-856/ PHONE (73) 220-5662
(1) GASOLINE	NAME		<u> </u>	
QM     SM     Zo     SY     Zo       DATE DISCHARGE BEGAN       SUI     SOURCE OF DISCHARGE       M     SOURCE OF DISCHARGE       TANK LEAK     UNKNOWN       PIPING LEAK     AGE	TANK TEST TANK R	ORY CONTROL SUBSURFA EMOVAL OTHER METHOD USED TO STOP DISCHARGE ( REMOVE CONTENTS REPAIR TANK OTHER TERIAL FIBERGLASS STEEL OTHER	CE MONITORING CHECK ALL THAT APP REPLACE TANK REPAIR PIPING CAUSE(S) CAUSE(S) CORROSH	NUISANCE CONDITIONS
CHECK ONE ONLY UNDETERMINED SOIL ONLY CHECK ONE ONLY SITE INVESTIGATION IN PROGRESS (DEFINING NO ACTION TAKEN POST CLEANUP				VE ACTUALLY BEEN AFFECTED) DMPLETED OR UNNECESSARY)
CHECK APPROPRIATE ACTION(S) (SEE BACK FOR DET.	IONITORING IN PROGRESS [	NO FUNDS AVAILABLE TO PROCE	ED EVALUA	TING CLEANUP ALTERNATIVES
	XCAVATE & DISPOSE (ED) XCAVATE & TREAT (ET) O ACTION REQUIRED (NA)	REMOVE FREE PRODUCT (F     PUMP & TREAT GROUNDWA     OTHER (OT)		VANCED BIO DEGRADATION (IT) PLACE SUPPLY (RS)
	•			
				HSC 05 (4/87)


# Appendix 3 Historical Documents

# Historical Aerial Photographs






















# Historical Topographic Maps























Appendix 4 Transaction Screen Questionnaire



### FAX COVER SHEET

CONFIDENTIAL NOTE: The information contained in this facsimile transmission is legally privileged and confidential information intended only for the use of the individual or entity named below. If the reader of this transmission is not the intended recipient, you are hereby notified that any use, dissemination, distribution or copy of this transmission is strictly prohibited. If you have received this transmission in error, immediately notify us by telephone and return the original transmission to us at the address below via the United States Postal Service. Thank you.

TO: Tricia Bartholome

NAME OF ORGANIZATION: Rincon Consultants

FAX NUMBER: (805) 641-1072

FROM: Curtis Covington

DATE: 12/06/04

NUMBER OF PAGES Including Cover: 7

RE:

MESSAGE:

□ MIDDLE/UPPER SCHOOL FAX	818-461-6715	LOWER SCHOOL OFFICE FAX	818461-6716
DADMISSION/DEVELOPMENT FAX	818-461-6714	BUSINESS OFFICE FAX	818-501-7820
HEAD OF SCHOOL FAX	818-461-6713	PHYSICAL PLANT FAX	818461-6712
ATHLETICS	818-461-6710	HR/PAYROLL	818-501-7823
		PURCHASING	818-501-7701

3900 Stansbury Avenue • Sherman Oaks, CA 91423-4699 • 818-783-1610

Dec 06 04 12:17p	BUCKLEY SCHOOL PIAN	T DEPT (818)990-4516	p.2
Nov 18 2004 5:25PM	RINCON CONSULTANTS	8056411072	p.2

#### Transaction Screen Questionnaire

#### Rincon Site Number 04-17840 - Buckley School, 3900 Stanabury, Sherman Oaks, California

This questionnaire should be completed by an individual considered to be knowledgeable of the subject property. We respectfully request that you fill out and return this form (via fax 805-841-1072) to us within one week from the date of this transmittal.

1)	<ul> <li>a commercial printing facility</li> <li>a dry cleaners</li> </ul>	<ul> <li>a junkyard or landfill</li> <li>a waste treatment, storage, disposal, processing or recycling facility</li> <li>any other industrial use</li> </ul>
2)	Please describe the current land uses of th property. Please indicate all businesses/co	e subject property and those surrounding your mpanies located on property.
24	Current use of Subject Property (please chack all that apply) Commercial (retail, offices, etc.) Residential (single family or apartments) Industrial (manufacturing, warehousing, processing) (Other-Please Describe	(please include a brief description of current operation) K-12 School
2b	Current use of Northern Adjoining Properties (please check all that apply) Commercial (retail, offloes, etc.) Residential (single family or apartments) Industrial (manufacturing, warehousing, processing) Other-Please Describe	(please include a brief description of current operation)
20	Current use of Southern Adjoining Properties (please check all that apply) Commercial (retail, offices, etc.) Residential (single family or apartments) Industrial (manufacturing, warehousing, processing) Other-Please Describe	(please include a brief description of current operation)
2d	Current use of Western Adjoining Properties (please check all that apply) Commercial (retail, offices, etc.) Residential (single family or apartments) Industrial (manufacturing, warehousing, processing) Other-Please Describe	(please include a brief description of current operation)
20	Current use of Eastern Adjoining Properties (please check all that apply) Commercial (retail, offices, etc.) Residential (single family or apartments) Industrial (manufacturing, warehousing, processing) Cother-Please Describe	(please include a brief description of current operation)

1

Dec	06	04	12:17p	BUCKLEY	SCHOOL	PIANT	DEPT	(818)990-4516
-----	----	----	--------	---------	--------	-------	------	---------------

Nov 18 2004 5:25PM RINCON CONSULTANTS

8056411072

11.222

AND STREET

 $\mathcal{N}(\mathcal{N},\mathcal{N},\mathcal{N})$ 

3

> ž, à

> > ×.

5

Section 2.

(in a canad

р.Э

Transaction Screen Questionnaire

Rincon Site Number 04-17849 - Buckley School, 3900 Stansbury, Sherman Oaks, California

3)	Please describe the previous land uses of y property, include property ownership and	
3.8	Previous use of Subject Property (please check all that apply) Commercial (retail, offices, etc.) Residential (single family or apartments) industrial (manufacturing, warehousing, processing) Cother-Please Describe	(please include a brief description of previous operations, former property owners, and dates of operation) Golf Course
3b	Previous use of Northern Adjoining Properties (please check ell that apply) Commercial (retall, offices, etc.) Residential (single family or apartments) Industrial (manufacturing, warehousing, processing) Other-Please Describe	(please include a brief description of previous operations)
36	Previous use of Southern Adjoining Properties (please check all that apply) □ Commercial (retail, offices, etc.) ▷ Residential (single family or apartments) □ Industrial (manufacturing, warehousing, processing) □ Other-Please Describe	(please include a brief description of previous operatione)
3d	Provious use of Western Adjoining Properties (please check sli that apply) © Commercial (retail, offices, etc.) © Residential (single family or apartments) © Industrial (manufacturing, warehousing, processing) © Other-Please Describe	(please include a brief description of previous operations)
30	Previous use of Eastern Adjoining Properties (please check all that apply) Commercial (retail, offices, etc.) Residential (single family or apartmenta) Industrial (manufacturing, warehousing, processing) Other-Please Describe	(please include a brief description of previous operations)

Who is the current owner of the facility?	Board of Trustees for The Backley School
When did current ownership begin?	1968
What is the age of the	35 yes.
Who is the previous owner of the property?	
	owner of the facility? When did current ownership begin? What is the age of the on-site facility? Who is the previous

2

1

16C 06 04 15:18b BD(	KLEY SCHOOL	PIANT DEPT	(818)990-4516
----------------------	-------------	------------	---------------

Nov 18 2004 5:25PM RIN

RINCON CONSULTANTS

p.4

Transaction Screen Questionnaire

Rincon Site Number 04-17840 - Buckley School, 3900 Stansbury, Sherman Oake, California

Please	indicate the propertie	e current	
electrice	al aervice provider -	LA. DWP	
water a	arvice provider -	LA DWP	
natural	gas service provider -	50 (a) 6145	
sewar a	ervice provider -	City of LiA	
	ste hauler -	Crown Proposal	

9)	sto	re or use any of the	wiedge has your facility previously or does your facility currently, following in individual containers larger than 5 gallons in volume or gate? (If yes or unknown, include how many, type, and size)
	٥		00
	0	Peeticides	in0
		Peints	no
		Other Chemicals or hezardous substances	nO

10)	Plasse Indicate any wi	astes generated at the facility.	
	Hazardous wasts:	Quantity:	Disposal Method:
	waste oil	55 gel drum	Plu by Safety Klein
	waste parent	30 gal drun	10/40 by Safety Kleen
		·	

 11) Are there currently or to the best of your knowledge have there been previously, any industrial drums (typically 66 gallon) or sacks of chemicals located on the property or at the factility?

 Image: same set of your known, please describe

 Image: same set of your known

 Image: same set of your known

12)	evi	ldence of fl	ently or to the best of your knowledge have there been previously, any Il dirt having been brought onto the property that originated from a elte or that is of an unknown origin?
	0	Yes	If Yes or Unknown, please describe
	×	No	
	0	Unknown	

3

I

## Dec 06 04 12:18p BUCKLEY SCHOOL PIANT DEPT (818)990-4516

Nov 18 2004 5:25PM RINCON CONSULTANTS

X No

٥

Unknown

÷

4

22 100

62 ś

100 1.1

R

1.2

p.5

	por	there currends or lago	ently or to the best of your knowledge have there been previously, any pits, one located on the property in connection with waste treatment or waste
	0	Yes	If Yes or Unknown, please describe
•	X	No	
	Q	Unknown	
14)		there curr I on the pro	ently or to the best of your knowledge have there been previously, any stained operty?
	0	Yes	If Yas or Unknown, please describe
	×	No	
	0	Unknown	
15)			ently or to the best of your knowledge have there been previouely, any storag or below ground) located on the property?
	×	Yes	it Yes or Unknown, please describe Fuel fanks were underground - they have been
	D	No	remarks were underground they view of
	0	Unknown	
16)	pip pro	es, fill pipe	ently or to the best of your knowledge have there been previously, any vent is, or access ways (stc.) Indicating a fill pipe protruding from the ground on th discent to any structure located on the property? If Yes or Unknown, please describe
	1	No	
		110	
	u	Unknown	
17)	U If t	he property en identifie	/ is served by a private well or non-public water system, have contaminants d in the well or system that exceed guidelines applicable to the water system it been designated as contaminated by any government agency?
17)	U If t	he property en identifie	
17)	U If t be or	he property on identifie has the we	d in the well or system that exceed guidelines applicable to the water system It been designated as contaminated by any government agency?

#### Dec 06 04 12:18p BUCKLEY SCHOOL PIANT DEPT (818)990-4516

p.6

Transaction Screen Questionnaire

Rincon Site Number 04-17840 - Buckley School, 3900 Stansbury, Sherman Oaks, California

19)	To the best of your knowledge has your facility previously or does your facility currently, discharge wastewater on or adjacent to the property other than storm water into a sanita sewer system?												
	0	Yes	if Yas or Unknown, please describe										
		No											
	0	Unknown											

20)	Ha	ve any of the followin perty? (please check	g ever been dumped above grade, buried and/or burned on the all that apply and describe if possible)
	0	hezerdous substances	no
	0	petroleum products	no
	0	unidentified waste materials	00
	0	tires	
	•	sutomotive or Industrial batteries	NO
	a	other waste materials (piesse	
	ł	describe)	no

21) Are there currently or to the best of your knowledge have there been previously, a transformer, capacitor or any hydraulic equipment on the property?
 Are the property?
 Yes if Yes or Unknown, please describe we have hydraulic lift canipment "transformers are been hydraulic lift canipment" transformers are located throughout the canges
 No
 Unknown

 22)
 Are there currently or to the best of your knowledge have there been previously, any records indicating the presence of PCB's?

 Indicating the presence of PCB's?

 If Yes

 If Yes or Unknown, please describe

 M

 No

 Indicating the presence of PCB's?

23)	700		any environmental liens or governmental notification relating to past or ations of environmental laws with respect to the property or any facility located by?
	0	Yes	If Yes or Unknown, please describe
	×	No	
	0	Unknown	

5

1

Nov 18 2004 5:25PM

8056411072

p.7

p.7

11 - 12 - 13

4

#### Transaction Screen Questionnaire

Rincon Site Number 04-17840 - Buckley School, 3900 Stanebury, Sherman Oaks, California

RINCON CONSULTANTS

24)	pet	roleum pro	n informed of the past or current existence of hazardous substances, iducts, or environmental violations with respect to the property or any facility property?
	0	Yes	If Yas or Unknown, please describe
	×	No	
		Unknown	

25)	faci	lity that inc	ny knowledge of any environmental site assessments of the property or licated the presence of hazardous substances or petroleum products on, or of, the property or recommended further assessment of the property?
	0	Yes	if Yes or Unknown, please describe
	×	No	
	D	Unknown	

26)	co	ncerning a l	of any past, threatened, or pending lawsults or administrative proceedings release of any hezardous substances or petroleum products involving the in owner or occupant of the property?
	D	Yes	if Yes or Unknown, please describe
	۶¢	No Uriknown	

This guestionnaire was c	completed by (please print)
Name	Curtis Covington
Title	Director of plant Operations
Firm	The Buckley School
Street Address	3900 Stansbury Are
City, State, Zip Code	Sherman Oaks, C.A. 91423
Phone Number	(918) 461-6765
Fax Number	1818) 461-6712
What is the Preparer's	relationship to the
property (I.e., owner, o	ecupant, property
manager, employee, a	gent, consultant, etc.)? Cmployee

Copies of the completed questionnairs should be faxed (preferably) or mailed to:

Rincon Consultants, Inc. 790 East Santa Clara Street

Ventura, California 93001 Attention: Environmental Site Assessment Division Fax: (805) 841 - 1072

Preparer represents that to the best of the preparer's knowledge the above statements and facts are true and correct and to the best of the preparer's knowledge no material facts have been suppressed or misstaged.

6

Signature

Date 12/6/04

## Appendix 5 Geophysical Survey



March 7, 2005

Project Number 5117

Ms. Tricia Aimsworth Rincon Consultants, Inc. 790 East Santa Cara Street Ventura, CA 93301

#### Subject: Geophysical Investigation at the Buckly School, Sherman Oaks, California

Dear Ms. Aimsworth:

A ground penetrating radar (GPR) survey was conducted on December 21, 2004 in a parking lot located at the Buckley School in Sherman Oaks, California. The purpose of the GPR survey was to screen an approximately 50 by 50-ft area for underground storage tanks believed to be on the property.

#### **METHODOLOGY**

GPR equipment used during this investigation consisted of a Geophysical Survey Systems Inc. (GSSI) SIR-3000 GPR system with a 400-MHz antenna (SIR-3000). Short duration EM pulses of high-frequency generated by a transmitting antenna propagate into the ground and are reflected from electrical discontinuities in the subsurface back to a receiving antenna. The propagation velocity of these EM waves in the subsurface is determined by the dielectric constant whereas the attenuation is primarily a function of ground conductivity and scattering. The dielectric constant is largely determined by water content, because the relative dielectric constant of water is 80 and that of rock and soil minerals typically is between 3 and 6. Attenuation is related to soil conductivity, which is primarily a function of clay content, moisture content, and dissolved solids in the pore water. Small percentages of clay in subsurface soils can rapidly increase the attenuation of GPR signals. Depth penetration is also a function of antenna frequency, and low frequency antennas can image to greater depths at the cost of resolution. At typical sites in Southern California, depth penetration of a 400-MHz antenna range from about 3 and 5 feet. High-amplitude, hyperbolic reflections are generally observed on GPR records over buried metallic objects such as pipes and tanks. Additional information on the GPR method can be found in the attached technical note.

ŗ

#### FIELD PROCEDURES

Before conducting the GPR survey, a 5- by 5-foot grid was established with baselines marked on the ground with chalk. The survey grid was established immediately to the west of a large debris pile, which was adjacent to a possible UST vent.

GPR data were acquired semi-continuously (32 scans per second), as the 400-MHz antenna was hand-towed along south to north survey lines spaced 2.5 feet apart. Spatial control was maintained by the chalk markings. GPR data were viewed in real time on the SIR-3000's color monitor and saved to the instrument's hard disk for later archiving. All field copies of GPR data are retained in the project files.

#### **DATA PROCESSING**

Most GPR data acquired during this investigation were not processed; rather interpretation was made using the field records. The GPR profiles presented as figures in this report were processed using the RADANTM for Windows software package developed by GSSI, Inc.

Data preparation and processing steps for the GPR profiles presented in the report included the following:

- Downloading data from the SIR-3000 hard disk to an office computer (all data)
- Trimming the ends of the line (data scans before the beginning and after the end of the survey line)
- File reversal as necessary
- Horizontal stacking, as necessary
- Vertical and horizontal high- and low-pass filtering
- Gain adjustment

- Horizontal distance normalization
- Importing GPR profiles into Corel Draw [™] 11
- Annotation of GPR records and plotting

All GPR data file names resulting from the various stages of processing were documented and data later archived.

#### RESULTS

There is one anomaly in the GPR data that warrants discussion. Figure 2 shows a highamplitude GPR anomaly located at a depth of approximately 2 ft. Depth of investigation was about 3 feet due to the interference from the rebar in the concrete. This anomaly is in line with the exposed vent, and extends 8 ft to the west. There are two interpretations for this anomaly.

The first interpretation is that this anomaly is the result from a small underground storage tank. This tank would be considered quite shallow, and may have had its crown removed.

The second interpretation is that this anomaly results from the vent line itself, in which case the UST may be immediately west of the western termination of the anomaly. We recommend that the anomaly be uncovered at its western edge to determine its exact nature. Excavation at this location would reveal either the western edge of a small UST (i.e. the anomaly is caused by a UST), the termination of the vent line at the eastern edge of a UST, or the severed end of the vent line at a former UST location.

If you have any questions concerning this investigation, please call us at 951-549-1234.

Sincerely, GEOVision Geophysical Services

Submitted by: JB Shawver Project Geophysicist


appert

Reviewed and Approved by: Antony J. Martin, R. GP. Technical Director

Attachments: Figure 1: Site Map Figure 2: Example Ground Penetrating Radar Profile Application Note – Geophysical Methods for Shallow Environmental Investigations

* This geophysical investigation was conducted under the supervision of a California Registered Geophysicist using industry standard methods and equipment. A high degree of professionalism was maintained during all aspects of the project from the field investigation and data acquisition, through data processing interpretation and reporting. All original field data files, field notes and observations, and other pertinent information are maintained in the project files and are available for the client to review for a period of at least one year.


A registered geophysicist's certification of interpreted geophysical conditions comprises a declaration of his/her professional judgment. It does not constitute a warranty or guarantee, expressed or implied, nor does it relieve any other party of its responsibility to abide by contract documents, applicable codes, standards, regulations or ordinances.




1.23

£ 61.11 z


÷



# Appendix 6 Soil Boring Logs




02-04-2005 H:\Los Angeles County\Latham and Watkins\Buckley School\Phase I\\Boring Logs\B1.bor




02-04-2005 Hillos Angeles CountylLatham and Walkins\Buckley School\Phase I\Boring Logs\B2.bor

1




02-04-2005 H:NLos Angeles County/Latham and Watkins/Buckley School/Phase II/Boring Logs/B3.bor



2


02-04-2005 H:\Los Angeles County\Latham and Watkins\Buckley Schoo\\Phase I\\Boring Logs\B4.bor

÷




02-04-2005 H:\Los Angeles County\Latham and Watkins\Buckley School\Phase II\Boring Logs\B5.bor


. -




ľ,


02-04-2005 H:\Los Angeles County/Latham and Watkins\Buckley School\Phase I\\Boring Logs\B6 bor











100

------

.

ł

ş 100

1

200


ę.

3 ŝ

÷,

02-04-2005 H:\Los Angeles County\Latham and Watkins\Buckley School\Phase I\Boring Logs\B10.bor

## Appendix 7 Laboratory Analytical Reports



## AMERICAN SCIENTIFIC LABORATORIES, LLC Environmental Testing Services

2520 N. San Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

#### Ordered By

Production of the second secon	the second se
	그 승규님께서 제공에 가장 수는 그것 않는 것 같은 것 같은 것 같은 것에서 가장 같은 것 같은 것 같은 것 같은 것 같이 가지?
Dingon Congul	
Rincon Consul	
· [1] 이상 영상 이상 사망에 관심하는 것은 사람에 관심하는 것은 이 것이 가지 않는 것이 가지 않는 것이 같은 것이 같은 것이 같은 것이 같은 것이 같은 것이 같은 것이 있다. 이 것이 같은 것이 같은 것이 같은 것이 같은 것이 같은 것이 같은 것이 없다. 것이 같은 것이 같은 것이 같은 것이 없다. 것이 같은 것이 같은 것이 없다. 것이 없는 것이 없는 것이 없다. 것이 없는 것이 없는 것이 없는 것이 없는 것이 없는 것이 없다. 것이 없는 것이 없는 것이 없는 것이 없는 것이 없다. 것이 없는 것이 없는 것이 없는 것이 없는 것이 없다. 것이 없는 것이 없는 것이 없는 것이 없는 것이 없다. 것이 없는 것이 없는 것이 없는 것이 없는 것이 없다. 것이 없는 것이 없는 것이 없는 것이 없는 것이 없는 것이 없다. 것이 없는 것이 없다. 것이 없는 한 것이 없는 것이 없 않는 것이 없는 것이 않 않는 것이 없는 것이 없 않 않는 것이 없는 것 않는 것이 없는 것이 않는 것이 않는 것이 않는 것이 않는 것이 않는 것이 없는 것이 않는 것이 없는 것이 없는 것이 않는 것이 않는 것이 않이 않는 것이 않는 것이 않는 것이 없는 것이 없는 것이 없는 것이 않는 것이 않는 것이 않는 것이 않이 않는 것이 않는 것 것이 않는 것이 않는 것이 않는 것이 않는 것이 없는 것이 없는 것이 않는 것이 않 않는 것이 않 않는 것이 없 않이 않 않 않이 않 않 않 않 않 않이 않 않 않이 않 않이	
化五氟基苯 化二乙二乙酰氨酸酸氢乙酯	그는 방법은 방법적으로 통하면 것이라. 이번 것은 것이라고 있는 것이 가지 않는 것을 물었다.
700 Poot Cant	a Clara Street
17V BASE DANL	a clara Deroec
그는 것 이 것 같은 것 것이 집에 집에 있는 것은 것을 했다.	网络爱爱斯特教教学的爱爱教教教教教学 医裂角膜炎 医胆汁和胆酸医治疗 医多足的变体
- 日本の語言のですような 単純語の構成的ななもの	그 생활님께 가장 감독 취업 것은 것은 너 가 많은 것 없는 것 않는 것 않는 것 않는 것 같이 있는 것 같이 많이 많이 없다.
Ventura, CA 9	3007
Tencura, ca J	- · · · · · · · · · · · · · · · · · · ·
- [ - 그는 것을 같은 것을 하는 것을 가지 않는 것을 하는 것을 수 있다. 것을 수 있는 것을 수 있다. 말을 하는 것을 수 있다. 말을 수	> 其他的意志的是否不可能能够不同的人们的意思。在我们还不能是不能能够不能能够不可能。

Telephone (805)641-1000 Attn Joe Inch

Date Reported 01/06/2005
--------------------------

24245	12/28/2004	RINCON
Job Number	Ordered	Client

Project ID: 04-17841 Project Name: Buckley School Site: 3900 Stansbury Ave. Sherman Oaks, CA


Enclosed are the results of analyses on 23 samples analyzed as specified on attached chain of custody.

Amolk MOLKY Brar Laboratory Manager

⁷ Rojert G. Araghi Laboratory Director

American Scientific Laboratories, LLC (ASL) accepts sample materials from clients for analysis with the assumption that all of the information provided to ASL verbally or in writing by our clients (and/or their agents), regarding samples being submitted to ASL, is complete and accurate. ASL accepts all samples subject to the following conditions:
1) ASL is not responsible for verifying any client-provided information regarding any samples submitted to the laboratory.

 ASL is not responsible for any consequences resulting from any inaccuracies, omissions, or misrepresentations contained in client-provided information regarding samples submitted to the laboratory.



## AMERICAN SCIENTIFIC LABORATORIES, LLC

of 3 Page .

Environmental Testing Services 2520 N. San Fernando Road, LA, CA 90065 Tel: (323) 223-9700 • Fax: (323) 223-9500

<i>сос</i> # №		9 global i		11		ELE	CTRONIC	REPORT	: [	] <i>El</i>	DF		EDD	AS	L J	OB#	¥	142	<u>45</u>	
Company: R	ncon	onsultan	ts										٨					UES7		
Address: And	E.Sar	uta Clara	Project Name: Site Address:	Buckl	0 er	School	Address:			~	7.	A C	\$	77	7	7	7	77	7,	$\overline{7}$
Venture	i.A.C	13001	Site Address:	Star	U h	in Allo	Invoice To:			/	73	The set	/ /		/ ,		'	· /		
Ventur Telephone (805 Fax:	1641-10	000	Sher	Man (	2	KS, CA	Address:				Ja A			4			/ ,			/
Special Instructi	on:	<del> </del>	Project ID:	1-175	24	1		······································	/	Eq.		35	50	<b>9</b> /		/ /			/ /	
		9	Project Manager: J	ne/T	Vie	cia	P.O.#:04	-17841	E A	\$/}	¥-	YS	The	' /		/ /		/ /		
I LAB USE	ONLY	SAMPLE D	DESCRIPTION			Container(s)			8	K	8				$ \begin{bmatrix} \\ \\ \end{bmatrix} $		f-	-[	<u> </u>	
E Lab IE M	,	Sample ID	Date	Time	#	Туре	Matrix	Preservation	8260	<b>PDISI</b>	ov,	82603	8 1 1 8						Rema	nrks
	R	1-5	12/2014	7.30	4	Sur AQE	Batsshoa	Wisth 300 Kine ut												
1 141606	C	01-10	1	(	$\left \right $	/	1	1	X	X										
2 141607	B	1-15					1		X	X	X									
3 141608		1-20							X		X									
4 141609		1-25							X		X							ţ	Sm	K
		52-5																	Pau	Theme
	6	2-10																		
5 141610	ß	2-15		V					Х										-	
6 141611		2-20	V	9:40		V	8	¥	X										1	The second
								L,	<b>_</b>											
Collected By: Relinquished <b>(</b>	3y:	5		12/28		me 10.10 me 1/08	Relinquis Receive For Labo	hed By: d bratory M	i (	Ľ	11		Date Date		/	f / Tin Tin	ne// ne//	_0		
Condition of S								/v					· · · · · ·	1 10	·+	<u></u>			Rus	h
Nhite - Report, Ye	l <b>iow</b> - Laborato	ry, Pink - Client																		



AMERICAN SCIENTIFIC LABORATORIES, LLC

Environmental Testing Services 2520 N. San Fernando Road, LA. CA 90065 Tel: (323) 223-9700 • Fax: (323) 223-9500

.

coc# <b>№</b>	28230 G	LOBAL I	D	<u></u>		ELEC	TRONIC	REPORT	:	] <i>EL</i>	DF		DD /	4SL	JOB	#	242	245	
Company: Ri	ncon Ca	solta	nts				Report To:	Rinur	)					ALYS					
Address:	• • • •		Project Name Site Address: 3400 Shur Project ID:	Buckl	Us	School	Address:					J.S.	$V = \int $	/ /	Γ ]	7	$\overline{\Box}$	[ ] ]	7
			Site Address:	ostans.	hu	mtre	Invoice To:			/	75			/ /					/
Telephone: Fax:			Shar	MAM 0	'n	to ca	Address:			7Å	$\frac{1}{2}$	₹/	La	//	/ /	/ ,		/ / /	
Special Instruction	on:		Project ID:	1-1780					/	20		30	heta			/ /			
			Project Manager:			1 Tricia	P.O.#: 04	17841		7e	Ţ		Š,				/ /	/ /	
1 LAB USE	ONLY	SAMPLE D	ESCRIPTION			Container(s)		1		9	8	2				i f			
T E Lab ID M	) Samı	ole ID	Date	Time	#	Туре	Matrix	Preservation	BOUS	SOCI	0109	8260B	3					Remai	ks
	B3-	5	12/22/01	9:55	4	SS SLEEPE	SOLLAQ	METRANEN SOON OISU							-				
7 141612	63-1	0	/		(	(	ſ	/	Х	X									
8 141613	13-1	5		<u>  </u>	$\prod$				X	Х									
9 141614	13-7								Х	X	Х								
10 141615	83-2	5							X	X	X								
11 141616	B3-7	0							X									THE PER	1/cm
	B4-5										·								1
12 14/617	04-11	د							X	鷻									
13/41618	B4-1	5		$\checkmark$					X	顺									
14 141619	64-2	Ň	V	12:50		¥	$\forall$	7	X										
Collected By:				12/28/02		me ໄປັນວ	Relinquis	-		1		Dé	nte		Ti	ime		ТАТ	
Relinquished E	31/2 ( (	lar	/ Date	n/2	Ti	me // 6V	Receive For Labo	d pratory p	K	P		Da	$\frac{1}{2}$	23/0	4 T.	ime /	108	[DNorm	nal
Condition of Sa	ample:	-		*				/					/	/				Rusi	

Page <u>2</u> Of <u>3</u>

Г

		AMERICAN SCI Environmental 1520 N. San Fernando	Testing Ser	vices			Fax: (323) 2	23-9500	ς J	ι,	, ι	,	Page	, <u> </u>	Of	3
coc,		231 <i>GLOBAL</i>						CREPORT	: 🗆 E	DF [	] ED	D A	SL J	IOB#	24:	245
Compa	any: Rinim	Consultar	rts				Report To:		<u> </u>					<del></del>	EQUES	ليتورب بمستند تمتيني بالبليد التترو بالمهري
Addres	ss:		Project Name	Buck	01.	School	Address:	7410	<u> </u>		8/	7	/ <b>z</b> /		77	111
			Site Address:	Shard	en	AU	Invoice To:		<del></del>	7 /ä	Ľ/ /		SK SK			
Telepho	ne:						Address:		/	64		/ / IJ	7/	' / ,	/ /	
Fax: Specia	Instruction:		Project ID:					. Ohn that	/ 8	/4]	Ŧ,				/ /	/ / /
			Project	4-172	<u><u>P</u></u>	ų		· · · · · · · · · · · · · · · · · · ·	-/8/	E L	Y.				/ /	
	AD HOE ONLY	0444017	Manager:		1	1	P.O.#: 04	-17841	/71	79	77	7 /		[		
	AB USE ONLY Lab ID	SAMPLE I Sample ID	DESCRIPTION Date	Time	#	Container(s) Type	Matrix	Preservation	2000B	Agend Agend						Remarks
15 J	41620	B5.5	12/27/04	1:10	4	SS SLOOM	SOLLAQ	NETHAL	XX	X						
	41621	B5-10		1	V	1	1	P	XX	X						
	41622	B5-15	(	1			1		XX	X						
	41623	P6-5	$\left  \right\rangle$		N				XX	X						
	41624	P6-10							XX	X						
	416.25	06-15		<u>\</u>	11			1	XX	$ \chi $	$\left\{ \cdot \cdot \cdot \right\}$	-				
	41626	87-5						+	X							
	41627	137-10	1 L	2.40		1 V	$\downarrow$	L L	X							
	41628	POOL SUMP	12/201	3,10	4		AQ	_	XX		X		-			
		• •														
Collec	eted By:		Date		Ti	me	Relinquis	hed By:	<del></del>		Date	<del></del>	<u> </u>	Time	→	TAT
	juished By:	Clark	Date	12/21	Ti	me   /09	Receive For Labo	d Dratory	listo	•	Date	e [2/2	2/04	/ Tim	=     OR	Normal
Condi White - R	tion of Sample: Report, Yellow - Lab	oratory, Pink - Client								·····		1	/ ·			Rush

, . , . , . , . , . . . .



# AMERICAN SCIENTIFIC LABORATORIES, LLC Environmental Testing Services

2520 N. San Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

Site

#### ANALYTICAL RESULTS

#### Ordered By

Rincon Consultants, Inc.	3900
790 East Santa Clara Street	Sher
Ventura, CA 93001	

3900 Stansbury Ave.
Sherman Oaks, CA

Telephone: (805)	641-1000			
Attn: Joe In	nch			
Page:	2			
Project ID:	04-17841	Job Number	Order Date	Client
Project Name:	Buckley School	24245	12/28/2004	RINCON

#### Method: 8015M/DHSLUFT, TPH DRO AND ORO

#### Batch No: 010405-2

Our Lab I.D.		141606	141609	141612	141614	141621
Sample ID		B1-10	B1-25	B3-10	B3-20	B5-10
Date Sampled		12/27/2004	12/27/2004	12/27/2004	12/27/2004	12/27/2004
Date Extracted		01/04/2005	01/04/2005	01/04/2005	01/04/2005	01/04/2005
Preparation Method						f
Date Analyzed		01/05/2005	01/05/2005	01/05/2005	01/05/2005	01/05/2005
Matrix		Soil	Soil	Soil	Soil	Soil
Units		mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Detection Limit Multiplier		1	1	1	1	1
Analytes	PQL	Results	Results	Results	Results	Results
TPH DRO (C13-C22)	10	ND	ND	ND	ND	ND
TPH ORO (C22+)	50	ND	ND	ND	ND	ND
Onr Lab LD.		141606	141609	141612	141614	141621

Our Lab I.D.	· · ·		141606	141609	141612	141614	141621
Surrogates		Con.Limit	% Rec.				
Surrogate Percent Recovery							
Chlorobenzene		70-120	101	119	120	97	101

## QUALITY CONTROL REPORT

	MS	MS DUP	RPD	MS/MSD	MS RPD			
Analytes	% REC	% REC	%	% Limit	% Limit	e.		
Diesel	99	108	8.7	75-120	15			



Environmental Testing Services

2520 N. San Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

Site

#### ANALYTICAL RESULTS

## Ordered By Rincon Consultants, Inc. 790 East Santa Clara Street Ventura, CA 93001

3900 Stansbury Ave.	•	• • • •		
Sherman Oaks, CA				

`	Telephone	: (805)641-1000
	Attn:	Joe Inch
	Page:	3
	Project ID:	04-17841

Project ID: 04-17841 Project Name: Buckley School

# Job NumberOrder DateClient2424512/28/2004RINCON

#### Method: 8015M/DHSLUFT, TPH DRO AND ORO

#### Batch No: 010405-2

Our Lab I.D.		141622	141623	141624	141625	141626
Sample ID		B5-15	B6-5	B6-10	B6-15	B7-5
Date Sampled		12/27/2004	12/27/2004	12/27/2004	12/27/2004	12/27/2004
Date Extracted		01/04/2005	01/04/2005	01/04/2005	01/04/2005	01/04/2005
Preparation Method						
Date Analyzed		01/05/2005	01/05/2005	01/05/2005	01/05/2005	01/05/2005
Matrix		Soil	Soil	Soil	Soil	Soil
Units		mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
Detection Limit Multiplier		1	1	1	1	1
Analytes	PQL	Results	Results	Results	Results	Results
TPH DRO (C13-C22)	10	ND	ND	ND	ND	ND
TPH ORO (C22+)	50	ND	ND	ND	ND	ND

Our Lab I.D.			141622	141623	141624	141625	141626
Surrogates		Con.Limit	% Rec.				
Surrogate Percent Recovery							
Chlorobenzene	 	70-120	120	100	114	99	118

## QUALITY CONTROL REPORT

	MS	MS DUP	RPD	MS/MSD	MS RPD			
Analytes	% REC	% REC	%	% Limit	% Limit			
Diesel	99	108	8.7	75-120	15		 	



Environmental Testing Services

2520 N. San Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

Site

#### ANALYTICAL RESULTS

#### Ordered By

Rincon Consultants, Inc.	
790 East Santa Clara Street	- -
Ventura, CA 93001	

3900 S	tansbury Ave.
Sherm	an Oaks, CA

Telephone: (805) Attn: Joe I				
Page:	4			
Project ID:	04-17841	Job Number	Order Date	Client
Project Name:	Buckley School	24245	12/28/2004	RINCON

## Method: 8015M/DHSLUFT, TPH DRO AND ORO

#### Batch No: 010405-2

Our Lab I.D.		141627				
Sample ID		B7-10				
Date Sampled		12/27/2004				
Date Extracted		01/04/2005				
Preparation Method				1		
Date Analyzed		01/05/2005				
Matrix		Soil				
Units		mg/kg				
Detection Limit Multiplier		1				
Analytes	PQL	Results			1	
TPH DRO (C13-C22)	10	ND	<u></u>		+	
TPH ORO (C22+)	50	ND			1	

Our Lab I.D.		141627		
Surrogates	Con.Limit	% Rec.		
Surrogate Percent Recovery				· · ·
Chlorobenzene	70-120	120		

## QUALITY CONTROL REPORT

	MS	MS DUP	RPD	MS/MSD	MS RPD		 	
Analytes	% REC	% REC	%	% Limit	% Limit			
Diesel	99	108	8.7	75-120	15	 		



Environmental Testing Services

2520 N. San Fernando Rd., Los Angeles, CA 90065 - Tel: (323) 223-9700 - Fax: (323) 223-9500

## ANALYTICAL RESULTS

Ordered By Site							
Rincon Consultants, Inc.	· ·		39	000 Stansbury	Ave.		
790 East Santa Clara Street			SI	nerman Oaks, (	CA		
Ventura, CA 93001							
Telephone: (805)641-1000							
Attn: Joe Inch							
Page: 5							
Project ID: 04-1784	1			Job Number			Client
Project Name: Buckley	School			24245	12/28,	/2004	RINCON
· · · · · · · · · · · · · · · · · · ·	Method: 8015M	/DHSLUF	T. TPH D	RO AND O	RO		
			-,	•			
Batch No: 010505-1			,	+····			
Our Lab I.D.	·		141607	141613	141615	141620	
Sample ID			B1-15	B3-15	B3-25	B5-5	
Date Sampled			12/27/2004				
Date Extracted			01/04/2005	01/04/2005	01/04/2005	01/04/2005	
Preparation Method		·					
Date Analyzed			01/05/2005	01/05/2005	01/05/2005	01/05/2005	
Matrix			Soil	Soil	Soil	Soil	
Units			mg/kg	mg/kg	mg/kg	mg/kg	
Detection Limit Multiplier			1	1	1	1	
Analytes		PQL	Results	Results	Results	Results	
TPH DRO (C13-C22)		10	ND	ND	ND	ND	
TPH ORO (C22+)		50	ND	ND	ND	ND	
			4 4 4 4 7 7 7	444.550			1
Our Lab I.D.			141607	141613	141615	141620	·
Surrogates	C	on.Limit	% Rec.	% Rec.	% Rec.	% Rec.	
Surrogate Percent Recovery							L
Chlorobenzene		70-120	92	87	88	98	

## QUALITY CONTROL REPORT

	MS	MS DUP	RPD	MS/MSD	MS RPD		 	
Analytes	% REC	% REC	%	% Limit	% Limit			
Diesel	95	99	4.1	75-120	15			



Environmental Testing Services

2520 N. San Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

Site

#### ANALYTICAL RESULTS

#### Ordered By

#### Rincon Consultants, Inc. 790 East Santa Clara Street Ventura, CA 93001

3900 Stansbury Ave.	
Sherman Oaks, CA	•

Telephone: (805	)641-1000	
Attn: Joe In	nch	
Page:	6	
Project ID:	04-17841	Job Numl
Project Name:	Buckley School	24245

# Job NumberOrder DateClient2424512/28/2004RINCON

## Method: 8015M/DHSLUFT, TPH as DRO and ORO

#### Batch No: 010405-2

Our Lab I.D.		141628				
Sample ID		Pool Sump				
Date Sampled		12/27/2004				
Date Extracted		01/03/2005				
Preparation Method						
Date Analyzed		01/05/2005	·			
Matrix		Water				
Units		mg/L		1	1	
Detection Limit Multiplier		1		1		
Analytes	PQL	Results				
TPH DRO (C13-C22)	0.50	ND				
TPH ORO (C22+)	0.50	ND				

Our Lab I.D.		141628			
Surrogates	Con.Limit	% Rec.			
Surrogate Percent Recovery		÷ ,	· .		
Chlorobenzene	70-120	118			

## QUALITY CONTROL REPORT

	MS	MS DUP	RPD	MS/MSD	MS RPD			[]
Analytes	% REC	% REC	%	% Limit	% Limit		4	
Diesel	99	108	8.7	75-120	15			 



2520 N. San Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

## ANALYTICAL RESULTS

#### Ordered By

Attn:

Rincon Consultants, Inc.	3900 Stansbury Ave.
790 East Santa Clara Street	Sherman Oaks, CA
Ventura, CA 93001	

Page:	7			
Project ID:	04-17841	Job Number	Order Date	Client
Project Name:	Buckley School	24245	12/28/2004	RINCON

## Method: 8260B, Volatile Organic Compounds

#### Batch No: 010305-1C

Telephone: (805)641-1000 Joe Inch

Our Lab I.D.		141628			
Sample ID		Pool Sump	 		
Date Sampled		12/27/2004	 		
Date Extracted		01/03/2005			
Preparation Method			 		
Date Analyzed		01/03/2005	 		
Matrix		Water	 		1
Units		ug/L	 	+	+
Detection Limit Multiplier		1	 		
Analytes	PQL	Results	 		
Acetone	5.00	ND	 		· · · · · · · · · · · · · · · · · · ·
Benzene	1.000	ND	 		+
Bromobenzene (Phenyl bromide)	1.000	ND	 		
Bromochloromethane (Chlorobromomethane)	1.000	ND	 		
Bromodichloromethane (Dichlorobromomethane)	1.000	ND	 ·	1	
Bromoform (Tribromomethane)	5.000	ND	 	+	
Bromomethane (Methyl bromide)	3.000	ND	 	4	
2-Butanone (MEK, Methyl ethyl ketone)	5.00	ND	 		
n-Butylbenzene	1.000	ND	 		
sec-Butylbenzene	1.000	ND	 	1	<u>}</u>
tert-Butylbenzene	1.000	ND	 	+	
Carbon disulfide	1.000	ND	 		+
Carbon tetrachloride (Tetrachloromethane)	1.000	ND	 	+	+
Chlorobenzene	1.000	ND	 		
Chloroethane	3.000	ND	 		·
2-Chloroethyl vinyl ether	5.000	ND	 		
Chloroform (Trichloromethane)	1.000	ND	 		
Chloromethane (Methyl chloride)	3.000	ND	 		
4-Chlorotoluene (p-Chlorotoluene)	1.000	ND	 	<u> </u>	
2-Chlorotoluene (o-Chlorotoluene)	1.000	ND	 <u></u>	<u> </u>	+
1,2-Dibromo-3-chloropropane (DBCP)	5.000	ND	 		+
Dibromochloromethane	1.000	ND	 ····		
1,2-Dibromoethane (EDB, Ethylene dibromide)	1.000	ND	 		
Dibromomethane	1.000	ND	 		+
1,2-Dichlorobenzene (o-Dichlorobenzene)	1.000	ND	 	<b>+</b> • •	
1,3-Dichlorobenzene (m-Dichlorobenzene)	1.000	ND	 		+




2520 N. San Fernando Rd., Los Angeles, CA 90065 - Tel: (323) 223-9700 - Fax: (323) 223-9500

## ANALYTICAL RESULTS

Page:	8			
Project ID:	04-17841	Job Number	Order Date	Client
Project Name:	Buckley School	24245	12/28/2004	RINCON
i toject Name.	Duchiel			h

# Method: 8260B, Volatile Organic Compounds

Our Lab I.D.		141628				
Sample ID		Pool Sump		1		
Date Sampled	1	12/27/2004				
Analytes	PQL	Results				<u> -</u>
1,4-Dichlorobenzene (p-Dichlorobenzene)	1.000	ND			+	1
Dichlorodifluoromethane	3.000	ND				
1,1-Dichloroethane	1.000	ND				
1,2-Dichloroethane	1.000	ND				
1,1-Dichloroethene (1,1-Dichloroethylene)	1.000	ND				
cis-1,2-Dichloroethene	1.000	ND				
trans-1,2-Dichloroethene	1.000	ND				
1,2-Dichloropropane	1.000	ND				
1,3-Dichloropropane	1.000	ND				
2,2-Dichloropropane	1.000	ND				
1,1-Dichloropropene	1.000	ND				
cis-1,3-Dichloropropene	1.000	ND				
trans-1,3-Dichloropropene	1.000	ND			1	
Ethylbenzene	1.000	ND				
Hexachlorobutadiene (1,3-Hexachlorobutadiene)	3.000	ND				
2-Hexanone	5.000	ND				
Isopropylbenzene	1.000	ND				
p-Isopropyltoluene (4-Isopropyltoluene)	1.000	ND				
MTBE	2.000	ND		-		
4-Methyl-2-pentanone (MIBK, Methyl isobutyl ketone)	5.00	ND				
Methylene chloride (Dichloromethane, DCM)	5.00	ND				
Naphthalene	1.000	ND				
n-Propylbenzene	1.000	ND				
Styrene	1.000	ND				
1,1,1,2-Tetrachloroethane	1.000	ND				
1,1,2,2-Tetrachloroethane	1.000	ND			<b>_</b>	
Tetrachloroethene (Tetrachloroethylene)	1.000	ND				
Toluene (Methyl benzene)	1.000	ND				
1,2,3-Trichlorobenzene	1.000	ND				
1,2,4-Trichlorobenzene	1.000	ND				
1,1,1-Trichloroethane	1.000	ND				
1,1,2-Trichloroethane	1.000	ND				
Trichloroethene (TCE)	1.000	ND				
Trichlorofluoromethane	1.000	ND	·····			
1,2,3-Trichloropropane	1.000	ND				
1,2,4-Trimethylbenzene	1.000	ND				
1,3,5-Trimethylbenzene	1.000	ND				
Vinyl acetate	5.00	ND				
Vinyl chloride (Chloroethene)	3.000	ND				
o-Xylene	1.000	ND			+	+··· · · · · · · · · · · · · · · · · ·
m- & p-Xylenes	2.000	ND			<b>†</b>	



Environmental Testing Services

2520 N. Sun Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

## ANALYTICAL RESULTS

Page:	9			<del>.</del>
Project ID:	04-17841	Job Number	Order Date	Client
Project Name:	Buckley School	24245	12/28/2004	RINCON

## Method: 8260B, Volatile Organic Compounds

Our Lab I.D.		141628		
Surrogates	Con.Limit	% Rec.		
Surrogate Percent Recovery				
Bromofluorobenzene	70-120	116		
Dibromofluoromethane	70-120	117		
Toluene-d8	70-120	106		

## QUALITY CONTROL REPORT

-		MS	MS DUP	RPD	MS/MSD	MS RPD	•		1		· · ·
	Analytes	% REC	% REC	%	% Limit	% Limit					
	Benzene	102	94	8.2	75-120	15			+	<u> </u>	
•	Chlorobenzene	97	94	3.1	75-120	15					
-	1,1-Dichloroethene	114	112	1.8	75-120	15					
	(1,1-Dichloroethylene)										
,	MTBE	116	108	7.1	75-120	15					
	Toluene (Methyl benzene)	107	94	12.9	75-120	15		1			
	Trichloroethene (TCE)	104	98	5.9	75-120	15		1			



Environmental Testing Services

2520 N. San Fernando Rd., Los Angeles, CA 90065 - Tel: (323) 223-9700 - Fax: (323) 223-9500

### ANALYTICAL RESULTS

#### Ordered By

Attn:

#### Site

Rincon Consultants, Inc.	
790 East Santa Clara Street	
Ventura, CA 93001	

Sherman Oaks, CA	3900 Stansbury Ave.	· · · · · · · · · · · · · · · · · · ·	
······································	Sherman Oaks, CA		

Page:	10			
Project ID:	04-17841	Job Number	Order Date	Client
Project Name:	Buckley School	24245	12/28/2004	RINCON

## Method: 8260B, Volatile Organic Compounds

#### Batch No: 010305-1C

Telephone: (805)641-1000

Joe Inch

Our Lab I.D.		141621	141622	141624	141625	
Sample ID		B5-10	B5-15	B6-10	B6-15	
Date Sampled		12/27/2004	12/27/2004	12/27/2004	12/27/2004	
Date Extracted		01/03/2005	01/03/2005	01/03/2005	01/03/2005	
Preparation Method		1				
Date Analyzed	· · · · · · · · · · · · · · · · · · ·	01/03/2005	01/03/2005	01/03/2005	01/03/2005	
Matrix		Soil	Soil	Soil	Soil	
Units		ug/kg	ug/kg	ug/kg	ug/kg	
Detection Limit Multiplier		1	1	1	1	
Analytes	PQL	Results	Results	Results	Results	
Acetone	50.0	ND	ND	ND	ND	
Benzene	2.00	ND	ND	ND	ND	
Bromobenzene (Phenyl bromide)	10.00	ND	ND	ND	ND	
Bromochloromethane (Chlorobromomethane)	10.00	ND	ND	ND	ND	
Bromodichloromethane (Dichlorobromomethane)	10.00	ND	ND	ND	ND	
Bromoform (Tribromomethane)	50.00	ND	ND	ND	ND	
Bromomethane (Methyl bromide)	30.00	ND	ND	ND	ND	
2-Butanone (MEK, Methyl ethyl ketone)	50.00	ND	ND	ND	ND	
n-Butylbenzene	10.00	ND	ND	ND	ND	
sec-Butylbenzene	10.00	ND	ND	ND	ND	
tert-Butylbenzene	10.00	ND	ND	ND	D	
Carbon disulfide	10.00	ND	ND	ND	ND	
Carbon tetrachloride (Tetrachloromethane)	10.00	ND	ND	ND	ND	
Chlorobenzene	10.00	ND	ND	ND	ND	
Chloroethane	30.00	ND	ND	ND	ND	
2-Chloroethyl vinyl ether	50.00	ND	ND	ND	ND	
Chloroform (Trichloromethane)	10.00	ND	ND	ND	ND	
Chloromethane (Methyl chloride)	30.00	ND	ND	ND	ND	
4-Chlorotoluene (p-Chlorotoluene)	10.00	ND	ND	ND	ND	
2-Chlorotoluene (o-Chlorotoluene)	10.00	ND	ND	ND	ND	
1,2-Dibromo-3-chloropropane (DBCP)	50.00	ND	ND	ND	ND	
Dibromochloromethane	10.00	ND	ND	ND	ND	
1,2-Dibromoethane (EDB, Ethylene dibromide)	10.00	ND	ND	ND	ND	
Dibromomethane	10.00	ND	ND	ND	ND	
1,2-Dichlorobenzene (o-Dichlorobenzene)	10.00	ND	ND	ND	ND	
1,3-Dichlorobenzene (m-Dichlorobenzene)	10.00	ND	ND	ND	ND	



Environmental Testing Services

2520 N. San Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

## ANALYTICAL RESULTS

Page:	11				
Project ID:	04-17841	Job Number	Order Date	Client	
Project Name:	Buckley School	24245	12/28/2004	RINCON	

## Method: 8260B, Volatile Organic Compounds

Our Lab I.D.		141621	141622	141624	141625
Sample ID		B5-10	B5-15	B6-10	B6-15
Date Sampled		12/27/2004	12/27/2004	12/27/2004	12/27/2004
Analytes	PQL	Results	Results	Results	Results
1,4-Dichlorobenzene (p-Dichlorobenzene)	10.00	ND	ND	ND	ND
Dichlorodifluoromethane	30.00	ND	ND	ND	ND
1,1-Dichloroethane	10.00	ND	ND	ND	ND
1,2-Dichloroethane	10.00	ND	ND	ND	ND
1,1-Dichloroethene (1,1-Dichloroethylene)	10.00	ND	ND	ND	ND
cis-1,2-Dichloroethene	10.00	ND ·	ND	ND	ND
trans-1,2-Dichloroethene	10.00	ND	ND	ND	ND
1,2-Dichloropropane	10.00	ND	ND	ND	ND
1,3-Dichloropropane	10.00	ND	ND	ND	ND
2,2-Dichloropropane	10.00	ND	ND	ND	ND
1,1-Dichloropropene	10.00	ND	ND	ND	ND
cis-1,3-Dichloropropene	10.00	ND	ND	ND	ND
trans-1,3-Dichloropropene	10.00	ND	ND	ND	ND
Ethylbenzene	2.00	ND	ND	ND	ND
Hexachlorobutadiene (1,3-Hexachlorobutadiene)	30.00	ND	ND	ND	ND
2-Hexanone	50.00	ND	ND	ND	ND
Isopropylbenzene	10.00	ND	ND	ND	ND
p-Isopropyltoluene (4-Isopropyltoluene)	10.00	ND	ND	ND	ND
MTBE	5.00	ND	ND	ND	ND
4-Methyl-2-pentanone (MIBK, Methyl isobutyl ketone)	50.00	ND	ND	ND	ND
Methylene chloride (Dichloromethane, DCM)	50.00	ND	ND	ND	ND
Naphthalene	10.00	ND	ND	ND	ND
n-Propylbenzene	10.00	ND	ND	ND	ND
Styrene	10.00	ND	ND	ND	ND
1,1,1,2-Tetrachloroethane	10.00	ND	ND	ND	ND
1,1,2,2-Tetrachloroethane	10.00	ND	ND	ND	ND
Tetrachloroethene (Tetrachloroethylene)	10.00	ND	ND	ND	ND
Toluene (Methyl benzene)	2.00	ND	ND	ND	ND
1,2,3-Trichlorobenzene	10.00	ND	ND	ND	ND
1,2,4-Trichlorobenzene	10.00	ND	ND	ND	ND
1,1,1-Trichloroethane	10.00	ND	ND	ND	ND
1,1,2-Trichloroethane	10.00	ND	ND	ND	ND
Trichloroethene (TCE)	10.00	ND	ND	ND	ND
Trichlorofluoromethane	10.00	ND	ND	ND	ND
1,2,3-Trichloropropane	10.00	ND	ND	ND	ND
1,2,4-Trimethylbenzene	10.00	ND	ND	ND	ND
1,3,5-Trimethylbenzene	10.00	ND	ND	ND	ND
Vinyl acetate	50.0	ND	ND	ND	ND
Vinyl chloride (Chloroethene)	30.00	ND	ND	NĎ	ND
o-Xylene	2.00	ND	ND	ND	ND
m- & p-Xylenes	4.00	ND	ND	ND	ND



Environmental Testing Services

2520 N. San Fernando Rd., Los Angeles, CA 90065 (Tel: (323) 223-9700 (Fax: (323) 223-9500

## ANALYTICAL RESULTS

Page:	12				,
Project ID:	04-17841	Job Number	Order Date	Client	
Project Name:	Buckley School	24245	12/28/2004	RINCON	

## Method: 8260B, Volatile Organic Compounds

Our Lab I.D.		141621	141622	141624	141625	
Surrogates	Con.Limit	% Rec.	% Rec.	% Rec.	% Rec.	
Surrogate Percent Recovery						
Bromofluorobenzene	70-120	118	117	118	119	
Dibromofluoromethane	70-120	105	112	116	106	
Toluene-d8	70-120	104	108	108	106	

#### QUALITY CONTROL REPORT

······································	MS	MS DUP	RPD	MS/MSD	MS RPD	1		
Analytes	% REC	% REC	%	% Limit	% Limit			
Benzene	102	94	8.2	75-120	15		 	
Chlorobenzene	97	94	3.1	75-120	15		 	
1,1-Dichloroethene	114	112	1.8	75-120	15	 1		
(1,1-Dichloroethylene)								
MTBE	116	108	7.1	75-120	15		 	
Toluene (Methyl benzene)	107	94	12.9	75-120	15	1		
Trichloroethene (TCE)	104	98	5.9	75-120	15			



Environmental Testing Services

2520 N. San Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

#### ANALYTICAL RESULTS

Ordered By		Site
Rincon Consulta 790 East Santa C	-	3900 Stansbury Ave. Sherman Oaks, CA
Ventura, CA 930	001	
Telephone: (80	5)641-1000	
Attn: Joe	Inch	
Page:	13	
Project ID:	04-17841	Job Number Order Date Client

Project ID:	04-17841	Job Number	Order Date	Client
Project Name:	Buckley School	24245	12/28/2004	RINCON

## Method: 8260B, Volatile Organic Compounds

Our Lab I.D.		141620	141623		
Sample ID		B5-5	B6-5		
Date Sampled		12/27/2004	12/27/2004		
Date Extracted		01/04/2005	01/04/2005	 	
Preparation Method				 	
Date Analyzed		01/04/2005	01/04/2005	 	1
Matrix		Soil	Soil	 	
Units		ug/kg	ug/kg		<u> </u>
Detection Limit Multiplier		1	1	 	
Analytes	PQL	Results	Results	 ·	
Acetone	50.0	106	120	 	<u></u>
Benzene	2.00	ND	ND	 	+
Bromobenzene (Phenyl bromide)	10.00	ND	ND	 	
Bromochloromethane (Chlorobromomethane)	10.00	ND	ND	 	
Bromodichloromethane (Dichlorobromomethane)	10.00	ND	ND	 	
Bromoform (Tribromomethane)	50.00	ND	ND	 	
Bromomethane (Methyl bromide)	30.00	ND	ND	 	
2-Butanone (MEK, Methyl ethyl ketone)	50.00	ND	ND	 	[
n-Butylbenzene	10.00	ND	ND	 	
sec-Butylbenzene	10.00	ND	ND	 1	
tert-Butylbenzene	10.00	ND	ND		
Carbon disulfide	10.00	ND	ND	 	
Carbon tetrachloride (Tetrachloromethane)	10.00	ND	ND	 	
Chlorobenzene	10.00	ND	ND	 	
Chloroethane	30.00	ND	ND		
2-Chloroethyl vinyl ether	50.00	ND	ND		
Chloroform (Trichloromethane)	10.00	ND	ND		
Chloromethane (Methyl chloride)	30.00	ND	ND		
4-Chlorotoluene (p-Chlorotoluene)	10.00	ND	ND		
2-Chlorotoluene (o-Chlorotoluene)	10.00	ND	ND		
1,2-Dibromo-3-chloropropane (DBCP)	50.00	ND	ND		
Dibromochloromethane	10.00	ND	ND		
1,2-Dibromoethane (EDB, Ethylene dibromide)	10.00	ND	ND	 	
Dibromomethane	10.00	ND	ND		
1,2-Dichlorobenzene (o-Dichlorobenzene)	10.00	ND	ND		
1,3-Dichlorobenzene (m-Dichlorobenzene)	10.00	ND	ND		



Environmental Testing Services

2520 N. San Fernando Rd., Los Angeles, CA 90065 (1823) 223-9700 (Fas: (323) 223-9500

## ANALYTICAL RESULTS

Page:	14			
Project ID:	04-17841	Job Number	Order Date	Client
Project Name:	Buckley School	24245	12/28/2004	RINCON

## Method: 8260B, Volatile Organic Compounds

Our Lab I.D.		141620	141623			
Sample ID		B5-5	B6-5			
Date Sampled		12/27/2004	12/27/2004			
Analytes	PQL	Results	Results			
1,4-Dichlorobenzene (p-Dichlorobenzene)	10.00	ND	ND			
Dichlorodifluoromethane	30.00	ND	ND			
1,1-Dichloroethane	10.00	ND	ND			
1,2-Dichloroethane	10.00	ND	ND			
1,1-Dichloroethene (1,1-Dichloroethylene)	10.00	ND	ND			
cis-1,2-Dichloroethene	10.00	ND	ND			
trans-1,2-Dichloroethene	10.00	ND	ND			
1,2-Dichloropropane	10.00	ND	ND	<u> </u>		
1,3-Dichloropropane	10.00	ND	ND			
2,2-Dichloropropane	10.00	ND	ND			
1,1-Dichloropropene	10.00	ND	ND			
cis-1,3-Dichloropropene	10.00	ND	ND			
trans-1,3-Dichloropropene	10.00	ND	ND			
Ethylbenzene	2.00	ND	ND	<u>_</u>		
Hexachlorobutadiene (1,3-Hexachlorobutadiene)	30.00	ND	ND			
2-Hexanone	50.00	ND	ND			
Isopropylbenzene	10.00	ND	ND			
p-Isopropyltoluene (4-Isopropyltoluene)	10.00	ND	ND			
MTBE	5.00	ND	ND			
4-Methyl-2-pentanone (MIBK, Methyl isobutyl ketone)	50.00	ND	ND			
Methylene chloride (Dichloromethane, DCM)	50.00	ND	ND			
Naphthalene	10.00	ND	ND			
n-Propylbenzene	10.00	ND	ND			
Styrene	10.00	ND	ND			
1,1,1,2-Tetrachloroethane	10.00	ND	ND			
1,1,2,2-Tetrachloroethane	10.00	ND	ND			
Tetrachloroethene (Tetrachloroethylene)	10.00	18	27			
Toluene (Methyl benzene)	2.00	ND	ND			
1,2,3-Trichlorobenzene	10.00	ND	ND			
1,2,4-Trichlorobenzene	10.00	ND	ND			· · · · · · · · · · · · · · · · · · ·
1,1,1-Trichloroethane	10.00	ND	ND			
1,1,2-Trichloroethane	10.00	ND	ND			
Trichloroethene (TCE)	10.00	ND	ND			
Trichlorofluoromethane	10.00	ND	ND			
1,2,3-Trichloropropane	10.00	ND	ND			
1,2,4-Trimethylbenzene	10.00	ND	ND			
1,3,5-Trimethylbenzene	10.00	ND	ND			
Vinyl acetate	50.0	ND	ND			
Vinyl chloride (Chloroethene)	30.00	ND	ND			
o-Xylene	2.00	ND	ND		+	
m- & p-Xylenes	4.00	ND	ND			



Environmental Testing Services

2520 N. San Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

#### ANALYTICAL RESULTS

Project ID: 04-17841 Job Number Order Date Client	Page:	15			
			Job Number	Order Date	Client
	Project Name:	Buckley School	24245	12/28/2004	RINCON

## Method: 8260B, Volatile Organic Compounds

Our Lab I.D.		141620	141623		
Surrogates	Con.Limit	% Rec.	% Rec.		
Surrogate Percent Recovery					
Bromofluorobenzene	70-120	108	114		
Dibromofluoromethane	70-120	102	103	 	
Toluene-d8	70-120	100	98		

### QUALITY CONTROL REPORT

	MS	MS DUP	RPD	MS/MSD	MS RPD		T	
Analytes	% REC	% REC	%	% Limit	% Limit			
Benzene	114	104	9.2	75-120	15	 	1	
Chlorobenzene	106	101	4.8	75-120	15			
1,1-Dichloroethene	118	106	10.7	75-120	15			
(1,1-Dichloroethylene)								
MTBE	120	112	6.9	75-120	15		1	
Toluene (Methyl benzene)	114	103	10.1	75-120	15	 		
Trichloroethene (TCE)	106	100	5.8	75-120	15			



Environmental Testing Services

2520 N. San Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

#### ANALYTICAL RESULTS

#### Ordered By

Attn:

Rincon Consultants, Inc.		
790 East Santa Clara Street		
Ventura, CA 93001	<u>.</u>	

Site

3900 Stansbury Ave. Sherman Oaks, CA

Page:	16			
Project ID:	04-17841	Job Number	Order Date	Client
Project Name:	Buckley School	24245	12/28/2004	RINCON

## Method: 8260B, Gas/BTEX and Oxygenates

#### Batch No: 010305-1C

Telephone: (805)641-1000


Joe Inch

Our Lab I.D.		141606	141607	141610	141611	141613
Sample ID		B1-10	B1-15	B2-15	B2-20	B3-15
Date Sampled		12/27/2004	12/27/2004	12/27/2004	12/27/2004	12/27/2004
Date Extracted		01/03/2005	01/03/2005	01/03/2005	01/03/2005	01/03/2005
Preparation Method						
Date Analyzed		01/03/2005	01/03/2005	01/03/2005	01/03/2005	01/03/2005
Matrix		Soil	Soil	Soil	Soil	Soil
Units		ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
Detection Limit Multiplier		1	1	1	1	1
Analytes	PQL	Results	Results	Results	Results	Results
Benzene	2.00	2	ND	2	ND	7
DIPE	5.00	ND	ND	ND	ND	ND
ETBE	5.0	ND	ND	ND	ND	ND
Ethylbenzene	2.00	ND	ND	ND	ND	ND
MTBE	5.00	ND	ND	ND	ND	206
ТАМЕ	5.00	ND	ND	ND	ND	ND
ТВА	20	ND	ND	ND	ND	320
Toluene (Methyl benzene)	2.00	2	ND	ND	ND	3
o-Xylene	2.00	ND	ND	ND	ND	ND
m- & p-Xylenes	4.0	ND	ND	ND	ND	ND
TPH as Gasoline (C4-C12)	500	ND	ND	ND	ND	646

Our Lab I.D.		141606	141607	141610	141611	141613	
Surrogates	Con.Limit	% Rec.	% Rec.	% Rec.	% Rec. % Rec. %		
Surrogate Percent Recovery							
Bromofluorobenzene	70-120	120	120	119	114	118	
Dibromofluoromethane	70-120	114	110	116	120	116	
Toluene-d8	70-120	104	107	106	106	106	

### QUALITY CONTROL REPORT

	MS	MS DUP	RPD	MS/MSD	MS RPD	 		T	
Analytes	% REC	% REC	%	% Limit	% Limit		-		
Benzene	102	94	8.2	75-120	15			 	



Environmental Texting Services

2520 N. San Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

#### ANALYTICAL RESULTS

,	Page:	17	·····		
	Project ID:	04-17841	Job Number	Order Date	Client
`	Project Name:	Buckley School	24245	12/28/2004	RINCON

## Method: 8260B, Gas/BTEX and Oxygenates QUALITY CONTROL REPORT

	MS	MS DUP	RPD	MS/MSD	MS RPD			
Analytes	% REC	% REC	%	% Limit	% Limit			
MTBE	116	108	7.1	75-120	15	 1		
Toluene (Methyl benzene)	107	94	12.9	75-120		 		



Environmental Testing Services

2520 N. San Fernandu Rd., Los Angeles, CA 90065 Tel. (323) 223-9700 Fax: (323) 223-9500

#### ANALYTICAL RESULTS

#### Ordered By

Site

Rincon Consultants, Inc.	3900 Stansbury Ave.
790 East Santa Clara Street	Sherman Oaks, CA
Ventura, CA 93001	

Telephone: (805)641-1000

Attn: Joe Inch

Page: 18 P P

Project ID:	04-17841	Job Number	Order Date	Client
Project Name:	Buckley School	24245	12/28/2004	RINCON

#### Method: 8260B, Gas/BTEX and Oxygenates

#### Batch No: 010305-1C

Our Lab I.D.		141616	141617		
Sample ID		B3-30	B4-10		 
Date Sampled		12/27/2004	12/27/2004		 
Date Extracted		01/03/2005	01/03/2005		 
Preparation Method					 
Date Analyzed		01/03/2005	01/03/2005		 
Matrix		Soil	Soil		 
Units		ug/kg	ug/kg	· · · · · · · · · · · · · · · · · · ·	 
Detection Limit Multiplier		1	1		 
Analytes	PQL	Results	Results		
Benzene	2.00	13	ND		 
DIPE	5.00	ND	ND		
ETBE	5.0	ND	ND		 
Ethylbenzene	2.00	53	ND		 
MTBE	5.00	1050	129		 
TAME	5.00	ND	ND		 
ТВА	20	302	392		 
Toluene (Methyl benzene)	2.00	ND	2		 
o-Xylene	2.00	18	ND		 
m-& p-Xylenes	4.0	36	ND		 
TPH as Gasoline (C4-C12)	500	1930	550		 

Our Lab I.D.		141616	141617			
Surrogates	Con.Limit	% Rec.	% Rec.		· .	
Surrogate Percent Recovery				<del>.</del>		
Bromofluorobenzene	70-120	114	120			
Dibromofluoromethane	70-120	115	96			
Toluene-d8	70-120	108	100			

## QUALITY CONTROL REPORT

	MS	MS DUP	RPD	MS/MSD	MS RPD		 ·	
Analytes	% REC	% REC	%	% Limit	% Limit			
Benzene	102	94	8.2	75-120	15		 	



isnytronmental Testing Services

2520 N. San Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

## ANALYTICAL RESULTS

Page:	19			······
Project ID:	04-17841	Job Number	Order Date	Client
Project Name:	Buckley School	24245	12/28/2004	RINCON
Troject Rame.				

# Method: 8260B, Gas/BTEX and Oxygenates <u>QUALITY CONTROL REPORT</u>

		MS	MS DUP	RPD	MS/MSD	MS RPD			
	Analytes	% REC	% REC	%	% Limit	% Limit	•		
	MTBE	116	108	7.1	75-120	15		 	 
1	Toluene (Methyl benzene)	107	94	12.9	75-120	15			



Environmental Testing Services

2520 N. San Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

Site

## ANALYTICAL RESULTS

#### Ordered By

Rincon Consultants, Inc.	
790 East Santa Clara Street	
Ventura, CA 93001	

3900 Stansbury Ave.	
Sherman Oaks, CA	

Attn: Joe In	nch			
Page:	20			
Project ID:	04-17841	Job Number	Order Date	Client

## Method: 8260B, Gas/BTEX and Oxygenates


#### Batch No: 010305-2C

Our Lab I.D.		141615	141619	
Sample ID		B3-25	B4-20	
Date Sampled		12/27/2004	12/27/2004	
Date Extracted		01/03/2005	01/03/2005	
Preparation Method				
Date Analyzed		01/04/2005	01/04/2005	
Matrix		Soil	Soil	
Units		ug/kg	ug/kg	
Detection Limit Multiplier		5	5	
Analytes	PQL	Results	Results	
Benzene	10	295	27	
DIPE	25	ND	ND	
ETBE	25	ND	ND	
Ethylbenzene	10	670	53	
MTBE	25	2740	6950	
ТАМЕ	25	ND	ND	
ТВА	100	ND	ND	
Toluene (Methyl benzene)	10	1980	54	
o-Xylene	10	1090	75	·····
m- & p-Xylenes	20	2700	170	
TPH as Gasoline (C4-C12)	2500	28500	10200	

Our Lab I.D.		141615	141619		
Surrogates	Con.Limit	% Rec.	% Rec.	<u>,</u>	
Surrogate Percent Recovery				 	
Bromofluorobenzene	70-120	109	108	 · · · · · · · · · · · · · · · · · · ·	
Dibromofluoromethane	70-120	106	104		
Toluene-d8	70-120	105	105	 	·····

## QUALITY CONTROL REPORT

	MS	MS DUP	RPD	MS/MSD	MS RPD	1		T	
Analytes	% REC	% REC	%	% Limit	% Limit		-		
Benzene	102	92	10.3	75-120	15	 			



Environmental Testing Services

2520 N. San Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

## ANALYTICAL RESULTS

	Page:	21			
-	Project ID:	04-17841	Job Number	Order Date	Client
-	Project Name:	Buckley School	24245	12/28/2004	RINCON

# Method: 8260B, Gas/BTEX and Oxygenates <u>QUALITY CONTROL REPORT</u>

	MS	MS DUP	RPD	MS/MSD	MS RPD			
Analytes	% REC	% REC	%	% Limit	% Limit			
MTBE	99	96	3.1	75-120	15		}	
Toluene (Methyl benzene)	102	94	8.2	75-120	15			 



Invironmental Testing Services

2520 N. San Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

Site

#### ANALYTICAL RESULTS

#### Ordered By

Attn:

Rincon Consultants, Inc.	
790 East Santa Clara Street	
Ventura, CA 93001	

3900 Stansbury Ave.	
Sherman Oaks, CA	
	· ·

Page:	22				
Project ID:	04-17841	Job Num	ber	Order Date	Client
Project Name:	Buckley School	24245	5	12/28/2004	RINCON

#### Method: 8260B, Gas/BTEX and Oxygenates

#### Batch No: 010405-1C

Telephone: (805)641-1000 Joe Inch

Our Lab I.D.		141608	141614		
Sample ID		B1-20	B3-20		
Date Sampled		12/27/2004	12/27/2004	······	
Date Extracted		01/04/2005	01/04/2005		
Preparation Method					
Date Analyzed		01/04/2005	01/04/2005		
Matrix		Soil	Soil		
Units		ug/kg	ug/kg		
Detection Limit Multiplier		1	1		
Analytes	PQL	Results	Results		
Benzene	2.00	32	70		
DIPE	5.00	ND	ND		
ETBE	5.0	ND	ND		
Ethylbenzene	2.00	24	19		
MTBE	5.00	816	1050		· · · · · · · · · · · · · · · · · · ·
ТАМЕ	5.00	ND	ND		
ТВА	20	798	792		
Toluene (Methyl benzene)	2.00	90	ND		
o-Xylene	2.00	67	ND		
m- & p-Xylenes	4.0	128	ND		
TPH as Gasoline (C4-C12)	500	2050	2550		*****

Our Lab I.D.		141608	141614	•	
Surrogates	Con.Limit	% Rec.	% Rec.	·	· ·
Surrogate Percent Recovery				 	
Bromofluorobenzene	70-120	108	106	 	
Dibromofluoromethane	70-120	106	108	 <u> </u>	
Toluene-d8	70-120	102	100	 	

## QUALITY CONTROL REPORT

	MS	MS DUP	RPD	MS/MSD	MS RPD	 T		[]
Analytes	% REC	% REC	%	% Limit	% Limit		1	
Benzene	114	104	9.2	75-120	15			



Environmental Testing Services


2520 N. San Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

#### ANALYTICAL RESULTS

Page:	23	· · · · · · · · · · · · · · · · · · ·			,
Project ID:	04-17841	Job Number	Order Date	Client	
Project Name:	Buckley School	24245	12/28/2004	RINCON	į

## Method: 8260B, Gas/BTEX and Oxygenates QUALITY CONTROL REPORT

	MS	MS DUP	RPD	MS/MSD	MS RPD			
Analytes	% REC	% REC	%	% Limit	% Limit			
MTBE	120	112	6.9	75-120	15			
Toluene (Methyl benzene)	114	103	10.1	75-120	15			



Environmental Testing Services

2520 N. San Fernando Rd., Los Angeles, CA 90065 - Tel: (323) 223-9700 - Fax: (323) 223-9500

#### ANALYTICAL RESULTS

#### Ordered By

Rincon Consultants, Inc.
790 East Santa Clara Street
Ventura, CA 93001

3900 Stansbury Ave. Sherman Oaks, CA

Telephone: (805)641-1000

Joe Inch Attn:

24 Page: Project ID: Project Na

D:	04-17841	Job Number	Order Date	Client
ame:	Buckley School	24245	12/28/2004	RINCON

#### Method: 8260B, Gas/BTEX and Oxygenates


#### Batch No: 010405-1C

Our Lab I.D.		141612	
Sample ID		B3-10	
Date Sampled		12/27/2004	
Date Extracted		01/04/2005	
Preparation Method			
Date Analyzed	· · · · · · · · · · · · · · · · · · ·	01/04/2005	
Matrix		Soil	
Units		ug/kg	
Detection Limit Multiplier		5	
Analytes	PQL	Results	
Benzene	10	ND	
DIPE	25	ND	
ETBE	25	ND	
Ethylbenzene	10	ND	
MTBE	25	ND	
ТАМЕ	25	ND	
ТВА	100	ND	
Toluene (Methyl benzene)	10	ND	
o-Xylene	10	ND	
m- & p-Xylenes	20	ND	
TPH as Gasoline (C4-C12)	2500	93400	

Our Lab I.D.	14161	12			
Surrogates	Con.Limit % Red	3.			
Surrogate Percent Recovery				 	
Bromofluorobenzene	70-120 11	6			
Dibromofluoromethane	70-120 9	9		 	
Toluene-d8	70-120 10	2	······	 	

## QUALITY CONTROL REPORT

	MS	MS DUP	RPD	MS/MSD	MS RPD			
Analytes	% REC	% REC	%	% Limit	% Limit		· .	
Benzene	114	104	9.2	75-120	15			 



Environmental Testing Services

2520 N. San Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

## ANALYTICAL RESULTS

Page:	25			······
Project ID:	04-17841	Job Number	Order Date	Client
Project Name:	Buckley School	24245	12/28/2004	RINCON

## Method: 8260B, Gas/BTEX and Oxygenates QUALITY CONTROL REPORT

	MS	MS DUP	RPD	MS/MSD	MS RPD			
Analytes	% REC	% REC	%	% Limit	% Limit			
MTBE	120	112	6.9	75-120	15			
Toluene (Methyl benzene)	114	103	10.1	75-120	15			



Environmental Testing Services

2520 N. San Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

#### ANALYTICAL RESULTS

Ordered By	Site
Rincon Consultants, Inc.	3900 Stansbury Ave.
790 East Santa Clara Street	Sherman Oaks, CA
Ventura, CA 93001	
T-1	
Telephone: (805)641-1000	

Page:	26			· · · · · · · · · · · · · · · · · · ·	
Project ID:	04-17841		Job Number	Order Date	Client
Project Name:	Buckley School	•	24245	12/28/2004	RINCON

## Method: 8260B, Gas/BTEX and Oxygenates

#### Batch No: 010405-1C

Joe Inch

Attn:

Our Lab I.D.		141609				
Sample ID		B1-25				
Date Sampled		12/27/2004				
Date Extracted		01/04/2005				
Preparation Method						
Date Analyzed		01/04/2005	· · · · - · · ·	-		
Matrix		Soil				
Units		ug/kg		-		
Detection Limit Multiplier		100				
Analytes	PQL	Results			· ·	
Benzene	200	8400	······			
DIPE	500	ND				
ETBE	500	ND				
Ethylbenzene	200	13700				
MTBE	500	3130				
ТАМЕ	500	ND				
ТВА	2000	ND				1
Toluene (Methyl benzene)	200	31000		1		
o-Xylene	200	32000				1
m- & p-Xylenes	400	72200				
TPH as Gasoline (C4-C12)	50000	1080000				

Our Lab I.D.		141609			
Surrogates	Con.Limit	% Rec.	· · · ·	1	
Surrogate Percent Recovery					
Bromofluorobenzene	70-120	105		-	
Dibromofluoromethane	70-120	101			
Toluene-d8	70-120	100			

#### QUALITY CONTROL REPORT

	MS	MS DUP	RPD	MS/MSD	MS RPD	-		
Analytes	% REC	% REC	%	% Limit	% Limit			
Benzene	114	104	9.2	75-120	15		 	ł



Environmental Testing Services

2520 N. Sun Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

## ANALYTICAL RESULTS

Page:	27			
Project ID:	04-17841	Job Number	Order Date	Client
Project Name:	Buckley School	24245	12/28/2004	RINCON

## Method: 8260B, Gas/BTEX and Oxygenates QUALITY CONTROL REPORT

	MS	MS DUP	RPD	MS/MSD	MS RPD			
Analytes	% REC	% REC	%	% Limit	% Limit			•
MTBE	120	112	6.9	75-120	15			
Toluene (Methyl benzene)	114	103	10.1	75-120	15			



Environmental Testing Services

2520 N. San Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

## ANALYTICAL RESULTS

#### Ordered By

Attn:

Rincon Consultants, Inc.	
790 East Santa Clara Street	
Ventura, CA 93001	

Site	
------	--

3900 Stansbury Ave.	
Sherman Oaks, CA	

Page:	28			
Project ID:	04-17841	Job Number	Order Date	Client
Project Name:	Buckley School	24245	12/28/2004	RINCON

#### Method: 8260B, Gas/BTEX and Oxygenates

#### Batch No: 010505-1C

Telephone: (805)641-1000


Joe Inch

Our Lab I.D.		141618			
Sample ID		B4-15	 		
Date Sampled		12/27/2004	 	+	
Date Extracted		01/05/2005	 		
Preparation Method			 		
Date Analyzed		01/05/2005	 · · · · · · ·		
Matrix		Soil			
Units		ug/kg	 		
Detection Limit Multiplier		1	 	•	
Analytes	PQL	Results			
Benzene	2.00	4	 		
DIPE	5.00	ND	 		
ETBE	5.0	ND	 ·····		
Ethylbenzene	2.00	ND	 		
MTBE	5.00	1270	 	1	
TAME	5.00	ND			
ГВА	20	346			
Toluene (Methyl benzene)	2.00	2			
p-Xylene	2.00	ND	 		
m- & p-Xylenes	4.0	ND	 		
TPH as Gasoline (C4-C12)	500	2020	 		

Our Lab I.D.		141618			
Surrogates	Con.Limit	% Rec.			
Surrogate Percent Recovery					 
Bromofluorobenzene	70-120	106	·		
Dibromofluoromethane	70-120	99			 
Toluene-d8	70-120	102			

## QUALITY CONTROL REPORT

	 MS	MS DUP	RPD	MS/MSD	MS RPD			
Analytes	 % REC	% REC	%	% Limit	% Limit			
Benzene	113	113	<1	75-120	15	 		



Environmental Testing Services

2520 N. San Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

## ANALYTICAL RESULTS

	Page:	29	······································		······
-	Project ID:	04-17841	Job Number	Order Date	Client
-	Project Name:	Buckley School	24245	12/28/2004	RINCON
	j	-			

# Method: 8260B, Gas/BTEX and Oxygenates <u>QUALITY CONTROL REPORT</u>

	MS	MS DUP	RPD	MS/MSD	MS RPD		
Analytes	% REC	% REC	%	% Limit	% Limit		
MTBE	120	109	9.6	75-120	15	 	 
Toluene (Methyl benzene)	109	114	4.5	75-120	15		



Environmental Testing Services

2520'N San Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

#### ANALYTICAL RESULTS

#### Ordered By

Attn:

Rincon Consultants, Inc.	
790 East Santa Clara Street	
Ventura, CA 93001	

Si	te	

3900 Stansbury Ave.		
Sherman Oaks, CA		

Page:	30			
Project ID:	04-17841	Job Number	Order Date	Client
Project Name:	Buckley School	24245	12/28/2004	RINCON

## Method: 8260B, TPH as Gas

#### Batch No: 010305-1C

Telephone: (805)641-1000

Joe Inch

Our Lab I.D.		141628	-		·
Sample ID		Pool Sump			
Date Sampled		12/27/2004			
Date Extracted		01/03/2005			
Preparation Method					
Date Analyzed		01/03/2005			
Matrix		Water			
Units		ug/L			
Detection Limit Multiplier		1			
Analytes	PQL	Results			
TPH as Gasoline (C4-C12)	50	ND		<del></del>	

Our Lab I.D.		141628			
Surrogates	Con.Limit	% Rec.			
Surrogate Percent Recovery			- [· · · ·		
Bromofluorobenzene	70-120	116		·	
Dibromofluoromethane	70-120	117	 		
Toluene-d8	70-120	106			

## QUALITY CONTROL REPORT

	MS	MS DUP	RPD	MS/MSD	MS RPD			
Analytes	% REC	% REC	%	% Limit	% Limit			
Benzene	102	94	8.2	75-120	15	 	 	
Chlorobenzene	97	94	3.1	75-120	15	 		
1,1-Dichloroethene (1,1-Dichloroethylene)	114	112	1.8	75-120	15	 	 	
Toluene (Methyl benzene)	107	94	12.9	75-120	15	 	 	
Trichloroethene (TCE)	104	98	5.9	75-120	15		 	



Environmental Testing Services

2520 N. San Fernando Rd., Los Angeles. CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

#### ANALYTICAL RESULTS

Ordered By	Site
Rincon Consultants, Inc.	3900 Stansbury Ave.
790 East Santa Clara Street	Sherman Oaks, CA
Ventura, CA 93001	
Telephone: (805)641-1000	
Attn: Joe Inch	
Page: 31	

Project ID:	04-17841	Job Number	Order Date	Client
Project Name:	Buckley School	24245	12/28/2004	RINCON

## Method: 8082, Polychlorinated Biphenyls(PCBs) by Gas Chromatography

#### Batch No:

Our Lab I.D.		141627		
Sample ID		B7-10		
Date Sampled		12/27/2004		
Date Extracted		12/30/2004		
Preparation Method				
Date Analyzed		12/30/2004		
Matrix		Soil		
Units		ug/kg		
Detection Limit Multiplier		1		
Analytes	PQL	Results		
Aroclor-1016 (PCB-1016)	33.00	ND	-	
Aroclor-1221 (PCB-1221)	67.00	ND		
Aroclor-1232 (PCB-1232)	33.00	ND		
Aroclor-1242 (PCB-1242)	33.00	ND		
Aroclor-1248 (PCB-1248)	33.00	ND		
Aroclor-1254 (PCB-1254)	33.00	ND		
Aroclor-1260 (PCB-1260)	33.00	ND		

Our Lab I.D.		141627	·		
Surrogates	Con.Limit	% Rec.			
Surrogate Percent Recovery					
Decachlorobiphenyl	43-169	114			

### QUALITY CONTROL REPORT

#### Batch No:

· ·	LCS	LCS DUP	LCS RPD	LCS/LCSD	LCS RPD			
Analytes	% REC	% REC	% REC	% Limit	% Limit			
Aroclor-1260 (PCB-1260)	102	95	7.1	39-150	<30		 	



# AMERICAN SCIENTIFIC LABORATORIES, LLC Environmental Testing Services

2520 N. San Fernaudo Rd., Los Angeles, CA 90065 (Tel: (323) 223-9700 (Fax: (323) 223-9500

## ANALYTICAL RESULTS

Ordered By			Si	te			
Rincon Consultan 790 East Santa Cl Ventura, CA 9300	ara Street			00 Stansbury erman Oaks, (			
Telephone: (805)	)641-1000						
Attn: Joe In	nch						
Page:	32						
Project ID:	04-17841		-	Job Number	c Order	Date	Client
Project Name:	Buckley School			24245	12/28	/2004	RINCON
	Method: 6010	B/7471A, C	CR Title 22	Metals (TT	LC)		
Our Lab I.D.	· · · ·		141620	141621	141622	141623	141624
Sample ID			B5-5	B5-10	B5-15	B6-5	B6-10
Date Sampled			12/27/2004	12/27/2004	12/27/2004	12/27/2004	12/27/2004
Date Extracted			01/04/2005	01/04/2005	01/04/2005	01/04/2005	01/04/2005
Preparation Metho	od						
Date Analyzed			01/04/2005	01/04/2005	01/04/2005	01/04/2005	01/04/2005
Matrix			Soil	Soil	Soil	Soil	Soil
Units			mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg
Detection Limit M	fultiplier		1	1	1	1	1
Analytes		PQL	Results	Results	Results	Results	Results
AA Metals							
Mercury		0.20	ND	ND	ND	ND	ND
ICP Metals							
Antimony		0.50	1.03	ND	0.51	0.90	1.03
Arsenic		0.25	11.8	3.14	6.45	12.2	9.51
Barium		0.50	155	72.1	138	178	222
Beryllium		0.50	ND	ND	ND	ND	ND
Cadmium		0.50	0.50	0.91	1.88	0.57	1.72
Chromium		0.50	34.5	16.2	12.2	35.0	27.5
Cobalt		0.50	10.3	4.73	3.40	13.7	7.87
Copper		0.50	24.0	29.1	15.5	26.5	23.7
Lead		0.25	4.63	0.74	ND	4.25	2.31
Molybdenum		0.50	0.68	3.00	5.14	0.74	1.06
Nickel		0.50	25.6	38.9	22.3	28.6	26.6
Selenium		0.50	ND	ND	ND	ND	ND
Silver		0.50	ND	ND	ND	ND	ND
Thallium		0.50	ND	ND	ND	ND	ND
Vanadium		0.50	60.1	66.5	66.6	62.4	57.6
Zinc		0.50	55.9	69.3	47.3		57.7

## QUALITY CONTROL REPORT

		LCS	LCS/LCSD					
Analytes		% REC	% Limit					
AA Metals					1		 	
Mercury	•	108	80-120				 	
ICP Metals							 	
Antimony		87	80-120		1		 	




Environmental Testing Services

2520 N. San Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

## ANALYTICAL RESULTS

Page: Project ID:	<b>33</b> 04-17841			Job Number	Order Date	Client	
Project Name:	Buckley School		F	24245	12/28/2004	RINCON	
		1. CO10D/7471A C			~)		
	Method	1: 6010B/7471A, C		•	-)		
		QUALITY CO	NTROL R	REPORT			
	LCS	LCS/LCSD					
Analytes	% REC	% Limit					
ICP Metals							
Arsenic	89	80-120	·				
Barium	87	80-120					
Beryllium	91	80-120					
Cadmium	90	80-120					
Chromium	86	80-120					
Cobalt	91	80-120		_			
Copper	88	80-120					
Lead	85	80-120					
Molybdenum	85	80-120					
Nickel	92	80-120					
Selenium	89	80-120					
Silver	89	80-120					
Thallium	85	80-120					
Vanadium	87	80-120					
Zinc	92	80-120					



Environmental Testing Services


2520 N. San Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

## ANALYTICAL RESULTS

Ordered By			Site							
Rincon Consultant	s, Inc.		3900 Stansbury Ave.							
790 East Santa Cla	-			erman Oaks, CA						
Ventura, CA 9300					· .					
			L		<u> </u>					
Telephone: (805)	641-1000									
Attn: Joe In										
Page:	34									
Project ID:	04-17841			Job Number	Order Date	Client				
Project Name:	Buckley School		) 	24245	12/28/2004	RINCON				
	Mathad: 60	)10B/7471A, C		Metale (TTI	<u>()</u>					
		//////////////////////////////////////		· · · · · · · · · · · · · · · · · · ·						
Our Lab I.D.			141625	141627						
Sample ID			B6-15	B7-10						
Date Sampled			12/27/2004	12/27/2004						
Date Extracted			01/04/2005	01/04/2005						
Preparation Metho	.d									
Date Analyzed			01/04/2005	01/04/2005						
Matrix			Soil	Soil						
Units			mg/Kg	mg/Kg						
Detection Limit M	ultiplier		1	1						
Analytes	·····	PQL	Results	Results						
AA Metals										
Mercury	<u></u>	0.20	ND	ND						
ICP Metals	· · ·		· · ·							
Antimony	<u></u>	0.50	0.64	ND						
Arsenic		0.25	6.67	14.1						
Barium		0.50	113	50.8						
Beryllium		0.50	ND	ND						
Cadmium		0.50	2.76	1.24						
Chromium		0.50	23.9	11.3						
Cobalt		0.50	2.48	4.26						
Copper		0.50	20.0	17.5						
Lead		0.25	ND	0.58						
Molybdenum		0.50	5.61	3.82						
Nickel		0.50	29.7	24.2						
Selenium		0.50	ND	ND						
Silver		0.50	ND	ND						
Thallium		0.50	ND	ND	· · · · · · · · · · · · · · · · · · ·					
Vanadium		0.50	76.6	71.5						
Zinc		0.50	60.4	36.0						

## QUALITY CONTROL REPORT

	LCS	LCS/LCSD						
Analytes	% REC	% Limit	-				-	
AA Metals			 t					
Mercury	108	80-120	 					
ICP Metals								
Antimony	87	80-120	 <u> </u>	1		 		· · · · · · · · · · · · · · · · · · ·



# AMERICAN SCIENTIFIC LABORATORIES, LLC Environmental Testing Services

2520 N. San Fernando Rd., Los Angeles, CA 90065 (Tel: (323) 223-9700 (Fax: (323) 223-9500)

## ANALYTICAL RESULTS

Page: Project ID:	<b>35</b> 04-17841					Number	h	er Date	Clie	
Project Name:	Buckley School				24245		12/28/2004		RINC	CON
	Method	l: 6010B/7	471A, C	CR Tit	le 22 Me	etals (TTL	C)			
		QUAL	JTY CO	NTRO	L REPO	RT				
	LCS	LCS/LCSD	·						· · · · · · · · · · · · · · · · · · ·	
Analytes	% REC	% Limit	ļ							
ICP Metals				<del>-</del>						
Arsenic	89	80-120								
Barium	87	80-120								
Beryllium	91	80-120								
Cadmium	90	80-120								
Chromium	86	80-120								
Cobalt	91	80-120								
Copper	88	80-120								
Lead	85	80-120								
Molybdenum	85	80-120								
Nickel	92	80-120								
Selenium	89	80-120	_							
Silver	89	80-120								
Thallium	85	80-120								
Vanadium	87	80-120								
Zinc	92	80-120								



Environmental Testing Services

2520 N. San Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

## ANALYTICAL RESULTS

#### Ordered By

Telephone: (805)641-1000 Joe Inch

Rincon Consultants, Inc.	
790 East Santa Clara Street	
Ventura, CA 93001	

3900 Stansbury Ave.
Sherman Oaks, CA

Page:	36			
Project ID:	04-17841	Job Number	Order Date	Client
Project Name:	Buckley School	24245	12/28/2004	RINCON

## Method: 6010B, Lead (ICP)

#### Batch No:

Attn:

Our Lab I.D.		141607	141608	141609	141614	141615
Sample ID		B1-15	B1-20	B1-25	B3-20	B3-25
Date Sampled		12/27/2004	12/27/2004	12/27/2004	12/27/2004	12/27/2004
Date Extracted		01/04/2005	01/04/2005	01/04/2005	01/04/2005	01/04/2005
Preparation Method	1					
Date Analyzed		01/04/2005	01/04/2005	01/04/2005	01/04/2005	01/04/2005
Matrix	1	Soil	Soil	Soil	Soil	Soil
Units	†	mg/Kg	mg/Kg	mg/Kg	mg/Kg	mg/Kg
Detection Limit Multiplier		1	1	1	1	1
Analytes	PQL	Results	Results	Results	Results	Results
ICP Metals			in interest of the			
Lead	0.25	1.40	2.14	ND	1.40	1.91

## QUALITY CONTROL REPORT

#### Batch No:

	LCS	LCS/LCSD					
Analytes	% REC	% Limit			÷	• •	
ICP Metals						· .	
Lead	85	80-120	1				 



AMERICAN SCIENTIFIC LABORATORIES, LLC Environmental Testing Services

2520 N. San Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

#### Ordered By

Telephone

Attn

Rincon Co	onsultants, Inc.	
790 East	Santa Clara Street	
Ventura,	CA 93001	

(805)641-1000 Tricia Bartholome

Number of Pages	8		
Date Received	01/03/2005		
Date Reported	01/12/2005	· · ·	

Job Number	Ordered	Client
24280	01/03/2005	RINCON

Project ID: 04-17841 Project Name: Buckley School

Site: 3900 Stansbury Ave. Sherman Oaks, CA


Enclosed are the results of analyses on 3 samples analyzed as specified on attached chain of custody.

Amolk MOLKY Brar Laboratory Manager


Rojert G. Araghi Laboratory Director

American Scientific Laboratories, LLC (ASL) accepts sample materials from clients for analysis with the assumption that all of the information provided to ASL verbally or in writing by our clients (and/or their agents), regarding samples being submitted to ASL, is complete and accurate. ASL accepts all samples subject to the following conditions: 1) ASL is not responsible for verifying any client-provided information regarding any samples submitted to the laboratory.

 ASL is not responsible for any consequences resulting from any inaccuracies, omissions, or misrepresentations contained in client-provided information regarding samples submitted to the laboratory.



AMERICAN SCIENTIFIC LABORATORIES, LLC Environmental Testing Services



ι

2520 N. San Fernando Road, LA. CA 90065 Tel: (323) 223-9700 • Fax: (323) 223-9500

.


*,* . .

со	<i>c</i> # <b>№</b>	282	32 global	ID	17			ELEC	TRO	NIC	REPORT	: [	] E	DF		DD	ASI	L JO	)B#	20	128	30	<u></u>	
	npany: Ri	nlow	n Consult	tav	uts	<del> </del>			Report	To:	lincer	2									JEST			0
Add	190 t	Sa	nta Clara	Proje	ect Name.	Buck	lee	Schol	Addres	s:				7		77	7	7	/		ΓŢ		[]	┣
	Jentur	a (f	+ 92001	Site	Address:	stan	bŭ	yAre	Invoice	e To:				75	¥ /			/ /						ŀ
Telej Fax:	phone: (805)	They	1-10001	2	herm	ran O	aki		Addres	ss:			1	Ş		5			/ /		' /		/	
Spe	cial Instruction			Proj		4-178	24			<u></u>	<del></del>	/	18	1	.7-1				' /		/ ,			ľ
			······································	Proj	ect hager:	Tricic			P.O.#:	$\gamma q$	17841	7	₹⁄0	Y	¥£	' /		/ ,		/ /	· /			_
	LAB USE OI	NLY	SAMPLE L				· · · · · · · · · · · · · · · · · · ·	Container(s)	<b>L</b>			5	[n	8		-{	$\int \int$	-	{-	-{	-	(		C
E M	Lab ID		Sample ID		Date	Time	#	Туре	Matri	x	Preservation	Polsm	R R R	8260				:		1		Rema	arks	F
			58-5	DI	30/04		l	liner	soi	l				0							-	HOL	D	(
		<u>r</u>	18-95		1		3	VOAS	1		I methand													ι
1	141805	S P	8-9				1	liner				Х	X											Ş
		1	58-9				3	VDAS			1 methans 2 Nathson	1	1								1	HOL	D	
			47-8				1	liner				•									1	1		(
		<u>م</u>	9-8			-	3	VDAS			1 methand 2 Natisa	,								-	1			0
2	141806		59-10				1	liner				X			X	-				-	1			<b>`</b>
	•	<b>1</b>	9-10				3				Inethant SNatso			X									<u></u>	
	an a	P P	510-5				1	lines												-	+	Ha	D	F
			-10-5		I		3	VDAS	$\mathbf{V}$		Inethand 2 Na HSD					_				-		L		E
Coll	ected By: 1	Licont		NO TI	rh ^{Date}	12/30/01	Tii	me	Relin		ned By:	4	I	l <u></u>	D	ate			Tim	 ie	<u> </u>		<b></b>	0
Reli	inquished By		iclinsons	7 1	Date	1/3/05	Til	me 10 43	Rece For L	eivec abo	ratory M	osi		•	D	ate /-	3-6	15	Tim	ne /0	,43			C F
Cor	ndition of San	· • •	C Co C LA - JU- Co V			1905		<u>_</u>	I				- C		···					<u></u>		Rus	sh	
					·										· · · · · · · · · · · · · · · · · · ·							1		

ر τ.



. . . . .




Environmental Testing Services

2520 N. San Fernando Road, LA, CA 90065 Tel: (323) 223-9700 • Fax: (323) 223-9500

со	<i>C</i> # №	28	233 _{GLOBAL}	ID			ELEC	CTRONIC	REPORT	: [	] <i>El</i>	DF		EDD	AS	SL J	IOB,	#	24	28	0
Con	npany: Rin	LIV	anta Clara	t				Report To:	Zincor	١							IS				1
Add	tress: HO	1 11	anta Clarci	Project Name:	Luck	le	School	Address:				6		//	/	/	7	7	7	7	777
Ù	entur	i		Site Address:	tansb	un (	Aves	Invoice To:			[	75)				/ /		/ /		/ /	/ / /
Telej Fax:	phone (805)	62	11-1000	Shennan				Address:			$\langle \mathcal{S} \rangle$	7.	R	7 /							
Spe	cial Instruction	:	- 	Project ID:	)4-17	8	41					Y	Por the				/ /		· /		
				Project Manager:	Trad	1		Р.О.#:04	-17841	Ē	77	7	4		$\square$	/		/			/
T T E	LAB USE O	NLY	<del></del>	DESCRIPTION			Container(s)	Matrix	Preservation	ROISIN	g	33								ļ	Remarks
м	Lab ID		Sample ID	Date	Time	#	Туре			R	a	<u>FE</u>									
3	141807	<u> </u>	B10-10	12/3004			liner	soil	·	X,		X									
		l	B10-10	v		3	VOAS	11	Inethand DNatliag		X				-						
	• ••• •• • • ••• ••• ••• ••• •••						· · · · · · · · · · · · · · · · · · ·								-						
					······································																
	M-1																				
	• • • • • • • • • • • • • • • • • • •				<del></del>		- 														
Col	lected By: /	lie	17 Au Bart	Date	izhaha	Tir	ne	Relinquisl	hed By:					Date	1	l		me		-+	
Rel	inquished By	N	Ini Anster	l Date	1/3/05		ne 10 ⁴⁸	1	ratory M	118	e_				-7-	1.0			04.	3	TAT Normal
Соі	ndition of Sar	nple:	<u></u>		4 700			1	. /		-/			t	<u>×</u>	~ ~ ~			·		Rush

. . . .



States and the states of the State ON


25 YUN She Lemande Kit, Los Angeles, CA 90065 [Tel: (323) 223-9700 [Fax: (323) 223-9800]

#### ANALYTICAL RESULTS

Ordered By				Si	te		
Rincon Consultants 790 East Santa Clar Ventura, CA 93001	a Street				00 Stansbury erman Oaks, (		
Telephone: (805)6 Attn: Tricia	41-1000 Bartholome						
Page:	2			r			 
Project ID: Project Name:	04-17841 Buckley Sch	001			<b>Job Numbe</b> 24280	r Order 1 01/03/	 Client RINCON
Batch No: 0106		Method: 8015	WI/DISLUI	r1, 1rn D	KU AND U	ĸŬ	
Our Lab I.D.				141805	141806	141807	
Sample ID				B8-9	<b>B9-10</b>	B10-10	 
Date Sampled				12/30/2004	12/30/2004	12/30/2004	 
Date Extracted				01/04/2005	01/04/2005	01/04/2005	
Preparation Method	1						 
Date Analyzed				01/07/2005	01/07/2005	01/07/2005	 
Matrix				Soil	Soil	Soil	
Units				mg/kg	mg/kg	mg/kg	 
Detection Limit Mu	ultiplier			1	1	1	 
Analytes			PQL	Results	Results	Results	 
TPH DRO (C13-C22)			10	ND	ND	ND	 
TPH ORO (C22+)			50	ND	ND	ND	 
			······	141805	141806	141807	 
Our Lab I.D.				111000			
Our Lab I.D. Surrogates Surrogate Percent R	ecovery	·····	Con.Limit		% Rec.	% Rec.	 

Batch No: 010605-2

	MS	MS DUP	RPD	MS/MSD	MS RPD	 		
Analytes	% REC	% REC	%	% Limit	% Limit			
Diesel	105	100	4.9	75-120	15	 		



en an trèis ann an t-A**CC**N

25.20 × (San Fellounder Rev. Lex Arecle), CA 90065, Tel: (325) (223-9700, Fax: (323) 223-9890

#### ANALYTICAL RESULTS


	Ordered By	Site
•	Rincon Consultants, Inc.	3900 Stansbury Ave.
	790 East Santa Clara Street	Sherman Oaks, CA
	Ventura, CA 93001	
•		
	Telephone: (805)641-1000	
2	Attn: Tricia Bartholome	

Page:	3			
Project ID:	04-17841	Job Number	Order Date	Client
Project Name:	Buckley School	24280	01/03/2005	RINCON

#### Method: 8260B, Volatile Organic Compounds

#### Batch No: 010405-1C

Our Lab I.D.		141806	141807	11 10 10 10 10 10 10 10 10 10 10 10 10 1		
Sample ID		<b>B9-10</b>	B10-10		•	
Date Sampled		12/30/2004	12/30/2004			
Date Extracted	•	01/04/2005	01/04/2005	· · · · · · · · · · · · · · · · · · ·		
Preparation Method			· • · · · · · · · · · · · · · · · · · ·		• • • •	
Date Analyzed		01/04/2005	01/04/2005	+		
Matrix		Soil	Soil			
		ug/kg	ug/kg	+		
Units		ug/kg			- · · · ·	
Detection Limit Multiplier		1	1			
Analytes	PQL	Results	Results			
Acetone	50.0	ND	ND			
Benzene	2.00	ND	ND			
Bromobenzene (Phenyl bromide)	10.00	ND	ND			
Bromochloromethane (Chlorobromomethane)	10.00	ND	ND	(		
Bromodichloromethane (Dichlorobromomethane)	10.00	ND	ND			
Bromoform (Tribromomethane)	50.00	ND	ND			
Bromomethane (Methyl bromide)	30.00	ND	ND			
2-Butanone (MEK, Methyl ethyl ketone)	50.00	ND	ND			
n-Butylbenzene	10.00	ND	ND			
sec-Butylbenzene	10.00	ND	ND			
tert-Butylbenzene	10.00	ND	ND			
Carbon disulfide	10.00	ND	ND			
Carbon tetrachloride (Tetrachloromethane)	10.00	ND	ND			
Chlorobenzene	10.00	ND	ND		1	
Chloroethane	30.00	ND	ND			
2-Chloroethyl vinyl ether	50.00	ND	ND			
Chloroform (Trichloromethane)	10.00	ND	ND			
Chloromethane (Methyl chloride)	30.00	ND	ND			
4-Chlorotoluene (p-Chlorotoluene)	10.00	ND	ND			
2-Chlorotoluene (o-Chlorotoluene)	10.00	ND	ND			
1,2-Dibromo-3-chloropropane (DBCP)	50.00	ND	ND	· · · · ·		
Dibromochloromethane	10.00	ND	ND			
1,2-Dibromoethane (EDB, Ethylene dibromide)	10.00	ND	ND			
Dibromomethane	10.00	ND	ND	···· * ·		· · · ·
1,2-Dichlorobenzene (o-Dichlorobenzene)	10.00	ND	ND			2
1,3-Dichlorobenzene (m-Dichlorobenzene)	10.00	ND	ND	•		



³⁴ D. S. S. Ferrara, Ka. Prov. Soc. U.S. CA 90065, *Vol.* (523) 223–9706, *Pure* 1325(223) 9800


#### ANALYTICAL RESULTS

Page:	4	p			1
Project ID:	04-17841	Job Number	Order Date	Client	ĺ
Project Name:	Buckley School	24280	01/03/2005	RINCON	
1 I UIUUU I Raino.					

#### Method: 8260B, Volatile Organic Compounds

#### Batch No: 010405-1C

Our Lab I.D.		141806	141807				
Sample ID	-	B9-10	B10-10				
Date Sampled		12/30/2004	12/30/2004				4
Analytes	PQL	Results	Results				
1,4-Dichlorobenzene (p-Dichlorobenzene)	10.00	ND	ND				+
Dichlorodifluoromethane	30.00	ND	ND				
1,1-Dichloroethane	10.00	ND	ND			· · ····•• · ·•	
1,2-Dichloroethane	10.00	ND	ND	· · · • · · · · · · · · · · · · · · · ·			+
	10.00	ND	ND	· ···· ··· · ···			
1,1-Dichloroethene (1,1-Dichloroethylene)	10.00	ND	ND				
cis-1,2-Dichloroethene	10.00	ND	ND				
trans-1,2-Dichloroethene	10.00	ND	ND				
1,2-Dichloropropane	10.00	ND					
1,3-Dichloropropane	1	1	ND				
2,2-Dichloropropane	10.00	ND	ND				ļ
1,1-Dichloropropene	10.00	<b>ND</b>	ND	· · · · · · ···			
cis-1,3-Dichloropropene	10.00	ND	ND	······			
trans-1,3-Dichloropropene	10.00	ND	ND 3				
Ethylbenzene	2.00	4	· · · · · · · · · · · · · · · · · · ·				
Hexachlorobutadiene (1,3-Hexachlorobutadiene)	30.00	ND	ND				
2-Hexanone	50.00	ND	ND				
sopropylbenzene	10.00	ND	ND				
o-Isopropyltoluene (4-Isopropyltoluene)	10.00	ND	ND		T		
MTBE	5.00	ND	ND				
4-Methyl-2-pentanone (MIBK, Methyl isobutyl ketone)	50.00	ND	ND				
Methylene chloride (Dichloromethane, DCM)	50.00	ND	ND		1		
Naphthalene	10.00	ND	ND		-		
n-Propylbenzene	10.00	ND	ND	· · ·		· •	
Styrene	10.00	ND	ND			-	
1,1,1,2-Tetrachloroethane	10.00	ND	ND		1		
1,1,2,2-Tetrachloroethane	10.00	ND	ND	- ·			
Tetrachloroethene (Tetrachloroethylene)	10.00	ND	ND				al.a a a
Toluene (Methyl benzene)	2.00	ND	ND		+		4
1,2,3-Trichlorobenzene	10.00	ND	ND				
1,2,4-Trichlorobenzene	10.00	ND	ND				
1,1,1-Trichloroethane	10.00	ND	ND	· ··· · ·			· · · · ·
1,1,2-Trichloroethane	10.00	ND	ND				
Trichloroethene (TCE)	10.00	ND	ND				
Trichlorofluoromethane	10.00	ND	ND	,			
	10.00	ND	ND				
1,2,3-Trichloropropane	10.00	:			+ .		
1,2,4-Trimethylbenzene		ND	ND	•	1		
1,3,5-Trimethylbenzene	10.00	ND	ND				
Vinyl acetate	50.0	ND	ND				
Vinyl chloride (Chloroethene)	30.00	ND	ND				
o-Xylene	2.00	ND	ND				
m- & p-Xylenes	4.00	ND	ND				



 $= - E_{\rm e}^2 E_{\rm e}^2 + E_{\rm e}^2 + E_{\rm e}^2 E_{\rm e}^2 + E_{\rm e$ 

[15] Weinstein Revision Revision (North Control of North 1990) 21 (1990) For (323) 223 (1990).

#### ANALYTICAL RESULTS

2	Page:	5		1		
	Project ID:	04-17841	Job Numbe	r Order Date	Client	
ì	Project Name:	Buckley School	24280	01/03/2005	RINCON	


#### Method: 8260B, Volatile Organic Compounds

	Our Lab I.D.		141806	141807	 	
-	Surrogates	Con.Limit	% Rec.	% Rec.		
-	Surrogate Percent Recovery					
	Bromofluorobenzene	70-120	111	116	 	
1	Dibromofluoromethane	70-120	82	84	 	
•	Toluene-d8	70-120	102	104		

#### QUALITY CONTROL REPORT

#### Batch No: 010405-1C

		MS	MS DUP	RPD	MS/MSD	MS RPD		T		
ŗ	Analytes	% REC	% REC	%	% Limit	% Limit				
,	Benzene	114	104	9.2	75-120	15	 			 
	Chlorobenzene	106	101	4.8	75-120	15				 
۲	1,1-Dichloroethene	118	106	10.7	75-120	15				
	(1,1-Dichloroethylene)									
1	MTBE	120	112	6.9	75-120	15			Ĩ	
2	Toluene (Methyl benzene)	114	103	10.1	75-120	15				
	Trichloroethene (TCE)	106	100	5.8	75-120	15	 1			 



# American Scientific Laboratories, LLC

Renaramental Testing Services

2520 N. Son Fernando Rd., Los Angeles, CA 90065 - Irl, (227) 223-9700 - Fax: (323) 223-9590

#### ANALYTICAL RESULTS

Ordered By	Site
Rincon Consultants, Inc.	3900 Stansbury Ave.
790 East Santa Clara Street	Sherman Oaks, CA
Ventura, CA 93001	
Telephone: (805)641-1000	

relephone. (605	<i>j</i> 0+1-1000			
Attn: Trici	a Bartholome			
Page:	6			
Project ID:	04-17841	Job Number	Order Date	Client
Project Name:	Buckley School	24280	01/03/2005	RINCON

#### Method: 8082, Polychlorinated Biphenyls(PCBs) by Gas Chromatography

Batch No:

Our Lab I.D.		141805		•
Sample ID		B8-9		
Date Sampled		12/30/2004		
Date Extracted		01/04/2005		
Preparation Method	······································			
Date Analyzed		01/06/2005		
Matrix		Soil		
Units	· · · · · · · · · · · · · · · · · · ·	ug/kg		
Detection Limit Multiplier		1		
Analytes	PQL	Results	· · · ·	
Aroclor-1016 (PCB-1016)	33.00	ND		
Aroclor-1221 (PCB-1221)	67.00	ND		
Aroclor-1232 (PCB-1232)	33.00	ND		
Aroclor-1242 (PCB-1242)	33.00	ND		
Aroclor-1248 (PCB-1248)	33.00	ND		
Aroclor-1254 (PCB-1254)	33.00	ND		
Aroclor-1260 (PCB-1260)	33.00	ND		

Our Lab I.D.		141805		
Surrogates	Con.Limit	% Rec.		
Surrogate Percent Recovery				
Decachlorobiphenyl	43-169	90	 	

#### QUALITY CONTROL REPORT

#### Batch No:

	LCS	LCS DUP	LCS RPD	LCS/LCSD	LCS RPD	
Analytes	% REC	% REC	% REC	% Limit	% Limit	
Aroclor-1260 (PCB-1260)	113	113	<1	39-150	<30	



# American Scientific Laboratories, LLC

Environmental Testing Services

2520 N. San Fernando Rd., Los Angeles, CA 90065 - Tel: (323) 223-9700 - Fax: (323) 223-9500

#### ANALYTICAL RESULTS

Ordered By		Site	Site						
Rincon Consultan 790 East Santa Cl	-	3900 Stansbury Av Sherman Oaks, CA	3900 Stansbury Ave. Sherman Oaks, CA						
Ventura, CA 9300									
Telephone: (805) Attn: Tricia	)641-1000 a Bartholome								
Page:	7								
Project ID:	04-17841	Job Number	Order Date	Client					
Project Name:	Buckley School	24280	01/03/2005	RINCON					

### Method: 6010B/7471A, CCR Title 22 Metals (TTLC)

Batch No:

Our Lab I.D.		141806	141807	
Sample ID		B9-10	B10-10	
Date Sampled		12/30/2004	12/30/2004	
Date Extracted		01/06/2005	01/06/2005	
Preparation Method				
Date Analyzed		01/06/2005	01/06/2005	
Matrix		Soil	Soil	
Units		mg/Kg	mg/Kg	······
Detection Limit Multiplier		1	1	
Analytes	PQL	Results	Results	
AA Metals				
Mercury	0.20	ND	ND	
ICP Metals				
Antimony	0.50	0.63	0.75	
Arsenic	0.25	0.90	3.57	
Barium	0.50	64.1	125	
Beryllium	0.50	ND	ND	
Cadmium	0.50	2.87	0.81	
Chromium	0.50	10.7	10.4	
Cobalt	0.50	3.23	4.31	
Copper	0.50	19.8	20.0	
Lead	0.25	0.38	2.18	
Molybdenum	0.50	1.92	1.58	
Nickel	0.50	22.8	19.4	
Selenium	0.50	ND	ND	
Silver	0.50	0.84	0.70	
Thallium	0.50	ND	ND	
Vanadium	0.50	40.1	44.6	
Zinc	0.50	55.5	51.8	

#### QUALITY CONTROL REPORT

Batch No:

	LCS	LCS/LCSD			 -	
Analytes	% REC	% Limit				



Environmental Tessing Services

2520 N. San Fernando Rd. Los Angeles, CA 90065 (Tel: (323) 223/9706 (Fax: (323) 223/9500

#### ANALYTICAL RESULTS

Page:	8	· · _ · _ ·		;1
Project ID:	04-17841	Job Number	Order Date	Client
Project Name:	Buckley School	24280	01/03/2005	RINCON

# Method: 6010B/7471A, CCR Title 22 Metals (TTLC) <u>QUALITY CONTROL REPORT</u>

Batch No:

	LCS	LCS/LCSD				1		 1
Analytes	% REC	% Limit						
AA Metals								
Mercury	90	80-120						
ICP Metals								
Antimony	84	80-120						 
Arsenic	86	80-120						 
Barium	86	80-120		1				
Beryllium	89	80-120				1		 
Cadmium	87	80-120						
Chromium	86	80-120						
Cobalt	90	80-120						
Copper	87	80-120						
Lead	84	80-120						
Molybdenum	84	80-120						
Nickel	87	80-120		1				
Selenium	88	80-120		1				
Silver	92	80-120						 
Thallium	83	80-120						
Vanadium	86	80-120						
Zinc	89	80-120						

# **Site Assessment Report**

Buckley School 3900 Stansbury Avenue Sherman Oaks, California

Submitted to:

Los Angeles Fire Department Underground Storage Tank Program

Prepared by:

 Rincon Consultants, Inc. January 7, 2006



Rincon Consultants, Inc.

790 East Santa Clara Street Ventura, California 93001

805 641 1000 FAX 641 1072

info@rinconconsultants.com www.rinconconsultants.com

January 7, 2006 Project Number 04-17842

Captain Frank Comfort Los Angeles Fire Department Underground Storage Tank Program 200 North Main Street, Rm. 1700 Los Angeles, CA 90012

#### Site Assessment Report 3900 Stansbury Avenue Sherman Oaks, California ID Number 916061598

Dear Captain Comfort:

This *Site Assessment Report* has been prepared for the Buckley School property located at 3900 Stansbury Avenue in Sherman Oaks, California. Services were provided in accordance with Rincon's *Site Assessment Workplan*, dated October 31, 2005, and the Los Angeles Fire Department's approval letter, dated December 9, 2005. The purpose of this assessment was to collect and analyze soil and groundwater samples from the vicinity of the former underground storage tank. The following report summarizes the work preformed, the findings, and provides conclusions and a recommendation.

Please contact us with any questions regarding this Report.

Scientists

Sincerely, RINCON CONSULTANTS, INC.

Environmental

Geoffrey Frieman, MESM Project Manager, Environmental Services

Walter Hamann, PG, CEG, REA II Vice President, Environmental Services

л



Engine

### **EXECUTIVE SUMMARY**

This report presents the findings of a soil and groundwater assessment conducted by Rincon Consultants on behalf of the Buckley School, located at 3900 Stansbury Avenue in Sherman Oaks, California (Figure 1). The site is approximately an 18-acre developed property with a private school (elementary through high school), located in an area that is comprised of residential land uses and open space. The Buckley School campus is currently developed with approximately 16 structures.

The purpose of the soil and groundwater assessment was to collect and analyze soil and groundwater samples from the vicinity of the former underground storage tank (UST). One soil boring was advanced to groundwater near the center of the former UST pit, and converted to a groundwater monitoring well.

On December 22, 2005, a hollow-stem auger drill rig was used to drill one soil boring at the former UST area (Figure 2). The soil boring was converted into a 2-inch diameter groundwater monitoring well (MW-1). MW-1 was installed to assess groundwater at the former UST area at the Site (Figure 2). During drilling of the soil boring, soil samples were collected at five-foot intervals. A total of ten soil samples were collected during this assessment.

No soil discoloration was noted, however, gasoline odor was noted in the soil samples collected between 20 and 25 feet below grade. The photoionization detector (PID) readings ranged from 0 to 64.4 parts per million by volume (ppmv) for the soil samples collected. Soil was predominately comprised of silty sands and sandy clays with layers of hard brittle siltstone at approximately 25, 45, and 55 feet below grade. Methyl tertiary butyl ether (MTBE) was detected in samples at 20 and 30 feet below grade. Total petroleum hydrocarbons (TPH) as gasoline range, carbon range C4- C12, was detected at 20 feet below the existing grade.

Groundwater was encountered in the boring at an approximate depth of 55 feet below grade. The boring was deepened to 70 feet below grade to enable installation of a groundwater monitoring well. However, groundwater was encountered during the sampling of the groundwater monitoring well at 41.19 feet below the top of casing. The analyzed groundwater sample did not have detectable levels of TPH-gasoline, benzene, ethylbenzene, total xylenes, or fuel oxygenates. Toluene was detected at 1.2 micrograms per liter ( $\mu$ g/L).

To evaluate the significance of TPH-gasoline and VOC levels in soil, the levels were compared to Maximum Soil Screening Levels (MSSL) established by the Regional Water Quality Control Board – Los Angeles Region (RWQCB) for TPH and VOCs above Drinking Water Aquifers (*Interim Site Assessment and Cleanup Guidebook*, dated May 1996). The Los Angeles RWQCB MSSL for TPH-gasoline at the site was determined to be 500 milligrams per kilogram (mg/kg). A concentration of 0.682 mg/kg TPH-gasoline was detected in the soil sample collected below the former UST at 20 feet below grade. This value is below the MSSL for this constituent. The screening level for benzene at 30 and 20 feet above groundwater was calculated to be 0.0079 mg/kg and 0.0082 mg/kg, respectively. Benzene was detected at a concentration of 0.006 mg/kg and 0.003 mg/kg in the soil at depths of 30 and 20 feet above groundwater, respectively. These values are below the MSSL for this constituent. The screening level for benzene to for this constituent.

### **INTRODUCTION**

This report presents the findings of a soil and groundwater assessment conducted by Rincon Consultants on behalf of the Buckley School located at 3900 Stansbury Avenue in Sherman Oaks, California (Figure 1). The site is approximately an 18-acre developed property with a private school (elementary through high school), located in an area that is comprised of residential land uses and open space. The Buckley School campus is currently developed with approximately 16 structures.

The following sections provide: an overview of the project history; the purpose and scope of the project; the physical setting, sampling and analytical testing methodologies; the results of the sampling and testing program; and conclusions and recommendations.

#### **PROJECT HISTORY**

Rincon performed a Phase I and Phase II Environmental Site Assessment (ESA), dated March 25, 2005, for the Buckley School property. As part of the March 25, 2005 report, an environmental database search and a site reconnaissance was performed. As a follow-up to the database search and the site reconnaissance, we filed a request with Los Angeles City Fire Department (LAFD) and the Regional Water Quality Control Board (RWQCB) to review documents pertaining to the subject site. The following is based on the document review conducted by Rincon for the subject site on December 2, 2004.

#### **Review of LAFD Files**

According to an LAFD Fire/Life Safety Violation notice, dated May 27, 1988, Buckley School was directed to remove product from the leaking underground storage tank (UST), monitor the groundwater sump (located beneath the swimming pool, downgradient of the UST area) for flammable vapors, provide an integrity test of the UST, and provide the LAFD with a report of analysis from soil borings to determine whether or not an unauthorized release has occurred.

According to a June 2, 1988 LAFD Fire/Life Safety Violation notice, Buckley School was required to provide a site assessment including the extent of contamination, location of groundwater, groundwater flow direction, and cleanup recommendations.

According to an Engineering Report on Soil Gas Investigation, prepared by Enviropro Inc. on October 31, 1988, one 10,000-gallon gasoline tank was removed in July of 1988. During the excavation of the tank (July 1998), two soil samples were collected and analyzed for total petroleum hydrocarbons (TPH). TPH was detected at a concentration of 46,600 milligrams per kilogram (mg/kg) in the soil sample collected from the north end of the excavation (Sample #1). A preliminary soil gas investigation was conducted by Enviropro Inc. on August 11, 1988 using a photoionization detector (PID). A total of 29 boreholes were drilled to depths from 1 to 1.5 feet below grade. The boreholes were covered with a plastic film and vapors were allowed to collect in the borehole. PID readings were collected from the boreholes by penetrating the plastic film with the PID sampling probe. The report states that the results of the soil gas investigation are only qualitative, because no direct measurement of soil or groundwater contamination has been provided. PID readings collected from various locations near the tank excavation area and the Pavilion area, downgradient of the former tank area, indicate the highest volatile organic compound (VOC) concentration was detected near the tank excavation to the east. The report proposes that a subsequent remedial investigation be conducted, including the installation of three groundwater monitoring wells.

A LAFD letter, dated April 12, 1989, states that groundwater beneath the site has been impacted and the case has been referred to the State Regional Water Quality Control Board (SRWQCB).

#### **Review of RWQCB Files**

A May 27, 1988 State of California Hazardous Substance Spill Report indicates that the LAFD notified the RWQCB of the gasoline UST release. The spill report indicates that the UST leaked an unknown quantity of gasoline into the swimming pool and school grounds sump pump, causing fuel to be pumped into a drainage ditch, which flows to the Los Angeles River.

According to a June 2, 1988 Underground Storage Tank Unauthorized Release (Leak) / Contamination Site Report, an unknown quantity of gasoline was released from the UST. The leak was discovered on May 27, 1988 during a tank test. The discharge was reportedly stopped by removal of tank contents. A piping leak was the determined source of discharge of the 10,000-gallon, 16 year-old steel tank.

A RWQCB case closure letter, dated July 22, 1996, indicates site closure was granted and no further action was required related to the UST release. A copy of the July 22, 1996 RWQCB letter is included in Appendix 1.

#### March 25, 2005 Phase II Environmental Site Assessment

The findings of the March 25, 2005 Phase I ESA indicated that the former presence of a UST and associated gasoline release on the subject site was a recognized environmental condition.

To evaluate the potential site impact associated with the former UST, a Phase II ESA was conducted at the site on December 27 and 30, 2004. The Phase II included the collection of subsurface soil samples (B1 through B4) from four locations in the vicinity of the former UST (Figure 3) and the analysis of select soil samples for the presence of TPH, benzene, toluene, ethylbenzene and xylenes (BTEX), lead, and fuel oxygenates.

The soil sample laboratory analytical results are summarized in Table 1. The findings of the Phase II indicate that the RWQCB MSSLs for TPH as gasoline (TPH-g) and benzene were exceeded in sample B1 at 25 feet below grade. BTEX and methyl tertiary butyl ether (MTBE) were detected in soil samples collected at various depths in borings B1, B3, and B4 at concentrations that could potentially exceed the MSSLs. Without actual depth to groundwater data for these locations, exact MSSLs cannot be calculated to determine whether these thresholds have been exceeded. The MSSL exceedence and potential exceedences were identified in the four borings advanced in the vicinity of the former UST area. Groundwater was not encountered in these borings during the Phase II ESA. Therefore, impact to groundwater and depth to groundwater could not be assessed.

On behalf of the Buckley School, Rincon submitted a Site Assessment Workplan (dated November 18, 2005) to the LAFD. The purpose of the workplan was to assess the impact to groundwater and the depth to groundwater at the former UST area. The LAFD approved the workplan in a letter dated December 9, 2005 (Appendix 2).

#### PURPOSE AND SCOPE

The purpose of the soil and groundwater assessment was to collect and analyze soil and groundwater samples from the vicinity of the former UST. One soil boring was advanced to groundwater near the center of the former UST pit, and converted to a groundwater monitoring well.

Our scope of work included the following:

- Provide advance notice of field sampling to the LAFD.
- Obtain a groundwater monitoring well permit.
- Conduct a geophysical survey of the proposed boring locations.
- Drill one soil boring to approximately 70 feet below grade using a hollow-stem auger drill rig near the center of the former UST location.
- Collect soil samples from the soil boring at 5-foot intervals starting at 5 feet below grade and ending at approximately 70 feel below grade for purposes of soil classification, field screening for VOCs, and retaining undisturbed samples for laboratory analysis.
- Convert the soil boring to groundwater monitoring well MW-1. Develop, purge, and sample groundwater monitoring well MW-1.
- Analyze soil and groundwater samples for BTEX, TPH-g, and fuel oxygenates (including MTBE) by EPA Method 8260B.
- Prepare this report documenting our findings.

#### GEOLOGIC AND HYDROGEOLOGIC SETTING

#### Topography

The current USGS topographic map (Van Nuys Quadrangle, 1966, photorevised 1972) indicates that the site is situated at an elevation ranging from about 800 to 900 feet above mean sea level with topography sloping downward to the west-northwest on the eastern portion of the site and to the east-southeast on the western portion of the site.

#### Geology and Hydrogeology

The project area is near the southern boundary of the San Fernando Valley alluvial basin. The sediments in the area are erosional remnants of the sedimentary rocks found along the southern boundary of the Santa Monica Mountains. These sedimentary rocks consist of claystones and siltstones. Erosion of these sediments generally results in fine-grained alluvial deposits.

According to the Geologic Map of the Beverly Hills and Van Nuys (South 1/2) Quadrangles (Dibblee, 1991), the site is underlain by Quaternary-age alluvium and Miocene-age unnamed shale and Monterey Formation. The alluvium is comprised of unconsolidated deposits of gravel, sand and silt-clay, derived mostly from Santa Monica Mountains and including gravel and sand from stream channels. The unnamed shale is comprised of soft, white-weathering diatomaceous shale to diatomite. The Monterey Formation is comprised of white-weathering, thin bedded, moderately hard, dark siliceous shale, and tan to light gray semi-friable bedded sandstone.

The GeoCheck summary report reviewed for the March 25, 2005 Phase I ESA indicates that the site is underlain by a Tertiary age stratified sequence. The USDA soil survey for the general area of the property indicates that the soil types present in the site vicinity are primarily gravelly loam. Based on the results of the soil sampling performed by Rincon for the December 27 and 30, 2004 Phase II ESA and as part of the current assessment, soil was comprised primarily of sandy, silty clay mixtures, and siltstone.

#### Hydrogeology

The site is located in the southern portion of the Los Angeles River Watershed. In the San Fernando Valley area, groundwater depths range from near land surface to 100 feet below ground surface. Based on the results of the groundwater monitoring well installation (MW-1), groundwater was encountered at an approximate depth of 55 feet below grade. During groundwater sampling on January 10, 2006, groundwater was encountered at 41.19 feet below the top of casing. Groundwater flow direction has not been established for this site. However, based on the assumption that the groundwater flow direction in the area parallels the topographic gradient, the general anticipated groundwater flow direction in the vicinity of the former UST would be to the east-northeast.

### METHODOLOGY

#### **GEOPHYSICAL SURVEY**

On December 22, 2005, Spectrum Geophysics of Burbank, California conducted a geophysical survey at the Site under the oversight of Rincon Consultants. The purpose of the geophysical survey was to assess the presence of utilities at each of the boring locations. The survey included the use of ground-penetrating radar (GPR) and electromagnetic utility locating equipment.

#### UTILITY MARKING AND NOTIFICATION

Consistent with California law, Underground Service Alert was notified prior to the commencement of subsurface sampling. The utility marking service identifies known utility locations in the public right of way.

#### GROUNDWATER MONITORING WELL INSTALLATION

Prior to groundwater monitoring well installation, a groundwater monitoring well permit was obtained from the County of Los Angeles Department of Health Services. A copy of the permit is included in Appendix 3.

On December 22, 2005, Test America Drilling Corporation of Anaheim, California, used a hollow-stem auger drill rig to drill one soil boring at the former UST area (Figure 2). The soil boring was converted into a 2-inch diameter groundwater monitoring well (MW-1). MW-1 was installed to assess groundwater at the former UST area at the Site (Figure 2). The well was installed under the responsible oversight of Rincon's California Professional Geologist.

#### SOIL SAMPLING

During drilling of the soil boring, soil samples were collected at five-foot intervals. The samples were collected by driving a modified California Split Spoon sampler with brass liner inserts. Soil retained for laboratory analysis from select sample intervals was preserved onsite using EPA method 5035. Soil was collected from the brass liner using a disposable Lock N' Load sampling device. The Lock N' Load soil sample was then placed into 40-milliliter (ml) VOA vials containing either sodium bisulfate preservative or a methanol preservative, provided by the analytical laboratory. The samples were labeled, placed in a sealable plastic bag, and stored in a cooler with blue ice pending delivery to the analytical laboratory. In addition, a liner from each sample interval was sealed with Teflon, capped, labeled, placed in a sealable plastic bag, and stored is sample interval was used to screen for volatile organics using a PID and to classify the soil using the Unified Soil Classification System.

Groundwater was encountered in the boring at an approximate depth of 55 feet below grade. The boring was deepened to 70 feet below grade to enable installation of a groundwater monitoring well. Soil cuttings generated during drilling were stored onsite in a roll-off soil bin. Augers were decontaminated between uses by steam cleaning. Sampling equipment was decontaminated between uses by washing with a non-phosphate solution followed by a potable water rinse. The decontamination fluids were stored onsite in a 55-gallon DOT drum.

The field log of the boring is included as Appendix 4, Log of Boring/Monitoring Well.

#### GROUNDWATER MONITORING WELL DEVELOPMENT AND SAMPLING

On January 10, 2006, the well was developed and purged with a submersible pump. Prior to development and purging of the well, depth to water and total well depth were measured using an electronic water level indicator. The well was surged to suspend sediments in the well casing. A submersible pump was then used to purge and develop the well. A temperature-conductivity-pH meter was used to monitor aquifer parameters during development and purging. These parameters were monitored to verify that the aquifer conditions had stabilized and the sample to be collected is representative of the aquifer conditions at that location. Approximately 10 well volumes of water (37 gallons) were removed from MW-1 using the submersible pump. Purged water was pumped directly into labeled, 55-gallon DOT drum. The purging equipment was decontaminated between uses by washing with a non-phosphate solution followed by a potable water rinse.

After allowing the well to recover to within 80% of its original level, a groundwater sample was collected using a disposable bailer. The sample was retained in 40-ml VOA vials. Care was taken to ensure no headspace or bubbles were created within the vials. The sample was labeled, placed in a sealable plastic bag and stored in a cooler with blue ice pending delivery to an analytical laboratory. A copy of the groundwater sampling data sheet is included as Appendix 5, Groundwater Sampling/Purging Data Sheet.

#### LABORATORY ANALYSIS

The soil and groundwater samples were transported to American Scientific Laboratories of Los Angeles, a California Certified laboratory, under chain-of-custody documentation. Five soil samples (collected at 10, 20, 30, 40 and 50 feet below grade) and one groundwater sample were tested for TPH-g, BTEX, and fuel oxygenates by EPA Method 8260B.

### RESULTS

#### SOIL SAMPLING

No soil discoloration was noted, however, gasoline odor was noted in the soil samples collected between 20 and 25 feet below grade. The PID readings ranged from 0 to 64.4 parts per million by volume (ppmv) for the soil samples collected. Soil was predominately comprised of silty sands and sandy clays with layers of hard brittle siltstone at approximately 25, 45, and 55 feet below grade. Groundwater was encountered in the boring at a depth of approximately 55 feet below grade. A copy of the soil boring log is included in Appendix 4.

A summary of the analytical testing program is included in Table 2. A copy of the laboratory analytical report is included in Appendix 6.

#### **GROUNDWATER SAMPLING**

Groundwater was encountered during drilling at a depth of approximately 55 feet below grade. However, groundwater was encountered at approximately 41.19 feet below grade during the sampling of the groundwater monitoring well.

Results of the groundwater analytical testing are summarized in Table 3, Groundwater Analytical Testing Summary. A copy of the laboratory analytical report is included in Appendix 6. The analyzed groundwater sample did not have detectable levels of TPH-gasoline, benzene, ethylbenzene, total xylenes, or fuel oxygenates. A level of  $1.2 \mu g/L$  toluene was detected in the groundwater sample.

#### SOIL AND GROUNDWATER DISPOSAL

Soil cuttings generated during drilling were stored onsite in a roll-off bin. Purged groundwater generated during drilling and well development was stored onsite in properly labeled DOT approved 55-gallon drums. On December 30, 2005 BESI transported the soil cuttings to TPST Soil Recyclers of Adelanto, California, a licensed recycling facility. Copies of the records documenting the proper disposal of the soil cuttings are included in Appendix 7. Copies of the records documenting the proper disposal of the purge water will be forwarded upon receipt from the appropriate disposal facility.

#### CONCLUSIONS

To evaluate the significance of TPH-gasoline and VOC levels in soil, the levels were compared to MSSL established by RWQCB for TPH and VOCs above Drinking Water Aquifers (*Interim Site Assessment and Cleanup Guidebook*, dated May 1996). The guidance document has been used to determine when a site may require remedial action or to establish an acceptable clean up standard for a particular constituent. The document was developed to simplify the remediation process by facilitating the selection of soil cleanup levels for petroleum and VOC-impacted sites. The RWQCB soil threshold methodology was primarily developed for the protection of

#### Buckley School Site Assessment Report – 3900 Stansbury Avenue, Sherman Oaks, California

groundwater. Site-specific information used to select the appropriate RWQCB screening level includes the hydrocarbon range of the contaminant, soil lithology, and depth to shallow groundwater below the contaminated area. Groundwater is located between approximately 41 to 55 feet below grade, contaminated soil is primarily present between approximately 10 and 20 feet below grade, so the contaminated soil is 20 to 30 feet above ground water and the soils are comprised of interbedded silt, sand, and clay. To calculate the cleanup value, we have modeled the sediment at 10 feet below grade to be represented as 30% clay, 30% silt, and 40% sand; and at 20 feet below grade to be represented by 60% clay and 40% sand. Using the RWQCB table, the depth between contaminated soil and groundwater and soil type (30 feet - 30% clay, 30% silt, and 40% sand) and (20 feet - 40% sand and 60% clay) the attenuation factor (AF) were calculated to be of (7.9) and (8.2); respectively. The drinking water maximum contamination limit (MCL) for BTEX is b=0.001, t=0.15, e=0.007, x=1.75 milligrams per liter (mg/L). To calculate the soil cleanup screening levels at respective depths they multiply the AF by the MCL for the respective constituent.

#### **TPH in Soil Samples**


Los Angeles RWQCB MSSL for TPH-g is determined based on the distance between the soil contamination, at any given sample, and the underlying groundwater. TPH-gasoline was detected in the soil sample collected below the former UST at 20 feet below grade. Since groundwater is located between approximately 41 to 55 feet below grade, the MSSL for TPH-gasoline at the site was determined to be 500 mg/kg. TPH-g was detected in onsite alluvium at a maximum concentration of 0.682 mg/kg. This value is well below the calculated MSSL for TPH-g.

#### **VOCs in Soil Samples**

BTEX and MTBE were detected in the analyzed soil samples. The reported contaminant levels in the soil samples are well below the RWQCB action levels for these constituents, with the exception of benzene and MTBE. The level of BTEX and MTBE in soil were compared to their respective MSSL. Based on soil lithology, and depth to shallow groundwater below the contaminated area, the screening level for Benzene at 30 and 20 feet above groundwater was calculated to be 0.0079 mg/kg and 0.0082 mg/kg, respectively. Benzene was detected at a concentration of 0.006 mg/kg and 0.003 mg/kg in the soil at depths of 30 and 20 feet above groundwater, respectively. These values are well below the MSSL for this constituent. Based on Table 4.1 in the *Interim Site Assessment and Cleanup Guidebook*, dated May 1996, the screening level for MTBE at 20 feet above groundwater was calculated to be 0.0442 mg/kg. MTBE was detected at a concentration of 0.386 mg/kg in the soil at depths of 20, which exceeds the screening level.


#### Toluene in Groundwater Sample


To evaluate the significance of toluene in groundwater, the level was compared to MCLs established by Title 22 of the California Code of Regulations. The MCL for toluene in drinking water is 150  $\mu$ g/L. Toluene was detected in groundwater samples collected during this assessment at 1.2  $\mu$ g/L. The reported contaminant level is well below the MCL for this constituent.



North







300

~

150

Approximate Scale in Feet

Source: USGS - March 29, 2004

North Groundwater Monitoring Well Location

	Site Map	
Buckl 3900 Star Sherman C	Figure 2	

		TPH (mg/kg)					Ethyl-	Total		
Boring	Depth (feet)	Gasoline (C4-C12)	DRO (C13-C22)	ORO (C22+)	Benzene (mg/kg)	Toluene (mg/kg)	benzene (mg/kg)	Xylenes (mg/kg)	Oxygenates (mg/kg)	Lead (mg/kg)
	5	-	-	-	-	-	-	-	-	-
	10	ND	ND	ND	0.002	0.002	ND	ND	ND	-
	15	ND	ND	ND	ND	ND	ND	ND	ND	1.40
B1	20	2.05	-	-	0.032	0.09	0.024	0.195	MTBE - 0.816 TBA - 0.798	2.14
	25	1,080	ND	ND	8.4	31	13.7	104.2	MTBE - 3.13	ND
	5	-	-		-	-	~	-	-	-
B2	10	-	-	-	-	-	-	-	-	-
D2	15	ND	-	-	0.002	ND	ND	ND	ND	-
	20	ND	-	-	ND	ND	ND	ND	ND	-
	5	-	-	-		-	-	-	-	-
	10	93.4	ND	ND	ND	ND	ND	ND	ND	-
В3	15	0.646	ND	ND	0.007	0.003	ND	ND	MTBE - 0.206 TBA - 0.32	-
63	20	2.55	ND	ND	0.07	ND	0.019	ND	MTBE - 1.05 TBA - 0.792	1.40
	25	28.5	ND	ND	0.295	1.98	0.67	3.79	MTBE - 2.74	1.91
	30	1.93	-	-	0.013	ND	0.053	0.054	MTBE - 1.05 TBA - 0.302	-
	5	-	-	-	-	-	-	-	-	-
B4	10	0.55	-	-	ND	0.002	ND	ND	MTBE - 0.129 TBA - 0.392	-
	15	2.02	-	-	0.004	0.002	ND	ND	MTBE - 1.27 TBA - 0.346	-
	20	10.2	-	-	0.027	0.054	0.053	0.245	MTBE - 6.95	-
Detection	n Limit	0.5-50	10	50	0.002-0.2	0.002-0.2	0.002-0.2	varies	varies	varies

#### Table 1 - Analytical Testing Summary - TPH, BTEX, and Oxygenates December 27 and 30, 2004

- Not analyzed ND - Not detected

mg/kg - milligrams per kilogram (parts per million)

Analyses:

TPH-G (total petroleum hydrocarbons, gasoline range) by EPA Method 8260B

TPH-DRO / TPH-ORO (total petroleum hydrocarbons, diesel range organics / oil range organics) by EPA Method 8015M BTEX and Oxygenates by EPA Method 8260B

Lead by EPA Method 6010B

#### Table 2 - Analytical Testing Summary - TPH-g, BTEX, and Oxygenates December 22, 2005

Boring	Depth (feet)	TPH-gasoline (C4-C12) (mg/kg)	Benzene (mg/kg)	Toluene (mg/kg)	Ethyl- benzene (mg/kg)	Total Xylenes (mg/kg)	Oxygenates (mg/kg)
	10	ND	0.003	0.003	ND	ND	ND
	20	0.682	0.006	0.004	0.008	0.008	MTBE-0.386
MW-1	30	ND	ND	0.015	0.004	0.025	MTBE-0.005
	40	ND	ND	0.005	0.004	0.006	ND
	50	ND	ND	0.002	ND	ND	ND
Detection	Limit	0.500	0.002	0.002	0.002	varies	varies

mg/kg - milligrams per kilogram (parts per million) ND - Not detected

TPH-gasoline (total petroleum hydrocarbons, gasoline range)

Analyses:

TPH-G (total petroleum hydrocarbons, gasoline range) by EPA Method 8260B BTEX and Oxygenates by EPA Method 8260B

Table 3 - Water Analytical Testing Summary - TPH-g, BTEX, and Oxygenates

Sample Designation	TPH-gasoline (C4-C12) (μg/L)	Benzene (µg/L)	Toluene (µg/L)	Ethyl- benzene (µg/L)	Total Xylenes (µg/L)	Oxygenates (µg/L)
MW-1	ND	ND	1.2	ND	ND	ND
<b>Detection Limit</b>	50	1.0	1.0	1.0	varies	varies
MCL	NA	1.0	150.0	700.0	1750.0	varies

µg/L - micrograms per liter (parts per billion)

ND - not detected at or above detection limit

NA - not applicable

TPH-gasoline (total petroleum hydrocarbons, gasoline range)

Analyses:

TPH-G (total petroleum hydrocarbons, gasoline range) by EPA Method 8260B BTEX and Oxygenates by EPA Method 8260B

Appendix 1 Los Angeles Regional Water Quality Control Board Letter July 22, 1996

STATE OF CALIFORNIA-ENVIRONMENTAL PROTEC, IN AGENCY

PETE WILSON, Governor

RECEIVEL

JUL 30 103

INDERGROUND TAN

#### CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD LOS ANGELES REGION 101 CENTRE PLAZA DRIVE MONTEREY PARK, CA 91754-2156 [213] 266-7500 FAX: [213] 266-7600

July 22, 1996

- <u>....</u>

Mr.Walter Baumhoff Buckley School 3900 Stansbury Avenue Sherman Oaks, CA 91423

#### UNDERGROUND STORAGE TANK CASE CLOSURE BUCKLEY SCHOOL 3900 STANSBURY AVENUE, SHERMAN OAKS (ID #916061598)

Dear Mr. Baumhoff

This letter confirms the completion of the site investigation and remedial action for the underground storage tank(s) formerly located at the above-described location.

.

Based on the available information and with the provision that the information provided to this agency was accurate and representative of site conditions, no further action related to the underground storage tank release is required.

This notice is issued pursuant to a regulation contained in Title 23, California Code of Regulations, Division 3, Chapter 16, Section 2721(e).

Please contact our office if you have any questions regarding this matter.

Sincerely,

ROBERT P. GHIRELLI, D. Env. Executive Officer

DAVE DEANER Acting Assistant Executive Officer Underground Tanks

cc:

Mr. Allan Patton, State Water Resources Control Board, Underground Storage Tank Program

Captain Jesse Pasos, Los Angeles City Fire Department, Underground Tanks



Appendix 2 Los Angeles Regional Water Quality Control Board Letter December 9, 2005

BOARD OF FIRE COMMISSIONERS

> DALILA T. SOTELO PRESIDENT JILL FURILLO VICE-PRESIDENT

ANDREW FRIEDMAN GENETHIA HUDLEY-HAYES CASIMIRO U. TOLENTINO

BLANCA GOMEZ-REVELLES EXECUTIVE ASSISTANT II

December 9, 2005





ANTONIO R. VILLARAIGOSA MAYOR DEPARTMENT OF FIRE

WILLIAM R. BAMATTRE FIRE CHIEF

200 NORTH MAIN STREET LOS ANGELES, CA 90012

(213) 978-3800 FAX: (213) 978-3815 http://www.lafd.org

Facility ID# 916061598

Elizabeth McGregor Buckley School 3900 Stansbury Avenue Sherman Oaks, CA 91423

#### Buckley School 3900 Stansbury Avenue Sherman Oaks, California

Dear Elizabeth McGregor:

The Fire Department has reviewed the Site Assessment Workplan dated November 18, 2005, as submitted by Rincon Consultants, Incorporated.

Based on the information provided, this Department approves your Report.

Using the Site Address and Permit Number shown at the top of this letter, please label the title of your pending report to be submitted as "SITE ASSESSMENT REPORT."

In order to facilitate further processing of your pending report and other document submittals, please complete and return the attached "Required Information Form" with your future submittals, according to the instructions at the top of the form.

If you require additional information from the Los Angeles Fire Department, please contact Inspector II Neal Reitzell of the Environmental Unit, at (213) 482-6528.

Very truly yours,

WILLIAM R. BAMATTRE Fire Chief

Grank K. Comfort

Frank K. Comfort, Captain I Commander, Environmental Unit

FKC:NR:amo:3900StansburyAve#916061598air

cc: Walter Hamann, Rincon Consultants, Incorporated


and a second second


Appendix 3 Groundwater Monitoring Well Permit

WA	WELL PERMIT APPLICATION - NON-PRODUCTION WELLS WATER & SEWAGE / MOUNTAIN & RURAL PROGRAMS - ENVIRONMENTAL HEALTH DIVISION SOSO COMMERCE DRIVE, BALDWIN PARK, CA 91706 (626) 430-5380 FAX (626) 813-3016 DATE: 2/6/05-									
	New Well Construct Reconstruction or Decommissioning Other:		CAT	MONITORING HEAT EXCHANGE CATHODIC OTHER (Specify): INJECTION EXTRACTION						
LOCATION	SITE ADDRESS 3900 Stans	our Acenue :	CITY Shevni	an Caks	, CA	ZIP CODE 9002				
4 1/0 C/	Township OIW	Range $15W$	<u></u>	Section Z	7	Map Book Page/ Grid 562	A-6			
MELL				ttach site map with	vell locations	······				
ans	Type and Size of Production Casing 85'-	10) + solid (0!-	85')	Company Contact Person		Consultants Frieman	- G			
STRUCTURE	Sanitary / Annular Scaling Material		(solid)	Address	790 E.	Santa Clara St.	CONSULTANT			
NELL ST	Depth of Sanitary / // / / / / / / / / / / / / / / / /	2 sand (83'-110'), be	atonite	City, State Zip	Vente	wa, CA 93001	- IN			
	Conductor Casing	13/, 9104 10 2	2	Telephone	(805)	641-1000				
	Seal Well Owner Buc	kley School		FOUND TO DIFFE		IONS ENCOUNTERED IN THE FIELD A OPE OF WORK PRESENTED TO THIS O V BE BEOLURED				
NOL	Address 3900	Stansbury A	ke.	r						
DRILLER INFORMATION	City/Zip Code Sher	man Oaks, CA 9	70012	DISPOSITION OF PERMIT (Department Use Only) THIS PERMIT IS CONSIDERED COMPLETE WHEN THE WORK PLAN IS APPROVED AND WHEN THE WELL COMPLETION LOG IS RECEIVED. NO WELL						
CK INP	Telephone (818)	1461-6720		CONSTRUCTION	ONING CAN BE INITIATED WITHOUT IS DEPARTMENT.					
RILLE	Well Driller Tes	+ America (For	Rives n)	WORK PLAN APPROVAL This Approval is Valid for 180 Days						
NER / I	Address 1016	E. Katella Ave.								
	City/Zip Code 4mah	eim, CH 92800	5	Date 1-17-06	11/19	non				
	C-57 License No. Telephone 714	939-6850		Conditions	V					
F		/// 00			· · · · · · · · · · · · · · · · · · ·					
	Well Depth log / records					· · · · · · · · · · · · · · · · · · ·				
DNINO	Method of Well Assessment				· · · · · · · · · · · · · · · · · · ·					
	Depth and Number of Perforations				<u> </u>	····	·····			
WELL DECOMMISS	Type of Perforator Size of Perforations			1-19-06-	VERIGIEN	THAT ONLY MW-1	,			
MEL	Type and Amount of Sealant			WAS IN.	STALLED	-PER GEOFF PRIEM	IAN,			
	Method of Upper Seal Pressure Application					WERE NOT NECESSAG				
				AND WILL THEREPOLE NOT BE						
Cou	I hereby agree to comply in every respect with all the regulations of the County Environmental Health Division and with all ordinances and laws of			INSTALLED						
the County of Los Angeles and the State of California pertaining to well construction, reconstruction and decommissioning. Upon completion of well and within thirty days thereafter, I will furnish the Environmental Health office with a completion log of the well giving date drilled, depth			of the		FINAL	INSPECTION				
			th of the	Date,	REHS					
well, perforations in the casing, and any other data deemed necessary b County Environmental Health Pivision. Ar Rancon Comput				1-19-06	1 Man					
	Aufflyin		•	The well log must be		NIT ISSUED epartment prior to issuance of the final app	roval			
	Icant Name: (PRINT) Bircon	at's Signature		Date	REHS					
lep	Acant Name: (PRINT) 641-104	00		1-19-06	Mg	-p	]			
5A668 -13 (Re	A 					$\cup$				

e generation de la constante de la

Appendix 4 Log of Boring/Monitoring Well





Appendix 5 Groundwater Sampling/Purging Data Sheet

			•								
Job No: 04-1	7842	Date: 1-10-	0.5								
Project/Location Buch	lley School / Shernan Dal	s Well Number: MW	//								
Observation Period Sta	rt: Stop:	Survey Reference Point:	North								
Sampled By: ST		Witnessed By:									
	PUR	GING DATA									
Type of Pump	5 4 5	Pump Inlet Depth (ft)									
Well Diameter (in)	Σ.	Depth of Well (ft)	64.41								
Depth to Water (ft)	41.19	Length of Water Column (ft)	23.22								
Product Thickness (ft)	None	Volume Multiplier (gal/ft)	0.16								
One Casing Volume (gal)	3.72	Three Casing Volumes (gal)	11:16								
Purge Time, Start	11:20	Purge Time, Stop	11:50								
Total Purge Time	30 minutes	Purge Rate (gpm)	1.2								
Purge Volume (gal)	37	Drawdown (ft)	48:13								
	CASING OR BO	REHOLE VOLUME	=6.94								
0.5-Inch I	Diameter = 0.010 gal/ft	4-inch D	iameter = 0.65 gal/ft								
	Diameter <i>=</i> 0.023 gai/ft	4	iameter = 1.46 gal/ft								
	iameter = 0.041 gal/ft		ameter = 3.30 gal/ft								
f .	Nameter = 0.092 gal/ft	1	lameter = 5.87 gal/ft								
2-inch D	iameter = 0.16 gal/ft		iameter = 9.18 gal/ft								
7. YY INDICATOR DATA											
Volume Pumped (gal) B	efore Purge 200   14,88	22.32 29.76 3	3-48 37.2								
Raramoter TDS	632 1600 1684	1626 1606 1	581 1562 At Sampling								
Temperature (C)	9.0 19.3 19.1	19. 18. 21	8.6 18.9								
Conductivity (micromhos)	264 3204 3371	3249 6 8 3	164 3124								
H E	,80. 6.68 6.66	6.64 6.64 6	5.66 6.65								
issolved Oxygen											
omments:	×2 ×4	×6 ×8 X	9 ×10								
•	. MISCELLANE	OUS DATA	<u></u>								
ondition of Traffic Box: (	5000 .		e e e e e e e e e e e e e e e e e e e								
um Identification labeling: 人	Ion - Haz Woste										
	A.C.		Q								
Waita til	112:25 der	the water a	st 41.86								
Sampled	at 12:25 der	D									
		anne an tha tha ann an tha tha tha an tha									

ć'

.

:

÷.,

•

``

Rincon Consultants, Inc.

i

9

35

Appendix 6 Laboratory Analytical Reports



2520 N. San Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

#### Ordered By

	and the second second second second	ومحود والمراجع والمراجع ومحرجي سيهجو والمجار والمح	医马克氏试验检尿道 医无外的 化二乙基乙烯 化乙基乙基乙烯 化乙基乙基	and a standard of a standard of the second standard of the standard of the
	the second second second and second	and the second secon	a na dina sa kata na sa kata kata kata kata kata kata kata	e an i shin ang salawan na ng san i ang san géné berandan s
	KINCOD	Consultan	ro Tha	
		~~**** C T . C CT Y	LD / LILL .	
	D more service with a second car as	and the second state of the se	and the second	and the second
	1. A. B. S.	1	the second s	the design of the second s
	1100 m		and the second	and the second state of th
	アイターした 一切分 気工	- Santa C	lara Street	
		and a start of the same the the technology where	the second of the second second with the second	an and and a start when the first start in the first start and the first start and
	TT	A	and the second	to the second
- 4	(A'( _)   b =)   b = - []	, CA 9300	the second state of the second states and share the	
- 1				a sharin a sharin ku ku sharin marka ka sharin ka sharin a sharin a sharin a sharin a sharin a sharin a sharin
- 1				

Telephone (805)641 - 1000Attn Geoff Frieman

	)et													
	R													
	R													

28008	12/23/2005	RINCON
Job Number	Ordered	Client

Project ID: 04-17842 Project Name: Buckley Site: 3900 Stansbury Ave. Sherman Oaks, CA

> Enclosed are the results of analyses on 5 samples analyzed as specified on attached chain of custody.


Wendy Lu **Organics Supervisor** 

Rojert G. Araghi Laboratory Director

American Scientific Laboratories, LLC. (ASL): accepts sample materials from clients for analysis with the assumption that all of the information provided to ASL verbally or in writing by our clients (and/or their agents), regarding sample's being submitted to ASL is complete and accurate. ASL accepts all samples subject to the following conditions: 1) ASD is not responsible for verifying any client-provided information regarding any samples submitted to the laboratory. 2) ASD is not responsible for any consequences resulting from any inaccuracies; omissions, or misrepresentations contained in client-provided information regarding samples submitted to the laboratory.



AMERICAN SCIENTIFIC LABORATORIES, LLC Environmental Testing Services 2520 N. San Fernando Road, LA, CA 90065 Tel: (323) 223-9700 • Fax: (323) 223-9500



n

COC# GLOBAL ID ELECTRONIC DEDCAT	_
Company: River (Antarta Tal Co	
Address: 790 E. Sanza Clann Project Name: BVCKley Address: Van (1) Gite Address: Van (1) Gite Address: (and Gite Addres) (	STED
The E Store changes	TTT
Venture CA 93001 Site Address: 3900 STANSPURY for Rhom SA	/ / / /
Fax: GOS/GUI-1072 SHERMAN OTUS CA Address: 740 ESAWA Char St	
Fax: 605/641-1072 SHERMAN OTUS CA Address: 740 ESMAN Char S	
Project Difference CA New Martin	
Project     Project       Manager:     Desff       I     LAB USE ONLY       SAMPLE     DESCRIPTION       Container(s)	
E total	
Lab ID     Sample ID     Date     Time     #     Type     Matrix     Preservation	Remarks
MW1-5 12/22/05-12:00 4 61 BRASS WASOUTHO	
1 10000 At 11 10 I I I I I I I I I I I I I I I I I	Hold
12:0 XX	
MW1-15 12:20	
2162377 MWI-20 12:30 XX	Itold
MW1-25 12:40	
	Hold
MW1-35 B:00	
4162379 MWI-40 13:10 XX	Hold
MWI-45 13:20	
5 162380 MWI-50 V 13:30 N V XV	Itold
Collected By:	
Relinguished By: Date Time	
Date 1923/ Time (); (/) Received	TAT (
Condition of Sample: Date 230 Time 0.2	




# AMERICAN SCIENTIFIC LABORATORIES, LLC Environmental Testing Services 2520 N. San Fernando Road, LA, CA 90065 Tel: (323) 223-9700 + 1

Page 2 of 2

A CONTRACTOR CONTRACTOR CONTRACTOR

-	22011 Sun Pernando Roda, LA, CA 90065	Tel: (323) 223-9700 • Fax: (323) 223-9500
20	5000	

<i>coc</i> # №	<b>35289</b> GLOBAL	ID						_			00	
Company:	ion Consultank				ECTRONIC Report Tos	D	: L] EDF			·······		
Address:	host Claren	Project Name: Rychum Site Address:	y Sch	nes/	Address: 790 E.	stud	Mars 1	H B	ANALY:	sis rec	QUESTED	
KMILAA Telephone: 505/64	1-107)	STERMA	DANGE	1-1-1-	Invoice To:	Rucon		46				
Special Instruction	n:	Project ID: OLL-17 Project		<u>+ks</u>	Venna Venna	Start A CA	Clara M	¥X / /				/
LAB USE O	NLY SAMPLE	Manager: C	1coFF	Container(s	P.O.#; OU-1	7842		[[]				
Lab ID	Sample ID	Date	Time	# Туре	Matrix	Preservation					Rei	marks
	MW1-55	12/22/05	13:40	4 6 CRE	SWASOUTIT	Solid				┥┥┥	Ho	1]
	MW1-60 MW1-65		13:50					+			lto	id Id
*	MW1-70		14:10			<u> </u>				++		11
	MW -75	V	14:20	V					_		Ho	
										<u></u>		
										+		
												·
ollected By:		Date		Time								
linquished By	Ne AVV	Date	2/23/65	Time 10,40	Relinquis Received For Labo	hed By:	1 10	Date		Time	T,	AT
ndition of San - Report, Yellow	nple: V - Laboratory, Pink - Client					I YEAK	<u> </u>	Date	22300	Timto		'ormal ush
· · · · ·												· · · · ·



2520 N. San Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

#### ANALYTICAL RESULTS

#### Ordered By

#### Site

Rincon Consultants, Inc.	
790 East Santa Clara Street	
Ventura, CA 93001	

3900 Stansbury Ave.		
Sherman Oaks, CA		

Telephone: (805)	641-1000			
Attn: Geoff	Frieman			
Page:	2			
Project ID:	04-17842	Job Number	Order Date	Client
Project Name:	Buckley	28008	12/23/2005	RINCON

#### Method: 8260B, Gas/BTEX and Oxygenates

#### Batch No: 122905-2C


Our Lab I:D.		162376	162378	162379	162380	
Sample ID	1	MW1-10	MW1-30	MW1-40	MW1-50	i
Date Sampled	1	12/22/2005	12/22/2005	12/22/2005	12/22/2005	
Date Extracted	1	12/30/2006	12/30/2006	12/30/2006	12/30/2006	
Preparation Method						
Date Analyzed		12/30/2006	12/30/2006	12/30/2006	12/30/2006	
Matrix		Soil	Soil	Soil	Soil	
Units		• ug/kg	ug/kg	ug/kg	ug/kg	
Detection Limit Multiplier		1	1	1	1	
Analytes	PQL	Results	Results	Results	Results	
Benzene	2.00	3	ND	ND	ND	
DIPE	5.00	ND	ND	ND	ND	··· ···
ETBE	5.0	ND	ND	ND	ND	
Ethylbenzene	2.00	ND	4	4	ND	
MTBE	5.00	ND	5	ND	ND	
TAME	5.00	ND	ND	ND	ND	
ГВА	20	ND	ND	ND	ND	
Toluene (Methyl benzene)	2.00	3	15	5	2	
p-Xylene	2.00	ND	6	ND	ND	
n-& p-Xylenes	4.0	ND	19	6	ND	
(CPH as Gasoline (C4-C12)	500	ND	ND	ND	ND	

Our Lab I.D.		162376	162378	162379	162380	
	Con.Limit	* Rec.	% Rec.	% Rec.	% Rec.	
Surrogate Percent Recovery						
Bromofluorobenzene	70-120	106	105	107	120	
Dibromofluoromethane	70-120	119	119	120	112	
Toluene-d8	70-120	107	106	110	96	

#### QUALITY CONTROL REPORT

#### Batch No: 122905-2C

Analytes	MS % REC	MS DUP % REC	RPD %	MS/MSD % Limit				
Benzene	113	109	3.6	75-120	15			



### American Scientific Laboratories, LLC

Environmental Testing Services

2520 N. San Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500


#### ANALYTICAL RESULTS

Page: Project ID:	<b>3</b> 04-17842	Job Number	Order Date	Client
Project Name:	Buckley	28008	12/23/2005	RINCON

### Method: 8260B, Gas/BTEX and Oxygenates QUALITY CONTROL REPORT

#### Batch No: 122905-2C

Analytes	MS % REC	MS DUP % REC	بسريد والمتحج والعربين	MS/MSD % Limit					
MTBE	108	112	3.6	75-120	15	1	····· ····		
Toluene (Methyl benzene)	115	120	4.3	75-120	15				



### American Scientific Laboratories, LLC

Environmental Testing Services

2520 N. San Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

#### ANALYTICAL RESULTS

#### Ordered By

#### Site

Rincon Consultants, Inc.				· · . · . . · .		
790 East Santa Clara Street						
Ventura, CA 93001	125	÷	•	:	5 <u>5</u> .	•

3900 Stansbury Ave.			÷.,	
Sherman Oaks, CA				

Telephone: (805)	541-1000			
Attn: Geoff	Frieman			
Page:	4			
Project ID:	04-17842	Job Number	Order Date	Client
Project Name:	Buckley	 28008	12/23/2005	RINCON

#### Method: 8260B, Gas/BTEX and Oxygenates

#### Batch No: 123005-1C


Our Lab LD.		162377				
Sample ID		MW1-20			1	1
Date Sampled		12/22/2005			1	
Date Extracted		12/30/2006				
Preparation Method						
Date Analyzed		12/30/2006				
Matrix		Soil				
Units		ug/kg				
Detection Limit Multiplier		1				
Analytes	PQL	Results				
Benzene	2.00	6				
DIPE	5.00	ND				
ETBE	5.0	ND				
Ethylbenzene	2.00	8				
MTBE	5.00	386				
TAME	5.00	D				
ТВА	20	ND				
Toluene (Methyl benzene)	2.00	4				
o-Xylene	2.00	2	1	1		
m-& p-Xylenes	4.0	6				
TPH as Gasoline (C4-C12)	500	682				

Our Lab I.D.		162377		
Surrogates	Con.Limit	% Rec.		
Surrogate Percent Recovery				
Bromofluorobenzene	70-120	95		
Dibromofluoromethane	70-120	117		
Toluene-d8	70-120	107		

#### QUALITY CONTROL REPORT

#### Batch No: 123005-1C

Analytes	MS % REC	1	RPD %	MS/MSD % Limit				
Benzene	117	106	9.9	75-120	15			



2520 N. San Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

#### ANALYTICAL RESULTS

Page:	5			
Project ID:	04-17842	Job Number	Order Date	Client
Project Name:	Buckley	28008	12/23/2005	RINCON
<b>J</b>				

### Method: 8260B, Gas/BTEX and Oxygenates QUALITY CONTROL REPORT

#### Batch No: 123005-1C

Analytes	MS % REC	MS DUP % REC	RPD %	MS/MSD % Limit				
MTBE	101	90	11.5	75-120	15		 	
Toluene (Methyl benzene)	117	113	3.5	75-120	15		 	



2520 N. San Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

#### Ordered By

医前端骨间 医皮肤结核 医试验检试验检检试验检检试验 法保证的现在分词 法法法法 医前侧侧侧 化合物化合物 法保证 医神经炎 化化合物化合物 化化合物 化分析 化合物 化分析 化分析 化分析 化分析 化分析 化分析 化分析	
Rincon Consultants, Inc.	
790 East Santa Clara Street	
Ventura, CA 93001	

Telephone (805)641-1000 Attn Shawn Decker

- I NIN	mbe:		Ga		- Con 1997	1	4	Sec. 11. 1997			
- 1 - <b>1</b> -	uwe.	L O	L	laee					1. S.		
1. 15 and 10.											
1 N N		· · · · · · · · · · · · · · · · · · ·									
1.00	Sec. 19. 23		· · · · · · · · · · · · · · · · · · ·								0.037
Da	TO.	200	0.7.770		- n		1 / つ ハ	AC			
		NOU	- <b>.</b>		. v.	L/ L.	L/ ZU	UD			
1			a server en al a	A.S. 40, A.M.A.					and the second second		10.00
1.2											
1	1. 1. 1. 1. 1.	· · · · ·		1. A State of the second se			1 1 A A			والمراجع والمراجع المراجع	
Da	с. н. –	керс	этг ө	<b>C</b>			1120	<b>n F</b>			
an fairne fair to	1. A					-/	1.40	V.U.			
	1	1. A.	S								

Job Number	Ordered	Client
28135	01/11/2006	RINCON

Project ID: 04-17842 Project Name: Buckley School

Enclosed are the results of analyses on 1 sample analyzed as specified on attached chain of custody.

Wendy Lu Organics Supervisor

Aruch-

Rojert G. Araghi Laboratory Director

American Scientific Laboratories, LLC (ASL) accepts sample materials from clients for analysis with the assumption that all of the information provided to ASL verbally or in writing by our clients (and/or their spents), regarding samples being submitted to ASL, is complete and accurate. ASL accepts all samples subject to the following conditions:
 ASL is not responsible for verifying any client-provided information regarding any samples submitted to the laboratory.
 ASL is not responsible for any consequences resulting from any inaccuration, or misrepresentations contained in client-provided information regarding samples submitted to the laboratory.

		AMERICAN SCI Environmental 2 2520 N. San Fernando	lesting Ser	vices			Fax: (323) 22	3-9500						P	age _	_/	. Of	L	, _
	C# Nº 3!	5284 GLOBAL I	חו			ELEA	CTRONIC	REPORT	:г		r r	'' FI	, חר	asi		R# 9	2813	5	
	mpany: Riv	1604 Consu	Harts,	Inc	シ.		Report To:	Rinco				an an					2UES		- 7 <b>C</b>
Ad	dress: 790 (	E. Santa Clara	Project Name:	Buckle		Schal	Address:	1-1100	и		6 int	<b>!</b>		7	7	77	7013	TTT	H
1	patura, (	A 93001	Site Address:		7_	-1081	Invoice To:				FX FX			/ /		' /			
Tele	phone: 805 641 805 6.41-	-1000					Address:		L	K	Ψ		/ /				· / ,		
Spe	cial Instruction:		Project ID:	t = 1 - 1						/\``\X ~`\X				/ /					N
	u 41 52 18 18 18 18 18 18 18 18 18 18 18 18 18 18 18 18		Project	$\frac{7-7}{5}$	18	92	P.O.#:			ξ X		[ ]						/ /	
I	LAB USE ONLY	SAMPLE D	Manager: SU	lawn 1	F	Container(s)	1.0.#.	1	A	7		4	[	_/					0
T E M	Lab ID	Sample ID	Date	Time	#	Туре	Matrix	Preservation	82608									Remarks	F
	163090	MW-1	1-10-06	12:30	3	VOA	H.O	None				+				+			-
				· <u> </u>			1.20	roone					┝──┼	+				-	C
					$\left  - \right $									-+					
													<b>├</b>	_					S
												ļ							T
							<u> </u>												0
				·····							_	<u> </u>							D
																			Y
																			1
$\left  - \right $												1				+		+	R
													╞╌┼	+					E
Col	lected By:	an	Date	1-10-06	Tin	ne 12:31	Relinquis	hed By:	1	<u>I</u>		Dat				 Time			
Rei	inquished By:	sen	Date	1-11-04	Tin	ne 12:30	Receive For Labo	d bratory //	A	e-		Dat		1.1.	l	Time	11.0	TAT	0
	ndition of Sample:		· · · · · · · · · · · · · · · · · · ·		·····-			/ /	$\gamma$	$\geq$				10	12	i ine /	7.	Rush	R
	- Report, Yellow - La	boratory, Pink - Client						V			·····								D

#### RECOMMENDATIONS

The analytical results from the soil and groundwater monitoring indicate the at all detected contaminants are below the respective screening levels for the detected constituents with the exception of MTBE at 20 feet below grade. The groundwater sample did no have any detected constituents that exceed its maximum contaminant level in drinking water. Due to the low levels and the impermeable soil lithology between the contamination and groundwater we recommend no further action for the site and we respectfully request that the RWQCB maintain case closure.

#### LIMITATIONS

This report has been prepared for and is intended for the exclusive use of Buckley School and its assignees. The contents of this report should not be relied upon by any other party without the written consent of Rincon Consultants, Inc.

Our conclusions regarding the site are based on the results of a limited subsurface sampling program. The results of this evaluation are qualified by the fact that only limited sampling and analytical testing was conducted during this assessment.

This scope was not intended to completely establish the quantities and distribution of contaminants present at the site or to determine the cost to remediate the site. The concentrations of contaminants measured at any given location may not be representative of conditions at other locations. Further, conditions may change at any particular location as a function of time in response to natural conditions, chemical reactions and other events. Conclusions regarding the condition of the site do not represent a warranty that all areas within the site are similar to those sampled.

groundwater was calculated to be 0.0442 mg/kg. MTBE was detected at a concentration of 0.386 mg/kg in the soil at depths of 20 which exceeds the screening level. The maximum contamination level (MCL), established by the RWQCB, for toluene in drinking water is 150  $\mu$ g/L. Toluene was detected in groundwater samples collected during this assessment at 1.2  $\mu$ g/L. The reported contaminant level is below the MCL for this constituent.

The analytical results from the soil and groundwater monitoring indicate the at all detected contaminants are below the respective screening levels for the detected constituents with the exception of MTBE at 20 feet below grade. The groundwater sample did no have any detected constituents that exceed its maximum contaminant level in drinking water. Due to the low levels and the impermeable soil lithology between the contamination and groundwater we recommend no further action for the site and we respectfully request that Los Angeles Fire Department (LAFD) maintain case closure.



2520 N. San Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

#### ANALYTICAL RESULTS

Ordered By .

Rincon Consultants, Inc.	
790 East Santa Clara Street	
Ventura, CA 93001	

Telephone: (805)641-1000

Attn: Shawn Decker

Page:2Project ID:04-17842Project Name:Buckley School

Job Number Order Date Client // 28135 01/11/2006 RINCON

#### Method: 8260B, Gas/BTEX and Oxygenates

#### Batch No: 011206-1C

Our Lab I.D.		163090		
Sample ID		MW-1		
Date Sampled		01/10/2006		
Date Extracted		01/12/2006		 T
Preparation Method				
Date Analyzed		01/12/2006		
Matrix		Water		
Units .		ug/L		 
Detection Limit Multiplier		1		
Analytes	PQL	Results		
Benzene	1.000	ND		· · ·
DIPE	2.000	ND		
ETBE	2.000	ND		
Ethylbenzene	1.000	ND		
MTBE	2.000	ND		 
TAME	2.000	ND		
TBA	10.00	ND	 	
Toluene (Methyl benzene)	1.000	1.2		
o-Xylene	1.000	ND		 
m-&p-Xylenes	2.000	ND		
TPH as Gasoline (C4-C12)	50	ND		 

Our Lab I.D.		163090		
Surrogates	Con.Limit	% Rec.		20 10 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
Surrogate Percent Recovery				
Bromofluorobenzene	70-120	103		
Dibromofluoromethane	70-120	97		
Toluene-d8	70-120	107		

#### QUALITY CONTROL REPORT

Batch No: 011206-1C

Analytes	MS % REC	MS DUP % REC	RPD %	MS/MSD % Limit	MS RPD % Limit			
Benzene	103	114	10.1	75-120	15			



### American Scientific Laboratories, LLC

Environmental Testing Services

2520 N. San Fernando Rd., Los Angeles, CA 90065 Tel: (323) 223-9700 Fax: (323) 223-9500

#### ANALYTICAL RESULTS

Page:	3			
Project ID:	04-17842	Job Number	Order Date	Client
	Buckley School	28135	01/11/2006	RINCON
Project Name:	Duckieg benoor	•		L

## Method: 8260B, Gas/BTEX and Oxygenates <u>QUALITY CONTROL REPORT</u>

#### Batch No: 011206-1C

Analytes			RPD %		والمراجع والمراجع			
MTBE	82	88	7.1	75-120	15			
Toluene (Methyl benzene)	118	120	1.7	75-120	15			

## Appendix 7 Waste Manifest

s Manifes	Î.		· · · ·	yclers of ( lous Soils			niite	
Date of Shipment:	Responsible f	or Payment:	Transporte	er Tryck #:	Facility #:	Given by TPS7		Load
12 321 2005	BELSHI	RE	207	1733	A07	26	505	11
Generator's Name and Bill	ing Address:	-		Generator's Phone	e #:	Generator's	US EPA ID N	0.
BUCKLEY SCHO	OL			Person to Contact:				
3900 STANSBU	RY							
SHERMAN OAKS	3, CA			FAX#:		Customer Ac	count Number	with TPST:
Consultant's Name and Bill	ling Address:			Consultant's Phon	e #:			
				Person to Contact:	<u></u>			
				FAX#:	· ·	Customer Acc	count Number w	vith TPST:
Generation Site (Transport f	rom): (name & address,	)		Site Phone #:		BTEX Levels	•	
BUCKLEY SCHOO 3900 STANSBUR		· · · .		Person to Contact:	•	TPH Levels		
SHERMAN OAKS		•		FAX#:		AVG. Levels		
Designated Facility (Transpo	· ·			Facility Phone #: 800-862-804	01	Facility Perm	it Numbers	····· · · ·
TPST SOIL RECY 12328 HIBISCUS				Person to Contact: DELLENA JE	FREY			
ADELANTO, CA			. h	FAX#: 760-246-800				
Transporter Nante and Maili	ng Address:			Transporter's Phone	#•	Transporter's	US EPA ID No	).:
<b>B.E.S.I</b>				949-450-101		CAROO	0165175	
8.E.S.I.				949-450-101 Person to Contact:		CAROO Transporter's 45064	DOT No.:	
B.E.S.I. 25971 TOWNE CALLAKE FOREST, CA	ENTRE DRIVE A 92610		1	949-450-101	.0	CAROO Transporter's	DOT No.: 7 unt Number wit	
8.E.S.I. 25971 TOWNE C	ENTRE DRIVE A 92610 BE Moisture Content	SI# 120059 Contaminated by:	1 1 1 1 2 0,03	949-450-101 Person to Contact BRIAN CASS FAX#: 949-450-117	.0	CAROO Transporter's 45064 Customer Accor	0165175 DOT No.: 7 unt Number wit 93	h TPST:
B.E.S.I. 25971 TOWNE C LAKE FOREST, C	ENTRE DRIVE A 92610 BE Moisture Content 0 - 10% 10 - 20% 20% - over 0	SI# 120059 Contaminated by: Gas Diesel Diese	1 1 1 1 2 0,03	949-450-101 Person to Contact BRIAN CASS FAX#: 949-450-117	7	CAROD Transporter's 45064 Customer Acco 10001 Gross Weight	0165175 DOT No.: 7 unt Number wit 93	h TPST: Net Weight
B.E.S.I. 25971 TOWNE CL LAKE FOREST, CL Description of Soil Sand Q Organic Q Sand Q Organic Q	ENTRE DRIVE A 92610 Be Moisture Content 0 - 10% 20% - over 0 - 10% 10 - 20%	SI# 120059 Contaminated by: Gas □ Diesel □ Other □ Diesel □	1 1 1 1 2 0,03	949-450-101 Person to Contact BRIAN CASS FAX#: 949-450-117	7	CAROD Transporter's 45064 Customer Acco 10001 Gross Weight	10165175 DOT No.: 7 unt Number wit 93 Tare Weight	h TPST: Net Weight
B.E.S.I. 25971 TOWNE CL LAKE FOREST, CL Description of Soil Sand Q Organic Q Sand Q Organic Q	ENTRE DRIVE A 92610 Be Moisture Content 10 - 20% 0 20% - over 0 10 - 20% 0 20% - over 0	Contaminated by: Gas Diesel Diesel Contaminated Contamin	1 1 1 1 2 0,03	949-450-101 Person to Contact BRIAN CASS AX#: 949-450-117 Qty: Description	7	CARDO Transporter's 45064 Customer Acco 10001 Gross Weight 3990	10185175 DOT No.: 7 ant Number wit 93 Tare Weight 3 (64/4	h TPST: Net Weight
B.E.S.I. 25971 TOWNE C. LAKE FOREST, C. Description of Soil Sand C Organic C Clay C Other C Sand C Organic C Clay C Other C	ENTRE DRIVE A 92610 BE Moisture Content 0 - 10% 0 10 - 20% 0 20% - over 0 0 - 10% 0 10 - 20% 0 20% - over 0 0 - 10% 0 10 - 20% 0 20% - over 0 0 - 10% 0 10 - 20% 0 20% - over 0 0 - 10% 0 10 - 20% 0 20% - over 0 0 - 10% 0 10 - 20% 0 20% - over 0 0 - 10% 0 10 - 20% 0 20% - over 0 0 - 10% 0 10 - 20% 0 20% - over 0 0 - 10% 0 10 - 20% 0 20% - over 0 0 - 10% 0 10 - 20% 0 20% - over 0 0 - 10% 0 10 - 20% 0 20% - over 0 0 - 10% 0 10 - 20% 0 20% - over 0 0 - 10% 0 0 - 00% 0 0 - 0	SI# 120059 Contaminated by: Gas □ Diesel □ Other □ Diesel □ Other □ We certify that the	Approx.	949-450-101 Person to Contact BRIAN CASS FAX#: 149-450-117 Oty: Description Scale Scale Enced herein is take and nothing has in	7 on of Delivery e Ticket# en entirely from 1	CARDE Transporter's 45064 Customer Account 10001 Gross Weight 3790 25 those soils descr	10185175 DOT No.: 7 unt Number wit 93 Tare Weight 3 (64/d 7 3 2 7 ibed in the S	h TPST: Net Weight 32140 1-72 oil Data
B.E.S.I. 25971 TOWNE C. LAKE FOREST, C. Description of Soll Sand Organic O Clay Other O Sand Organic O Clay Other O List any exception to items listed at Generator's and/or consult Sheet completed and certific	ENTRE DRIVE A 92610 BE Moisture Content 0 - 10% 0 10 - 20% 0 20% - over 0 0 - 10% 0 10 - 20% 0 20% - over 0 0 - 10% 0 10 - 20% 0 20% - over 0 0 - 10% 0 10 - 20% 0 20% - over 0 0 - 10% 0 10 - 20% 0 20% - over 0 0 - 10% 0 10 - 20% 0 20% - over 0 0 - 10% 0 10 - 20% 0 20% - over 0 0 - 10% 0 10 - 20% 0 20% - over 0 0 - 10% 0 10 - 20% 0 20% - over 0 0 - 10% 0 10 - 20% 0 20% - over 0 0 - 10% 0 10 - 20% 0 20% - over 0 0 - 10% 0 10 - 20% 0 20% - over 0 0 - 10% 0 0 - 00% 0 0 - 0	SI# 120059 Contaminated by: Gas □ Diesel □ Other □ Diesel □ Other □ We certify that the	Approx.	949-450-1QJ Person to Contact BRIAN CASS FAX# 949-450-117 Gty: Description Scale Enced herein is take	7 on of Delivery e Ticket# en entirely from 1	CARDE Transporter's 45064 Customer Account 10001 Gross Weight 3790 25 those soils descr	10185175 DOT No.: 7 17 17 17 17 17 17 17 10 16 16 17 16 17 17 17 17 17 17 17 17 17 17 17 17 17	h TPST: Net Weight 32440 1-72 oil Data Iter it in
B.E.S.I. 25971 TOWNE C. LAKE FOREST, C. Description of Soll Sand Organic O Clay Other O Sand Organic O Clay Other O List any exception to items listed at Generator's and/or consult Sheet completed and certific iny way. Thint or Type Name: Dawic O Construction:	ENTRE DRIVE A 92610 BE Moisture Content 0 - 10% 10 - 20% 20% - over 0 - 10% 20% - over 0 - 10% 20% - over 20% - over 10 - 20% 20% - over 20%	SI # 120059 Contaminated by: Gas Diesel O Other O Diesel O Diesel O Other O Ne certify that the Generation Site sho Consultant O	Approx.	Person to Contact BRIAN CASS FAX#: 149-450-117 Oty: Description Scale enced herein is take and nothing has re and date:	7 on of Delivery e Ticket# en entirely from theen added or door that such soil is	CARDO Transporter's 45064 Customer Acco 10001 Gross Weight 3792 those soils descr ne to such soil to being delivered	10185175 DOT No.: 7 unt Number wit 93 Tare Weight 3646 $732^{2}$ ibed in the S that would al Month D $12^{3}3$ in exactly the second seco	h TPST: Net Weight S 3C/4D 1.72 oil Data Iter it in ay Year B 0.5 he same
B.E.S.I. 25971 TOWNE C. LAKE FOREST, C. Description of Soil Sand Organic O Clay Other O Sand Organic O Clay Other O Sand Organic O Clay Other O Clay Other O Sand Organic O Clay Other O Sand Organic O Clay Other O Sand O Clay Other O Sand O Clay Other	ENTRE DRIVE A 92610 BE Moisture Content 0 - 10% 10 - 20% 20% - over 0 0 - 10% 20% - over 0 0 - 0% 20% - 0% - 0% 20% - 0% - 0% - 0% - 0% - 0% - 0% - 0% -	SI# 120059 Contaminated by: Gas Diesel O Other O Diesel O Other O Diesel O Other O Ne certify that the Generation Site sho Consultant O receipt of the soil a fy that this soil is	Approx.	Person to Contact BRIAN CASS FAX#: 149-450-117 Oty: Description Scale Inced herein is take and nothing has reand date:	7 on of Delivery e Ticket# en entirely from theen added or door that such soil is	CARDO Transporter's 45064 Customer Acco 10001 Gross Weight 3792 those soils descr ne to such soil to being delivered	10185175 DOT No.: 7 unt Number wit 93 Tare Weight 3646 $732^{2}$ ibed in the S that would al Month D $12^{3}3^{3}$ in exactly the second	h TPST: Net Weight S 3C/4D 1.72 oil Data Iter it in ay Year B 0.5 he same
B.E.S.I. 25971 TOWNE C. LAKE FOREST, C. Description of Soil Sand Organic O Clay Other O Sand Organic O Clay Other O Sand Organic O Clay Other O Clay Other O Sand Organic O Clay Other O Sand Organic O Clay Other O Sand O Clay Other O Sand O Clay Other	ENTRE DRIVE A 92610 BE Moisture Content 0 - 10% 20% - over 0 0 - 10% 0 20% - over 0 0 10% 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	SI# 120059 Contaminated by: Gas Diesel O Other O Diesel O Other O Diesel O Other O Ne certify that the Generation Site sho Consultant O receipt of the soil of fy that this soil is or in any way del	Approx.	Person to Contact BRIAN CASS FAX#: 149-450-117 Oty: Description Scale Inced herein is take and nothing has reand date:	7 on of Delivery e Ticket# en entirely from theen added or door that such soil is	CARDO Transporter's 45064 Customer Acco 10001 Gross Weight 3792 those soils descr ne to such soil to being delivered	10185175 DOT No.: 7 unt Number wit 93 Tare Weight 3646 $732^{2}$ ibed in the S that would al Month D $12^{3}3^{3}$ in exactly the second	h TPST: Net Weight 32140 1.72 oil Data ter it in ay Year B 03 he same Facility y Year
B.E.S.I. 25971 TOWNE CL LAKE FOREST, CL Description of Soll Sand C Organic C Clay Other C Sand Organic C Clay Other C Sand Organic C Clay Other C List any exception to items listed at Generator's and/or consulta Sheet completed and certific inty way. Trint or Type Name: David C Sources Type Name: David C Sources Type Name: Casser Sources Casser Construction: Organic C Sources Casser Construction: Construct of Construction: Condition as when received without off-loading, adding Casser Construction: Casser Casser Construction: Casser Casser Construction: Casser Casser Casser Construction: Casser Casser	ENTRE DRIVE A 92610 BE Moisture Content 0 - 10% 10 - 20% 0 20% - over 0 0 - 10% 0 20% - over 0 0 - 10% 0 20% - over 0 bove: ant's certification: I, ed by me/us for the Generator 0 I/We acknowledge I/We further certification to, subtracting from Carl La	SI # 120059 Contaminated by: Gas Diesel O Other O Diesel O Other O Diesel O Other O Ne certify that the Generation Site sho Consultant O receipt of the soil a fy that this soil is	Approx.	Person to Contact BRIAN CASS FAX#: 949-450-117 Gty: Description Scale moded herein is take and nothing has re and date: the over and certify factly transported junction bory to such site.	7 on of Delivery e Ticket# en entirely from theen added or door that such soil is	CARDO Transporter's 45064 Customer Acco 10001 Gross Weight 3792 those soils descr ne to such soil to being delivered	10185175 DOT No.: 7 ant Number wit 93 Tare Weight 3 (6 4/6 7 3 2 7 ibed in the S ibed in the S ibed in the S ibed in the S in exactly th Designated	h TPST: Net Weight 3440 1.72 oil Data ter it in ay Year B 65 ⁻ he same Facility y Year
B.E.S.I. 25971 TOWNE CL LAKE FOREST, CL Description of Soil Sand C Organic C Clay C Other C Sand C Organic C Clay Other C Sand C Organic C Clay Other C List any exception to items listed at Generator's and/or consult Sheet completed and certific try way. The or Type Name: Dawic C Base Transporter's certification: ondition as when received without off-loading, adding rint or Type Name: MAME Sala	ENTRE DRIVE A 92610 BE Moisture Content 0 - 10% 20% - over 0 0 - 10% 0 20% - over 0 0 10% 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	SI# 120059 Contaminated by: Gas Diesel O Other O Diesel O Other O Diesel O Other O Ne certify that the Generation Site sho Consultant O receipt of the soil of fy that this soil is or in any way del	Approx.	Person to Contact BRIAN CASS FAX#: 949-450-117 Gty: Description Scale moded herein is take and nothing has re and date: the over and certify factly transported junction bory to such site.	7 on of Delivery e Ticket# en entirely from theen added or door that such soil is	CARDO Transporter's 45064 Customer Acco 10001 Gross Weight 3792 those soils descr ne to such soil to being delivered	10185175 DOT No.: 7 ant Number wit 93 Tare Weight 3 (6 4/6 7 3 2 7 ibed in the S ibed in the S ibed in the S ibed in the S in exactly th Designated	h TPST: Net Weight 3440 1.72 oil Data ter it in ay Year B 65 ⁻ he same Facility y Year
B.E.S.I. 25971 TOWNE CL LAKE FOREST, CL Description of Soll Sand Organic O Clay Other O Sand Organic O Clay Other O List any exception to items listed at Generator's and/or consult Scheet completed and certific truy way. Trint or Type Name: Dawic I Construction: ondition as when received. Without off-loading, adding trint or Type Name: Dawic I Construction: ondition as when received. Without off-loading, adding trint or Type Name: MAMIN Sala	ENTRE DRIVE A 92610 BE Moisture Content 10 - 20% G 20% - over G 0 - 10% G 10 - 20% G 20% - over G 0 - 10% G 10 - 20% G 20% - over G 0 - 10% G 10 - 20% G 20% - over G 20% - over G 10 - 20% G	SI# 120059 Contaminated by: Gas Diesel D Other D Diesel D Other D Diesel D Other D Me certify that the Generation Site sho Consultant D receipt of the soil a ify that this soil is a or in any way dele	Approx.	249-430-101 Person to Contact SRIAN CASS FAX#: 249-450-117 Gty: Description Scale meand herein is take and nothing has intered herein is take and nothing has re and date: Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale S	7 on of Delivery e Ticket# en entirely from theen added or door that such soil is	CARDO Transporter's 45064 Customer Acco 10001 Gross Weight 3792 those soils descr ne to such soil to being delivered	10185175 DOT No.: 7 ant Number wit 93 Tare Weight 3 (6 4/6 7 3 2 7 ibed in the S ibed in the S ibed in the S ibed in the S in exactly th Designated	h TPST: Net Weight 3440 1.72 oil Data ter it in ay Year B 65 ⁻ the same Facility y Year
B.E.S.I. 25971 TOWNE CL LAKE FOREST, CL Description of Soll Sand C Organic C Clay Other C Sand Organic C Clay Other C Sand Organic C Clay Other C List any exception to items listed at Generator's and/or consulta Sheet completed and certific any way. Thint or Type Name: Dawie C Base Transporter's certification: ondition as when received. without off-loading, adding rint or Type Name: Dawie C C Construction: Ordition as when received. Without off-loading, adding rint or Type Name: Carrepancies: FAC#	ENTRE DRIVE A 92610 BE Moisture Content 10 - 20% G 20% - over G 0 - 10% G 10 - 20% G 20% - over G 0 - 10% G 10 - 20% G 20% - over G 0 - 10% G 10 - 20% G 20% - over G 20% - over G 10 - 20% G	SI# 120059 Contaminated by: Gas Diesel D Other D Diesel D Other D Diesel D Other D Me certify that the Generation Site sho Consultant D receipt of the soil a ify that this soil is a or in any way dele	Approx. Approx. Approx. Signatur described a being dire aying delit Signatur Lescept as r	249-430-101 Person to Contact SRIAN CASS FAX#: 249-450-117 Gty: Description Scale meand herein is take and nothing has intered herein is take and nothing has re and date: Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale Scale S	7 on of Delivery e Ticket# en entirely from theen added or door that such soil is	CARDO Transporter's 45064 Customer Acco 10001 Gross Weight 3792 those soils descr ne to such soil to being delivered	10185175 DOT No.: 7 ant Number wit 93 Tare Weight 3 (6 4/6 7 3 2 7 ibed in the S ibed in the S ibed in the S ibed in the S in exactly th Designated	h TPST: Net Weight 3440 1.72 oil Data ter it in ay Year B 65 he same Facility y Year
B.E.S.I. 25971 TOWNE CL LAKE FOREST, CL Description of Soll Sand C Organic C Clay Other C Sand C Organic C Clay C Other C Clay Clay C Other C Clay Clay C Other C Clay Clay Clay Clay Clay Clay Clay Clay	ENTRE DRIVE A 92610 BE Moisture Content 10 - 20% G 20% - over G 0 - 10% G 10 - 20% G 20% - over G 0 - 10% G 10 - 20% G 20% - over G 0 - 10% G 10 - 20% G 20% - over G 20% - over G 10 - 20% G	SI# 120059 Contaminated by: Gas Diesel D Other D Diesel D Other D Diesel D Other D Me certify that the Generation Site sho Consultant D receipt of the soil a ify that this soil is a or in any way dele	Approx. Approx. Approx. Signatur described a being dire aying delit Signatur Lescept as r	Person to Contact BRIAN CASS FAX#: P49-450-117 Oty: Description Scale Inced herein is take and nothing has ibove and certify is scily transported joury to such site. Fand date: Fand date: Fand date: Fand date: Fand date: Fand date:	7 on of Delivery e Ticket# en entirely from theen added or door that such soil is	CARDO Transporter's 45064 Customer Acco 10001 Gross Weight 3792 those soils descr ne to such soil to being delivered	10185175 DOT No.: 7 ant Number wit 93 Tare Weight 3 (6 4/6 7 3 2 7 ibed in the S ibed in the S ibed in the S ibed in the S in exactly th Designated	h TPST: Net Weight 3440 1.72 oil Data ter it in ay Year B 65 he same Facility y Year

i

, ,