From: Daniel Schneidereit < Daniel. Schneidereit@lacity.org>

Sent time: 08/18/2020 02:42:03 PM

To: Luciralia Ibarra < luciralia.ibarra@lacity.org>; Mindy Nguyen < Mindy.Nguyen@lacity.org>
Subject: Department of Building and Safety's letter regarding Hollywood Center and CGS comments.

Attachments: Dept of Building and Safety Hollywood Center letter r.pdf

Hi Luci and Mindy,

Here's a copy of our letter regarding Hollywood Center. Sorry it's a bit late. I was on vacation all last week.

Thanks

Daniel Schneidereit Engineering Geologist II



BOARD OF BUILDING AND SAFETY COMMISSIONERS

VAN AMBATIELOS PRESIDENT

> JAVIER NUNEZ VICE PRESIDENT

JOSELYN GEAGA-ROSENTHAL GEORGE HOVAGUIMIAN ELVIN W. MOON

CITY OF LOS ANGELES



ERIC GARCETTI MAYOR DEPARTMENT OF
BUILDING AND SAFETY
201 NORTH FIGUEROA STREET
LOS ANGELES, CA 90012

OSAMA YOUNAN, P.E. GENERAL MANAGER SUPERINTENDENT OF BUILDING

> JOHN WEIGHT EXECUTIVE OFFICER

CITY OF LOS ANGELES INTER-DEPARTMENTAL CORRESPONDENCE

August 7, 2020

To:

Luciralia Ibarra, Principle City Planner

Department of City Planning

From:

Daniel Schneidereit, Engineering Geologist II

Department of Building and Safety

Subject:

The California Geological Survey's Comments Regarding the Hollywood Center

Fault Investigation

At the request of the Department of City Planning the Department of Building and Safety has reviewed a July 16, 2020 letter by the California Geological Survey (CGS) that concerns the proposed Hollywood Center development (Vesting Tentative Tract 82152). The CGS states they have new data they believe indicate there may be an active fault traversing the southerly portion of the site.

We acknowledge the CGS's concern and believe the best way to resolve this issue is for the developer to excavate another exploratory trench to demonstrate, or rule out, the presence of an active fault in the southerly part of the site. The trench needs to be approximately 30 feet deep or more to expose the necessary strata, and may require the use of shoring.

It is our understanding that the geologic consultants for the project are currently working on a scope of work for a trench. As part of the review, the Department of Building and Safety will ensure there will be transparency with the CGS, by requesting the CGS geologists to observe the trench and verify the exploration results.

Please contact me if you have further questions.

Thank you.

DCS