



DEPARTMENT OF CITY PLANNING RECOMMENDATION REPORT

City Planning Commission

Date:	October 10, 2019	Case No.:	CPC-2015-4557-MCUP-CUX-TDR-SPR-DD
Time:	After 8:30 a.m.	CEQA No.:	ENV-2015-4558-EIR
Place:	Los Angeles City Hall Los Angeles City Council Chamber, Room 340 200 North Spring Street, Los Angeles, CA 90012	Related Cases:	VTT-73966 VTT-73966-1A
Public Hearing Completed:	August 28, 2019	Council No.:	14 – Huizar
Appeal Status:	Transfer of Development Rights (TDR) appealable to City Council by applicant if disapproved in whole or in part. All other entitlements appealable to City Council.	Plan Area:	Central City
		Plan Overlay:	None
		Certified NC:	Downtown Los Angeles
		Land Use:	Regional Center Commercial
		Zone:	C2-4D
Expiration Date:	October 10, 2019	Applicant:	Olymfig26, LLC
Multiple Approvals:	Yes	Representative:	PSOMAS (Anne Williams)

PROJECT LOCATION: 813-815 West Olympic Boulevard; 947-951 S. Figueroa Street

PROPOSED PROJECT: The Project includes demolition and removal of all existing development on the Project Site and development of a single 57-story high-rise building containing up to 65,074 square feet of retail/commercial space (in three stories); 33,498 square feet of office space (in six stories); 10,801 square feet of hotel conference center/ballroom space (on one story); 8,448 square feet of residential condominium amenities (on the same story as the hotel conference center); 373 hotel rooms (216,065 square feet in 17 stories, including lobby/amenities level); 374 residential condominium units (435,731 square feet in 24 stories); and 9,556 square feet of penthouse amenity area (in two stories) for a project total of 779,173 square feet of total floor area. A six-level subterranean parking garage would be located beneath the building, and eight levels of above ground parking would be provided within the podium level of the building. Six levels of the above ground parking would be wrapped with office uses on the Olympic Boulevard street frontage. Two additional stories dedicated to mechanical facilities would also be included in the proposed structure. The project proposes a maximum floor area ratio (FAR) of up to 13:1.

REQUESTED ACTIONS:
ENV-2015-4558-EIR

1. Pursuant to Section 21082.1(c)(3) of the California Public Resources Code, the consideration and certification of the Environmental Impact Report (EIR), ENV-2015-4558-EIR, SCH No. 2016061048, for the above-referenced project, and adoption of the Statement of Overriding Considerations setting forth the reason and benefits of adopting the EIR with full knowledge that significant impacts may remain;
2. Pursuant to Section 21081.6 of the California Public Resources Code, the adoption of the proposed Mitigation Measures and Mitigation Monitoring Program; and
3. Pursuant to Section 21081 of the California Public Resources Code, the adoption of the required Findings for the certification of the EIR;

CPC-2015-4557-MCUP-CUX-ZV-TDR-SPR:

1. Pursuant to LAMC Sections 14.5.6 and 14.5.8 through 14.5.12, a **Transfer of Floor Area Rights** (TFAR) Application for the transfer of greater than 50,000 square feet of floor area to the Project Site from the City of Los Angeles, including its Convention Center. Approval of the TFAR would result in a FAR of up to 13:1 in lieu of 6:1 FAR and up to 779,173 square feet of total floor area;
2. Pursuant to LAMC Section 12.24-W,1 and 12.24-W,18, a **Master Conditional Use** to permit for a full line of alcoholic beverages for on-site consumption within up to 16 premises and up to four premises for off-site consumption;
3. Pursuant to 12.24 W.18, a **Conditional Use Permit** (CUX) to allow dancing within the commercial areas;
4. Pursuant to LAMC Section 16.05, **Site Plan Review** for a project that would result in an increase of 50 or more dwelling units or guest rooms.
5. Pursuant to LAMC Section 12.21-G,3, a **Director's Determination** to provide less than one on-site tree per four residential dwelling units (63 trees in lieu of 94 trees); and
6. Pursuant to LAMC Section 12.21-A,16(h), a **Director's Determination** to provide short-term bicycle parking inside a building and short-term and long-term bicycle parking on a level other than the ground floor or nearest floor to the ground floor in a parking garage; and

RECOMMENDED ACTIONS:

ENV-2016-4889-EIR

1. **FIND**, based on the independent judgment of the decision-maker, after consideration of the whole of the administrative record, the project was assessed in the previously certified Olympic Tower Environmental Impact Report (EIR), which includes the Draft EIR, No. ENV-2015-4558-EIR (SCH No. 2016061048) dated October 4, 2018, the Final EIR, dated August 14, 2019, and the Errata, dated September 2019, certified on August 28, 2019; and pursuant to CEQA Guidelines, Sections 15162 and 15164, no subsequent EIR or addendum is required for approval of the project;

OR

If the City Planning Commission grants the appeal of the Vesting Tentative Tract Map (VTT-73966-1A) and denies the tract map:

FIND the City Planning Commission has reviewed and considered the information contained in the Environmental Impact Report prepared for this project, which includes the Draft EIR, No. ENV-2015-4558-EIR (SCH No. 2016061048) dated, October 4, 2018, the Final EIR, dated August 14, 2019 and Errata, dated September 2019 (Olympic Tower Project EIR), as well as the whole of the administrative record, and

CERTIFY that:

The Olympic Tower Project EIR has been completed in compliance with the California Environmental Quality Act (CEQA);

The Olympic Tower Project EIR was presented to the City Planning Commission as a decision-making body of the lead agency; and

The Olympic Tower Project EIR reflects the independent judgment and analysis of the lead agency.

ADOPT the following:

The related and prepared Olympic Tower Project Environmental Findings;
The Statement of Overriding Considerations;
The Mitigation Monitoring Program prepared for the Olympic Tower Project EIR.

Advise the applicant that, pursuant to California State Public Resources Code Section 21081.6, the City shall monitor or require evidence that mitigation conditions are implemented and maintained throughout the life of the project and the City may require any necessary fees to cover the cost of such monitoring; and


Advise the applicant that pursuant to State Fish and Game Code Section 711.4, a Fish and Game Fee and/or Certificate of Fee Exemption may be required to be submitted to the County Clerk prior to or concurrent with the Environmental Notice of Determination ("NOD") filing.


CPC-2015-4557-TDR- MCUP-SPR-DD

1. **Approve and Recommend** that the City Council approve the requested **Transfer of Floor Area Rights** (TFAR) Application for the transfer of greater than 50,000 square feet of floor area to the Project Site from the City of Los Angeles, including its Convention Center;
2. **Approve a Master Conditional Use** to permit for a full line of alcoholic beverages for on-site consumption within up to 16 premises and up to four premises for off-site consumption;
3. **Approve a Conditional Use Permit** to allow dancing within the commercial uses;
4. **Approve a Director's Decisions** to allow less than one on-site tree per four residential dwelling units (63 trees in lieu of 94 trees);
5. **Approve a Director's Decision** to allow short-term bicycle parking inside a building and short-term and long-term bicycle parking on a level other than the ground floor or nearest floor to the ground floor in a parking garage;
6. **Approve a Site Plan Review** for a project resulting in an increase of 50 or more dwelling units or guest rooms;
7. **Adopt** the attached Findings;
8. **Advise** the applicant that, pursuant to California State Public Resources Code Section 21081.6, the City shall monitor or require evidence that mitigation conditions are implemented and maintained throughout the life of the project and the City may require any necessary fees to cover the cost of such monitoring; and
9. **Advise** the applicant that pursuant to State Fish and Game Code Section 711.4, a Fish and Game Fee and/or Certificate of Fee Exemption may be required to be submitted to the County Clerk prior to or concurrent with the Environmental Notice of Determination ("NOD") filing.

VINCENT P. BERTONI, AICP
Director of Planning



Lisa Webber, AICP, Deputy Director

Heather Bleemers, Senior City Planner

Sergio Ibarra, City Planner
Phone: (213) 473-9985

ADVICE TO PUBLIC: **The exact time this report will be considered during the meeting is uncertain since there may be several other items on the agenda. Written communications may be mailed to the Commission Secretariat, Room 272, City Hall, 200 North Spring Street, Los Angeles, CA 90012 (Phone No. 213-978-1300). While all written communications are given to the Commission for consideration, the initial packets are sent to the week prior to the Commission's meeting date. If you challenge these agenda items in court, you may be limited to raising only those issues you or someone else raised at the public hearing agendized herein, or in written correspondence on these matters delivered to this agency at or prior to the public hearing. As a covered entity under Title II of the Americans with Disabilities Act, the City of Los Angeles does not discriminate on the basis of disability, and upon request, will provide reasonable accommodation to ensure equal access to these programs, services and activities. Sign language interpreters, assistive listening devices, or other auxiliary aids and/or other services may be provided upon request. To ensure availability of services, please make your request not later than three working days (72 hours) prior to the meeting by calling the Commission Secretariat at (213) 978-1295.*

TABLE OF CONTENTS

Project Analysis	A-1
Project Description	
Background	
Project Analysis	
Issues	
Environmental Analysis	
Conclusion	
Conditions of Approval	C-1
Findings.....	F-1
Entitlement Findings	
CEQA Findings	
Public Hearing and Communications	P-1
Exhibits:	
A – Project Plans	
B – Mitigation Monitoring Program & Errata	
C – LADOT Approval Letter	
D – ZIMAS Zoning Map	

Environmental Impact Report link:

<http://planning.lacity.org/development-services/eir/olympic-tower-la-project-1>

PROJECT ANALYSIS

Project Description

The Project proposes to develop a mixed-use project (Project) on a 37,031 square-foot site (0.85 acres) located within the Central City Community Plan area of the City of Los Angeles (City). The proposed Project is a mixed-use development consisting of one building with 374 residential condominium units, a hotel with 373 guest rooms, a 10,801 square foot conference center, 33,498 square feet of office uses, and 65,074 square feet of commercial floor area. The building will be 57 stories and approximately 742 feet tall. The ground floor will include 20,745 square feet of commercial uses, and elevator lobbies for the offices, hotel and residential uses as seen on page G 0.11 of Exhibit A. There will also be mechanical rooms, valet parking and driveway ramps to the parking within the building. The second and third floors will include approximately 44,329 square feet of commercial uses. Levels 4 and 5 will be devoted to automobile parking. Levels 6-11 will include offices and parking on each floor. Level 12 is devoted solely to mechanical equipment. The project is further summarized below.

Olympic Tower Project Totals	
Use	Provided
Residential	
Dwelling Units	374 Units
Commercial	
Retail/Restaurant	65,074 Sq. Ft.
Office Space	33,498 Sq. Ft.
Hotel	
Guest Rooms	373 Rooms
Assembly Space/Conference Center	10,801 Sq. Ft.


Level 13 will be devoted to indoor and outdoor open space (including a pool) and amenities for the residential units in the building along with a ballroom/conference center to support the hotel. The 14th floor includes the lobby for the hotel, a restaurant space and indoor and outdoor amenities for the hotel guests, including a pool. Levels 15-30 consists of hotel guest rooms. Level 31 is another transition floor devoted solely to mechanical equipment to serve the building. The 374 residential condominium units will be located on levels 32-55. Level 56 will include indoor and outdoor amenities for residents, including a pool for the use of the penthouse units located on levels 48-55. On the top level (57th floor) an indoor club house will be located for use of the residential tenants of the building as shown on page G 0.15 of the project plans (Exhibit A).

In addition to the 8 above-ground levels of parking, there will also be six basement levels devoted to required parking for the Project, for a total of 838 spaces. Valet bicycle parking (a total of 571 long-and short-term spaces) will also be located on these levels on Level B1 and B2, with the valet office on Level B1.

Development of the Project will require removal of the one-story carwash and restaurant buildings that currently occupy the site.

The Ground Level and podium level floor plans are shown on A101 through A113 of the projects plans within Exhibit A.

Access and Circulation



Vehicular movements into and out of the Project site would be provided via three access points along Cottage Place: one driveway providing access for the residential land use component, a porte cochere (i.e., main drop-off and pick-up area) for all of the commercial land use components, and a loading driveway for loading, trash collection and waste management. These will be new driveways along the alley only. No driveways are proposed along Olympic boulevard or Figueroa Street.

a) Residential Driveway

The residential Project driveway would be located on the east side of Cottage Place (i.e., along the westerly property frontage) near the northwest corner of the project site. This driveway would provide restricted access only for residents of the Project. The driveway would descend one level down where a valet parking station would be located. Valet parking for residents would be provided on a 24-hour basis. Also, the residential project driveway would accommodate left-turn and right-turn ingress and egress turning movements.

b) Porte Cochere

The porte cochere would be located on the east side of Cottage Place (i.e., along the westerly property frontage) at the southwest corner of the Project site. Access to the project's porte cochere would be provided for all of the commercial land use components and would be accommodated via Cottage Place, including a minor widening for its connection to Olympic Boulevard. Valet parking for commercial land use guests, visitors, patrons, and employees would be provided on a 24-hour basis. A total of three service lanes would be provided within the porte cochere, including two general service lanes and one taxi service lane.

c) Loading Driveway

Loading activities (e.g., associated with loading, trash collection, and waste management) would utilize the driveway located on the east side of Cottage Place (i.e., along the westerly property frontage) at the northwest corner of the project site. The loading driveway would accommodate left-turn and right-turn ingress and egress turning movements.

Pedestrian Access

The Project would be designed to provide connections to the adjacent public sidewalks and would include site enhancements to promote walkability. Covered outdoor dining areas, retail, and office uses on the first eleven floors partially wrap around above-ground parking provided at the site. The Project site would be accessible by pedestrians from the sidewalks and covered walkways along the north side of Olympic Boulevard, the west side of Figueroa Street, and the east side of Cottage place. Hotel Guest and Resident entrances are accessible through the valet and porte cochere driveway on the east side of Cottage Place and the covered walkway along Olympic Boulevard, which wraps around the building; both points of access lead to the hotel lobby where elevators are provided for all uses. Access to retail is provided through the uncovered entrance along Olympic Boulevard which provides access to centrally located escalators that provide access to the first three levels of retail. Elevators for retail and parking are located in the ground retail lobby.

Bicycle Access

The Applicant proposes to provide basement floor valet pick-up/drop-off service for bicycles belonging to hotel guests, employees and office/commercial tenants and visitors (the general public). The bicycles would be parked by attendants in designated bike racks and lockers on Levels B1 and B2. Residents and guests of the condominium units would use the residential elevators to move their bicycles from street level to Level B1 where the residential valet pick-up/drop-off will be located, and parking attendants on Level B1 will park these bicycles in storage racks and lockers on Levels B1 and B2. No outside bike racks for short-term bicycle parking will be provided.

Vehicular Parking

The Project would be required to provide 689 vehicle parking spaces (without any applicable LAMC-allowed reductions) and would provide 838 vehicle parking spaces as summarized below. The project is electing not to reduce parking based on the bicycle parking ordinance or its proximity to light rail. Twenty percent of the Project's provided vehicle parking spaces would be capable of accommodating electric vehicle (EV) charging stations, and an additional five percent would be wired as EV charging stations for immediate use.

Vehicle Parking

Use	Amount	Rate	Total
Required Parking			
Residential - Studio	24 units	1.0 space/unit	24
Residential – Condo (3 habitable rooms)	200 units	1.0 space/unit	200
Residential – Condo (>3 habitable rooms)	64 units	1.25 spaces/unit	80
Residential –Condo (>3 habitable rooms)	56 units	1.25 spaces/unit	70
Residential – Penthouse Condo (>3 habitable rooms)	30 units	1.25 spaces/unit	38

Hotel (Rooms 1-20)	20 guest rooms	1:2 space/guest room	10
Hotel (Rooms 21-40)	20 guest rooms	1:4 space/guest room	5
Hotel (Rooms 41-373)	373 guest rooms	1:6 space/guest room	56
Ballroom/Conference Center	10,801 sf	1 space/100 sf	108
Office	33,498 sf	1 space/1,000 sf	33
Retail/Commercial	65,074 sf	1 space/1,000 sf	65
Initial Total Required			689
<i>Parking Reductions – Proximity to Light Rail</i>			<i>145</i>
<i>Parking Reductions – Provided Bicycle Parking</i>			<i>142</i>
Final Total Required			588
Project Parking			
Below ground (eight levels for residential uses)			438
Above ground (on Levels 4-12 for commercial, hotel, and office uses)			400
Total Project Parking			838

Bicycle Parking

LAMC 12.21 A.16(a)(2) requires new projects to provide bicycle parking spaces. Multi-family residential buildings with more than three dwelling units require one long-term bicycle parking space per unit and one short-term bicycle parking space per 10 units. Office uses require one long-term bicycle parking space per 10,000 square feet and one short-term bicycle parking space per 5,000 square feet. Retail uses require one long term and one short-term bicycle parking space per 2,000 square feet. Hotel uses require one long term and one short-term bicycle parking space per 20 guest rooms. Ballroom/conference uses require one long-term bicycle parking space per 700 square feet and one short-term bicycle parking space per 350 square feet. Short-term bicycle parking shall consist of bicycle racks that support the bicycle frame at two points. Long-term bicycle parking shall be secured from the general public and enclosed on all sides and protect bicycles from inclement weather. As required the Project would include 123 short-term and 448 long-term bicycle spaces at a minimum, consistent with LAMC requirements.

Bicycle parking requirements per LAMC Section 12.21 A.16(a) include short-term and long-term parking. The Project would be required to provide 571 bicycle parking spaces in accordance with Ordinance No. 185,480. The Project would provide a total of 37 short-term and 374 long-term spaces for a total of 411 spaces for residential uses. 66 bicycle parking spaces would be provided for commercial uses, with 33 short-term and 33 long-term spaces. A combined total of 94 spaces, which include 53 short-term and 41 long-term spaces for hotel, conference, and office uses would be provided, as summarized below. As part of the Director's Decision, the project will include alternative siting for bicycle parking, with a bicycle valet on the 1st basement floor which will be easily accessible by pedestrians and cyclists.

Bicycle Parking

Use	Amount	Rate	Short-Term Required	Long-Term Required
Residential	374 units	1 per 10 units (short-term) 1 per unit (long-term)	37	374
Hotel	373 rooms	1 per 20 rooms (short-term) 1 per 20 rooms (long-term)	19	19
Ballroom/Conference	10,801 sf	1 per 350 sf (short-term) 1 per 700 sf (long-term)	31	15

Office	33,498 sf	1 per 10,000 sf (short-term) 1 per 5,000 sf (long-term)	3	7
Commercial	65,074 sf	1 per 2,000 sf (short-term) 1 per 2,000 sf (long-term)	33	33
Total Required			123	448
Total Provided			123	448

Landscaping and Open Space

The Project would provide approximately 73,848 square feet of open space and recreational amenities. The project is required to provide 42,650 square feet of open space. Levels 13, 56, and 57 would provide a total of 42,759 square feet of indoor/outdoor open space. Private open space would total 31,108 square feet on indoor/outdoor open space.

Common Open Space

The Project's common open space will be located on three separate roof decks on levels 13, 56 and 57.

Level 13 will provide 11,370 square feet of outdoor common open space and 8,112 square feet of indoor common open space. Amenities will include a fitness/gym for residents, a pool and deck area, men and women's locker rooms, a bar/lounge area, and three separate ballrooms with balconies and connections to the large outdoor open space.

Level 56 will provide 13,703 square feet of outdoor common open space and 5,085 square feet of indoor common open space. Amenities will include a fitness/gym for residents, a pool and landscaped deck area, sauna, men and women's locker rooms, barbeque and seating areas.

Level 57 will provide a 721-square-foot outdoor observation deck and 3,749 square feet of indoor sky lounge areas with panoramic views of the city. The indoor sky lounge will accommodate dining/seating areas, a bar, and meeting rooms. This level will overlook the landscaped roof deck on level 56 below.

Private Open Space

The Project will include a total of 31,108 square feet of indoor and outdoor and private open space in the form of balconies and covered recreational spaces for each of the proposed condominium units on levels 32 through 55. Along the north side of the proposed tower, each unit will have a private balcony that will project away from the tower and be open to sky and will range in size from 75 to 155 square feet in accordance with open space standards in LAMC 12.21.G.2(4)(b)(2). Along the south-facing side of the tower, each unit will have private-covered recreational space in excess of the required common open space for the overall Project.

Covered Sidewalks and the Public Realm

The Olympic Tower project is unique in that the building's proposed exoskeleton will enhance adjacent sidewalks and pedestrian-oriented frontages along Olympic Boulevard and Figueroa Street. In these areas, the exoskeleton structure will be vaulted 40 feet high along levels 1 and 2 and extend 8.5 feet from the façade to provide additional shading and covering to a sidewalk easement area. This covered area will total approximately 5,000 square feet and will be porous and open to the public sidewalk and will effectively function as publicly accessible open space. Landscaping and public signage will highlight primary entrances to the retail and commercial spaces, the hotel lobby, and residential entrances. The covered area will also provide opportunities for active pedestrian-oriented uses and amenities, including outdoor dining and seating along Olympic Boulevard and Figueroa Street. As pedestrians travel through this space,

they will be surrounded by an attractive streetscape along Olympic and Figueroa and open and transparent double-height shopfronts on the Project's ground floor.

No native or protected trees are present on the Project Site or along the sidewalks adjacent to the Project Site. Existing trees, including street trees, would be removed to facilitate development of the Project. Proposed landscaping would consist of 63 trees throughout the ground floor exterior of the Project as well as trees in planters in all of the exterior common spaces throughout the building. Additionally, the Project would be designed as a "vertical garden," with vines and other vegetation running along cables attached to the building's exterior. The vertical garden would be developed on the upper levels of the building and would include accessible exterior planters that would be maintained with appropriate soil and materials to support healthy plant growth. The types of plants included in the vertical garden would include a combination of vines, trees, and shrubs that are appropriate for a vertical garden. Each of the planting areas would be readily accessible for pruning, maintenance, and replanting to ensure the health of the plants and the aesthetic nature of the vertical garden. An irrigation system would be installed in the building that would connect to each of the planting areas for the specific purpose of irrigating the garden.

Sustainability Features

The Project would include project design features designed to improve energy efficiency and water conservation, as set forth in the Draft Environmental Impact Report, Section IV.M, Utilities and Service Systems, Water, and in compliance with minimum Code requirements; and to encourage efficiency in construction, as described in Section IV.C Air Quality of the Draft Environmental Impact Report. These features summarized below and are incorporated into the project's Conditions of Approval as part of the Mitigation Monitoring Program, as seen in Condition of Approval Nos. 26 and 27:

Project Design Features

- PDF-GHG-1: The Project shall include rooftop photovoltaic panels, calculated to provide power to common and amenity areas (refer to Figure III-4 and Figure III-35 in Section III [Project Description]).
- PDF-GHG-2 The Project shall include façade photovoltaic panels contained within the glass panels to provide power to the building exterior lighting and LED lighting (refer to Figure III-32 and Figure III-33 in Section III [Project Description]).
- MM-I-1 All diesel-powered construction vehicles shall be equipped with exhaust mufflers or other suitable noise reduction devices capable of achieving a sound attenuation of at least 3 dBA. Should they be required, generators would be solar-powered.

PDF-WATER1 Water Conservation Measures

- High Efficiency Toilets with a flush volume of 1.1 gallons per flush or less
- Urinals – Waterless
- Showerheads with a flow rate of 1.5 gallons per minute or less
- ENERGY STAR Certified Residential Clothes Washers – Integrated Water Factor of 3.7 or less, front-loading, and capacity of 2.3 cubic feet
- ENERGY STAR Certified Residential Dishwashers – 3.07 gallons per cycle or less, standard type
- Centralized Domestic Water Heating System with hot water return branches
- Point of Use Water Heaters may be used where conditions warrant
- Individual metering and billing for water use for every residential dwelling unit and commercial unit

- Water-Saving pool filter
- Pool/Spa recirculating filtration equipment
- Pool splash troughs around the perimeter that drain back into the pool
- Install a meter on the pool make-up line so water use can be monitored and leaks can be identified and repaired
- Reuse pool backwash water for irrigation
- Leak Detection System for swimming pools and Jacuzzi
- Micro-Spray
- Hydro-zoning Irrigation – Commercial zoning with plant factor 0.3 and Residential zoning with plant factor 0.4
- Drip/Subsurface Irrigation to Commercial zone (4,251 square feet) and Residential zone (8,474 square feet)
- Primary (On-Site) Waste Water Treatment Systems – Possible uses are public toilets and irrigation. Exact usage information not yet known.

Background

Location and Setting

The Project Site is located in a highly urbanized area dominated by commercial development. The Project Site is bounded on each side by a public right-of-way, and located directly north, across Olympic Boulevard from LA Live, and the larger Los Angeles Sports and Entertainment District (LASED). The LASED includes Staples Center, LA Live, the Microsoft Theater, and restaurant and commercial uses adjacent to the Project Site.

At the southwest corner of Francisco Street and Olympic Boulevard are the 54-story Ritz-Carlton Residences and the JW Marriott Hotel. The Residence in Marriott is located at the northwest corner of the Francisco Street and Olympic Boulevard. Across Cottage Place is a surface parking lot, and multiple structures, including a two-story Los Angeles Department of Water and Power building, a one-story Salvation Army building directly across Cottage Place, and the Residence Inn Marriott Los Angeles and a four-story office building located across Francisco Street. To the east of the project site across Figueroa Street is the 26-story 717 Olympic apartment building. Abutting the north edge of the project site, is the Hotel Figueroa, a surface parking lot, and a three-story emergency housing building. At the southeast corner of the Figueroa Street and Olympic boulevard intersection is the Luxe City Center Hotel.

Project Site and Characteristics

The Project site is located within the Central City Community Plan area of the City. The Central City Community Plan area is located in the Downtown of Los Angeles. The plan area is bounded by Sunset Boulevard/Cesar Chavez Avenue to the north; Alameda Street to the east; the Santa Monica Freeway (Interstate 10) to the south; and the Harbor Freeway (California State Route 110) to the west. The eastern edge of the approximately 2.0-mile-wide by 2.0-mile long plan area is on the eastern edge of downtown Los Angeles, while the western edge abuts the western side of downtown Los Angeles. The plan area is surrounded by the City's community plan areas of Central City North to the north and the east; Southeast Los Angeles to the south; and both Westlake and South Los Angeles to the west.

The Project site is completely developed with a single concrete block type structure containing a commercial car wash and detailing center and restaurant. The car wash, operational since 1980, occupies the majority of the structure (approximately 9,130 square feet of building area), with the detailing area being located outside at the lot corner adjacent to Cottage Place and Olympic Boulevard. A hand waxing area under an overhead shed, a garbage enclosure, and a carport over the entrance to the washing area (extending north to the wall on the northern Project site

boundary) are located in the north and western portions of the Project site. A shoeshine service is located inside the lobby/waiting area of the car wash. The site plan is shown below.



Site Plan

Existing Land Use Designation and Zoning

The Project Site is located within the planning boundary of the Central City Community Plan, which was last updated in January 2003. Under the Community Plan, the Project Site is designated for Regional Center Commercial uses. The entire Project Site is zoned by the Los Angeles Municipal Code (LAMC) as C2-4D (Commercial, Height District 4 with a Development Limitation). The C2 Zone permits a wide array of land uses, such as retail stores, offices, hotels, schools, parks, and theaters; and allows any land use permitted in the C1.5 and C1 zones, which, in turn, allow residential uses per the R4 density. Height District 4 within the C2 zone does not impose any height limit. The maximum permitted floor area of the Project Site is restricted by the "D" limitation pursuant to Ordinance 164,307, which restricts the FAR to 6:1 without a transfer of floor area. With a transfer of floor area, the maximum FAR permitted is 13:1. An FAR of 6:1 permits a total floor area of approximately 222,186 square feet. The proposed project FAR is 13:1 or approximately 779,638 square feet. The total TFAR requested is 556,987 square feet (from both the Convention Center and a CRA donor site).

Central City Community Plan Update

It should also be noted that the City of Los Angeles Department of City Planning is currently updating the Central City Community Plan in conjunction with the Central City North Community Plan, whose areas together make up Downtown Los Angeles (sometimes known as DTLA), in a combined planning process referred to as the DTLA 2040 Plan. The purpose of the DTLA 2040 Plan is to develop and implement a future vision for Downtown Los Angeles that supports and sustains ongoing revitalization while thoughtfully accommodating projected future growth. As Downtown has been a rapidly changing setting within Los Angeles, it supports a collection of economic opportunities and entrepreneurship, people, culture, and distinct neighborhoods, and sits at the center of the regional transportation network.

Specifically, the following core principles will represent the long-term priorities for the DTLA 2040 Plan:

- Accommodate anticipated growth through 2040 in an inclusive, equitable, sustainable, and healthy manner while supporting and sustaining Downtown's ongoing revitalization
- Reinforce Downtown's jobs orientation
- Grow and support the residential base
- Strengthen neighborhood character
- Promote a transit, bicycle, and pedestrian friendly environment
- Create linkages between districts
- Create a World-Class Streets and Public Realm

Entitlements

In order to develop the Project, the following land use entitlements are required:

- Approval of a **Transfer of Floor Area Rights (TFAR)** for the transfer of greater than 50,000 square feet of floor area from the City of Los Angeles-owned Convention Center (Donor Site) to the project site (Receiver Site). Approval of the TFAR would result in a FAR of 13:1 in lieu of 6:1 FAR, a transfer of up to 455,161 square feet, to permit a maximum of 779,173 square feet of total floor area.
- Approval of a **Master Conditional Use Permit** to permit the sale and dispensing of a full line of alcoholic beverages for on-site and off-site sale and service of alcohol at multiple locations, and a **Conditional Use Permit** to allow dancing and live entertainment;
- Pursuant to LAMC Section 12.27, a **Director's Decision** to provide less than one on-site tree per four residential dwelling units (63 trees in lieu of 94 trees);
- Pursuant to LAMC Section 12.27, a **Director's Decision** to provide short-term bicycle parking inside a building and short-term and long-term bicycle parking on a level other than the ground floor or nearest floor to the ground floor in a parking garage; and
- A **Site Plan Review** for a project resulting in an increase of 50 or more dwelling units.

In addition, on September 6, 2019 the Advisory Agency approved Vesting **Tentative Tract Map** No. VTT-73966 for the merger and resubdivision of a 0.85 acre into one ground lot and 31 airspace lots (32 lots in total) and for condominium purposes for a mixed-use development, a Haul Route for export of 115,500 cubic yards of soil, and a deviation from Advisory Agency Parking Policy AA-2000-01. An appeal was filed by an aggrieved party on September 16, 2019.

Streets and Circulation

Harbor Freeway (State Route 110) is a State-maintained highway located approximately 0.3 miles west of the project site.

Olympic Boulevard is a designated Boulevard II in Mobility Plan 2035 with a right-of-way width of 110 feet, and is improved with a gutter, curb, and sidewalk along the project site's South street frontage. Olympic Boulevard is a two-way street with no parking permitted. The designated half right of way is 55 feet. Pursuant to VTT-73966, a 10-foot wide private pedestrian walk easement shall be provided along Olympic Boulevard adjoining the tract and shall be open for public use.

Figueroa Street is a designated Modified Avenue I in Mobility Plan 2035. The designated right

of way is 100 feet and the half right of way is 50 feet.

Cottage Place is a designated Standard Local Street in Mobility Plan 2035 with a right-of-way width of 60 feet. Bureau of Engineering is requesting longitudinal gutter along Cottage Place.

Freeway Access

Within the Project vicinity, primary regional access is provided by State Route 110 (SR-110 or Harbor Freeway), which runs north-south to the west of the Project Site. The SR-110 is accessible via 8th Street, 5th Street, 3rd Street, Bixel Street (to the northwest of the site), and Georgia Street.

Public Transit

The proposed Project is transit accessible and is in proximity to many bus transit lines, MTA rail lines (Metro Rail) and DASH service. The Metro Rail Expo and Blue Lines run beneath Flower Street, one block to the east of the Project site. The Pico Station is located on these lines approximately 0.2 miles (three blocks) south of the Project site. The 7th Street/Metro Center station, which serves the Expo and Blue Lines as well as the Red, Purple, and is located approximately 0.35 miles (four blocks) northeast of the Project site. The 7th Street/Metro station connects passengers to Pasadena, East Los Angeles, Long Beach, Culver City, Santa Monica, Hollywood, Koreatown, and North Hollywood. Prior to project build out, Metro forecasts 2021 as completion of construction of the Regional Connector Project, which would expand service by connecting the Gold, Blue, and Expo Light Rail Lines expanding destinations at both stations, projected operation is 2021.

The Los Angeles County Metropolitan Transportation Authority (Metro) provides bus, transit way, and rail service to the immediate vicinity of the Project site. Olympic Boulevard carries Metro Rapid bus line 728 and Metro Local bus line 28 past the Project site with a stop adjacent to the Project site. Figueroa Street carries Metro Express bus lines 442 and 460 and Metro Local bus line 81 past the Project site (northbound) and one block to the east on Flower Street (southbound). In addition, the Metro Silver Line transit way (Metro Busway Routes 910 and 950X), running from El Monte to San Pedro via Downtown, runs northbound on Figueroa Street past the Project site and southbound on Flower Street, one block to the east.

Bicycle Facilities

The MyFig Project was recently completed along Figueroa Street. It included expanded bicycle infrastructure, including buffered bicycle lanes, striped bicycle lanes, bus boarding islands, and other facilities. The City's Mobility Plan designates a network of bicycle lanes and routes in the Central City area. None of the surrounding streets are designated as bicycle facilities in the plan. The nearest designated street is Flower Street, which is designated as Tier Three. Figueroa Street, as mentioned above is currently improved with the MyFig project, which includes Tier two bicycle lanes, and protected Tier One protected bicycle lane. Additionally, a Metro Bike Share dock is located at Figueroa and 9th Street (865 South Figueroa Street), with capacity for up to 15 bicycles.

Relevant Cases

On-Site:

VTT-73966: Tentative Tract application for the project located at 813-815 West Olympic Boulevard and 947-951 S. Figueroa Street to create for the merger and resubdivision of a 0.85 acre into one ground lot and 31 airspace lots (32 lots in total) and for condominium purposes for a mixed-use development, a Haul Route for export of 115,500 cubic yards of soil, and a deviation from Advisory Agency Parking Policy AA-2000-01.

VTT-73966-1A: Appeal of Tentative Tract 74564 on September 16, 2019.

ENV-2015-4558-EIR: Environmental Impact Report (EIR) for the proposed Olympic Tower Project. On September 6, 2019, the Deputy Advisory Agency and Hearing Officer, on behalf of the City Planning Commission, considered, pursuant to Section 21082.1(c) of the California Public Resources Code, the adequacy of ENV-2015-4558-EIR (SCH No. 2016061048), findings, Statement of Overriding Considerations and accompanying mitigation measures, Mitigation Monitoring Program as the environmental clearance for the project. The Notice of Availability of the Final Environmental Impact Report was issued on August 14, 2019. On September 16, 2019, VTT-73966 was appealed, thereby decertifying the EIR.

Ordinance 164307-SA2460 "D-Limitation:" On January 30, 1989 the City Planning Commission adopted an ordinance amending the zoning map to restrict FAR for parcels in the Center City Community Plan area. The project site was one of the areas affected, and the FAR was restricted to 6:1 with provisions for a Transfer of Floor Area to exceed the limit.

CPC-2010-213-CA: On May 13, 2010 the City Planning Commission approved a Code Amendment to modify the authority and procedures for effectuating a Transfer of Floor Area Rights and make other technical changes as a result of expiring amended CBD project area.

Off-Site:

ZA-2018-2727 – On April 10, 2019, the Zoning Administrator approved pursuant to Section 12.24 W.1, a Master Conditional Use Permit for the approval of up to 4 new restaurants, 2 with full line of alcoholic beverages (type 47), 2 with service of beer & wine only, with up to 1 with live music within 16,045 s.f. of int. ground floor retail space & 1059 s.f. mezzanine, 1,874 s.f. of outdoor area (up to 628 seats) with 96 outdoor seats) and hours of operation 6am- 2am daily, located in the C2-4D-SN zone.

ZA-2017-2378 – On October 11, 2018, the Zoning Administrator approved a master Conditional use Permit to allow the sales and service of a full-line of alcoholic beverages for on-site consumption, and live entertainment in conjunction with four venues to include a restaurant and club/lounge/bars located in the historic Variety Arts Building.

CPC-2017-173-TDR-BL-MCUP-SPR: On January 17, 2017, an application for a mixed-use project consisting of 220 room hotel, 200 residential condominiums, and 984,940 square feet of commercial space was submitted, was filed for the property located at 913 South Figueroa Street. This case is currently pending.

CPC-2017-173- TDR-BL-MCUP-SPR – Proposed project for the Transfer of Development (TFAR) per section 14.5.6.B for a project that is greater than 50,000 square feet of floor area for the transfer of 473,038 square feet of floor area to the project site, pursuant to 12.32.R, building line removal along a portion of Figueroa Street, a Master Conditional Use Permit per section 12.24.W.1. to permit the onsite sale and consumption of alcoholic beverages within the proposed hotel and at up to 10 restaurants, and site plan review per section 16.04 for the development of 200 residential dwelling units, 220 hotel guest rooms, and 94,080 square feet of commercial uses.

ZA-2016-4203-TDR-CUB-SPR: On March 12, 2018 the Zoning Administrator approved a Director's Determination for a Transfer of Floor Area of 49,999 square feet of floor area, for a 247-room hotel, and a Conditional Use Permit for the on-site sale and consumption of alcohol, located at 926 James M. Wood Boulevard.

CPC-2015-1158-SN-TDR-MCUP-CUX-SPR: At its meeting of November 9, 2017, the City Planning Commission approved a mixed-use development consisting of a 300-room hotel, 435 residential units, and 58,959 square feet of commercial uses at 1020 South Figueroa Street.

ZA-2015-3169-CUB – On April 1, 2016, the Zoning Administrator approved a conditional use permit to allow the sale and dispensing of a full line of alcoholic beverages for on-site consumption within an 18 story hotel.

CPC-2015-4557-MCUP-CUX-ZV-TDR-SPR: On December 16, 2015, an application for 374 residential units, 373 hotel rooms, 33,498 square feet of office, 10,801 square feet of conference center, and 65,074 square feet of commercial space, was filed for the property located at 813 West Olympic Boulevard. This case is currently pending.

CPC-2015-1158-SN-TDR-MCUP-CUX-SPR - On November 9, 2017 the City Planning Commission approved a TFAR request from the LA Convention Center to subject site to allow an FAR of 8.03:1 in lieu of 6:1, Sign District, a Master Conditional Use Permit to allow on and off-sale of alcoholic beverages and with live entertainment, Site Plan Review approval , all in conjunction with the development of a mixed-use project consisting of a 300 room hotel, 435 residential units and 58,959 square feet of commercial uses.

ZA-2014-2221-ZV-SPR: On September 15, 2014, the Zoning Administrator approved multiple Zone Variances and Site Plan Review for the construction of the Metropolis project comprised of 1,250 residential condominiums, located at 811 Francisco Street.

ZA-2013-2284 – On October 20, 2014, the Zoning Administrator approved a Master Conditional Use Permit to allow for the sales and service of a full line of alcoholic beverages for on-site consumption, and live entertainment in conjunction with four separate venues to include a restaurant and club/lounge/bars located within the historic Variety Arts Building, proposed hours of operation will be from 7 am to 2 am daily and for alcohol service from 11 am to 2 am daily.

CPC-2012-849-GPA-VZC-SP-SN: On September 13, 2012, the City Planning Commission recommended that the City Council approve the demolition and replacement of the existing West Hall Building in the Convention Center and building a new multi-event center.

CPC-2006-7109- DA-SP-ZC – On December 2, 2006, the City Planning Commission approved a Development Agreement for the Los Angeles Sports and Entertainment District Specific Plan.

ZA-2002-4583 – On January 22, 2003, the Zoning Administrator approved a conditional use permit for a full line of alcoholic beverages for an existing restaurant.

CPC-2000-5433 – On December 11, 2003, the City Planning Commission approved a Development Agreement for the Los Angeles Sports and Entertainment District Specific Plan.

ZA-1999-820-CUZ – On March 16, 2000, the Zoning Administrator approved a wireless telecommunications facility in the C2-4D-Zone.

Project Analysis (site planning and architectural design)*Citywide Design Guidelines*

The Citywide Design Guidelines, adopted by the City Planning Commission, establish a baseline for urban design expectations and present overarching design themes and best practices for residential, commercial, and industrial projects. Commission policy states that approved projects should either substantially comply with the Guidelines or achieve the same objectives through alternative methods, and that the Guidelines may be used as a basis to condition an approved project. These design guidelines focus on several areas of opportunity for attaining high quality design in mixed-use projects, including: enhancing the quality of the pedestrian experience along commercial corridors; nurturing an overall active street presence; establishing appropriate height and massing within the context of the neighborhood; maintaining visual and spatial relationships with adjacent buildings; and optimizing high quality infill development that strengthens the visual and functional quality of the commercial environment.

The Olympic Tower project achieves these goals through several features. The residential, commercial, retail, office, hotel and restaurant uses proposed for the infill site are substantially compatible with the surrounding uses. Further, the siting of ground floor and podium level retail and ballroom uses along each of Figueroa Street, and Olympic Boulevard street frontages will activate the street, consistent with the guidelines. The project has located a publicly accessible arcade along both Olympic Boulevard and Figueroa Street, consistent with the Guidelines, by activating the streets surrounding the Project Site, and providing additional pedestrian realm amenities. The Project has located primary entrances for pedestrians that are safe, easily accessible, and a short distance from transit stops and will result in a more cohesive and vibrant street environment along Olympic Boulevard when compared to the existing conditions. The Project will also include bicycle parking, with a bicycle valet on the 1st basement floor and easily accessible by pedestrians and cyclists. The Project further enhances the pedestrian streetscape environment by improving the 13-foot sidewalk along Olympic Boulevard and the 13-foot sidewalk along Figueroa Street with a 10-foot private easement for public use, complying with the Downtown Design Guidelines.

Located in one of the most prominent and visible corners of Downtown Los Angeles, Olympic Tower will house a variety of uses (Retail, Office, Hotel and Condominiums) compatible with the existing urban environment. The project has been conceived (along Olympic Boulevard) with a sweeping inward “bent” feature facing Downtown's Entertainment area (LA Live, Staples Center, Microsoft Theatre, etc.) and is designed to be modern in style, while creating south facing landscaped elevated open atriums at the condominium amenities and hotel levels. The 57 story building is designed with vertical gardens where real vegetation grows along its structural grid contained within its double-paned glass creating a visually interesting development, and integrating the tower into the changing Downtown Skyline. At the street level the project is pedestrian friendly, utilizing the side alley to provide all the vehicular access to the different functions and levels while maintaining the sidewalks and parkways along Figueroa Street and Olympic Boulevard for the exclusive uses of pedestrian traffic and potentially sidewalk seating. The retail ground level and upper two floors of commercial use are designed to encourage the flowing connection to the pedestrian traffic by weaving its storefronts and accesses into the main lobbies.

The structural component is part of the architectural expression, wrapping the building around its entire perimeter, eliminating interior columns at the free standing tower and culminating at the roof top with a structural trellis tying the vertical structural grid. The underground parking (directly accessed from the side alley) is dedicated solely to the residential units while the above ground parking garage provides 24-hour valet service for the commercial retail and office uses and the hotel use; both parking areas also provide valet bicycle parking. The building design recognizes

its adjacency to the historic Hotel Figueroa by detaching the tower above the hotel roof level, and the Olympic Tower's Figueroa Street facade is designed in a more sensitive scale making the first levels of the tower also more compatible with the scale of Hotel Figueroa's architectural rhythm.

The hotel, office, residential and conference center small access lobbies are located at the ground floor, while the large spaces dedicated to lobbies for each use and the amenities are provided in the upper floors connected through exclusive elevators. Pursuant to the city's regulations allowing the substitution of helipads by special Fire access requirements, the building design provides a fire elevator all the way up to the top of the building.

Future development planned for the Site, as listed in off-site related cases consist of mixed-use developments ranging from 18 to 66 stories in height, include hotel, residential, and commercial uses, and are architecturally modern in their design. Furthermore, the surrounding area is zoned C2-4D or LASED, with Height District 4 not restricting height, and LASED restrictions ranging from 150-660 feet. Both zones allow for intense uses, and varied building forms, and the area is not homogenous in character, nor solely residential; therefore, the project would not conflict with future development and complement existing uses.

Parking Podium

The Project proposes a twelve-story podium, including eight levels of above-grade parking. The above ground parking levels will be on levels 4 through 12. Levels 4 and 5 will be devoted to automobile parking and will be wrapped by glass and levels 6 through 12 will be wrapped with office uses along Figueroa Street and Olympic Boulevard. Along the Cottage Place alley the parking podium will be wrapped by corrugated metal, with an aluminum louvered profile and no visual penetration from the outside into the inside of the garage.

City Center Redevelopment Plan

In addition, the Site is located within the City Center Redevelopment Project Area. The Redevelopment Plan for the project area was adopted on May 15, 2002, with an end date of May 15, 2032. The City Center Redevelopment Plan contains numerous objectives, with which the Project complies, including: developing and revitalizing downtown as a major center of the metropolitan region; preparing the Central City to accept regional growth and development; promoting the development of a full range of uses and employment opportunities; and emphasizing green spaces and public amenities. The land use designations and regulations for any property in the Redevelopment Plan Area defer to and are superseded by the applicable City General Plan, Community Plan and Zoning Ordinance land use designations and regulations. Therefore, the project would be consistent with the Plan objectives and any proposed plan amendments or zoning regulations applicable to the Site would be reflected and incorporated into the Redevelopment Plan.

Walkability Checklist

The Citywide Design Guidelines complement and expand upon the Walkability Checklist, which provides guidance and tools for encouraging pedestrian activity, promoting high quality urban form, and place-making within project sites. The Checklist reinforces many of the same principles identified in the Citywide Design Guidelines, and addresses such topics as building orientation, building frontage, landscaping, off-street parking and driveways, building signage, and lighting within the private realm; and sidewalks, street crossings, on-street parking, and utilities in the public realm.

The proposed project is consistent with the goals and implementation strategies identified in the Walkability Checklist. In general, the site design creates active environments by supporting a

variety of pedestrian activities, including a landscaped arcade along Figueroa Street and Olympic Boulevard. The building is oriented towards and easily accessible from adjacent public streets and open spaces. The project incorporates different textures, colors, materials, and distinctive architectural features that add visual interest, and adds scale and interest to building façades by articulated massing. Driveways are limited to Cottage Place in order to reduce pedestrian conflicts along Olympic Boulevard and Figueroa Street. Improvements to the public right-of-ways include improved and expanded sidewalks, new street trees, and street lighting. These on- and off-site project features and improvements will contribute to the creation of a safe and engaging pedestrian environment, and will enrich the quality of the public realm around the project site, consistent with the objectives of the Walkability Checklist.

Urban Design Studio Professional Volunteer Program

The Project was reviewed by Urban Design Studio staff and the Professional Volunteer Program (PVP) on November 7, 2017, resulting in the following comments with regard to the architectural design of the project:

Comments by Urban Design Studio/Architects/Volunteer staff:

- Consider revising Bicycle access and circulation. How do you get a bike to bike parking? Through which elevator? Is there a bike parking valet? Is there directional signage for parking on ground floor? Where is short-term bicycle parking?
- Consider where Sage glass and photovoltaic panels be placed? Not very clear in plans.
- Consider improving the loading area. Loading area is far too small for the programming proposed.
- Consider moving Greenwall closer to the ground floor to activate the area/arcade.
- Consider wayfinding signage for commercial uses, parking, etc.

In response to the PVP comments received, the Applicant has provided clarification on the drawings and additional explanation of the Project's design characteristics. The Applicant submitted an updated plan set dated January 30, 2019 which clarifies the following information:

- Residents will have exclusive access to amenity decks on the 13th, 56th and 57th floors. With respect to the 56th and 57th floors, the concept is to reserve these areas to be accessed exclusively by Penthouse (Floors 48 – 55/the 2- and 3-bedroom unit) owners.
- Following PVP review, and in compliance with the new (2018) bicycle parking ordinance, the project's bicycle parking was revised (See, in particular, pp. A1B1, A1B2)
 - 1st Basement Level accommodates all (72) Short-Term Bicycle Parking and 33 Long-Term Ones.
 - At 2nd Basement Level we have introduced an L shape to the Bicycle storage space to hold 204 Long-Term Bicycle Parking Spaces.
 - Specific Path is designated outside the bicycle storage space for easy elevator access. Lockers and shower are integrated in the bicycle storage space.
- The majority of the building will be SageGlass except for building elements closer to the ground floor that do not need or require the performance characteristics of SageGlass.
- The City has reviewed the project and found it (loading area) to be acceptable. See Los Angeles Department of Transportation report (DOT Case No. CEN 15-43386, dated 6/12/17, especially at p. 6 "Project Access and Circulation" and Attachment 3).

- The project is conceived as a dignified, sleek structure, with an overall consistent façade that begins at the sidewalk and ties at the rooftop. In fulfillment of this design intent, it is important that the glazing starts at the sidewalk and moves all the way to the tower's pinnacle. To add interest, and to interact with the exuberance of L.A. Live and the entertainment district to the south of the project, a greenwall has been integrated – but purposely confined to - the mid-tower atrium. Therefore, this suggestion would be inconsistent with the design intent.
- The project will have comprehensive and appropriate wayfinding signage, per City code.

Transfer of Floor Area (TFAR) Public Benefits Transfer Plan

As previously described, the Project Site is located within the Central City Community Plan area, designated as Regional Center Commercial with a corresponding zone of C2-4D, subject to the “D” Limitations contained within Ordinance No. 164,307, Subarea 1920. The “D” Limitation restricts the floor area of buildings to a maximum of six times the buildable area, or a 6:1 FAR. Projects may exceed the permitted FAR through rehabilitation of existing buildings, consistent with provisions of the redevelopment plan, or by receiving approval of a transfer of floor area through a process adopted by the City Council.

The Project proposed to demolish an existing 16,329 square-foot car wash and restaurant, and associated surface parking lot for the construction of a new mixed-use development. The Applicant has requested a transfer of greater than 50,000 square feet of floor area from the City of Los Angeles-owned Convention Center (Donor Site) to the project site (Receiver Site). Approval of the Transfer would result in a FAR of 13:1 in lieu of 6:1 FAR, a transfer of up to 455,161 square feet, to permit a maximum of 779,173 square feet of total floor area. As part of the request, the Applicant has submitted a Transfer Plan indicating the proposed distribution of the Public Benefit Payment required pursuant to LAMC Section 14.5.9. The Public Benefit Payment requires that at least 50 percent of the payment be provided as a cash payment by the Applicant to the Public Benefit Trust Fund, unless otherwise approved by City Council. The remaining 50 percent of the payment may be provided by the direct provision of Public Benefits by the Applicant.

Pursuant to LAMC Section 14.5.5, DCP staff engaged in a TFAR Early Consultation Session meeting on September 20th, 2018, with representatives from the Mayor's Office, and the Office of the Chief Legislative Analyst to discuss any development issues regarding the Project, including parking and transportation requirements, transfers, and public benefits. The committee reviewed the public benefits initially proposed by the Applicant and identified three potential areas for the direct provision of public benefits: affordable housing, public open space and homeless services. Based on the issues discussed at the Early Consultation Session meetings, the Applicant has proposed the following Transfer Plan:

Olympic Tower Public Benefit Payment Transfer Plan		
Total Public Benefit Payment		\$18,027,494.33
50% Public Benefit Cash Payment		\$9,013,747.17
50% Public Benefit Direct Provision		\$9,013,747.17
Allocation of Public Benefit Direct Provision		
Los Angeles Housing and Community Investment Department	50%	\$4,506,873.58

Department of Recreation and Parks (Redevelopment of Pershing Square Park)	50%	\$4,506,873.58
Total	100%	\$18,027,494.33

Conclusion

The project is a mixed-use project that provides 374 new multi-family residential units on a site that currently does not provide any housing units. The project will also provide up to 65,074 square feet of commercial retail and restaurant uses that will provide beneficial services to project residents and to the surrounding community. It also provides a 373 room hotel directly adjacent to the Los Angeles Sports and Entertainment District, and within walking distance to the Los Angeles Convention Center. The project will improve and enhance the pedestrian environment on the project site by replacing an existing one-story carwash and restaurant with a mixed-use project that provides ground floor retail and a publicly accessible arcade along Olympic Boulevard and Figueroa Street, and bicycle parking. The project will create a consistent street wall, scale, and pedestrian-oriented street front along Olympic Boulevard, and Figueroa Street. The project will also improve the streetscape around the project site consistent with the streetscape plan for the Los Angeles Sports and Entertainment District. It will develop a mixed-use development in close proximity to transit options, the Los Angeles Sports and Entertainment District, and the Downtown area, locating High density housing and commercial space as directed by City plans and policies, pursuant to the parcel zoning, and in line with State and City climate and sustainability plans. Additionally it will provide additional hotel rooms and employment opportunities in the Los Angeles Sports and Entertainment District and Downtown Area. The proposed development is compatible with the site's Regional Center Commercial land use designation and the policies of the General Plan. The requested Transfer of Floor Area, Master Conditional Use Permit, Conditional Use for Live Entertainment dancing, Director's Determination to allow outdoor dining, Director's Determination to provide less than one on-site tree per four residential units and to allow short-term and long-term bicycle parking to be located on the second level of underground parking, and Site Plan Review Deviation, will allow for greater housing options in the Central City Area, and a range of commercial options, including restaurants, and a hotel. The requested Transfer of Floor Area, Master Conditional Use Permit, and Site Plan Review are in conformance with the public necessity, convenience, general welfare, and good zoning practice. Staff recommends approval of the attached entitlements which support the policies of the Land Use Element of the General Plan.

The project results in a development that includes a beneficial and complementary mix of uses that create active and safe pedestrian environments, and offer a variety of amenities and open space features. The project's location, uses, height, and other features will be compatible with the surrounding neighborhood, and will not adversely affect public health, welfare, and safety. Furthermore, overriding considerations of economic, social, aesthetic, and environmental benefits for the project justify adoption of the project and utilization of the previously certified EIR. Based on the information submitted, the testimony received at the public hearing, the analysis in the EIR, and the whole of the record, the Department of City Planning is recommending that the City Planning Commission approve Planning Staff's recommended actions as stated above.

CONDITIONS OF APPROVAL

Pursuant to Sections 12.24, 14.5, 16.05 and 12.21 of the Los Angeles Municipal Code, the following conditions are hereby imposed upon the use of the subject property:

1. **Site Development.** The use and development of the property shall be in substantial conformance with the plot plan submitted with the application and marked Exhibit "A", dated August 22, 2019, except as may be revised as a result of this action. No change to the plans will be made without prior review by the Department of City Planning, and written approval by the Director of Planning, with each change being identified and justified in writing. Minor deviations may be allowed in order to comply with provisions of the Municipal Code, the subject conditions, and the intent of the subject permit authorization.
2. **Development Services Center.** Prior to sign-off on building permits by the Department of City Planning's Development Services Center for the project, the Department of City Planning's Major Projects Section shall confirm, via signature, that the project's building plans substantially conform to the conceptual plans stamped as Exhibit "A", as approved by the City Planning Commission.

Note to Development Services Center. The plans presented to, and approved by, the City Planning Commission (CPC) included specific architectural details that were significant to the approval of the project. Plans submitted at plan check for condition clearance shall include a signature and date from Major Projects Section planning staff to ensure plans are consistent with those presented at CPC.

3. **Uses.** The mixed-use development shall consist of up to 374 residential condominiums, 373 hotel rooms, and up to 65,074 square feet of commercial space. The project consists of approximately 779,173 square feet of floor area.
4. **Transfer of Floor Area Rights.**
 - a. **Floor Area.** The Development shall not exceed a maximum Floor Area Ratio (FAR) of 13:1 and a total floor area of 779,173 square feet. The Transfer Payment and Public Benefit Payment shall be pro-rated to the amount of TFAR being acquired in the event the maximum amount of TFAR is not required. The base lot area used to calculate the base floor area shall be 37,031 square feet with a 6:1 FAR. Changes to the Project that result in a 20 percent decrease in floor area, or more, shall require new entitlements.
 - b. **TFAR Transfer Payment.** The Project is subject to and shall pay a TFAR Transfer Payment in conformance with Section 14.5.6 through 14.5.12 of the Code. Such payment shall be based on the actual amount of floor area transferred to the Project site.
 - i. The total amount of floor area authorized to be transferred from the Los Angeles Convention Center by this action shall not exceed 455,161 square feet. The total floor area of the Project Site (Receiver Site) shall not exceed 779,173 square feet.
 - ii. The Applicant shall provide a TFAR Transfer Payment consistent with LAMC Section 14.5.10 in the amount of \$5 per square foot, or \$2,275,805 for the transfer of 455,161 square feet from the Los Angeles Convention Center located at 1201 South Figueroa Street (Donor Site) to the Project Site (Receiver Site).

- iii. Approximately 101,826 square feet from the site at 320 W. 3rd Street (Assessor Parcel Number 5149-015-035) shall be transferred to the subject project by way of a private transfer. This floor area shall not be utilized at 320 W. 3rd Street. Prior to the issuance of any permits relative to this matter, an agreement concerning this condition shall be recorded onto the property at 320 W. 3rd Street. The agreement shall run with the land and shall be binding on any subsequent owners, heir, or assigns. Further, the agreement must be submitted to the Planning Department for approval before being recorded. After recordation, a Certified Copy bearing the Recorder's number and date must be given to the City Planning Department for attachment to the subject case file. The Applicant shall also submit documentation of the existing floor area currently utilized at 320 W. 3rd Street, to be verified by the Department of Building and Safety.
- c. **Public Benefit Payment.** The Project is subject to and shall pay a Public Benefit Payment in conformance with Section 14.5.6 through 14.5.12 of the Code.
- i. The Applicant shall provide a Public Benefit Payment consistent with LAMC Section 14.5.9 in the amount of \$18,027,494.33 provided that at least 50 percent (or \$9,013,747.17) of the Public Benefit Payment consist of cash payment by the Applicant to the Public Benefit Trust Fund. Direct provision payments shall be paid directly to the recipients and not to the City of Los Angeles. Proof shall be provided in the form of a cleared check or bank statement and a letter signed by the Executive Director of each organization. Consistent with the TFAR Ordinance, the Project shall provide 50 percent (or \$9,013,747.17) of the Public Benefit Payment by directly providing the following public benefits:
 - 1. A payment to the Los Angeles Housing and Community Investment Department in the amount of \$4,506,873.58 (25%). The funds shall be utilized for construction and operation of affordable housing developments.
 - 2. A payment to Pershing Square Improvement Fund, in the amount of \$4,506,873.58 (25%). The funds shall be utilized for the revitalization of Pershing Square.
 - ii. At the time of issuance of the Certificate of Occupancy for the Project, the Applicant shall provide an update to the file from each recipient of direct provisions detailing how the money has been spent thus far.
 - iii. The Applicant shall pay the required Public Benefit Payment, less the cost of the Direct Provision of Public Benefits, in cash to the Public Benefit Trust Fund, pursuant to the terms of Transfer of Floor Area Rights Ordinance No. 181,574, Article 4.5 of the LAMC. The Public Benefit Payment proof of cash payment and direct provision of public benefits is required upon the earliest occurrence of either:
 - 1. The issuance of the building permit for the Project; or
 - 2. Twenty-four months after the final approval of the Transfer and the expiration of any appeals or appeal period; should the Applicant not make the required payments within the specified time, subject approval shall expire, unless extended by the Director in writing.

5. **Height.** The proposed buildings shall be limited to a height of up to 742 feet and 1 inch consistent with Exhibit A.
6. **Sustainability.**
 - a. The Project shall comply with the Los Angeles Municipal Green Building Code, Section 99.05.211, to the satisfaction of the Department of Building and Safety.
 - b. The Project shall comply with the Los Angeles Municipal Green Building Code, Section 99.05.211, to the satisfaction of the Department of Building and Safety.
 - c. **Solar and Electric Generator.** Where power poles are available, electricity from power poles and/or solar-powered generators rather than temporary diesel or gasoline generators shall be used during construction. In particular, solar-powered generators shall be used for the construction trailer(s) on-site.
7. **Parking**
 - a. **Vehicle Parking.** The minimum number of residential and commercial automobile parking spaces shall be provided as required by LAMC Section 12.21 A.4(a), (i), and (p) pursuant to a deviation granted by the Advisory Agency.
 - b. **Bicycle Parking.** Bicycle parking shall be provided consistent with Ordinance No. 185,480, which amended Sections 12.03, 12.21 and 12.26 of the Los Angeles Municipal Code to update the bicycle parking regulations, effective on May 9, 2018, with the exception of the alternative bicycle siting design granted herein pursuant to the Director's Determination.
 - c. Bicycle valet service will be provided for residents, hotel guests, restaurant patrons and the general public 24 hours a day, seven days a week. An on-site designated pick-up/drop-off area will be located on the basement floor accessible by elevator as designated on Exhibit A (Site Plans).
 - d. Prior to the issuance of a building permit, the driveway and parking plan shall be submitted for review and approval to the Department of Transportation.
8. **Electric Vehicle Parking.** The project shall include at least 20 percent of the total code-required parking spaces capable of supporting future electric vehicle supply (EVSE). Plans shall indicate the proposed type and location(s) of EVSE and also include raceway method(s), wiring schematics and electrical calculations to verify that the electrical system has sufficient capacity to simultaneously charge all electric vehicles at all designated EV charging locations at their full rated amperage. Plan design shall be based upon Level 2 or greater EVSE at its maximum operating ampacity. In addition, five percent of the total code required parking spaces shall be further provided with EV chargers to immediately accommodate electric vehicles within the parking areas. When the application of either the required 20 percent or five percent results in a fractional space, round up to the next whole number. A label stating "EVCAPABLE" shall be posted in a conspicuous place at the service panel or subpanel and next to the raceway termination point.

At least 5 percent of the total code-required parking spaces shall be equipped with EV charging stations. Plans shall indicate the proposed type and location(s) of charging stations. Plan design shall be based on Level 2 or greater EVSE at its maximum operating capacity. When the application of the 5-percent requirement results in a fractional space, round up to the next whole number.

9. Parking Podium.

- a. Any above-grade parking structure shall be designed to be utilized and easily repurposed to other uses, including gallery or event spaces.
 - b. The height of the parking level shall have sufficient clearance to be adaptable to non-parking uses. Once converted, the building shall permit a minimum floor to ceiling height of nine feet for commercial uses and eight feet for residential uses.
 - c. Parking structures or that portion of a building or structure that is used for parking at grade or above grade shall be designed to minimize vehicle headlight and parking structure interior lighting impacts (“spillover”) on adjacent streets and properties.
10. Prior to the issuance of the building permit, a copy of the letter of decision for Case No.VTT-73966 shall be submitted to the satisfaction of the Development Services Center.
11. **Landscaping.** Prior to the issuance of a building permit, a landscape and irrigation plan shall be submitted to the Department of City Planning for approval. The landscape plan shall be in substantial conformance with the landscape plan stamped Exhibit A.
 - a. **Tree Wells.**
 - i. The minimum depth of tree wells shall be as follows:
 1. Minimum depth for trees shall be 42 inches.
 2. Minimum depth for shrubs shall be 30 inches.
 3. Minimum depth for herbaceous plantings and ground cover shall be 18 inches.
 4. Minimum depth for an extensive green roof shall be three inches.
 - ii. The minimum amount of soil volume for tree wells shall be based on the size of the tree at maturity as follows:
 1. 600 cubic feet for a small tree (less than 25 feet tall at maturity).
 2. 900 cubic feet for a medium tree (25-40 feet tall at maturity).
 3. 1,200 cubic feet for a large tree (more than 40 feet tall at maturity).
 - b. Any trees that are required pursuant to LAMC Section 12.21 G and are planted on any podium or deck shall be planted in a minimum three-foot planter.
12. **Downtown Design Guide.** Plans shall be revised to reflect that the Project is consistent with the following:
 - a. Street trees shall be spaced not more than an average of 25 feet on center and shall comply with Downtown Design Guide Section 9.F.
 - b. Continuous landscaped parkways shall be provided along Olympic Boulevard and Figueroa Street, where feasible. Where there is curbside parking, one walkway for each one or two parking spaces shall be provided through the parkway. If landscaped parkways are not feasible, the trees shall be planted in tree wells designed to the standards identified in the Downtown Design Guide, a minimum of 7’ wide.
 - c. Exterior lighting for the building and landscaping shall comply with Downtown Design Guide Section 8.F.
 - d. A master sign plan for the entire project shall be submitted to planning staff in the Major Projects Section prior to final clearance. The master sign plan shall identify all sign types that can be viewed from the street, sidewalk or public right-of-way and shall comply with Downtown Design Guide Section 10.

13. **Stormwater/irrigation.** The project shall implement on-site stormwater infiltration as feasible based on the site soils conditions, the geotechnical recommendations, and the City of Los Angeles Department of Building and Safety Guidelines for Storm Water Infiltration. If on-site infiltration is deemed infeasible, the project shall analyze the potential for stormwater capture and reuse for irrigation purposes based on the City Low Impact Development (LID) guidelines.
14. **Trash/Storage.**
 - a. All trash collection and storage areas shall be located on-site and not visible from the public right-of-way.
 - b. Trash receptacles shall be stored in a fully enclosed building or structure, constructed with a solid roof, at all times.
 - c. Trash/recycling containers shall be locked when not in use.
15. **Lighting**
 - a. Outdoor lighting shall be designed and installed with shielding, such that the light source cannot be seen from adjacent residential properties, the public right-of-way, nor from above.
 - b. Areas where nighttime uses are located shall be maintained to provide sufficient illumination of the immediate environment so as to render objects or persons clearly visible for the safety of the public and emergency response personnel.
 - c. All pedestrian walkways, storefront entrances, and vehicular access ways shall be illuminated with lighting fixtures.
 - d. Lighting fixtures shall be harmonious with the building design. Wall mounted lighting fixtures to accent and complement architectural details at night shall be installed on the building to provide illumination to pedestrians and motorists.
16. **Glare.** The exterior of the proposed structure shall be constructed of materials such as, but not limited to, high-performance and/or non-reflective tinted glass (no mirror-like tints or films) and pre-cast concrete or fabricated wall surfaces to minimize glare and reflected heat.
17. **Reflectivity.** Glass used in building façades shall be non-reflective or treated with a non-reflective coating in order to minimize glare from reflected sunlight.
18. **Noise.** All exterior windows having a line of sight of an Avenue (Major or Secondary Highway) shall be constructed with double-pane glass and use exterior wall construction which provides a Sound Transmission Coefficient (STC) value of 50, as determined in accordance with ASTM E90 and ASTM E413, or any amendment thereto. Or, the applicant, as an alternative, may retain an acoustical engineer to submit evidence, along with the application for a building permit, any alternative means of sound insulation sufficient to mitigate interior noise levels below a CNEL of 45 dBA in any habitable room.
19. **Mechanical Equipment.** Any structures on the roof, such as air conditioning units and other equipment, shall be fully screened from view of any abutting properties and the public right-of-way. All screening shall be setback at least five feet from the edge of the building.

20. **Solar Roof Panels.** The project shall provide photovoltaic panels as shown on the roof plan on page A100 of Exhibit A as part of an operational photovoltaic system to be maintained for the life of the project.
21. **Utilities.** All utilities shall be fully screened from view of any abutting properties and the public right-of-way.
22. **Signage.** There shall be no off-site commercial signage on construction fencing during construction.
23. Prior to the issuance of the building permit, a copy of the letter of decision for Case No.VTT-73966 shall be submitted to the satisfaction of the Development Services Center.
24. **Graffiti.** All graffiti on the site shall be removed or painted over to match the color of the surface to which it is applied within 24 hours of its occurrence.
25. A copy of the first page of this grant and all Conditions and/or any subsequent appeal of this grant and its resultant Conditions and/or letters of clarification shall be printed on the building plans submitted to the Development Services Center and the Department of Building and Safety for purposes of having a building permit issued.

Master Conditional Use for the Sale and Dispensing of Alcoholic Beverages

26. All other use, height and area regulations of the Municipal Code and all other applicable government/regulatory agencies shall be strictly complied with in the development and use of the property, except as such regulations are herein specifically varied or required.
27. The use and development of the property shall be in substantial conformance with the plot plan and floor plan submitted with the application and marked Exhibit A, except as may be revised as a result of this action.
28. All graffiti on the site shall be removed or painted over to match the color of the surface to which it is applied within 24 hours of its occurrence.
29. A copy of the first page of this grant and all Conditions and/or any subsequent appeal of this grant and its resultant Conditions and/or letters of clarification shall be printed on the building plans submitted to the Department of City Planning and the Department of Building and Safety for purposes of having a building permit issued at any time during the term of this grant.
30. The authorized use shall be conducted at all times with due regard for the character of the surrounding district, and the right is reserved to the Zoning Administrator to impose additional corrective Conditions, if, in the Zoning Administrator's opinion, such Conditions are proven necessary for the protection of persons in the neighborhood or occupants of adjacent property.

Authorized herein is the sale, dispensing, and consumption of a full line of alcoholic beverages for on-site and off-site consumption in conjunction with:

- a. On-site consumption for hotel (including, but not limited to, lobby, lobby bar, pool/pool deck, spa, etc. and portable units to serve alcohol for on-site consumption anywhere within the hotel use)
- b. On-site consumption for mini-bars within each hotel room or suite

- c. On-site consumption for up to two (2) restaurants or bars within the hotel area
 - d. On-site consumption for the conference center or ballrooms within the Project site
 - e. On-site consumption for condominium (including, but not limited to, lobby, lobby bar, pools, pool decks, outdoor recreational space, sky lounge, etc.)
 - f. On-site consumption for up to ten (10) restaurants or bars located anywhere within the commercial or office areas of the Project, including, but not limited to, outside areas, sidewalks, or rooftop areas, and
 - g. Off-site consumption for up to four (4) retail uses located anywhere within the Project site, including, but not limited to, the hotel, residential, or commercial uses.
31. **Plan Approval (MPA) Requirement.** Each individual venue shall be subject to a Master Plan Approval (MPA) determination pursuant to Section 12.24-M of the Los Angeles Municipal Code in order to implement and utilize the Master Conditional Use authorization granted. The purpose of the Master Plan Approval determination is to review each proposed venue in greater detail and to tailor site-specific conditions of approval for each of the premises including but not limited to hours of operation, seating capacity, size, security, live entertainment, the length of a term grant and/or any requirement for a subsequent MPA application to evaluate compliance and effectiveness of the conditions of approval. The Zoning Administrator may impose more restrictive or less restrictive conditions on each individual tenant at the time of review of each Plan Approval application. A public hearing for any Master Plan Approval (MPA) request may be waived at the discretion of the Chief Zoning Administrator.
32. A camera surveillance system shall be installed and operating at all times to monitor the interior, entrance, exits and exterior areas, in front of and around the premises. Recordings shall be maintained for a minimum period of 30 days.
33. **STAR/LEAD Training.** Within the first six months of operation, all employees involved with the sale of alcohol shall enroll in the Los Angeles Police Department "Standardized Training for Alcohol Retailers" (STAR) or Department of Alcoholic Beverage Control "Licensee Education on Alcohol and Drugs" (LEAD) training program. Upon completion of such training, the applicant shall request the Police Department or Department of Alcoholic Beverage Control to issue a letter/certificate identifying which employees completed the training. Thereafter, STAR/LEAD training shall be conducted for all new hires within three (3) months of their employment.
34. The Applicant shall be responsible for monitoring both patron and employee conduct on the premises and within the parking areas under his/her control to assure such conduct does not violate applicable laws.
35. Loitering is prohibited on the premises or the area under the control of the applicant. "No Loitering or Public Drinking" signs shall be posted in and outside of the subject facility.
36. At least one on-duty manager with authority over the activities within the facility shall be on the premises during business hours. The on-duty manager's responsibilities shall include the monitoring of the premises to ensure compliance with all applicable State laws, Municipal Code requirements and the conditions imposed by the Department of Alcoholic Beverage Control (ABC) and the conditional use herein. Every effort shall be undertaken in managing the subject premises and any exterior area over which the building owner exercises control to discourage illegal and criminal activities.

37. The Applicant shall be responsible for maintaining the premises and adjoining sidewalk free of debris or litter.
38. An electronic age verification device shall be purchased and retained on the premises to determine the age of any individual and shall be installed on at each point-of-sales location. This device shall be maintained in operational condition and all employees shall be instructed in its use.
39. The restaurant establishments shall be maintained as a bona fide eating places (restaurants) with an operational kitchen and shall provide a full menu containing an assortment of foods normally offered in such restaurants. Food service shall be available at all times during operating hours. The establishment shall provide seating and dispense food and refreshments primarily for consumption on the premises and not solely for the purpose of food takeout or delivery.
40. The owner or the operator shall comply with California Labor Code 6404.5 which prohibits the smoking of tobacco or any non-tobacco substance, including from electronic smoking devices or hookah pipes, within any enclosed place of employment.
41. All deliveries shall be made in the designated on-site loading area. No loading or unloading of deliveries shall be permitted along Olympic Boulevard or Figueroa Street.
42. Trash pick-up, compacting, loading and unloading and receiving activities shall be limited to 7:00 a.m. to 6:00 p.m. Monday through Friday and 10:00 a.m. to 4:00 p.m. on Saturday. No deliveries or trash pick-up shall occur on Sunday.
43. The outside disposal of glass bottles and containers shall only occur between the hours of 7:00 a.m. to 6:00 p.m.
44. **Designated Driver Program.** Prior to the utilization of this grant, the applicant shall establish a "Designated Driver Program" which shall include, but not be limited to, signs/cards, notation on websites/social media, notifying patrons of the program. The signs/cards/website/social media shall be visible to the customer and posted or printed in prominent locations or areas. These may include signs/cards on each table, at the entrance, at the host station, in the waiting area, at the bars, or on the bathrooms, or a statement in the menus, a website, or on social media.
45. Any music, sound or noise which is under control of the applicant shall not violate Sections 112.06 or 116.01 of the Los Angeles Municipal Code (Citywide Noise Ordinance). At any time, a City representative may visit the site during operating hours to measure the noise levels. If, upon inspection, it is found that the noise level exceeds those allowed by the citywide noise regulation, the owner/operator will be notified and will be required to modify or eliminate the source of the noise or retain an acoustical engineer to recommend, design and implement noise control measures within property such as, noise barriers, sound absorbers or buffer zones.
46. There shall be no Adult Entertainment of any type pursuant to LAMC Section 12.70.
47. **Private Events.** Any use of the restaurant for private events, including corporate events, birthday parties, anniversary parties, weddings or other private events which are not open to the general public, shall be subject to all the same provisions and hours of operation stated herein.

48. **Cafe and Entertainment Permit.** A Cafe and Entertainment Permit shall be obtained from the Los Angeles Police Commission. A copy shall be submitted to the Department of City Planning for inclusion in the case file.
49. The applicant / operator shall obtain permits from the Los Angeles Police Permit Processing Section, pursuant to LAMC Sections 103.102 and 103.106. Copies of said permits shall be submitted to the Department of City Planning **within 30 days of their issuance** for inclusion in the case file.
50. Dancing shall be permitted from 9:00 AM until 2:00 AM, seven nights a week; Monday through Sunday, pursuant to a current Los Angeles Police Commission permit. **Prior to the utilization of this grant**, evidence of the permit shall be submitted to the Department of City Planning for inclusion in the case file.
51. **MViP – Monitoring Verification and Inspection Program.** At any time, before, during, or after operating hours, a City inspector may conduct a site visit to assess compliance with, or violations of, any of the conditions of this grant. Observations and results of said inspection will be documented and used to rate the operator according to the level of compliance. If a violation exists, the owner/operator will be notified of the deficiency or violation and will be required to correct or eliminate the deficiency or violation. Multiple or continued documented violations or Orders to Comply issued by the Department of Building and Safety which are not addressed within the time prescribed therein, may result in denial of future requests to renew or extend this grant.
52. Within 30 days of the effective date of this grant, a covenant acknowledging and agreeing to comply with all the terms and conditions established herein shall be recorded in the County Recorder's Office. The agreement (standard master covenant and agreement form CP-6770) shall run with the land and shall be binding on any subsequent owners, heirs or assigns. The agreement with the conditions attached must be submitted to the Development Services Center or the BESt (Beverage and Entertainment Streamlined Program) for approval before being recorded. After recordation, a certified copy bearing the Recorder's number and date shall be provided to the Development Services Center or BESt (Beverage and Entertainment Streamlined Program) for inclusion in the case file.
53. Should there be a change in the ownership and/or the operator of the business, the property owner and/or the business owner or operator shall provide the prospective new property owner and the business owner or operator with a copy of the conditions of this action prior to the legal acquisition of the property and/or the business. Evidence that a copy of this determination including the conditions required herewith has been provided to the prospective property owner and/or business owner/operator shall be submitted to the Department of City Planning in a letter from the new property owner and/or business owner or operator indicating the date that the new property owner and/or business owner or operator/management began and attesting to the receipt of this approval and its conditions. The new property owner and/or business owner or operator shall submit this letter to the Department of City Planning within 30 days of the beginning day of his/her new operation of the establishment along with any proposed modifications to the existing floor plan, seating arrangement or number of seats of the new operation.
54. Should there be a change in the ownership and/or the operator of the business, the Zoning Administrator reserves the right to require that the new owner or operator file a Plan Approval application, if it is determined that the new operation is not in substantial conformance with the approved floor plan, or the operation has changed in mode or character from the original approval, or if documented evidence be submitted showing a

continued violation(s) of any condition(s) of this grant resulting in a disruption or interference with the peaceful enjoyment of the adjoining and neighboring properties. The application, in association with the appropriate fees, and a 500-foot notification radius, shall be submitted to the Department of City Planning within 30 days of the date of legal acquisition by the new owner or operator. The purpose of the plan approval will be to review the operation of the premise and establish conditions applicable to the use as conducted by the new owner or operator, consistent with the intent of the Conditions of this grant. Upon this review, the Zoning Administrator may modify, add or delete conditions, and if warranted, reserves the right to conduct this public hearing for nuisance abatement/revocation purposes.

55. The authorized use shall be conducted at all times with due regard for the character of the surrounding district, and the right is reserved to the Zoning Administrator to impose additional corrective Conditions, if, in the Administrator's opinion, such Conditions are proven necessary for the protection of persons in the neighborhood or occupants of adjacent property.
56. The Zoning Administrator reserves the right to require that the owner or operator file a Plan Approval application, if it is determined that the new operation is not in substantial conformance with the approved floor plan, or the operation has changed in mode or character from the original approval, or if documented evidence be submitted showing a continued violation(s) of any condition(s) of this grant resulting in a disruption or interference with the peaceful enjoyment of the adjoining and neighboring properties. The application, in association with the appropriate fees shall be submitted to the Department of City Planning within 30 days of the date of legal acquisition by the new owner or operator. The purpose of the plan approval will be to review the operation of the premise and establish conditions applicable to the use as conducted by the new owner or operator, consistent with the intent of the Conditions of this grant. Upon this review, the Zoning Administrator may modify, add or delete conditions, and if warranted, reserves the right to conduct this public hearing for nuisance abatement/revocation purposes, pursuant to LAMC Section 12.27.1.
57. **Prior to the effectuation of this grant**, a covenant acknowledging and agreeing to comply with all the terms and conditions established herein shall be recorded in the County Recorder's Office. The agreement (standard master covenant and agreement form CP-6770) shall run with the land and shall be binding on any subsequent owners, heirs or assigns. The agreement with the conditions attached must be submitted to the Department of City Planning for approval before being recorded. After recordation, a certified copy bearing the Recorder's number and date shall be provided for inclusion in case file. Fees required per LAMC Section 19.01 E.(3) for Monitoring of Conditional Use Permits and Inspection and Field Compliance Review of Operations shall be paid to the City prior to the final clearance of this condition. Failure to record a covenant acknowledging and agreeing to comply with all the terms and conditions of the approved grant will result in non-effectuation of said grant.

Environmental Conditions

58. **Mitigation Monitoring Program.** The project shall be in substantial conformance with the mitigation measures in the attached MMP and stamped "Exhibit B" and attached to the subject case file. The implementing and enforcing agencies may determine substantial conformance with mitigation measures in the MMP. If substantial conformance results in effectively deleting or modifying the mitigation measure, the Director of Planning shall provide a written justification supported by substantial evidence as to why the mitigation measure, in whole or in part, is no longer needed and its effective deletion or modification will not result in a new significant impact or a more severe impact to a previously identified

significant impact.

If the project is not in substantial conformance to the adopted mitigation measures or MMP, a modification or deletion shall be treated as a new discretionary action under CEQA Guidelines, Section 15162(c) and will require preparation of an addendum or subsequent CEQA clearance. Under this process, the modification or deletion of a mitigation measure shall not require a Zone Change unless the Director of Planning also finds that the change to the mitigation measures results in a substantial change to the project or the non-environmental conditions of approval.

59. **Mitigation Monitor.** During the construction phase and prior to the issuance of building permits, the applicant shall retain an independent Construction Monitor (either via the City or through a third-party consultant), approved by the Department of City Planning, who shall be responsible for monitoring implementation of project design features and mitigation measures during construction activities consistent with the monitoring phase and frequency set forth in this MMP.

The Construction Monitor shall also prepare documentation of the applicant's compliance with the project design features and mitigation measures during construction every 90 days in a form satisfactory to the Department of City Planning. The documentation must be signed by the applicant and Construction Monitor and be included as part of the applicant's Compliance Report. The Construction Monitor shall be obligated to immediately report to the Enforcement Agency any non-compliance with the mitigation measures and project design features within two businesses days if the applicant does not correct the non-compliance within a reasonable time of notification to the applicant by the monitor or if the non-compliance is repeated. Such non-compliance shall be appropriately addressed by the Enforcement Agency.

60. **Tribal Cultural Resource Inadvertent Discovery.** In the event that objects or artifacts that may be tribal cultural resources are encountered during the course of any ground disturbance activities¹, all such activities shall temporarily cease on the project site until the potential tribal cultural resources are properly assessed and addressed pursuant to the process set forth below:

- Upon a discovery of a potential tribal cultural resource, the project Permittee shall immediately stop all ground disturbance activities and contact the following: (1) all California Native American tribes that have informed the City they are traditionally and culturally affiliated with the geographic area of the proposed project; (2) and the Department of City Planning at (213) 473-9723.
- If the City determines, pursuant to Public Resources Code Section 21074 (a)(2), that the object or artifact appears to be tribal cultural resource, the City shall provide any effected tribe a reasonable period of time, not less than 14 days, to conduct a site visit and make recommendations to the Project Permittee and the City regarding the monitoring of future ground disturbance activities, as well as the treatment and disposition of any discovered tribal cultural resources.

¹ Ground disturbance activities shall include the following: excavating, digging, trenching, plowing, drilling, tunneling, quarrying, grading, leveling, removing peat, clearing, pounding posts, augering, backfilling, blasting, stripping topsoil or a similar activity

- The project Permittee shall implement the tribe's recommendations if a qualified archaeologist, retained by the City and paid for by the project Permittee, reasonably concludes that the tribe's recommendations are reasonable and feasible.
 - The project Permittee shall submit a tribal cultural resource monitoring plan to the City that includes all recommendations from the City and any effected tribes that have been reviewed and determined by the qualified archaeologist to be reasonable and feasible. The project Permittee shall not be allowed to recommence ground disturbance activities until this plan is approved by the City.
 - If the project Permittee does not accept a particular recommendation determined to be reasonable and feasible by the qualified archaeologist, the project Permittee may request mediation by a mediator agreed to by the Permittee and the City who has the requisite professional qualifications and experience to mediate such a dispute. The project Permittee shall pay any costs associated with the mediation.
 - The project Permittee may recommence ground disturbance activities outside of a specified radius of the discovery site, so long as this radius has been reviewed by the qualified archaeologist and determined to be reasonable and appropriate.
 - Copies of any subsequent prehistoric archaeological study, tribal cultural resources study or report, detailing the nature of any significant tribal cultural resources, remedial actions taken, and disposition of any significant tribal cultural resources shall be submitted to the South Central Coastal Information Center (SCCIC) at California State University, Fullerton.
 - Notwithstanding the above, any information determined to be confidential in nature, by the City Attorney's office, shall be excluded from submission to the SCCIC or the general public under the applicable provisions of the California Public Records Act, California Public Resources Code, and shall comply with the City's AB 52 Confidentiality Protocols.
61. Archaeological Resources Inadvertent Discovery. In the event that any subsurface cultural resources are encountered at the project site during construction or the course of any ground disturbance activities, all such activities shall halt immediately, pursuant to State Health and Safety Code Section 7050.5. At which time the applicant shall notify the City and consult with a qualified archaeologist who shall evaluate the find in accordance with Federal, State, and local guidelines, including those set forth in the California Public Resources Code Section 21083.2 and shall determine the necessary findings as to the origin and disposition to assess the significance of the find. If any find is determined to be significant, appropriate avoidance measures recommended by the consultant and approved by the City must be followed unless avoidance is determined to be unnecessary or infeasible by the City. If avoidance is unnecessary or infeasible, other appropriate measures (e.g., data recovery, excavation) shall be instituted.
62. Paleontological Resources Inadvertent Discovery. In the event that any prehistoric subsurface cultural resources are encountered at the project site during construction or the course of any ground disturbance activities, all such activities shall halt immediately, at which time the applicant shall notify the City and consult with a qualified paleontologist to assess the significance of the find. In the case of discovery of paleontological resources, the assessment shall be done in accordance with the Society of Vertebrate Paleontology standards. If any find is determined to be significant, appropriate avoidance measures recommended by the consultant and approved by the City must be followed unless avoidance is determined to be unnecessary or infeasible by the City. If avoidance is unnecessary or infeasible, other appropriate measures (e.g., data recovery, excavation) shall be instituted.

Administrative Conditions:

63. **Approval, Verification and Submittals.** Copies of any approvals, guarantees or verification of consultations, review or approval, plans, etc., as may be required by the subject conditions, shall be provided to the Planning Department for placement in the subject file.
64. **Code Compliance.** Area, height and use regulations of the zone classification of the subject property shall be complied with, except where herein conditions are more restrictive.
65. **Covenant.** Prior to the issuance of any permits relative to this matter, an agreement concerning all the information contained in these conditions shall be recorded in the County Recorder's Office. The agreement shall run with the land and shall be binding on any subsequent property owners, heirs or assign. The agreement must be submitted to the Planning Department for approval before being recorded. After recordation, a copy bearing the Recorder's number and date shall be provided to the Planning Department for attachment to the file.
66. **Definition.** Any agencies, public officials or legislation referenced in these conditions shall mean those agencies, public officials, legislation or their successors, designees or amendment to any legislation.
67. **Enforcement.** Compliance with these conditions and the intent of these conditions shall be to the satisfaction of the Planning Department and any designated agency, or the agency's successor and in accordance with any stated laws or regulations, or any amendments thereto.
68. **Building Plans.** Page 1 of the grants and all the conditions of approval shall be printed on the building plans submitted to the City Planning Department and the Department of Building and Safety.
69. **Indemnification and Reimbursement of Litigation Costs.** The Applicant shall do all of the following:
 - (i) Defend, indemnify and hold harmless the City from any and all actions against the City relating to or arising out of, in whole or in part, the City's processing and approval of this entitlement, including but not limited to, an action to attack, challenge, set aside, void, or otherwise modify or annul the approval of the entitlement, the environmental review of the entitlement, or the approval of subsequent permit decisions, or to claim personal property damage, including from inverse condemnation or any other constitutional claim.
 - (ii) Reimburse the City for any and all costs incurred in defense of an action related to or arising out of, in whole or in part, the City's processing and approval of the entitlement, including but not limited to payment of all court costs and attorney's fees, costs of any judgments or awards against the City (including an award of attorney's fees), damages, and/or settlement costs.
 - (iii) Submit an initial deposit for the City's litigation costs to the City within 10 days' notice of the City tendering defense to the Applicant and requesting a deposit. The initial deposit shall be in an amount set by the City Attorney's Office, in its sole discretion, based on the nature and scope of action, but in no event shall the initial deposit be less than \$50,000. The City's failure to notice or collect the deposit does not relieve the Applicant from responsibility to reimburse the City pursuant to the requirement in paragraph (ii).
 - (iv) Submit supplemental deposits upon notice by the City. Supplemental deposits may be required in an increased amount from the initial deposit if found necessary by

the City to protect the City's interests. The City's failure to notice or collect the deposit does not relieve the Applicant from responsibility to reimburse the City pursuant to the requirement in paragraph (ii).

- (v) If the City determines it necessary to protect the City's interest, execute an indemnity and reimbursement agreement with the City under terms consistent with the requirements of this condition.

The City shall notify the applicant within a reasonable period of time of its receipt of any action and the City shall cooperate in the defense. If the City fails to notify the applicant of any claim, action, or proceeding in a reasonable time, or if the City fails to reasonably cooperate in the defense, the applicant shall not thereafter be responsible to defend, indemnify or hold harmless the City.

The City shall have the sole right to choose its counsel, including the City Attorney's office or outside counsel. At its sole discretion, the City may participate at its own expense in the defense of any action, but such participation shall not relieve the applicant of any obligation imposed by this condition. In the event the Applicant fails to comply with this condition, in whole or in part, the City may withdraw its defense of the action, void its approval of the entitlement, or take any other action. The City retains the right to make all decisions with respect to its representations in any legal proceeding, including its inherent right to abandon or settle litigation.

For purposes of this condition, the following definitions apply:

"City" shall be defined to include the City, its agents, officers, boards, commissions, committees, employees, and volunteers.

"Action" shall be defined to include suits, proceedings (including those held under alternative dispute resolution procedures), claims, or lawsuits. Actions includes actions, as defined herein, alleging failure to comply with any federal, state or local law.

- 70. Nothing in the definitions included in this paragraph are intended to limit the rights of the City or the obligations of the Applicant otherwise created by this condition.

ENTITLEMENT FINDINGS

1. Transfer of Floor Area Rights Findings

- a. **Pursuant to Section 14.5.6 B.2 of the Los Angeles Municipal Code, the increase in Floor Area generated by the proposed Transfer is appropriate with respect to the location and access to public transit and other modes of transportation, compatible with other existing and proposed development and the City's supporting infrastructure or otherwise determined to be appropriate for the long term development of the Central City.**

The proposed project is a mixed-use development consisting of residential, commercial, and hotel uses, within a Downtown location within walking distance of the Los Angeles Sports and Entertainment District (LASED), and part of the South Park Neighborhood. As such, the location is adjacent to the city's premiere convention, entertainment, and sports district, locating additional residents, employees, and hotel guests within walking distance to these uses. The Project is in conformance with General Plan Policies, and Objectives, as well as state and regional plans concentrating residential units and commercial space in proximity to established transit and destinations, such as LA Live, the Staples Center, the Convention Center and the Grammy Museum. Furthermore, the location provides convenient access to the LASED and Downtown area, supporting businesses, institutions, restaurants, and other uses. The Project Site is in proximity to employment centers in Downtown Los Angeles, and is well served by public transit providing comprehensive mobility options for residents, guests, visitors, and employees. Additionally, the proposed Project would include a hotel ballroom (which could be used for meetings), a conference center, and several pools, further supplementing existing amenities in the area that support the Convention Center as well as events in the Los Angeles Sports and Entertainment District.

The Proposed Project is transit accessible and is in proximity to many bus transit lines, MTA rail lines (Metro Rail) and DASH service. The site is approximately 0.4 miles north of Pico Station with portals at Flower Street and Pico Boulevard, and is served by the Blue and Expo Lines, with connections to the Silver Line Bus route. The 7th Street/Metro Center Station is located approximately 0.4 miles northeast of the Project Site with station portals at the northeastern corner of 7th Street and Figueroa Street, at the northeastern corner of 7th Street and Flower Street, and at the northwestern corner of 7th Street and Hope Street. The 7th/Metro Center Metro Rail station is served by Red, Purple, Blue, and Expo Lines, connecting passengers to Pasadena, East Los Angeles, Long Beach, Culver City, Santa Monica, Hollywood, Korea Town, and North Hollywood. Prior to project build out, Metro forecasts 2021 as the completion date of construction for the Regional Connector Project, which would expand service by connecting the Gold, Blue, and Expo Light Rail Lines expanding destinations at both stations. Additionally, MTA Bus lines serving the site include lines 66, 81, 442, and 460, the Metro Silver Line (910 and 950). LADOT Dash F, LADOT Commuter Express Bus Lines 419, 423, 438, 448 also have stops along Figueroa, as well as additional municipal bus lines. The Project site is along the now completed MyFig project, which spans Figueroa Street from 7th street to Martin Luther King Jr. Boulevard, which includes bus boarding islands, traffic calming features, buffered and striped bike lanes, and enhanced wayfinding signage. The project is also in proximity to multiple Metro Bike Share stations, including Figueroa and 9th, Hope and Olympic, Hope and 11th.

The proposed Project is compatible with both existing and recently completed development in the area, as well as proposed development. Additionally, the project is not seeking entitlements that would alter the zone or the General or Community Plan. Recent

high-rise multifamily mixed-use developments in the vicinity of the project include the four tower Metropolis development, with the highest tower reaching 56 stories located at Francisco Street and James M. Wood Boulevard, directly north of the site, and the Olympia Project at Olympic and Georgia Street, with the largest of three towers being 65 stories. Also nearby is the Circa development located at Flower Street and 12th Street consisting of two 35-story towers, Oceanwide Plaza located across the street from the Circa development at 53 stories, Hope and Flower towers 31 and 40 stories tall located at 1212 Flower Street, and multiple mid-rise residential developments throughout the South Park area as well as the 54-story Ritz Carlton Hotel at the southeast corner of Georgia Street and Olympic Boulevard. The South Park neighborhood, as intended in the Community Plan, has seen a large number of additional residential units built in the past decade, the project as proposed would follow this trend, consistent with large scale high-rise mixed-use developments listed above, similarly located adjacent or in the LASED. Furthermore, proposed development located at the northwest corner of James M. Wood Boulevard and Georgia Street, as well as two parcels north, on the north side of the Hotel Figueroa, each have mixed-use, mid- or high-rise projects proposed, each with hotel components. Specifically, 926 James M. Wood Boulevard would include a 247-room hotel and amenities, and 913 South Figueroa Street would include 220-room hotel, and 200 residential units. The project as proposed is consistent with both existing and proposed development in the South Park neighborhood, as well as additional development planned for the Central City Community Plan Area.

The Central City Community Plan includes residential objectives, and commercial objectives and policies which encourage this type of development in the area. Furthermore, the General Plan Framework Element designates the area as Regional Center Commercial. The Framework Element characterizes Regional Commercial Center Land Use Designation as “intended to serve as the focal points of regional commerce, identity, and activity.” “They are typically high-density places whose physical form is substantially differentiated from the lower-density neighborhoods of the City. Generally, regional centers will range from FAR 1.5:1 to 6:1 and are characterized by six- to twenty-story (or higher) buildings as determined in the Community Plan.” The Framework Element includes goals and objectives consistent with this description, which indicate the proposed development and recent developments in the area are consistent with the intent of the Land Use Designation.

The Project’s location is well-served by infrastructure, as the area is currently developed with a mix of uses, each connected to various existing utilities serving the area. The recent expansion of development has furthermore resulted in extensive study, and provision if deemed necessary, of utilities in the area. As discussed in the Draft EIR, prepared for the Project is estimated to generate a net total of approximately 174,397 gallons per day of wastewater. Wastewater generated by the Project would flow to the Hyperion Water Reclamation Plant (HWRP), which has an available treatment capacity of 450 million gallons per day and adequate capacity to treat the Project’s wastewater. As part of the Project’s permit process, the City would conduct further detailed gauging and evaluation to confirm specific sewer connection points and capacity. As discussed in the Draft EIR, a Water Supply Assessment was prepared for the Project by the Los Angeles Department of Water and Power (LADWP). LADWP estimates that the Project would consume approximately 194,576 gallons per day (or 0.194 million gallons per day). LADWP concluded that projected water supply available during normal, single dry, and multiple-dry water years as included in the 25-year projection of the 2015 Urban Water Management Plan (UWMP) is sufficient to meet the projected water demand associated with the Project, in addition to the existing and planned future demand on LADWP. In addition, with regards to the Water Supply Assessment, the Project has voluntarily agreed to incorporate a variety of water conservation measures into the Project that are beyond

those required by law. As discussed in the Draft EIR, the Project would consume approximately 7,184,493 kw-h/year (7,184.49 mw-h/year or 7.18 gw-h/year). Compared to LADWP's projected 2021-2022 total electricity sales (load forecast) of 23,609 gw-h, the Project's consumption of 7.18 gw-hr/yr would represent approximately 0.03 percent of the forecasted 2021-2022 electricity demand.

The site is centrally located near frequent transit services, would be compatible with densely developed surroundings, and would be in proximity to jobs, housing, and a wide range of uses and public services. The intensity and mix of the proposed residential and commercial uses are compatible with the current density and mix of uses in the area, and will contribute to the establishment of a 24-hour community in downtown Los Angeles. The Transfer is appropriate for the long-term development of the Central City because it will enable the project to include residential, hotel, and commercial uses in the South Park area, contributing to the revitalization and modernization of Downtown Los Angeles including job creation and increased City tax revenue generation, maintaining the strong image of downtown as the major center of the metropolitan region, and serving as a linkage and catalyst for other downtown development.

b. The Project is consistent with the purposes and objectives of the Redevelopment Plan.

Enacted on June 29, 2011, Assembly Bill 1x-26 (AB 26) revised provisions of the Community Redevelopment Law of the State of California, to dissolve all redevelopment agencies and community development agencies in existence and designate successor agencies, as defined, as successor entities. Among the revisions, the amendments to the law withdrew all authority to transact business or authorize powers previously granted under the Community Redevelopment Law (Section 34172.a.2), and vested successor agencies with all authority, rights, powers, duties and obligations previously vested with the former redevelopment agencies (Section 34172.b). The CRA/LA, is the Designated Local Authority, and successor agency to the CRA.

The project is located in the City Center Redevelopment Plan Area. The City Center Redevelopment Plan's primary objective is eliminating and preventing blight in the area. The project supports and is consistent with the following objectives of the City Center Redevelopment Plan:

1. To eliminate and prevent the spread of blight and deterioration and to rehabilitate and redevelop the project area in accordance with this plan.

The project site is currently occupied by a carwash and restaurant and associated surface parking lot. The proposed Project will redevelop the site into a 57-story high-rise building containing up to 65,074 square feet of retail/commercial space (in three stories); 33,498 square feet of office space (in six stories); 10,801 square feet of hotel conference center/ballroom space (on one story); 8,448 square feet of residential condominium amenities (on the same story as the hotel conference center); 373 hotel rooms (216,065 square feet in 17 stories, including lobby/amenities level); 374 residential condominium units (435,731 square feet in 24 stories); and 9,556 square feet of penthouse amenity area (in two stories) for a project total of 779,173 square feet of total floor area.

2. To further the development of Downtown as the major center of the Los Angeles metropolitan region, within the context of the Los Angeles General Plan as envisioned by the General Plan Framework, Concept Plan, City-wide Plan portions, the Central City Community Plan, and the Downtown Strategic Plan.

3. To create an environment that will prepare, and allow, the Central City to accept that share of regional growth and development which is appropriate, and which is economically and functionally attracted to it.
4. To promote the development and rehabilitation of economic enterprises including retail, commercial, service, sports and entertainment, manufacturing, industrial and hospitality uses that are intended to provide employment and improve the Project Area's tax base.

The Project Site is zoned C2, designated Regional Commercial Center and across from the Los Angeles Sports and Entertainment District within the Central City Community Plan. The Framework Element characterizes Regional Commercial Center Land Use Designation as "intended to serve as the focal points of regional commerce, identity, and activity. They are typically high-density places whose physical form is substantially differentiated from the lower-density neighborhoods of the City. Generally, regional centers will range from FAR 1.5:1 to 6:1 and are characterized by six- to twenty-story (or higher) buildings as determined in the Community Plan." The Framework Element includes goals and objectives consistent with this description, which indicate the Project and recent developments in the area are consistent with the intent of the Land Use Designation. The Project will support the greater downtown area and LASED as destinations, and provide additional space for uses that complement the nearby LASED and Convention Center, contributing to its economic vitality. Further, the Project will be consistent with Central City Community Plan's vision for the South Park District becoming a 24-hour community by developing the Site with a mix of uses that strengthens the link between the surrounding districts/neighborhoods, including the Civic Center /Little Tokyo District to the northeast, and the Financial Core and Bunker Hill Districts to the north.

5. To guide growth and development, reinforce viable functions, and facilitate the redevelopment, revitalization or rehabilitation of deteriorated and underutilized areas.

The Project will guide growth and development in the area and generate new job opportunities associated with the 65,074 square feet of retail/commercial space, 33,498 square feet of office space and 373-room hotel. The new residential condominium units proposed as part of the Project will offer a mix of unit types for new residents, as well as offering new restaurant space located in a transit rich area, siting new commercial growth in a location aligned with City plans and policies.

6. To create a modern, efficient and balanced urban environment for people, including a full range of around-the-clock activities and uses, such as recreation, sports, entertainment and housing.
7. To create a symbol of pride and identity which give the Central City a strong image as the major center of the Los Angeles Region.

The Project will be designed in a contemporary architectural style, via a tall and slender high-rise tower. The incorporation of an exoskeleton, non-uniform terraces as well as varied architecturally unique balconies will contribute to the downtown Los Angeles' distinct skyline, which give the Central City a strong image as the major center of the Los Angeles Region.

8. To facilitate the development of an integrated transportation system which will allow for the efficient movement of people and goods into, through, and out of the Central City.

As described in the previous finding, the Project Site is well-served by public transit, including both rail and bus service. The Project is transit accessible and is in close proximity to many bus transit lines, MTA rail lines (Metro Rail) and DASH service. The Metro Rail Expo and Blue Lines run beneath Flower Street, one block to the east of the Project site. The Pico Station is located on these lines approximately 0.2 miles (three blocks) south of the Project site. The 7th Street/Metro Center station, which serves the Expo and Blue Lines as well as the Red, Purple, and is located approximately 0.35 miles (four blocks) northeast of the Project site. 7th Street/Metro connects passengers to Pasadena, East Los Angeles, Long Beach, Culver City, Santa Monica, Hollywood, Korea Town, and North Hollywood. Prior to project build out, Metro forecasts 2021 as completion of construction of the Regional Connector Project, which would expand service by connecting the Gold, Blue, and Expo Light Rail Lines expanding destinations at both stations, projected operation is 2021. These subway lines provide access to other transit lines operated by Metro and connect passengers to Pasadena, East Los Angeles, Long Beach, Culver City, Santa Monica, Hollywood, Koreatown, and North Hollywood. Prior to Project buildout (2023), Metro forecasts 2021 as completion of construction of the Regional Connector Project, which would expand service by connecting the Gold, Blue, and Expo Light Rail Lines expanding destinations at both stations. The Project Site is also served by Metro bus lines. Olympic Boulevard carries Metro Rapid bus line 728 and Metro Local bus line 28 past the Project site with a stop adjacent to the Project site. Figueroa Street carries Metro Express bus lines 442 and 460 and Metro Local bus line 81 past the Project site (northbound) and one block to the east on Flower Street (southbound). In addition, the Metro Silver Line transit way (Metro Busway Routes 910 and 950X), running from El Monte to San Pedro via Downtown, runs northbound on Figueroa Street past the Project site and southbound on Flower Street, one block to the east.

9. To achieve excellence in design, based on how the Central City is to be used by people, giving emphasis to parks, green spaces, streetscapes, street trees, and places designed for walking and sitting, and to develop an open space infrastructure that will aid in the creation of a cohesive social fabric.

The Project will create a continuous and predominantly straight sidewalk and arcade; creating a buffer between pedestrians and moving vehicles by proposing an on-site hotel drop-off/pick-up area along the Cottage Place alley, including all vehicular entry for residents and visitors; and providing a clearly defined project entrance immediately accessible from Olympic Boulevard. The ground floor will be open to the street along Olympic Boulevard and will be accessible to pedestrians. Landscaping, including 63 on-site trees, will be incorporated throughout the various outdoor seating areas, outdoor bar and restaurant spaces, and the pool area. Where appropriate, landscaping will be used to provide a separation between uses (i.e. restaurant use, bar use, and outdoor seating area) and will be comprised of non-invasive and drought tolerant plant materials.

10. To provide a full range of employment opportunities for persons of all income levels.

The Project will introduce 373 new hotel guest rooms, 374 residential condominium units, 33,498 square feet of office space and 65,074 square feet of commercial uses resulting in a range of employment opportunities. Therefore, the Project's new hotel, residential, office and restaurant uses, employment opportunities, transit-oriented location, and other

community benefits make the Project consistent with the Redevelopment Plan's Objectives.

c. The Transfer serves the public interest by complying with the requirements of section 14.5.9 of the LAMC.

The Project proposes 50 percent of its transfer payment to the Public Benefit Trust Fund, and the payment was calculated pursuant to Section 14.5.9 C. The Project therefore complies with the requirement of a 50 percent minimum payment to the Trust Fund. Additional allocations are being made to the Los Angeles Housing and Community Investment Department Affordable Housing Trust Fund, providing affordable housing in the area, both a goal of the City and identified need across the region. Additional allocations include the Pershing Square Improvement Fund for the revitalization of Pershing Square. Below is a summary of the plan.

Olympic Tower Public Benefit Payment Transfer Plan		
Total Public Benefit Payment		\$18,027,494.33
50% Public Benefit Cash Payment		\$9,013,747.17
50% Public Benefit Direct Provision		\$9,013,747.17
Allocation of Public Benefit Direct Provision		
Los Angeles Housing and Community Investment Department	50%	\$4,506,873.58
Department of Recreation and Parks (Redevelopment of Pershing Square Park)	50%	\$4,506,873.58
Total	100%	\$18,027,494.33

d. The Transfer is in conformance with the Community Plan and any other relevant policy documents previously adopted by the Commission or the City Council.

The project site is located within the Central City Community Plan and has a Regional Center Commercial and High Density land use designations. The Central City Community Plan describes the Transfer of Floor Area Ratio (TFAR) as follows (page III-19):

"The transfer of floor area between and among sites is an important tool for Downtown to direct growth to areas that can best accommodate increased density and from sites that contain special uses worth preserving or encouraging."

The transfer is in conformance with the Central City Community Plan and other relevant policy documents in that the Community Plan provides for transfers of floor area up to 13:1 floor area ratio on parcels in Height District 4D and that the transfer allows for the project to advance a number of specific objectives and policies contained in the Community Plan, including:

Central City Community Plan

Residential

Objective No. 1-1:

To promote development of residential units in South Park.

Objective No. 1-2:	To increase the range of housing choices available to Downtown employees and residents.
<u>Commercial</u>	
Objective 2-2:	To retain the existing retail base in Central City
Objective 2-3:	To promote land uses in Central City that will address the needs of all the visitors to Downtown for business, conventions, trade shows, and tourism.
Policy 2-3.1:	Support the development of a hotel and entertainment district surrounding the Convention Center/Staples Arena with linkages to other areas of Central City and the Figueroa corridor.
Objective 2-4:	To encourage a mix of uses which create an active, 24-hour downtown environment for current residents and which would also foster increased tourism
Objective 2-4.1	Promote night life activity by encouraging restaurants, pubs, night clubs, small theaters, and other specialty uses to reinforce existing pockets of activity

The proposed mixed-use project supports Objective 1-1 and Objective 1-2 by providing up to 374 residential units within a high-rise tower arranged on the Project Site. Within the tower, a mix of one-, two-, and three-bedroom units would be provided. By providing a range of unit and bedroom sizes, and its location in the South Park neighborhood of the Community Plan, the project supports both Objective 1-1 and Objective 1-2.

The Project would also support Commercial Objectives 2-2 and 2-4 as the project provides 65,074 square feet of new commercial space as well as 33,498 square feet of office, supporting the existing commercial base in Central City as well as offering opportunities for new uses. The amount of commercial space allows for flexibility in leasehold sizes, and thereby uses, supporting both new and current uses in the Central City area. The project is also seeking a Conditional Use to serve alcoholic beverages as well as dancing and live entertainment, further allowing for flexibility in uses between retail and restaurant uses and helping to create an active, 24-hour Downtown. The addition of new uses, as well as up to 374 residential units in the South Park neighborhood supports the existing retail base by strengthening current and creating new residential demand for goods and services, as well as creating synergy between different commercial uses in the area, including LA Live, Staples Center, and the Convention Center.

The Project also complies with Objectives 2-3 and Policy 2-3.1 by creating a 373-room hotel and 98,572 square feet of commercial uses (retail, restaurant and office) located one block from LA Live, Staples Center, and the Convention Center. The proximity to this entertainment district would locate both visitors and residents adjacent to Downtown and the Los Angeles Convention Center, which host various businesses, conventions, trade shows, and tourist destinations, both providing a linkage to the Figueroa corridor. The Project will incorporate sidewalk treatments, an open-air arcade, and landscaping throughout the Project Site and perimeter that will encourage pedestrian street activity to help achieve Policy 2-3.1. The hotel and commercial uses will help create a vibrant 24-hour downtown environment that will serve the residents and employees of the South Park area, as well as tourism to achieve Objective 2-4 and Objective 2-4.1

The proposed Project would locate additional residents, commercial uses, and a hotel in close proximity to both the Convention Center and Downtown; and additional residents in

the area, providing commercial uses to meet new and current resident and visitor needs, supporting the Convention Center and the Los Angeles Sports and Entertainment District and contributing to a 24-hour Downtown environment.

Therefore, the Project is consistent with the Central City Community Plan.

2. Conditional Use Beverage Findings

The following are the findings for an MCUP and CUX, as required by LAMC Section 12.24 W.

- a. That the project will enhance the built environment in the surrounding neighborhood or will perform a function to provide a service that is essential or beneficial to the community, city, or region.**

The Project includes demolition and removal of all existing development on the Project Site and development of a single 57-story high-rise building containing up to 65,074 square feet of retail/commercial space (in three stories); 33,498 square feet of office space (in six stories); 10,801 square feet of hotel conference center/ballroom space (on one story); 8,448 square feet of residential condominium amenities (on the same story as the hotel conference center); 373 hotel rooms (216,065 square feet in 17 stories, including lobby/amenities level); 374 residential condominium units (435,731 square feet in 24 stories); and 9,556 square feet of penthouse amenity area (in two stories) for a project total of 779,173 square feet of total floor area. A six-level subterranean parking garage would be located beneath the building, and eight levels of above ground parking would be provided within the podium level of the building. Six levels of the above ground parking would be wrapped with office uses on the Olympic Boulevard street frontage. Two additional stories dedicated to mechanical facilities would also be included in the proposed structure. The project proposes a floor area ratio (FAR) of up to 13:1.

LAMC Section 12.24 W.1 allows a Conditional Use Permit to be granted for the sale and dispensing of alcoholic beverages. The Project requests a Master Conditional Use to permit the sale and dispensing of a full line of alcoholic beverages for off-site consumption for four establishments, and on-site consumption for up to sixteen establishments. On-site consumption would be provided for the hotel (including, but not limited to, lobby, lobby bar, pool/ pool deck, spa, etc. and portable units to serve alcohol for on-site consumption anywhere within the hotel use), for mini-bars within each hotel room or suite, for up to two (2) restaurants or bars within the hotel area, for the conference center or ballrooms within the Project site, for condominium uses (including, but not limited to, lobby, lobby bar, pools, pool decks, outdoor recreational space, sky lounge, etc.) and for up to ten (10) restaurants or bars located anywhere within the commercial or office areas of the Project, including, but not limited to, outside areas, sidewalks, or rooftop areas. Off-site consumption would occur for up to four (4) retail uses located anywhere within the Project site, including, but not limited to, the hotel, residential, or commercial uses. In conjunction with alcohol-related uses is a request for a Conditional Use Permit to allow dancing within the project's commercial and hotel uses.

The Project Site is located adjacent to the LASED, within the South Park neighborhood both of which have undergone significant changes in recent years, and are now characterized by large mixed-use developments, sports venues, entertainment venues, commercial uses, and restaurant uses. Additionally, a number of new hotels have been built in the area supporting the Convention Center. Additionally, as the Project is intended to support the LASED and Los Angeles Convention Center with its proposed hotel use, the up services would further augment this intent. Providing additional restaurant options

works to increase the attractiveness of both the LASED and Los Angeles Convention Center, further supporting area businesses, and the City. Restaurant uses with alcoholic services, as well as various hotel functions are necessary to support and provide amenities for the hotel use as proposed and consistent with various hotels in the area. Furthermore, concentration of alcoholic services in restaurants and entertainment venues is an integral part of the District and its attractiveness as a destination, is located directly south of the project site on the south side of Olympic Boulevard. This proximity makes the site important to the continued development of the LASED; the uses comprising the project augment, and additional alcohol services would further support the LASED as a 24-hour entertainment district.

The restaurants will also provide a beneficial service for the residents, employees, and visitors to the area, and the availability of alcohol sales is a desirable amenity that is typical of many restaurants. The proposed alcohol service, including dancing, will improve the viability and desirability of the proposed restaurants and hotel. Further, as conditioned, the sale of alcoholic beverages will occur within a controlled environment within the store by trained employees, subject to security measures, limited hours of operation, STAR training, inspections, and evaluations of any nuisance complaints. The service of alcoholic beverages in food establishments has become accepted as a desirable and expected use that is meant to complement food service. Since alcoholic beverage service is a common and expected amenity with meal service for many patrons. Hotel uses traditionally offer alcohol services as well, providing for full service accommodations to visitors. The proximity to the Los Angeles Sports and Entertainment District and Los Angeles Convention Center further create an appropriate atmosphere for the alcohol service, as well as expectations of alcoholic services in hotels and uses within entertainment, sports, and convention uses. Therefore, the grant for alcohol sales and dancing will be desirable to the public convenience and welfare and represents good zoning practice.

Therefore, as conditioned, the service of alcoholic beverages to permit the sale and dispensing of a full line of alcoholic beverages for off-site consumption for up to four establishments, and on-site consumption for up to sixteen establishments, including dancing, will enhance the built environment in the surrounding neighborhood and provide a service that is beneficial to the community, city or region.

- b. That the project's location, size, height, operations, and other significant features will be compatible with and will not adversely affect or further degrade adjacent properties, the surrounding neighborhood, or the public health, welfare and safety.**

The Project includes demolition and removal of all existing development on the Project Site and development of a single 57-story high-rise building containing up to 65,074 square feet of retail/commercial space (in three stories); 33,498 square feet of office space (in six stories); 10,801 square feet of hotel conference center/ballroom space (on one story); 8,448 square feet of residential condominium amenities (on the same story as the hotel conference center); 373 hotel rooms (216,065 square feet in 17 stories, including lobby/amenities level); 374 residential condominium units (435,731 square feet in 24 stories); and 9,556 square feet of penthouse amenity area (in two stories) for a project total of 779,173 square feet of total floor area. A six-level subterranean parking garage would be located beneath the building, and eight levels of above ground parking would be provided within the podium level of the building. Six levels of the above ground parking would be wrapped with office uses on the Olympic Boulevard street frontage. Two additional stories dedicated to mechanical facilities would also be included in the proposed structure. The project proposes a floor area ratio (FAR) of up to 13:1.

The Project Site is located in a highly urbanized area dominated by commercial development. The Project Site is bounded on each side by a public right-of-way, and located directly north, across Olympic Boulevard from LA Live, and the larger Los Angeles Sports and Entertainment District (LASED). The LASED includes Staples Center, LA Live, the Microsoft Theater, and restaurant and commercial uses adjacent to the Project Site. The proposed Project is transit accessible and is in close proximity to many bus transit lines, MTA rail lines (Metro Rail) and DASH service. The Metro Rail Expo and Blue Lines run beneath Flower Street, one block to the east of the Project site. The Pico Station is located on these lines approximately 0.4 miles (three blocks) south of the Project site. The 7th Street/Metro Center station, which serves the Expo and Blue Lines as well as the Red, Purple, and is located approximately 0.35 miles (four blocks) northeast of the Project site. 7th Street/Metro connects passengers to Pasadena, East Los Angeles, Long Beach, Culver City, Santa Monica, Hollywood, Korea Town, and North Hollywood. Prior to project build out, Metro forecasts 2021 as completion of construction of the Regional Connector Project, which would expand service by connecting the Gold, Blue, and Expo Light Rail Lines expanding destinations at both stations, projected operation is 2021.

Immediately to the north of the project site is the 13-story Hotel Figueroa, located at 939 S. Figueroa Street. Across Figueroa Street is the 26-story 717 West Olympic Boulevard tower, which includes a bank on the ground level. Located south of the project site is the Los Angeles Sports and Entertainment District and Los Angeles Convention Center, consisting of various large entertainment and sports related uses. To the west of the project site, across the Cottage Place alley, is a surface parking. Directly adjacent to the Hotel Figueroa is a proposed project application for a mixed-use project consisting of 220 room hotel, 200 residential condominiums, and 984,940 square feet of commercial space. Additionally, across Georgia Street is a proposed 247-room hotel. The surrounding area is generally zoned C2-4D, LASED, and is designated Regional Commercial Center land use. The nearest public schools (e.g. Los Angeles Universal Pre-School, Tenth Street Elementary School) are located 0.2 miles and a half mile away from the project site, respectively.

Redevelopment of the carwash and restaurant as well as the associated surface parking lot will also increase street activity by introducing a new building with a mix of uses that would remain open 24-hours a day and seven days a week, thereby providing a 24-hour presence and more eyes on the street to create a safer environment. The Project locates residential density, hotel, office and new commercial uses near several transit options that afford easy access to employment centers, entertainment, and services; promotes pedestrian activity in the general area by developing a vacant infill site; and provides a gathering point with new recreational and open space amenities available to residents and hotel guests. The sale, dispensing, and consumption of alcoholic beverages, as well as the option to provide dancing will be an incidental amenity for residents and hotel guests of the Site and will provide a new amenity for those who are visiting the downtown area.

No evidence was presented at the Hearing Officer hearing or in writing that the sale of alcoholic beverages for on- and off-site consumption will be materially detrimental to the immediate neighborhood. The sales of alcohol will not be detrimental to nearby schools, since the establishments serving alcohol will be carefully controlled and monitored, and will be located at least a 1,000 feet away and buffered throughout this distance by a wide variety of existing commercial and residential uses. The project has been designed in a manner to enhance the public realm and improve the aesthetics and safety of the surrounding area. The inclusion of alcohol uses will allow for added vibrancy within the

project, which is appropriate for a mixed-use transit priority project in a Regional Commercial Center. Furthermore, the location of the project site in close proximity to the LASED, characterized by primarily non-residential uses, or high-density residential uses, with numerous alcohol serving establishments nearby. Additional schools are unlikely to be located in the District, or immediately adjacent to the Project Site. Any establishments serving alcohol will be carefully controlled and monitored, while being compatible with immediately surrounding commercial uses consisting of the LASED, Los Angeles Convention Center, hotels, retail shops, restaurants and multi-family residential. The Proposed Project will provide a place for residents, workers and visitors to eat, drink, and socialize; as such, the sale of alcoholic beverages is a normal part of restaurant and hotel operation and an expected amenity.

Additionally, the conditions recommended herein will ensure that the establishment will not adversely affect or further degrade the surrounding neighborhood, or the public health, welfare, and safety. Approval of the conditional use will contribute to the success and vitality of the commercial development and help to reinvigorate the site and vicinity. Since the alcohol sales will be in conjunction with food service, and hotel uses, therefore, permitting alcohol sales on the site will not be detrimental to the development of the community.

Thus, as conditioned, the Project's location, size, height, operations and other significant features will be compatible with and will not adversely affect or further degrade adjacent properties, the surrounding neighborhood, or the public health, welfare, and safety. Furthermore, this grant also includes conditions of approval intended to address alcohol-related issues to safeguard public welfare and enhance public convenience, such as proper employee training. In addition, as each operator comes in, they will be required to file a plan approval to allow for the Zoning Administrator to review the floor plan, and impose any other conditions as deemed appropriate.

As discussed above, the Project's conditions will be supplemented by more specific conditions designed to address the characteristics of each individual establishment at Plan Approval which will be required, prior to the effectuation of the approval for each respective tenancy identified above. Under these Plan Approvals, the Zoning Administrator and LAPD will have the opportunity to comment and recommend any additional conditions, as warranted. It should be noted that approval of entertainment uses as defined in LAMC 12.14 A.10 is not required, as these uses are permitted in a C2 Zone. Further, the sale of alcohol is regulated by the State of California through the issuance of an Alcohol Beverage Control (ABC) license. Thus, as conditioned, combined with the enforcement authority of ABC and LAPD, the approval for the sale of alcohol will not be detrimental to the public health, safety and welfare.

The location of the project's alcohol-sale will continue to add to the diversification of commercial activities being conducted in the area and will not adversely affect the surrounding neighborhood. As mentioned, the alcohol-sales will be compatible and complement the LASED and Los Angeles Convention Center. The proposed hours of operation are reasonable and the sale of alcohol is in conjunction with hotel and restaurant uses. Therefore, as conditioned, it is anticipated that the project features and uses will not adversely affect or further degrade adjacent properties, the surrounding neighborhood, or public health, welfare, and safety.

- c. **That the project substantially conforms with the purpose, intent and provisions of the General Plan, the applicable community plan, and any applicable specific plan.**

The elements of the General Plan establish policies that provide for the regulatory environment in managing the City and for addressing concerns and issues. The majority of the policies derived from these Elements are in the form of Code Requirements of the Los Angeles Municipal Code (LAMC).

The Project site is located within the Central City Community Plan. The parcel is zoned C2-4D and is designated for Regional Center Commercial land uses. The proposed project will provide 65,074 square feet of commercial retail and restaurant uses along with required parking facilities.

The Project Site is located within the Central City Community Plan area, which designates the Site for Regional Center Commercial land uses corresponding to the CR, C1.5, C2, C4, C5, RD, R4, R5, RAS3, and RAS4 and High-Density Residential land uses with corresponding zone of R5.

The Project includes a 57-story, high-rise building consisting of 65,074 square feet of retail/commercial space, 33,498 square feet of office space, 373 hotel rooms, and 374 residential condominium units. The C2 Zone allows for restaurants/bars, hotel uses, and ballrooms uses and the service of alcoholic beverages through a Conditional Use approval.

The Central City Community Plan text is silent with regards to alcohol sales. In such cases, the decision-maker must interpret the intent of the Community Plan. The proposed request for the sale, dispensing, and consumption of a full line of alcoholic beverages and public dancing in conjunction with the hotel and restaurants/bars are consistent with the following Central City Community Plan objectives, including:

Objective 2-1: To improve Central City's competitiveness as a location for offices, business, retail, and industry.

Objective 2-3: To promote land uses in Central City that will address the needs of all the visitors to Downtown for business, conventions, trade shows, and tourism.

Objective 2-4: To encourage a mix of uses which create an active, 24-hour downtown environment for current residents and which would also foster increased tourism.

The Project is a mixed-use development that will provide hotel, residential, office and restaurant uses and will be located in an area with a mix of regional entertainment facilities, adjacent to the LASED, hotels, office buildings, ground floor retail, and commercial buildings. The Community Plan encourages new uses, which strengthen the economic base and promote land uses that address the needs of all downtown visitors.

The Project promotes land uses that will be consistent with existing uses, meet the needs of workers, residents, and visitors to downtown, and provide a mix of uses which result in a 24-hour downtown environment. The sale, dispensing, and consumption of a full-line of alcoholic beverages and dancing, in conjunction with the operations of the proposed hotel use, restaurant/bar uses and the banquet room, will be an added amenity for residents and patrons of the Project.

The approval of the requested Master Conditional Use Permit for the sale and consumption of alcohol and the Conditional Use Permit to allow dancing within the project's commercial areas for restaurant, hotel and bar uses will thus further the downtown neighborhood's role as a major population, employment and entertainment center and will result in a development that addresses the needs of the existing business and residents in the area as well as the projected growth in downtown Los Angeles. Therefore, the Project substantially conforms with the purposes, intent and provisions of the General Plan and the Community Plan.

The Project Site is an infill site. The Project's density will be consistent with the neighborhood density and contribute to the Central City's competitiveness by introducing new hotel, residential, and restaurant uses. The adopted Central City Community Plan designates the Project Site for Regional Center Commercial with a corresponding zone of C2-4D (Commercial, Height District 4 with D Development Limitation). The Commercial zones permit a wide array of land uses, such as retail stores, offices, hotels, schools, parks, and theaters. The C2 zone also allows any land use permitted in the C1.5 and C1 Zones, which, in turn, allow R4 and R3 Multiple Dwelling Zones, which include multiple dwelling units. Height District 4 within the C2 Zone does not impose any height limit with a maximum FAR of 13:1. However, while Height District 4 permits a FAR of 13:1, the maximum permitted floor area of the Project Site is further restricted by the D Limitation, which restricts the FAR to 6:1 without a transfer of floor area (per Ordinance 164,307). A Transfer of Floor area from the City of Los Angeles-owned Convention Center has been proposed, thereby permitting a maximum 13:1 FAR, in lieu of the otherwise permitted maximum 6:1 FAR.

As discussed above, the Project is consistent with the surrounding development located in the South Park neighborhood within the Central City Community Plan.

Additional required findings for the sale of alcoholic beverages:

d. The proposed use will not adversely affect the welfare of the pertinent community.

The subject property is located directly across the street from LASED and Los Angeles Convention Center, as well as adjacent to various hotel and entertainment uses. Multi-family residential, commercial, and SR-110 (Harbor Freeway) are also located in the vicinity of the Project Site. A variety of commercial uses are an intrinsic part of the service amenities necessary for the conservation, development, and success of a vibrant neighborhood, especially entertainment districts, such as the LASED, as well as supporting hotel uses. As the LASED is one of the premiere entertainment destinations, alcohol services are common in the vicinity, and even necessary for the entertainment uses in the District. Furthermore, the Project Site is located in close proximity to Downtown, which also offers various 24-hour amenities. The surrounding area is characterized by various alcohol related uses; the introduction of another such establishment would not create an adverse or unique condition. As conditioned, the sale of a full line of alcoholic beverages for on-site and off-site consumption in conjunction with the operation of new restaurants, hotel amenities, and any off-site sale establishments located on the Project Site will not adversely affect the welfare of the pertinent community. Negative impacts commonly associated with the sale of alcoholic beverages, such as criminal activity, public drunkenness, escort services, and loitering are mitigated by the imposition of conditions requiring deterrents against loitering and responsible management. Employees are required to undergo training on the sale of beer and wine including training provided by the Los Angeles Police Department Standardized Training for Alcohol Retailers (STAR) Program. Other conditions related

to excessive noise, litter and noise prevention will safeguard the residential community. Therefore, with the imposition of such conditions the sale of a full line of alcoholic beverages for on-site consumption at this location will further support and augment the Los Angeles Sports and Entertainment District, and not adversely affect or further degrade adjacent properties, the surrounding neighborhood, or the public health, welfare and safety.

- e. **The granting of the application will not result in an undue concentration of premises for the sale or dispensing for consideration of alcoholic beverages, including beer and wine, in the area of the City involved, giving consideration to applicable State laws and to the California Department of Alcoholic Beverage Control's guidelines for undue concentration; and also giving consideration to the number and proximity of these establishments within a one thousand foot radius of the site, the crime rate in the area (especially those crimes involving public drunkenness, the illegal sale or use of narcotics, drugs or alcohol, disturbing the peace and disorderly conduct), and whether revocation or nuisance proceedings have been initiated for any use in the area.**

According to the State of California Department of Alcoholic Beverage Control (ABC) licensing criteria in 2017, two (2) on-sale and one (1) off-sale licenses are allocated to Census Tract No. 2077.10. There are currently a total of 112 licenses (98 on-site and 14 off-site) in this Census Tract. In addition, 10 restaurants, bars, and markets within 600 and 1,000 feet serve alcohol.

According to statistics provided by the Los Angeles Police Department's Central Division, within Crime Reporting District No. 171, which has jurisdiction over the subject property, a total of 274 crimes were reported in 2017 (108 Part I and 166 Part II crimes), compared to the total citywide average of 191 crimes for the same reporting period.

Part 1 Crimes reported by LAPD include, Homicide (0), Manslaughter (0), Rape (3), Robbery (3), Aggravated Assault (7), Burglary (3), Auto Theft (4), Larceny (88). Part II Crimes reported include, Other Assault (22), Forgery/Counterfeit (2), Embezzlement/Fraud (2), Stolen Property (1), Weapons Violation (1), Prostitution Related (6), Sex Offenses (5), Offenses Against Family (1), Narcotics (7), Liquor Laws (23), Public Drunkenness (3), Disturbing the Peace (0), Disorderly Conduct (41), Gambling (0), DUI related (5), Moving Traffic Violations (3), and other offenses (37). Of the 247 total crimes reported for the census tract, five arrest were made for driving under the influence and 3 for public drunkenness.

Concentration can be undue when the addition of a license will negatively impact a neighborhood. Concentration is not undue when the approval of a license does not negatively impact an area, but rather such a license benefits the public welfare and convenience. No information was provided by LAPD showing that the approval of the Master Conditional Use Permit would negatively impact the neighborhood. Of the 247 arrests in the crime district, only 11 percent (31) of the total were for alcohol-related offenses, and five (5) were for driving under the influence (DUI). The above figures indicate that the mixed-use development is located in a high crime reporting district. Due to high crime statistics, conditions typically recommended by the Los Angeles Police Department, such as those related to the STAR Program and age verification, have been imposed in conjunction with this Master Conditional Use Permit approval. Each establishment is part of a larger development will benefit from oversight of the building complex as a whole. Any concerns associated with any individual venue can be addressed in more detail through the Approval of Plans determination which is an opportunity to consider more specific operational characteristics as a tenant is identified

and the details of each venue are identified. Security plans, floor plans, seating limitations and other recommended conditions, as well as the mode and character of the operation, will be addressed and assured through site specific conditions.

- f. **The proposed use will not detrimentally affect nearby residentially zoned communities in the area of the City involved, after giving consideration to the distance of the proposed use from residential buildings, churches, schools, hospitals, public playgrounds and other similar uses, and other establishments dispensing, for sale or other consideration, alcoholic beverages, including beer and wine.**

The Project Site is zoned for commercial uses and will continue to be utilized as such with the development of new restaurant uses on the project site. With regard to surrounding sensitive uses, there are the following within a 1,000-foot radius of the site:

Within 600 feet:

- Salvation Army (832 W. 9th St.)
- First United Methodist Church (1020 S. Flower St.)

Within 1000 feet:

- Grand/ Hope Park (919 S. Grand Ave.)

Consideration has been given to the distance of the subject establishment from the above-referenced sensitive uses. Both the Salvation Army and First United Methodist Church are located over 500 feet away from the proposed project. As conditioned, the Project would protect the health, safety and welfare of the surrounding neighbors. The potential effects of excessive noise or disruptive behavior have been considered and addressed by imposing conditions related to noise and loitering. The Project is consistent with the zoning and in keeping with the existing uses adjacent to the development and will contribute to a neighborhood and will serve the neighboring residents and the local employees as well as visitors. Therefore, as conditioned, the Project will not detrimentally affect residentially zoned properties or any other sensitive uses in the area.

3. Site Plan Review Findings

In order for the Site Plan Review to be granted, all three of the legally mandated findings delineated in Section 16.05-F of the Los Angeles Municipal Code must be made in the affirmative.

- a. **The project is in substantial conformance with the purposes, intent and provisions of the General Plan, applicable community plan, and any applicable specific plan.**

The Project proposes to develop a mixed-use project (Project) on a 37,031 square-foot site (0.85 acres) located within the Central City Community Plan area of the City of Los Angeles (City). The proposed Project is a mixed-use development consisting of one building with 374 residential condominium units, a hotel with 373 guest rooms, a 10,801 square foot conference center, 33,498 square feet of office uses, and 65,074 square feet of commercial floor area. The building will be 57 stories and approximately 742 feet tall. The ground floor will include 20,745 square feet of commercial uses, and elevator lobbies for the offices, hotel and residential uses. There will also be mechanical rooms, valet parking and driveway ramps to the parking within the building. The second and third floors will include approximately 44,329 square feet of commercial uses. Levels 4 and 5 will be devoted to automobile parking. Levels 6-11 will include offices and parking

on each floor. Level 12 is devoted solely to mechanical equipment. Level 13 will be devoted to indoor and outdoor open space (including a pool) and amenities for the residential units in the building along with a ballroom/conference center to support the hotel. The 14th floor includes the lobby for the hotel, a restaurant space and indoor and outdoor amenities for the hotel guests, including a pool. Levels 15-30 consists of hotel guest rooms. Level 31 is another transition floor devoted solely to mechanical equipment to serve the building. The 374 residential condominium units will be located on levels 32-55. Level 56 will include indoor and outdoor amenities for residents, including a pool for the use of the penthouse units located on levels 48-55. On the top level (57th floor) an indoor club house will be located for use of the residential tenants of the building.

The proposed mixed-use project is consistent with the General Plan Framework Element, the Center City Community Plan, the Housing Element, and the City Center Redevelopment Plan discussed below:

Framework Element

The General Plan Framework, last adopted in August 2001, establishes the City's long-range comprehensive growth strategy and provides guidance on citywide land use and planning policies, objectives, and goals. The Framework defines Citywide policies for land use, housing, urban form and urban design, open space and conservation, transportation, infrastructure and public spaces. The project is consistent with the following goals, objectives and policies of the Framework Element as described below.

Land Use Chapter

The Framework Element's Land Use Chapter (Chapter Three) establishes general principles to encourage growth and increase land use intensity around transit nodes, to create a pedestrian oriented environment while promoting an enhanced urban experience and provide for places of employment. The Project Site is designated as Regional Center Commercial in the Central City Community Plan. The Framework Element's Land Use Chapter identifies Regional Centers as the focal points of regional commerce, identity, and activity. The Framework Element further states that regional centers, typically, provide a significant number of jobs and many non-work destinations that generate and attract a high number of vehicular trips. Consequently, each center shall function as a hub of regional bus or rail transit both day and night. Good quality street, area, and pedestrian lighting is essential to generating feelings of safety, comfort, and well-being necessary for ensuring public nighttime use of transit facilities. Per the Framework Element, regional centers are typically high-density places whose physical form is substantially differentiated from the lower-density neighborhoods of the City. Generally, regional centers will range from FAR 1.5:1 to 6:1 and are characterized by six- to twenty-story (or higher) buildings as determined in the Community Plan. Their densities and functions support the development of a comprehensive and inter-connected network of public transit and services.

The Proposed Project is consistent with and meets the goals of the Regional Center designation by providing a mixed-use project with up to up to 374 residential units, 373-room hotel, and 98,572 square feet of commercial use. The Project is located within approximately 2,000 feet of both 7th Street/Metro Center Station and Pico Station, both served by the Metro Blue and Expo Light Rail lines, with 7th Street/Metro Center also served by the Metro Red and Purple Lines. The project site is served by multiple Metro, LADOT, and municipal bus routes, as well as the Metro Silver Line limited-service bus line. The project site is located adjacent to the Los Angeles Sports and Entertainment District, adjacent to numerous commercial and entertainment destinations, as well as

Staples Center and the Los Angeles Convention Center. The project will provide pedestrian amenities with improved streetscape treatments, ground level retail along Figueroa Street and Olympic Boulevard, and publically accessible open space within the arcades along both streets. The Project proposes a 13:1 FAR after a Transfer of Development Rights. The project is therefore consistent with the appropriate land uses for the Regional Center land use designation as envisioned in the Framework Element.

The project meets the following objectives and policies set forth in the Framework Element's Land Use chapter.

Regional Centers:

General Plan Framework's land use objectives and policies for the Regional Center Commercial designation.

- Objective 3.4: Encourage new multi-family residential, retail commercial, and office development in the City's neighborhood districts, community, regional, and downtown centers as well as along primary transit corridors/boulevards, while at the same time conserving existing neighborhoods and related districts.
- Policy 3.4.1: Conserve existing stable residential neighborhoods and lower-intensity commercial districts and encourage the majority of new commercial and mixed-use (integrated commercial and residential) development to be located (a) in a network of neighborhood districts, community, regional, and downtown centers, (b) in proximity to rail and bus transit stations and corridors, and (c) along the City's major boulevards, referred to as districts, centers, and mixed-use boulevards, in accordance with the Framework Long-Range Land Use Diagram.
- Objective 3.10: Reinforce existing and encourage the development of new regional centers that accommodate a broad range of uses that serve, provide job opportunities, and are accessible to the region, are compatible with adjacent land uses, and are developed to enhance urban lifestyles.

The Project would integrate housing with commercial uses and amenities in proximity to local and regional public transit, including less than 1,500 feet from the 7th Street/Metro Center transit hub with access to the Metro Red, Purple, Blue, and Expo Line rail transit as well as numerous bus lines. The Project is also less than 1,500 feet from the Pico Station, which is served by the Metro Blue and Expo Lines. The Project is also located on the same block as the MyFig project, which offers expanded transit amenities, such as bus lanes, bus boarding islands, as well as bicycle lanes, and wayfinding signage. The project would be pedestrian-oriented with access to the site from all of the surrounding streets, and entrances to commercial spaces along Olympic Boulevard. A publicly accessible arcade along both Olympic Boulevard and Figueroa Street would be designed to complement and respond to the adjacent LA Live Entertainment District, and would provide linkages to LA Live, Downtown Los Angeles, MyFig, and other surrounding uses. The Project will locate multi-family residential units, retail, and restaurant uses adjacent to these regional mobility amenities, further promoting pedestrian activity and multi-modal accessibility for residents and visitors,

ensuring complementary and supportive uses within the regional center designation. Additionally, the addition of a hotel, open space, and additional residents supports the Los Angeles Sports and Entertainment District by siting a hotel, retail commercial, office and restaurant uses, as well as additional residents within the district. Generally, regional centers are characterized by six- to 20-story (or higher) mid- and high-rise buildings with a floor-to-area ratio of 1.5:1 to 6:1 as determined in the Community Plan.

Distribution of Land Use:

Objective 3.1: Accommodate a diversity of uses that support the needs of the City's existing and future residents, businesses and visitors.

Objective 3.2: Provide for the spatial distribution of development that promotes an improved quality of life by facilitating a reduction of vehicle trips, vehicle miles traveled and air pollution.

Objective 3.4: Distribution of Land Use: Encourage new multi-family residential, retail commercial, and office development in the City's neighborhood districts, community, regional, and downtown centers as well as along primary transit corridors/boulevards, while at the same time conserving existing neighborhoods and related districts.

The Proposed Project complies with the intent of the objectives listed above related to distribution of land. The projects contains residential and retail development located on the same site within the South Park neighborhood of the Central City Community Plan Area. The Project Site is located adjacent to the LASED, as well as walking distance to Downtown, 7th Street/Metro Center, and Pico Station, providing connections throughout the region, and access to a myriad of commercial uses in Downtown Los Angeles. The proposed hotel use would develop up to 373 rooms hotel rooms within walking distance of the Convention Center, as well as residential and commercial uses, in a transit-rich, Downtown-adjacent LASED. The Project will provide visitors, current and future residents with transit accessible employment, hotel, commercial, and residential uses. The project proposes up 374 new residential units, supporting the needs of current and future residents, and contributing to the Mayor's Goal 1 of Executive Directive 13 of 100,000 new housing units by 2021.

Urban Form and Neighborhood Design Chapter

Goal 5A: A livable City for existing and future residents and one that is attractive to future investment. A City of interconnected, diverse neighborhoods that builds on the strengths of those neighborhoods and functions at both the neighborhood and citywide scales.

Objective 5.2 Encourage future development in centers and in nodes along corridors that are served by transit and are already functioning as centers for the surrounding neighborhoods, the community or the region.

Objective 5.5: Enhance the livability of all neighborhoods by upgrading the quality of development and improving the quality of the public realm.

Objective 5.9: Encourage proper design and effective use of the built environment to help increase personal safety at all times of the day.

Policy 5.9.2: Encourage mixed-use development which provides for activity and natural surveillance after commercial business hours through the development of ground floor

retail uses and sidewalk cafes. Mixed-use should also be enhanced by locating community facilities such as libraries, cultural facilities or police substations, on the ground floor of such building, where feasible

The Proposed Project complies with the intent of the goal, objectives, and policy listed above by developing a high-quality mixed-use structure, with architectural elements which complement and respond to the surrounding area, and the continued architectural evolution of the South Park neighborhood. The ground floor and arcade respond to both elements and needs of the South Park neighborhood. The tower level responds to both new high-rise mixed-use developments in South Park, as well as the more established Downtown Core. The Project also improves the public realm and safety of the area by providing publicly accessible open space in the form of an arcade along Figueroa Street and Olympic Boulevard, as well as by embracing the bustling pedestrian activity on Olympic and Figueroa by offering retail and restaurant opportunities at the ground level and upper two floors. These floors are designed to invite visitors in from the street and then encourage pedestrian flow throughout the Project, including the main lobbies. In addition to pedestrian scale lighting, the project will add more “eyes on the street” from the podium level uses, as well as streetscape improvements along Olympic Boulevard and Figueroa Street, which both add to the quality and safety of the public realm and area.

The Project’s distinct architecture and unique arrangement additionally compliment and respond to the existing LASED, providing both an additional destination in the District, as well as additional hotel space, complementing in both use and architecture the LASED and its surrounding uses, amenities, and attractions.

Open Space Chapter

Objective 6.2: Maximize the use of the City's existing open space network and recreation facilities by enhancing those facilities and providing connections, particularly from targeted growth areas, to the existing regional and community open space system.

Policy 6.4.7: Consider as part of the City's open space inventory of pedestrian streets, community gardens, shared school playfields, and privately-owned commercial open spaces that are accessible to the public, even though such elements fall outside the conventional definitions of "open space." This will help address the open space and outdoor recreation needs of communities that are currently deficient in these resources.

The Project includes publicly accessible open spaces along Figueroa Street and Olympic Boulevard. The total publically accessible open space is 5,000 square feet, in the form of an arcade along Olympic Boulevard and Figueroa Street. The Project will provide residential open space in excess of code requirements: based on the number of units and the mix of unit types, 42,650 square feet of open space is required, and a total of 73,848 square feet of open space will be provided in amenities and private balconies throughout the residential portions of the building.

The project includes several open space amenities for residents, including Level 13 which will be devoted to indoor and outdoor open space (including a pool) and amenities for the residential units in the building along with a ballroom/conference center to support the hotel. The 14th floor includes the lobby for the hotel, a restaurant space and indoor and outdoor amenities for the hotel guests, including a pool. Level 56 will include indoor and outdoor amenities for residents, including a pool for the use of the penthouse units located on levels 48-55. On the top level (57th floor) an indoor club house will be located for use of the residential tenants of the building.

Economic Development Chapter

Goal 7A: A vibrant economically revitalized City.

The Project proposes the demolition of an existing 13,130 square-foot carwash and restaurant, for the construction of 779,173 square-foot, mixed-use development. The development would contain up to 374 residential condominiums, 373 key hotel, and up to 98,572 square feet of commercial space. The additional residents, employees, and hotel guests would be located within walking distance to businesses, amenities, and attractions in Downtown, the LASED, as well as various transit options with connections throughout the region. Additionally, hotel rooms and supporting uses would be in close proximity to the Los Angeles Convention Center, further supporting the City's Convention Center and associated uses.

Goal 7B: A City with land appropriately and sufficiently designated to sustain a robust commercial and industrial base.

Objective 7.2: Establish a balance of land uses that provides for commercial and industrial development which meets the needs of local residents, sustains economic growth, and assures maximum feasible environmental quality.

Policy 7.2.3: Encourage new commercial development in proximity to rail and bus transit corridors and stations.

Policy 7.2.5: Promote and encourage the development of retail facilities appropriate to serve the shopping needs of the local population when planning new residential neighborhoods or major residential developments.

The project will further the above Goals, Objective and Policies through the introduction of up to 374 residential condominiums, a 373-key hotel, and up to 98,572 square feet of commercial space, including retail, restaurant and office. The Project's convenient location to rail and bus stops will allow residents and visitors easy access to the goods and services provided by the project. The commercial and hotel components of the project will provide long-term jobs in the area. The Project is consistent with the underlying commercial zoning, and is located within walking distance to numerous transit options. The additional commercial space, hotel and associated support amenities, are appropriate for the area, compliment the Convention Center located one block to the south, and offers additional opportunities for commercial space supporting LA Live. The mixed-use project will promote job creation and economic growth, strengthen the commercial sector, and contribute to a better balance of land uses that meets the needs of residents.

Goal 7D: A City able to attract and maintain new land uses and businesses.

The project will further the above goal through the introduction of a mixed-use development which would contain up to 374 residential condominiums, 373 key hotel, and up to 98,572 square feet of commercial space. Additionally, the Project supports the Los Angeles Sports and Entertainment District, as well as the Los Angeles Convention Center. The additional residents, hotel guests, commercial space, and employees will further support the Sports and Entertainment District and the South Park neighborhood.

Goal 7G: A range of housing opportunities in the City.

The project will provide a range of housing opportunities in the form of up to 374 new residential units within a mix of one-bedroom units, two-bedroom units, and three-bedroom units, on a site that currently does not contain residential units.

Housing Element

The 2013-2021 Housing Element of the General Plan is the City's blueprint for meeting housing and growth challenges. The Housing Element identifies a need for more housing while Chapter 6 of the Housing Element lists the goals, objectives, policies and programs that "embody the City's commitment to meeting housing needs." The applicable housing goals, objectives and policies are as follows:

- | | |
|-----------------------|--|
| <i>Goal 1:</i> | <i>A City where housing production and preservation result in an adequate supply of ownership and rental housing that is safe, healthy and affordable to people of all income levels, races, ages, and suitable for their various needs.</i> |
| <i>Objective 1.1:</i> | <i>Produce an adequate supply of rental and ownership housing in order to meet current and projected needs.</i> |
| <i>Policy 1.1.3:</i> | <i>Facilitate new construction and preservation of a range of different housing types that address the particular needs of the city's households.</i> |
| <i>Policy 1.1.4:</i> | <i>Expand opportunities for residential development, particularly in designated Centers, Transit Oriented Districts and along Mixed-Use Boulevards.</i> |
| <i>Goal 2:</i> | <i>A City in which housing helps to create safe, livable and sustainable neighborhoods.</i> |
| <i>Objective 2.2:</i> | <i>Promote sustainable neighborhoods that have mixed-income housing, jobs, amenities, services and transit.</i> |
| <i>Policy 2.2.5:</i> | <i>Provide sufficient services and amenities to support the planned population while preserving the neighborhood for those currently there.</i> |
| <i>Objective 2.4:</i> | <i>Promote livable neighborhoods with a mix of housing types, quality design and a scale and character that respects unique residential neighborhoods in the City.</i> |

Through the development of up to 374 residential units, the Project will achieve Objectives 1-1 and 2.2 and Policies 1.1.3. and 1.1.4 by introducing residential uses to the site through a range of housing options with a mix of one-bedroom units, two-bedroom units, and three-bedroom units.

Policy 1.1.4 would be achieved, as the residential and commercial uses will be well served by transit, including the Pico Light Rail Station operated by Metro which serves the Blue Line and the Expo Line, the 7th Street/Metro Center Station which provides rail service to the Blue, Expo, Red, and Purple Lines, multiple Metro bus lines, and DASH services. The project is also adjacent to the MyFig project, which consists of expanded transit amenities, such as bus lanes, bus boarding islands, and wayfinding signage.

Furthermore, the project will include 65,074 square feet of commercial retail and restaurant space, and 33,494 square feet of office, supporting Objectives 2.2, 2.4, and Policy 2.2.5 by locating these commercial amenities within a mixed-use building with residential units, office and a hotel, in a transit oriented neighborhood, adjacent to the Los Angeles Sports and Entertainment District, thereby providing complementary uses to the existing neighborhood. The flexibility in configurations of commercial space resulting from a significant portion of the ground floor of the site dedicated to commercial space, allows for varying commercial and restaurant uses to respond to both the needs of the residents in the project as well as the South Park Neighborhood as a whole. This flexibility and diversity of uses further supports the achievement of Objectives 2.2, 2.4, and Policy 2.2.5, specifically, new restaurant, retail and office space will provide both employment opportunities as well as further promote the Los Angeles Sports and Entertainment District as a destination within the region.

Central City Community Plan

The project site is located within the Central City Community Plan. The Plan designates the project site for Regional Center Commercial Land Uses with corresponding zones of CR, CR1.5, C2, C4, C5, R3, R4, R5, RAS3, and RAS4, which allow for the project's proposed residential and commercial uses. The project site is currently zoned C4-2D. Although the existing "D" Development Limitation restricts the maximum floor area ratio (FAR) to 6:1, the "D" limitation allows for up to 13:1 FAR with a Transfer of Development Rights, which the project is seeking. As set forth below, the project is consistent with the Community Plan.

The Central City Community Plan text includes the following relevant land use objectives, policies and programs:

Residential

Objective No. 1-1:

To promote development of residential units in South Park.

Objective No. 1-2:

To increase the range of housing choices available to Downtown employees and residents.

Commercial

Objective 2-2:

To retain the existing retail base in Central City

Objective 2-3:

To promote land uses in Central City that will address the needs of all the visitors to Downtown for business, conventions, trade shows, and tourism.

Policy 2-3.1:

Support the development of a hotel and entertainment district surrounding the Convention Center/Staples Arena with linkages to other areas of Central City and the Figueroa corridor.

Objective 2-4:

To encourage a mix of uses which create an active, 24-hour downtown environment for current residents and which would also foster increased tourism

The proposed mix use project supports the objectives of the Central City Community Plan through the provision of the uses the Project proposes. Specifically, Objective 1-1 and Objective 1-2 will be supported through the development of up to 374 residential units. The Project proposes to arrange the residential units in a high rise tower arranged on the project site (57 stories). Within the tower a mix of one, two, and three bed-room units would be provided, By providing a range of unit and bedroom sizes, and its location in the South Park neighborhood of the Community Plan, the project supports both Objective 1-1 and Objective 1-2.

The Project would also support Commercial Objectives 2-2 and 2-4 as the project provides 98,572 square feet of new commercial space, supporting the existing commercial base in Central City as well as offering opportunities for new uses. The amount of commercial space allows for flexibility in leasehold sizes, and thereby uses, supporting both new and current uses in the Central City area. The project is also seeking a Conditional Use to serve alcoholic beverages and dancing/live entertainment, further allowing for flexibility in uses between retail and restaurant uses. The addition of new uses, as well as up to 374 residential units in the South Park neighborhood supports the existing retail base by strengthening current and creating new residential demand for goods and services, as well as creating synergy between different commercial uses in the area.

The project also complies with Objectives 2-3 and Policy 2-3.1. The project would create a 373-room hotel and 98,572 square feet of commercial uses located across from LA Live, Staples Center, and the Convention Center. The proximity to the entertainment district would locate both visitors and residents adjacent to Downtown and the Los Angeles Convention Center, which host various businesses, conventions, trade shows, and tourist destinations, both accessible from the Figueroa Corridor. The project will incorporate sidewalk treatments, and landscaping throughout the project site and perimeter that will encourage pedestrian street activity to help achieve Policy 2-3.1. The hotel and commercial uses will help create a vibrant 24-hour downtown environment that will serve the residents and employees of the South Park area, as well as tourism to achieve Objective 2-4.

City Center Redevelopment Plan

The current project supports and is consistent with the following objectives of the City Center Redevelopment Plan:

2. To further the development of Downtown as the major center of the Los Angeles metropolitan region, within the context of the Los Angeles General Plan as envisioned by the General Plan Framework, Concept Plan, City-wide Plan portions, the Central City Community Plan, and the Downtown Strategic Plan.
3. To create an environment that will prepare, and allow, the Central City to accept that share of regional growth and development which is appropriate, and which is economically and functionally attracted to it.
4. To promote the development and rehabilitation of economic enterprises including retail, commercial, service, sports and entertainment, manufacturing, industrial and hospitality uses that are intended to provide employment and improve the Project Area's tax base.
5. To guide growth and development, reinforce viable functions, and facilitate the redevelopment, revitalization or rehabilitation of deteriorated and underutilized areas.
6. To create a modern, efficient and balanced urban environment for people, including a full range of around-the-clock activities and uses, such as recreation, sports, entertainment and housing.
12. To provide a full range of employment opportunities for persons of all income levels.

The introduction of up to 374 residential units will support Objective 3, and proposed retail, restaurant and office commercial space, as well as hotel will support Objectives 2, 4, and 6. The new residential units the project proposes will support Objective 3 by offering various options for new residents, as well as offering new commercial space located in a transit rich area, siting new commercial growth in a location aligned with City plans and policies. Furthermore, the location and additional residential and commercial uses support Objectives 2, 4, and 6 by adding a new skyline defining development, on a lot zoned and intended for high-density uses not currently occupied by such development, supporting the greater Downtown area and South Park as regional destinations, and providing additional space for uses that complement the nearby Los Angeles Sports and Entertainment District. The Project would include a hotel, in addition to 374 residential units and 65,074 square feet of retail and restaurant space, that provide a 24-hour community in downtown located across from LA Live, the Convention Center, and Staples Center. The project will comply with Objective 5 as the site consist of a carwash and restaurant, that will be demolished and redeveloped with a mixed-use hotel, residential, office and commercial project guiding growth and development in the area. The project will achieve Objective 12 by generating new job opportunities associated with the 98,572 square feet of commercial space, and a 373 room hotel.

- b. The Project consists of an arrangement of buildings and structures (including height, bulk and setbacks), off-street parking facilities, loading areas, lighting, landscaping, trash collection and other such pertinent improvements, that is or will be compatible with existing and future development on adjacent properties and neighboring properties.**

Height and Bulk

The Proposed Project's density and massing is appropriately scaled and compatible with existing and future surrounding multi-family and commercial uses. The Project proposes the demolition of an existing 13,130 square-foot carwash and restaurant, for the construction of a 779,173 square-foot mixed-use development. The development would include up to 374 residential condominiums, a 373-key hotel, and up to 98,572 square feet of commercial space within a 57 story high-rise tower including a twelve-story podium, for up to 779,173 square feet of floor area. The project's maximum floor area ratio (FAR) will be 13:1 with a maximum height of 742 feet.

The surrounding area is a highly-urbanized neighborhood that is characterized by a mix of land uses at various scales of development, including medium-density buildings, mid-rise residential buildings, high-rise mixed-use buildings, high-rise office towers, sports arenas, and the Los Angeles Convention Center. Northwest of the project site the Metropolis mixed-use development is operational, consisting of residential and hotel uses in four towers, the highest tower reaching 56 stories located at Francisco Street and James M. Wood Boulevard, directly north of the site. Also located nearby is the Circa development located at Flower Street and 12th Street consisting of two 35-story towers, Oceanwide Plaza is located across the street from the Circa development which is 53 stories at its tallest, Hope and Flower towers 31 and 40 stories tall located at 1212 Flower Street, and other multiple mid-rise residential developments throughout the South Park area. As well as the 54-story Ritz Carlton Hotel at the southeast corner of Georgia Street and Olympic Boulevard. The South Park neighborhood, as intended in the Community Plan, has seen a large number of additional residential units built in the past decade. The Project as proposed would follow this trend, consistent with the large scale high-rise mixed-use developments listed above, similarly located adjacent or in the Los Angeles Sports and Entertainment District. Furthermore, proposed development located at the northwest corner of James M. Wood Boulevard and Georgia Street, as

well as two parcels north, on the north side of the Hotel Figueroa, each have mixed-use mid-rise or high-rise projects proposed, each with hotel components. Specifically, 926 James M. Wood Boulevard would include a 247-room hotel and amenities, and 913 South Figueroa Street would include 220-room hotel, and 200 residential units. The project as proposed is consistent with both existing and proposed development in the South Park Neighborhood, as well as additional development planned for the Downtown Area. Therefore, the Project will therefore be consistent with the scale and character of the surrounding area.

The proposed building is designed to be modern in style, and has been articulated along all street frontages through the use of a steel exoskeleton that wraps around the entire building envelope, eliminating the need for interior columns and culminating at the roof top with a steel trellis tying the vertical structural grid. The result is that the building's exterior is well-articulated, and is able to offer an expansive mid-tower atrium that will create new vantage points and give hotel guests and visitors sweeping views of the City. In accordance with the City's latest standards, the project achieves an articulated pinnacle by providing a fire elevator all the way to the top, negating the need for a roof top helistop. The project incorporates design elements that visually provide for transitions in height and massing. The presence of a large, elevated, landscaped atrium on the 13th floor softens the impact of a tall structure in relation to the surrounding buildings. The Project's bent geometry further softens the impact of the Project's mass and height. Olympic Tower is designed in a modern form and scale, yet it simultaneously references the existing historic structures nearby. At the street level on the Figueroa Street side, the Project respects its adjacency to the historic Hotel Figueroa's façade by incorporating a more sensitive scale of articulation at the lower levels and by having a podium that is slightly shorter than the existing hotel. In addition, the Project's tower is detached and separated above the Hotel Figueroa's roof level. Landscaping and vegetation are incorporated into numerous levels along the atrium to add additional visual interest and material diversity. A variety of building materials will be utilized to provide vertical and horizontal articulation on the proposed building elevations to create visual interest, and create an iconic building. Materials anticipated to be utilized include glass, metal, concrete and corrugated metal as well as vegetation. Additionally, commercial store fronts activate each of the Olympic Boulevard, and Figueroa Street frontages, while an arcade linear plaza at Figueroa Street and Olympic Boulevard further activate the street level. At the tower level inset and external balconies that follow the exoskeleton grid, angular terraces, staggered tower placement, horizontal and vertical articulation at each tower level, and architectural treatments are employed to reduce massing and prevent uniformity of the structure, create a visually interesting development, and integrating the tower into the changing Downtown Skyline.

Parking and access

Vehicular access to the Project site would be provided at grade level via two new driveways on Cottage Place (alley). There is one existing curb cut on Olympic Boulevard that will be closed and there are no existing or proposed curb cuts on Figueroa Street. Parking will be provided in six subterranean parking levels and eight above-grade parking levels within the building on levels 4 through 11. Access to the garage levels would be from new driveways on Cottage Place. A total of 838 spaces will be provided. Vehicle and bicycle parking will satisfy the requirements of the Los Angeles Municipal Code, although a variance is being requested with respect to the design standards and location of the bicycle parking.

Based on the proposed mix of dwelling unit sizes, 412 residential parking spaces are required for 374 dwelling units, not counting permitted bicycle parking credits. When

applying the maximum permitted 15 percent vehicle parking space reduction allowed for providing 571 required long- and short-term bicycle parking spaces for the residential units, 350 residential vehicle parking spaces are required.

Additionally, the commercial component of the Project requires 277 parking spaces based on the mix of office, retail, hotel and conference center uses. When applying the maximum 30 percent vehicle parking space reduction to the non-residential parking requirement for the Project, the provision of 160 required long-and short term non-residential bicycle parking spaces allows a reduction of 39 vehicle parking spaces from 277 to 238 required parking spaces.

Based on the above, 588 parking spaces (350 residential plus 238 commercial) are required when factoring in bicycle parking reductions.

As part of the Project, a Transportation Demand Management Program (TDM) will be developed that will include programs intended to reduce vehicle miles traveled. The TDM program may include discounted employee and resident transit passes; a transportation information center, and participation in a flex car program on-site.

While the project does not lie within the boundaries of the LASED, it is across the street (Olympic) and therefore subject to the LASED Streetscape Plan. Pursuant to the LASED Streetscape Plan, the Project would include streetscape improvements including extensive landscape improvements, street trees and alternating streetlight and street tree patterns, improving the pedestrian environment.

Setbacks

The Project Site is bounded on the east, south, and west sides by public rights-of-way, and on the north by the Hotel Figueroa at 939 S. Figueroa Street. It is located directly north, across Olympic Boulevard, from LA Live and the larger Los Angeles Sports and Entertainment District (LASED). The LASED includes Staples Center, LA Live, the Microsoft Theater, and restaurant and commercial uses adjacent to the Project Site.

As a mixed-use project proposed in the C2 Zone, the project is not required to provide front yard setbacks. Pursuant to the C2 Zone, buildings partly or wholly erected for residential use must comply with the R-4 Zone requirements of 16-foot maximum side yards, and 20-foot maximum rear yard. The site is located within the Greater Downtown Housing Incentive Area, and per LAMC Section 12.22 C.3(a), there are no required setbacks except those required by the Urban Design Guidelines prepared by the Community Redevelopment Agency. The Project will not require street dedications on Olympic Boulevard or Figueroa Street. Olympic Boulevard is designated as Boulevard II in the recently adopted Mobility Element. This standard requires a 110-foot wide right-of-way with an 80 feet of roadway within the right-of-way. Currently Olympic Boulevard has 112 feet of right-of-way and 84 feet of roadway. The project will require the granting of a variable 10-foot wide sidewalk easement on Olympic Boulevard to comply with the Mobility Element and the LASED Streetscape Plan. The existing 13-foot wide sidewalk on Olympic Boulevard will be widened by 10-feet with the sidewalk easement providing a total of 23 feet of pedestrian realm as envisioned by the LASED Streetscape Plan, which requires a 15-foot sidewalk and an 8-foot private setback. Figueroa Street is designated as a Modified Avenue I in the Mobility Element. This standard requires a 100-foot wide right-of-way with a 73 feet of roadway within the right-of-way. Currently Olympic Boulevard has 110 feet of right-of-way and 73 feet of roadway. Thus no widening of the roadway is required. On Figueroa Street, the existing sidewalk complies with the sidewalk requirements in the Mobility Element and the Downtown Street

Standards which call for a 12-foot sidewalk in the public right-of-way and an 8 foot sidewalk easement. The project will require the granting of a 10-foot wide sidewalk easement on Olympic Boulevard to comply with the Mobility Element and the LASED Streetscape Plan. The existing 13-foot wide sidewalk on Olympic Boulevard will be widened by 10-feet with the sidewalk easement providing a total of 23 feet of pedestrian realm as envisioned by the LASED Streetscape Plan, which requires a 15-foot sidewalk and an 8-foot private setback.

The ground floor commercial and open space are consistent with the Guidelines, as they provide inviting, active, pedestrian friendly space with seating options and active uses. The varying setbacks are appropriate in that they provide for the provision of open space. As discussed above, the request conforms with the intent of the setback regulations in the LAMC, is compatible with and will not adversely affect adjacent properties, and is consistent with the General Plan. Therefore, the proposed setbacks for the project are consistent with the requirements of the LAMC.

Lighting

Exterior light fixtures for the proposed development will be architecturally integrated with the character of the buildings and would be designed to prevent glare, light trespass, and light pollution. Permanently installed exterior lighting will not blink, flash, or be of unusually high intensity. All exterior fixtures will be selected as full cut off fixtures designed to light downward only, or will utilize optical accessories to eliminate light pollution. Exterior fixtures will be directed away from adjacent properties and public rights-of-way, and be appropriate in height, intensity, and scale for the use they are serving.

Tower facade lighting will uplight the exterior exoskeleton on various levels of the ceilings. Light fixtures will be located and shielded as necessary to minimize light pollution in the sky. Vertical surfaces of the tower will not be illuminated. Podium facade lighting will include uplight vertical surfaces and integrated lighting highlighting vertical features, particularly of the exoskeleton. Light fixtures will be located and shielded as necessary to minimize any light pollution in the sky.

Lighting related to any signage included as part of the Project will comply with the illumination regulations contained in the LAMC.

On-Site Landscaping

The project proposes 84,966 square feet of common open space for residents and visitors, consisting of multiple amenity levels, including podium and mid-tower levels, pools, patios, recreation rooms, and gather places; and 22,539 square feet of private open space. Finally, the project proposes 38,938 square feet of recreation rooms at the podium level of each tower (Level 5). Podium Levels 2 and 4 include 43,704 square feet of amenity space, while the top of the podium, Level 5, includes 16,053 square feet of amenity space, pools, roof decks, and landscaping. Level 19 in Tower A, Level 27 in Tower B, and Level 34 in Tower C include open space and pools. Tower A includes an additional amenity level on Level 33 which includes a pool and roof deck.

Trash Collection and Loading Areas

The project has been designed to minimize the visual impact of trash receptacles and loading areas. Electrical rooms, storage rooms, trash enclosures, and loading spaces

are located within the project and are not visible from surrounding public streets and public view. All ancillary support uses and loading, trash, and receiving are located within the western portion of the project, shielded from public view with architectural elements consistent with treatments throughout the project. Rooftop equipment will be set back from the roof parapet edge and appropriately screened from public view. In addition, numerous conditions have been imposed on the project to ensure that any trash or mechanical equipment is fully screened and not visible to the public.

As described above, the Project consists of an arrangement of buildings and structures (including height, bulk and setbacks), off-street parking facilities, loading areas, lighting, landscaping, trash collection, and other such pertinent improvements that will be compatible with existing and future development on adjacent and neighbouring properties.

- c. That any residential project provides recreational and service amenities in order to improve habitability for the residents and minimize impacts on neighboring properties.**

The Project will provide residential open space in excess of code requirements based on the number of units and the mix of unit types, 42,650 square feet of open space is required, and a total of 73,848 square feet of open space will be provided in amenities and private balconies throughout the residential portions of the building. Based on the number of units and habitable rooms proposed, the project is required to provide a minimum 42,650 square feet of open space and 5,331 square feet of landscaping and groundcover. In total, the Project will provide 73,848 square feet of open space, comprised of 42,740 square feet (57.9%) of common open space and an added 31,108 square feet (42.1%) of private open space for each unit in the form of balconies and private covered recreational areas. Within these open spaces, the Project will provide 9,042 square feet of landscaping thereby improving the habitability and wellness opportunities for its residents and minimize impacts on neighboring properties. As such, the project provides recreational and services amenities in order to improve habitability for the residents and minimize impacts on neighboring properties.

4. DIRECTORS DECISION FOR OPEN SPACE (ON-SITE TREES) (LAMC §12.21 G.2(a)(3))

Pursuant to Los Angeles Municipal Code (LAMC) Section 12.21 G.3, the Applicant requests approval of a Director's Decision from (LAMC) Section 12.21 G.2(a)(3) to reduce the number of required trees planted on-site. For residential projects, LAMC Section 12.21 G.2(a)(3) requires one tree for every four dwelling units be planted. The proposed Project will have 374 dwelling units, which requires 94 trees be planted on-site and within the parkway adjacent to the site. However, due to the small size of the lot and the high-rise design of the Project, only 63 trees can be planted.

Approximately 20 street trees can be planted in the public right-of-way (sidewalks) based on the spacing standard in the Los Angeles Sports and Entertainment District (LASED) Streetscape Plan (20-feet on center and the 398 linear feet of street frontage on Olympic Boulevard and Figueroa Street). Further, because of other constraints related to minimum distances from street lights and other obstructions, only 15 street trees can be planted in the parkway along the Project site. With respect to on-site trees, due to space constraints by the high-rise building and small lot size only 48 trees can be planted on-site. Pursuant to Ordinance No. 185,573, the Applicant proposes to pay in lieu fees for the 31 required trees that cannot be planted on-site. The following findings shall be made.

a. The open space provided conforms with the objectives of this subsection.

The City requires usable open space be provided in residential projects to fulfill the following objectives: afford occupants of multiple residential dwelling units opportunities for outdoor living and recreation; provide safer play areas for children as an alternative to the surrounding streets, parking areas, and alleys; improve the aesthetic quality of multiple residential dwelling units by providing relief to the massing of buildings through the use of landscape materials and reduced lot coverage; and provide a more desirable living environment for occupants of multiple residential dwelling units by increasing natural light and ventilation, improving pedestrian circulation and providing access to on-site recreation facilities (LAMC Section 12.21 G.3).

The proposed Project meets these objectives by providing approximately 73,848 square feet of open space where 42,650 square feet is required. Open space and recreation amenities are proposed throughout the building. The 13th floor will have indoor and outdoor open space, including a pool, and amenities for the residential units in the building. The 14th floor includes indoor and outdoor amenities for the hotel guests, including a pool. Floor 56 will include indoor and outdoor amenities for residents, including a pool for use by owners of the penthouse units located on Floors 48-55. An indoor club house for the residents will be located on the 57th floor, the top level of the building.

The landscaping for the Project will include 26 trees on the 13th floor residential amenity deck and 22 trees on the 57th floor roof deck. The proposed number of trees will enhance the aesthetic quality of the open space and recreation amenities without overwhelming the spaces with shade cover.

The Project is located within walking distance to several public recreation areas including Grand Hope Park and LA Live/Staples Center and as such will improve pedestrian circulation and provide easy access to recreational opportunities.

b.. The proposed project complies with the total usable open space requirements.

As detailed below, 73,848 square feet of open space will be provided where 42,650 square feet of open space is required for the 374 dwelling units.

Site 1	Open Space (sf)
100 SF Less 3 Hab Rooms (x 224 units)	22,400
125 SF 3 Hab Rooms (x 120 units)	15,000
175 SF More than 3 Hab Rooms (x 30 units)	5,250
Open Space Required:	42,650
Common Open Space	Provided
Level 13	19,482
Level 56	18,788
Level 57	4,470
Subtotal	42,740
Private Open Space	Provided
level 32-35 Balconies	5,640

Level 36-47 Balconies	16,920
Level 48-51 Balconies	2,660
Level 52 & 54 Balconies	3,252
Level 53 & 55 Balconies	2,636
Subtotal	31,108
Total Open Space Provided	73,848

A summary of required vs. provided tree count is as follows:

Required Trees	94
On-Site Trees	48
Street Trees	<u>15</u>
Trees Provided	63

The Project is designed with amenity areas for residents including pools, a conference center, a fitness gym, and a sky lounge clubhouse. An additional outdoor amenity deck for the hotel guest will include a pool and landscaping. Open space areas will be attractively landscaped with trees.

Due to the small size of the lot (37,031 square feet), in order to accommodate a reasonable building footprint, while respecting the required building separation from the Hotel Figueroa, the proposed project is a tall, slender building that occupies almost the entire property at ground level. This limits the ability to plant trees at ground level. The constrained lot size also results in very limited opportunities to plant trees on amenity decks higher up in the building. The building does include a design feature to allow for open space above the 13th floor amenity deck on the north side of the building where 26 trees can be planted in large boxes. The open structural frame at the top of the building will also allow for opportunities to place 22 trees on the rooftop amenity deck as well. As such, the project complies with the total usable open space requirements.

DIRECTOR'S DECISION FOR BICYCLE PARKING SITING REQUIREMENTS

Pursuant to Los Angeles Municipal Code (LAMC) Section 12.21.A.16(h), the Applicant requests approval of Alternative Compliance (Director's Decision) to LAMC Section 12.21 A.16(e)(2)(iii and (iv) to deviate from the siting requirements for short- and long-term bicycle parking spaces by allowing all the parking spaces to be located inside the building within Levels B1 and B2 of the subterranean parking areas of the building in lieu of being located on the ground floor of the parking garage, or the level closest to the ground floor, with direct access to a public street.

The Applicant proposes to provide basement floor valet pick-up/drop-off service for bicycles belonging to hotel guests, employees and office/commercial tenants and visitors. The bicycles would be parked by attendants in designated bike racks and lockers on Levels B1 and B2, with the valet drop off located on Level B1. Residents and guests of the condominium units would use the residential elevators to move their bicycles from street level to Level B1 where the residential valet pick-up/drop-off will be located, and parking attendants on Level B1 will park these bicycles in storage racks and lockers on Levels B1 and B2. No outside bike racks for short-term bicycle parking will be provided. The following findings shall be made.

- a. **The location, dimensions, position, security, and safety allow for safe and reasonable accessible and convenient short - or long -term storage for the anticipated users of the bicycle parking, and that the proposed design or siting meets the needs of bicyclists at least as effectively as the requirements of Section 12.21 A.16.(e)(1).**

The required 571 short- and long-term bicycle parking spaces, proposed inside the building in the underground parking areas on Levels B1 and B2 will be designed in accordance with the standards listed in LAMC Section 12.21 A.16.(e)(1). Providing all the bicycle parking inside the building is necessary due to the small size of the irregular shaped parcel and the various design constraints of high-rise mixed-use buildings. Although the Code requires short-term bicycle parking to be located on the ground floor outside of the building and long-term bicycle parking be located along the shortest walking distance to the nearest pedestrian entrance or on the level of the parking garage closest to the ground floor and with direct access to a public street, the Project proposed alternative locations for short- and long-term bicycle parking using valet attendants will be convenient and provide a safe and secure bicycle storage area.

LAMC Sec. 12.21-A.16.(e)(2)(iii) and (iv)) requires specific locations for the short- and long-term bicycle parking, with the intent of making the bicycle parking convenient and accessible to residents, tenants, guests and visitors. The alternative compliance proposed for the project meets the intent of the applicable Code sections. The Applicant will provide the required number of short- and long-term bicycle parking spaces in a more convenient location. As described above, the applicant will provide valet bicycle attendants on the first basement floor that will secure the bikes in designated parking spaces, so bicycle riders will not have to travel below the ground floor (non-residential bicycle riders) or Level B1 (residential bicycle riders) to access their bicycles.

The size of the project, the small, irregularly shaped lot, and the need to place bicycle parking within the underground parking garage makes it infeasible to meet two of the specific requirements of the code. LAMC Section 12.21 A.16(e)(2)(iii) and (iv) require bike racks for short-term bicycle parking on the ground floor of the building and that long-term bicycle parking be located inside the parking garage and along the shortest walking distance to the nearest pedestrian entrance, or located on a level of the parking garage closest to the ground floor and with direct access to a public street. Providing short-term and long-term bicycle parking within those siting requirements is difficult within a multi-use structure on a very small lot.

Although the bicycle parking regulations specify the location of the long-term bicycle parking, the requirements are based on making the long-term bicycle parking convenient and accessible to residents. The difficulty in providing the Code-required number of long-term bicycle parking spaces in a structure with retail/restaurant uses on the ground floor and requiring direct access to the exterior can only be managed with the request to utilize parking levels B1 and B2 with valet drop-off (on Basement Level 1) to provide the bicycle parking spaces.

A Director's Decision is required for locating the short-term bicycle parking indoors and locating the short-term and long-term bicycle parking locations on Levels B1 and B2 which do not meet code requirements. However, the location is actually more convenient for residents given the slim tower configuration. Providing valet parking for bicycles on level B1 and close to the elevators, makes for a much shorter distance for residents, tenants and visitors to get from their bicycle to their unit and other locations in the building and vice versa. Therefore, the location, dimensions, position, security, and safety allow for safe and

reasonable accessible and convenient short - or long -term storage for the anticipated users of the bicycle parking, and that the proposed design or siting meets the needs of bicyclists at least as effectively as the requirements of Section 12.21 A.16.(e)(1).

CALIFORNIA ENVIRONMENTAL QUALITY ACT (“CEQA”) FINDINGS

Introduction

This Environmental Impact Report (EIR), consisting of the Draft EIR and the Final EIR, is intended to serve as an informational document for public agency decision-makers and the general public regarding the objectives and environmental impacts of the Olympic Tower Project (Project), located at 813–815 West Olympic Boulevard and 947–951 South Figueroa Street (Site or Project Site). The Project includes demolition and removal of all existing development on the Project Site and development of a single 57-story high-rise building containing up to 65,074 square feet of retail/commercial space; 33,498 square feet of office space; 10,801 square feet of hotel conference center/ballroom space; 8,448 square feet of residential condominium amenities; 373 hotel rooms (216,065 square feet in 17 stories, including lobby/amenities level); 374 residential condominium units (435,731 square feet in 24 stories); and 9,556 square feet of penthouse amenity area for a project total of 779,173 square feet of total floor area. A six-level subterranean parking garage would be located beneath the building, and eight levels of above ground parking would be provided within the podium level of the building. Six levels of the above ground parking would be wrapped with office uses on the Olympic Boulevard street frontage. The project proposes a floor area ratio (FAR) of up to 13:1.

The City of Los Angeles (the “City”), as Lead Agency, has evaluated the environmental impacts of implementation of the Olympic Tower Project by preparing an EIR (Case Number ENV-2015-4558-EIR/State Clearinghouse No. 2016061048). The EIR was prepared in compliance with the California Environmental Quality Act of 1970, Public Resources Code Section 21000 et seq. (CEQA) and the California Code of Regulations Title 15, Chapter 6 (the “CEQA Guidelines”). The findings discussed in this document are made relative to the conclusions of the EIR.

CEQA Section 21002 provides that “public agencies should not approve projects as proposed if there are feasible alternatives or feasible mitigation measures available which would substantially lessen the significant environmental effects of such projects[.]” The procedures required by CEQA “are intended to assist public agencies in systematically identifying both the significant effects of proposed projects and the feasible alternatives or feasible mitigation measures which will avoid or substantially lessen such significant effects.” CEQA Section 21002 goes on to state that “in the event [that] specific economic, social, or other conditions make infeasible such project alternatives or such mitigation measures, individual projects may be approved in spite of one or more significant effects thereof.”

The mandate and principles announced in CEQA Section 21002 are implemented, in part, through the requirement that agencies must adopt findings before approving projects for which EIRs are required. (See CEQA Section 21081[a]; CEQA Guidelines Section 15091[a].) For each significant environmental impact identified in an EIR for a proposed project, the approving agency must issue a written finding, based on substantial evidence in light of the whole record, reaching one or more of the three possible findings, as follows:

- 1) Changes or alterations have been required in, or incorporated into, the project that avoid or substantially lessen the significant impacts as identified in the EIR.
- 2) Such changes or alterations are within the responsibility and jurisdiction of another public agency and not the agency making the finding. Such changes have been, or can or should be, adopted by that other agency.

- 3) Specific economic, legal, social, technological, other considerations, including considerations for the provision of employment opportunities for highly trained workers, make infeasible the mitigation measures or alternatives identified in the EIR.

The findings reported in the following pages incorporate the facts and discussions of the environmental impacts that are found to be significant in the Final Environmental Impact Report for the project as fully set forth therein. Although Section 15091 of the CEQA Guidelines does not require findings to address environmental impacts that an EIR identifies as merely “potentially significant”, these findings nevertheless fully account for all such effects identified in the Final EIR for the purpose of better understanding the full environmental scope of the Project. For each environmental issue analyzed in the EIR, the following information is provided:

The findings provided below include the following:

- Description of Significant Effects - A description of the environmental effects identified in the EIR.
- Project Design Features - A list of the project design features or actions that are included as part of the Project.
- Mitigation Measures - A list of the mitigation measures that are required as part of the Project to reduce identified significant impacts.
- Finding - One or more of the three possible findings set forth above for each of the significant impacts.
- Rationale for Finding - A summary of the rationale for the finding(s).
- Reference - A reference of the specific section of the EIR which includes the evidence and discussion of the identified impact.

With respect to a project for which significant impacts are not avoided or substantially lessened either through the adoption of feasible mitigation measures or feasible environmentally superior alternatives, a public agency, after adopting proper findings based on substantial evidence, may nevertheless approve the project if the agency first adopts a statement of overriding considerations setting forth the specific reasons why the agency found that the project’s benefits rendered acceptable its unavoidable adverse environmental effects. (CEQA Guidelines §15093, 15043[b]; see also CEQA § 21081[b].)

Environmental Review Process and Record of Proceedings.

For purposes of CEQA and these Findings, the Record of Proceedings for the Project includes (but is not limited to) the following documents:

Initial Study. The Project was reviewed by the City of Los Angeles (Lead Agency) in accordance with the requirements of the CEQA (PRC 21000 et seq.). The City prepared an Initial Study in accordance with Section 15063(a) of the State CEQA Guidelines (14 Cal. Code Regs. §§ 15000 et seq.).

Notice of Preparation. Pursuant to the provisions of Section 15082 of the State CEQA Guidelines, the City then circulated a Notice of Preparation (NOP) to State, regional and local agencies, and members of the public for a 32-day period commencing on June 23, 2016 and ending July 25, 2016. The NOP also provided notice of a Public Scoping Meeting held on July 7, 2016 at 1025 East 16th Street. The purpose of the NOP and Public Scoping Meeting was to formally inform the public that the City was preparing a Draft EIR for the Project, and to solicit input regarding the scope and content of the environmental information to be included in the Draft EIR. Written comment letters responding to the

NOP and the Scoping Meeting were submitted to the City by various public agencies, interested organizations and individuals. The NOP, Initial Study, and NOP comment letters are included in Appendix A of the Draft EIR.

Draft EIR. The Draft EIR evaluated in detail the potential effects of the Project. It also analyzed the effects of a reasonable range of alternatives to the Project, including a “No Project” alternative. The Draft EIR for the Project (State Clearinghouse No. 2016061048) incorporated herein by reference in full, was prepared pursuant to CEQA and State, Agency, and City CEQA Guidelines (City of Los Angeles California Environmental Quality Act Guidelines). The Draft EIR was circulated for a 46-day public comment period beginning on October 4, 2018 and ending on November 19, 2018. A Notice of Availability (NOA) was distributed on October 4, 2018 to all property owners within 500 feet of the Project Site and interested parties, which informed them of where they could view the document and how to comment. The Draft EIR was available to the public at the City of Los Angeles, Department of City Planning, and the following local libraries: Los Angeles Central Library, Chinatown Branch Library, Echo Park Branch Library, Felipe de Neve Branch Library, Little Tokyo Branch Library, and Pico Union Branch Library. A copy of the document was also posted online at <https://planning.lacity.org>. Notices were filed with the County Clerk on October 14, 2018.

Notice of Completion. A Notice of Completion was sent with the Draft EIR to the Governor’s Office of Planning and Research State Clearinghouse for distribution to State Agencies on October 4, 2018, and notice was provided in newspapers of general and/or regional circulation.

Final EIR. The City released a Final EIR for the Project on August 14, 2019, which is hereby incorporated by reference in full. The Final EIR constitutes the second part of the EIR for the Project and is intended to be a companion to the Draft EIR. The Final EIR also incorporates the Draft EIR by reference. Pursuant to Section 15088 of the CEQA Guidelines, the City, as Lead Agency, reviewed all comments received during the review period for the Draft EIR and responded to each comment in Section III, Responses to Comments, of the Final EIR. In addition, the Final EIR contains a Mitigation Monitoring Program for the Project, included in Section V, Mitigation Monitoring Program, of the Final EIR. On August 14, 2019, responses were sent to all public agencies that made comments on the Draft EIR at least 10 days prior to certification of the EIR pursuant to CEQA Guidelines Section 15088(b). Notices regarding availability of the Final EIR were also sent to property owners and occupants within a 500-foot radius of the Project Site, as well as anyone who commented on the Draft EIR, and interested parties.

Public Hearing. A noticed public hearing for the Project was held jointly by the Deputy Advisory Agency and Hearing Officer on behalf of the City Planning Commission on August 28, 2019.

Errata. An Errata was released on September 6, 2019 to clarify the language of Mitigation Measure L-1.

In addition, the following documents and other materials also constitute the administrative record upon which the City approved the Project. The following information is incorporated by reference and made part of the record supporting these Findings of Fact:

- All Project plans and application materials including supportive technical reports;
- The City of Los Angeles General Plan and related EIR;

- The Southern California Association of Governments (SCAG)'s 2016-2040 Regional Transportation Plan/Sustainable Communities Strategy (RTP/SCS) and related EIR (SCH No. 2015031035);
- Municipal Code of the City of Los Angeles, including but not limited to the Zoning Ordinance and Subdivision Ordinance;
- All records of decision, resolutions, staff reports, memoranda, maps, exhibits, letters, minutes of meetings, summaries, and other documents approved, reviewed, relied upon, or prepared by any City commissions, boards, officials, consultants, or staff relating to the Project;
- Any documents expressly cited in these Findings of Fact, in addition to those cited above; and
- Any and all other materials required for the record of proceedings by Public Resources Code Section 21167.6(e).

Pursuant to CEQA Section 21081.6(a)(2) and CEQA Guidelines Section 15091(e), the documents and other materials that constitute the record of proceedings upon which the City has based its decision are located in and may be obtained from the Department of City Planning, as the custodian of such documents and other materials that constitute the record of proceedings, located at the City of Los Angeles, Figueroa Plaza, 221 North Figueroa Street, Room 1350, Los Angeles, CA 90012.

In addition, copies of the Draft EIR and Final EIR are available on the Department of City Planning's website at <http://planning.lacity.org> (to locate the documents click on the "Environmental Review" tab on the left-hand side, then "Final EIR," and click on the Project title, where the Draft and Final EIR are made available). The Draft and Final EIR are also available at the following four Library Branches:

Los Angeles Central Library—630 West Fifth Street, Los Angeles, CA 90071

Pico Union Branch Library—1030 South Alvarado Street, Los Angeles, CA 90006

Little Tokyo Branch Library—203 South Los Angeles Street, Los Angeles, CA 90012

Echo Park Branch Library—1410 West Temple Street, Los Angeles, CA 90026

Chinatown Branch Library—639 North Hill Street, Los Angeles, CA 90012

Felipe de Neve Branch Library—2820 West 6th Street, Los Angeles, CA 90057

Project Description

The Project Site is located at 813-815 W. Olympic Boulevard and 947-951 S. Figueroa Street in the City of Los Angeles (City) and within the Central City Community Plan Area of the City. The Project Site is located on the northwest corner of the intersection of Olympic Boulevard and Figueroa Street. The Project Site is bounded by Figueroa Street on the east, Olympic Boulevard on the south, Cottage Place on the west, and an adjacent hotel (Hotel Figueroa) on the north. The Project Site comprises approximately 37,031 net square feet (or 0.85 acres). The Project Site is zoned C2-4D (Commercial, Height District 4 with Development Limitation) and is designated Regional Center Commercial in the Central City Community Plan. The Project Site is completely

developed with a single concrete block type structure containing a commercial car wash and detailing center and three smaller businesses.

The Project includes demolition and removal of all existing development on the Project Site and development of a single 57-story high-rise tower building containing up to 65,074 square feet of retail/commercial space (in three stories); 33,498 square feet of office space (in six stories); 10,801 square feet of hotel conference center/ballroom space (on one story); 8,448 square feet of residential condominium amenities (on the same story as the hotel conference center); 373 hotel rooms (216,065 square feet in 17 stories, including lobby/amenities level); 374 residential condominium units (435,731 square feet in 24 stories); and 9,556 square feet of penthouse amenity area (in two stories). A six-level subterranean parking garage would be located beneath the building, and eight levels of above ground parking would be provided within the podium level of the building. Six levels of the above ground parking would be wrapped with office uses on the Olympic Boulevard street frontage. Two additional stories dedicated to mechanical facilities would also be included in the proposed structure.

No Impact or Less than Significant without Mitigation

Impacts of the Project that were determined to have no impact or be less than significant in the EIR (including having a less than significant impact as a result of implementation of project design features and regulatory compliance measures) and that require no mitigation are identified below. The City has reviewed the record and agrees with the conclusion that the following environmental issues would not be significantly affected by the Project and therefore, no additional findings are needed. The following information does not repeat the full discussions of environmental impacts contained in the EIR. The City ratifies, adopts, and incorporates the analysis, explanation, findings, responses to comments, and conclusions of the EIR.

Impact Summary

Aesthetics

In 2013, the State of California enacted Senate Bill 743 (SB 743), which added Public Resources Code Section 21099, providing s that “aesthetic and parking impacts of a residential, mixed-use residential, or employment center project on an infill Site within a transit priority area shall not be considered significant impacts on the environment.” Because the Project Site is located approximately three blocks from the Metro’s Blue, Expo, and Red rail line station at 7th Street/Metro Center Station along Figueroa Street, the Project Site is situated within a transit priority area as defined in Public Resources Code Section 21099. Further, the Project Site is located in an urban area on a lot currently developed with existing buildings and surface parking uses. Therefore, based on the above, the analysis in these CEQA findings is for informational purposes only and not for determining whether the Project would result in significant impacts to the environment.

The Project would not have a substantial adverse effect on a scenic vista. Due to topography, vegetation, and development, medium and long-distance views are not available from the Project Site area. Also, the Project Site is not visible within any scenic views. The Project would not result in any impacts related to scenic vistas.

The Project would not substantially damage scenic resources, including but not limited to trees, rock outcroppings, and historic buildings or other locally recognized desirable aesthetic natural feature within a state-designated scenic highway. The Project Site is not located on a state designated scenic highway. Further, the Project Site does not contain any rock outcroppings or historic buildings, nor are any recognized scenic resources present within the immediate area.

The Project would not substantially degrade the existing visual character or quality of the Site or its surroundings. While the Project would increase building heights on the Project Site when compared to the tallest existing building on the Project Site, it would not be out of proportion with

respect to some of the other structures in the general vicinity. The Project would comply with Section 8 of the Downtown Design Guide by utilizing a variety of building materials, colors, and elements, such as balconies, the exoskeleton itself, green walls within the exoskeleton, and various wall planes.

The Project would not create a new source of substantial light or glare which would adversely affect day or nighttime views of the area. The Project would include interior and exterior lighting that complies with the LAMC provision that requires minimizing the effect of the new sources of lighting. Consequently, no substantial changes in nighttime illumination would occur that would adversely affect nighttime views in the area and prevent spillover lighting. Also, the Project would be required to use non-reflective glass, pursuant to LAMC Section 93.0117. The Project would not create a new source of substantial light or glare which would adversely affect day or nighttime views in the area. The Project would not result in any impacts related to light and glare.

The Project would not have cumulative aesthetic impacts. Since the Project falls within the applicable definitions in SB 743, the Project would not have the potential to contribute to any cumulative aesthetics impacts. Also, any of the related projects that fall within the applicable definitions in SB 743 also would not have the potential to contribute to any significant cumulative aesthetics impacts.

Cumulative Impacts

As discussed in Draft EIR Section A, Aesthetics the project would not considerably contribute to a cumulative impact related to Aesthetics.

Agriculture and Forestry Resources

The Project would not convert Prime Farmland, Unique Farmland, or Farmland of Statewide Importance (Farmland), as shown on the maps prepared pursuant to the Farmland Mapping and Monitoring Program of the California Resources Agency, to non-agricultural use. The Extent of Important Farmland Map Coverage maintained by the Division of Land Protection indicates that the Project Site is not included in the Important Farmland category. Therefore, the Project would not convert Prime Farmland, Unique Farmland, or Farmland of Statewide Importance (Farmland) to non-agricultural use, as shown on the maps prepared pursuant to the Farmland Mapping and Monitoring Program of the California Resources Agency, and no impact would occur.

The Project would not conflict with existing zoning for agricultural use, or a Williamson Act Contract. The Project Site is not zoned for agricultural use, and the Site is not under a Williamson Act Contract. Thus, the Project would not conflict with existing zoning for agricultural use, or a Williamson Act Contract. Therefore, no impacts related to this issue would occur.

The Project would not conflict with existing zoning for, or cause rezoning of, forest land (as defined in Public Resources Code section 12220[g]), timberland (as defined by Public Resources Code section 4526), or timberland zoned Timberland Production (as defined by Government Code section 51104 [g]). The Project Site is not zoned as forest land or timberland. Therefore, no impacts related to this issue would occur.

The Project would not result in the loss of forest land or conversion of forest land to non-forest use. The Project Site does not contain any forest land. Therefore, no impacts related to this issue would occur.

The Project would not involve other changes in the existing environment, which due to their location or nature, could result in conversion of Farmland, to non-agricultural use. The Project Site and surrounding area are within an urban environment. No agricultural uses are located on the Project Site or within the area. Therefore, no impacts related to this issue would occur.

Cumulative Impacts

As discussed in above, the project would not considerably contribute to a cumulative impact related to Agriculture and Forestry Resources.

Air Quality

The Project would not conflict with or obstruct implementation of the applicable air quality plan. The Project would neither conflict with SCAQMD's 2016 AQMP nor jeopardize the region's attainment of air quality standards. The Project's proposed land uses are allowed under the existing land use designation and zoning, and the Project's population growth would fall within the forecasted growth for the City.

The Project would not violate any air quality standard related to operational emissions or contribute substantially to an existing or projected air quality violation related to operational emissions. The Project's operational emissions would not exceed SCAQMD's regional significance thresholds for VOC, NO_x, CO, PM₁₀, and PM_{2.5} emissions. Likewise, localized emissions of NO₂, CO, PM₁₀, and PM_{2.5} from on-Site sources would not approach the SCAQMD's localized significance thresholds.

The Project would not expose sensitive receptors to substantial pollutant concentrations from operational emissions or toxic air contaminants. The Project would generate on-going emissions from area and energy sources that would generate negligible pollutant concentrations of CO, NO₂, PM_{2.5}, or PM₁₀ at nearby sensitive receptors. The Project would not result in any substantial emissions of toxic air contaminants ("TACs") during the construction or operations phase. Based on a screening assessment of the potential for human health impacts from the temporary emissions of diesel particulate matter from construction activities on sensitive receptors, the Project would not warrant the need for a health risk assessment associated with on-Site activities because the Project's construction phase would be temporary and because the Project's construction activities would not generate high concentrations of pollutants.

The Project would not create objectionable odors affecting a substantial number of people. While the Project does include restaurant uses, compliance with industry standard odor control practices, SCAQMD Rule 402 (Nuisance), and SCAQMD Best Available Control Technology Guidelines would limit potential objectionable odor impacts during the Project's long-term operations phase to a less than significant level.

The Project would not have significant cumulative impacts on air quality from operational emissions. Individual projects that generate emissions below SCAQMD's significance thresholds would not contribute considerably to any potential cumulative impact. The Project would not produce cumulatively considerable emissions of non-attainment pollutants at the regional or local level.

Cumulative Impacts

As discussed in Draft EIR Section B, Air Quality, the project would not considerably contribute to a cumulative impact related to obstruction or conflict with implementation of an applicable air quality plan, violation or any air quality standard related to operation emissions or contribute substantially to an existing or projected air quality violation related to operational emissions, exposure of sensitive receptors to substantial pollutant concentrations from operation emissions or toxic air contaminants, or creation of objectionable odors.

Biological Resources

The Project would not have a substantial adverse effect, either directly or through habitat modification, on any species identified as a candidate, sensitive, or special status species in local or regional plans, policies, or regulations by the California Department of Fish and Game or U.S. Fish and Wildlife Service.

The Project Site is located in an urbanized area of the City and is currently developed with buildings, paving, and minimal landscaping. The Project Site does not contain any natural open spaces, act as a wildlife corridor, nor likely possess any areas of significant biological resource value. No hydrological features are present on the Site and there are likely no sensitive habitats present. Due to the lack of biotic resources, no candidate, sensitive, or special status species

identified in local plans, policies, regulations, by the California Department of Fish and Game, the California Native Plant Society, or the U.S. Fish and Wildlife Service would be expected to occur on the Project Site.

The Project Site has minimal landscaping, nearly entirely on the outer perimeter along the parking lot. Vegetation on the Site consists of eight ornamental (non-protected) trees. Four street trees are planted in the sidewalks adjacent to the Project Site. There are no protected trees on the Site, and all existing trees would be removed as part of the Project. Due to the developed history of the Site and lack of native or substantial vegetation, the likelihood of a listed species being on-Site is negligible. Therefore, no impact would occur as a result of the Project.

The Project would not have a substantial adverse effect on any riparian habitat or other sensitive natural community identified in the City or regional plans, policies, regulations by the California Department of Fish and Game or U.S. Fish and Wildlife Service. The Project Site is occupied by a car wash and associated building. No riparian or other sensitive natural communities are located on or adjacent to the Project Site. Therefore, implementation of the Project would not result in any adverse impacts to riparian habitat or other sensitive natural communities and no impact would occur.

The Project would not have a substantial adverse effect on federally protected wetlands as defined by Section 404 of the Clean Water Act (including, but not limited to, marsh, vernal pool, coastal, etc.) through direct removal, filling, hydrological interruption, or other means. The Project Site is developed with a car wash and associated building, does not contain any wetlands or natural drainage channels, and is located in an urbanized area of the Central City Community Plan Area of the City. Thus, the Project Site does not have the potential to support any riparian or wetland habitat. No federally protected wetlands (e.g., emergent, forested/shrub, estuarine and marine deep water, estuarine and marine, freshwater pond, lake, riverine) occur on or in the vicinity of the Project Site. Therefore, the Project would not result in the direct removal, filling, or hydrological interruption of a federally protected wetland as defined by Section 404 of the Clean Water Act, and no impact to federally protected wetlands would occur as a result of the Project.

The Project would not interfere substantially with the movement of any native resident or migratory fish or wildlife species or with established native resident or migratory wildlife corridors, or impede the use of native wildlife nursery Sites.

Due to the developed history of the Site and lack of native or substantial vegetation, the likelihood of a migratory species being on-Site is negligible. In addition, no bodies of water exist on-Site to provide habitat for fish. Due to the highly urbanized surroundings, there are no wildlife corridors or native wildlife nursery Sites in the Project vicinity. As such, Project implementation would neither interfere with the movement of any native resident or migratory fish or wildlife species or with established native resident or migratory wildlife corridors nor impede the use of native wildlife nursery Sites. Therefore, the Project would not interfere with the movement of any resident or migratory fish or wildlife species. Therefore, no impact would occur.

The Project would not conflict with any local policies or ordinances protecting biological resources, such as tree preservation policy or ordinance (e.g., oak trees or California walnut woodlands). Local ordinances protecting biological resources are limited to the City's Protected Tree Ordinance, as modified by Ordinance 177,404. The amended Protected Tree Ordinance provides guidelines for the preservation of all Oak trees indigenous to California (excluding the Scrub Oak or *Quercus dumosa*), as well as the following tree species: Southern California Black Walnut (*Juglans californica* var. *californica*); Western Sycamore (*Platanus racemosa*); and California Bay (*Umbellularia californica*).

There is no vegetation on the Project Site, with the exception of non-native trees. Four street trees are planted in the sidewalks adjacent to the Project Site. No protected trees are located on or adjacent to the Project Site. If the Project proposes the removal of the City's right-of-way trees, a permit would need to be obtained from the City's Urban Forestry Division. Further, any tree

removal would need to comply with the ordinance. Therefore, the Project would not conflict with any tree preservation policy or ordinance, and no impacts would occur.

The Project would not conflict with the provisions of an adopted Habitat Conservation Plan, Natural Community Conservation Plan, or other approved local, regional, or state habitat conservation plan. The Project Site is located in an urbanized area of the City and is currently developed with buildings, paving, and minimal landscaping. The Site is not located in or adjacent to an existing City or County Significant Ecological Area. Additionally, there is no adopted Habitat Conservation Plan, Natural Community Conservation Plan, or other approved local, regional, or state habitat conservation plan that applies to the Project Site. Implementation of the Project would not conflict with any habitat conservation plans. Therefore, no impact would occur.

Cumulative Impacts

As discussed in above, the project would not considerably contribute to a cumulative impact related to Biological Resources.

Cultural Resources

The Project would not cause a substantial adverse change in the significance of a historical resource as defined in CEQA Guidelines section 15064.5. As discussed in Draft EIR Section D Cultural Resources, there are no historical resources on the Project Site, and no historical resources would be demolished, altered, or relocated as a result of the Project.

The Project would not directly or indirectly destroy a unique paleontological resource or Site or unique geologic feature. The Project Site is completely developed with buildings, paving, and minimal landscaping.

The Project would not disturb any human remains, including those interred outside of formal cemeteries. The Project Site is completely developed with buildings, paving, and minimal landscaping. No human remains are known to exist at the Project Site.

Cumulative Impacts

As discussed in Draft EIR Section D, Cultural Resources, the project would not considerably contribute to a cumulative impact related to Cultural Resources.

Geology and Soils

The Project would not exacerbate existing hazardous environmental conditions by bringing people or structures into areas that are susceptible to potential substantial adverse effects, including the risk of loss, injury, or death involving rupture of a known earthquake fault, as delineated on the most recent Alquist-Priolo Earthquake Fault Zoning Map issued by the State Geologist for the area or based on other substantial evidence of a known fault. As discussed in Draft EIR Section E Geology and Soils, the Project Site is not located within an Alquist-Priolo Earthquake Fault Zone, and no known faults exist on the Project Site.

The Project would not exacerbate existing hazardous environmental conditions by bringing people or structures into areas that are susceptible to potential substantial adverse effects, including the risk of loss, injury, or death involving strong seismic ground-shaking. Conformance with California Building Code standards would ensure that no significant impacts related to ground shaking would occur.

The Project would not exacerbate existing hazardous environmental conditions by bringing people or structures into areas that are susceptible to potential substantial adverse effects, including the risk of loss, injury, or death involving seismic-related ground failure, including liquefaction. As discussed in Draft EIR Section E Geology and Soils, the Project Site is not located in an area designated as having a potential for liquefaction or ground subsidence.

The Project would not result in substantial soil erosion or the loss of topsoil. During the Project's construction phase, activities such as excavation, grading, and Site preparation could leave soils

at the Project Site susceptible to soil erosion. The Project Applicant would be required to comply with SCAQMD Rule 403 – Fugitive Dust to minimize wind and water-borne erosion at the Site, as well as prepare and implement a Stormwater Pollution Prevention Plan (“SWPPP”), in accordance with the National Pollutant Discharge Elimination System (“NPDES”) General Permit for Discharges of Storm Water Associated with Construction Activity and Land Disturbance Activities.

The Project would not be located on a geologic unit or soil that is unstable, or that would become unstable as a result of the Project, and potentially result in on- or off-Site landslide, lateral spreading, subsidence, liquefaction or collapse. As discussed in Draft EIR Section E Geology and Soils, the Project Site is not located in an area designated as having a potential for liquefaction or ground subsidence.

The Project would not be developed on a Site that is located on expansive soil, as defined in Table 18-1-B of the Uniform Building Code (1994), creating substantial risks to life or property caused in whole or in part by the Project exacerbating the expansive soil conditions. Based on the depth of the foundation system, as well as the vertical bearing pressure from the foundations, the proposed structure would not be prone to the effects of expansive soils.

The Project would not be developed on soils incapable of adequately supporting the use of septic tanks or alternative wastewater disposal systems where sewers are not available for the disposal of wastewater. The Project would not include use of a septic tank.

Cumulative Impacts

As discussed in Draft EIR Section E, Geology and Soils, the project would not considerably contribute to a cumulative impact related to Geology and Soils.

Greenhouse Gas (“GHG”) Emissions

The Project would not generate GHG emissions, either directly or indirectly, that may have a significant impact on the environment. The Project would be required to comply with numerous regulatory compliance measures, particularly those associated with the City’s Green Building Code, that would reduce the Project’s GHG emissions profile and would represent improvements with respect to the “No Action Taken” (“NAT”) scenario. In addition, the Project would include rooftop photovoltaic panels, calculated to provide power to common and amenity areas (refer to GHG-PDF-1) and façade photovoltaic panels contained within the glass panels to provide power to the building exterior lighting and LED lighting (refer to GHG-PDF-2). Thus, the Project’s emissions reductions as compared to the NAT Scenario demonstrate consistency with GHG Reduction Plans, Executive Orders S-3-05 and B-30-15, SCAG’s 2016-2040 RTP/SCS, and the City’s Green Building Ordinance. As a result of this and the analysis of net emissions, the Project’s contribution to global climate change would not be cumulatively considerable and would be less than significant.

The NAT scenario was provided in the Draft EIR for informational purposes and to support the City’s evaluation of the Project’s emissions and consistency with applicable GHG reduction plans and policies. The Draft EIR’s analysis included potential emissions under the NAT scenario and from the Project at build-out based on actions and mandates expected to be in force in 2020. Early-action measures identified in CARB’s Climate Change Scoping Plan that have not yet been approved were not credited in that analysis. By not speculating on potential regulatory conditions, the analysis took a conservative approach that likely overestimated the Project’s GHG emissions at build-out.

The Project would not conflict with an applicable plan, policy, or regulation adopted for the purpose of reducing GHG emissions. As discussed in Draft EIR Section F, Greenhouse Gas Emissions, the Project’s impact attributable to GHG emissions was evaluated based on consistency with applicable regulatory plans and policies to reduce GHG emissions, and was found not in conflict:

The Project would not have a significant cumulative impact on GHG emissions. As discussed in Draft EIR Section F, Greenhouse Gas Emissions, the Project would be consistent with the

approach outlined in CARB's *Climate Change Scoping Plan*.

Currently, there are no applicable CARB, SCAQMD, or City significance thresholds or specific reduction targets, and no approved policy or guidance to assist in determining significance at the project or cumulative levels. Therefore, consistent with CEQA Guideline Section 15064h(3), the City as Lead Agency has determined that the Project's contribution to cumulative GHG emissions and global climate change would be less than significant if the Project would be consistent with the applicable regulatory plans and policies to reduce GHG emissions, pursuant to Senate Bill 97, as described in the previous sub-section.

As noted earlier, the Project would be consistent with these climate action plans at the state, regional, and local level. As such, the Project would not conflict with any applicable plan, policy, or regulation of an agency adopted for the purpose of reducing the emissions of GHGs. In the absence of adopted standards and established significance thresholds, and given this consistency, it is concluded that the Project's impacts are not cumulatively considerable.

Project Design Features

With the implementation of GHG-PDF-1 and GHG-PDF-2, the Project and cumulative impacts related to GHG emissions are less than significant and no mitigation measures are required.

GHG-PDF-1: The Project includes rooftop photovoltaic panels, calculated to provide power to common and amenity areas (refer to Figure III-4 and Figure III-35 in Section III [Project Description] of the Draft EIR).

GHG-PDF-2: The Project includes façade photovoltaic panels contained within the glass panels to provide power to the building exterior lighting and LED lighting (refer to Figure III-32 and Figure III-33 in Section III [Project Description] of the Draft EIR).

Cumulative Impacts

As discussed in Draft EIR Section F, Greenhouse Gas Emissions, the project would not considerably contribute to a cumulative impact related to Greenhouse Gas Emissions.

Hazards and Hazardous Materials

The Project would not create a significant hazard to the public or environment through the routine transport, use, or disposal of hazardous materials. As discussed in Draft EIR Section G Hazards and Hazardous Materials, compliance with applicable city, state, and federal regulations related to the handling, storage, transport, and disposal of hazardous materials and waste during operation of the Project would ensure that no significant hazard to the public or the environment occurs. Therefore, Project impacts related to this issue would be less than significant.

The Project would not emit hazardous emissions or handle hazardous or acutely hazardous materials, substances, or waste within one-quarter mile of an existing or proposed school. The school closest to the Project Site is the Los Angeles Universal Pre-school, located approximately one block northeast of the Project Site. Therefore, no impacts related to this issue would occur.

The Project Site is not included on a list of hazardous materials Sites compiled pursuant to Government Code Section 65962.5 and as a result, the Project would not create a significant hazard to the public or the environment. The Project is not included on any list compiled pursuant to Government Code Section 65962.5. Thus, the Project would not create a significant hazard to the public or the environment as a result of being listed on a list of hazardous materials Sites compiled pursuant to Government Code Section 65962.5. Therefore, no impacts related to this issue would occur.

The Project would not result in an airport safety hazard for people residing or working in the Project Site area. The Project Site is not located within two miles of a public airport. The closest airport is the Bob Hope Airport located approximately 15.6 miles northwest of the Site. Thus, the Project would not result in a safety hazard associated with an airport for people residing or working

in the Project Site area. Based on the above, development of the Project would not have the potential to exacerbate current environmental conditions as to result in a safety hazard for people residing or working the Project Site area. Therefore, no impacts related to this issue would occur.

The Project would not result in a private airstrip safety hazard for people residing or working in the Project Site area. The Project Site is not located within the vicinity of a private airstrip. The closest airport is the Bob Hope Airport located approximately 15.6 miles northwest of the Site. Thus, the Project would not result in a safety hazard associated with an airport for people residing or working in the Project Site area. Based on the above, development of the Project would not have the potential to exacerbate current environmental conditions as to result in a safety hazard for people residing or working the Project Site area. Therefore, no impacts related to this issue would occur.

The Project would not impair implementation of or physically interfere with an adopted emergency response plan or emergency evacuation plan. During the Project's construction phase, the Project could require temporary roadway lane closures that run adjacent to the Project Site. Additionally, because the Project would exceed 75 feet in height, potential impacts associated with the Project's height and limitations of emergency response equipment could occur. However, prior to the issuance of a building permit, the Project Applicant would be required by the City of Los Angeles Fire Department ("LAFD") and the City's Department of Building and Safety to develop an emergency response plan for the Project in consultation with the LAFD. The emergency response plan shall include but not be limited to the following: mapping of emergency exits, evacuation routes for vehicles and pedestrians, location of nearest hospitals, and fire departments. Preparation and implementation of the Project-specific emergency response plan would ensure that Project impacts related to emergency response would be less than significant.

The Project would not expose people or structures to a significant risk of loss, injury or death involving wildland fires, including where wildlands are adjacent to urbanized areas or where residences are intermixed with wildlands. The Project is located in a highly urbanized area of the City that is not subject to wildland fires. Therefore, the Project would not expose people or structures to a significant risk of loss, injury or death involving wildland fires, including where wildlands are adjacent to urbanized areas or where residences are intermixed with wildlands. Based on the above, development of the Project would not have the potential to exacerbate existing environmental conditions so as to increase the potential to expose people or structures to significant risk of loss, injury or death involving wildland fires.

Cumulative Impacts

As discussed in Draft EIR Section G, Hazards and Hazardous Materials, the project would not considerably contribute to a cumulative impact related to Hazards and Hazardous Materials.

Hydrology and Water Quality

The Project would not violate any water quality standards or waste discharge requirements.

As discussed in the project initial study, the project would be required to comply with NPDES requirements and BMPs for construction, as well as LID requirements during operation. Conformance with these regulations would ensure construction and operational activities would result in less-than-significant impacts and would not violate water quality standards, waste discharge requirements, or otherwise substantially degrade water quality.

The Project would not substantially deplete groundwater supplies or interfere substantially with groundwater recharge such that there would be a net deficit in aquifer volume or a lowering of the local groundwater table level (e.g., the production rate of pre-existing nearby wells would drop to a level which would not support existing land uses or planned uses for which permits have been granted). There are no permeable surfaces on the Project Site. Both currently, and after construction groundwater recharge from the site would be negligible. The regional aquifer in the Los Angeles Basin that is a supply of drinking water for the region is located anywhere from

approximately 300 to 1,000 feet below the surface of the Project Site. The Project includes excavation to approximately 64 below ground surface. Groundwater encountered within this depth would be perched groundwater, which would be removed from the Site in accordance with applicable LARWQCB requirements. Additionally, all water consumption associated with the Project would be supplied by the Metropolitan Water District (MWD) and not from groundwater beneath the Project Site. Thus, there would be no impact to groundwater supplies.

The Project would not substantially alter the existing drainage pattern of the Site or area, including through the alteration of the course of a stream or river, in a manner, which would result in substantial erosion or siltation on- or off-Site. There are no natural watercourses on the Project Site or in the vicinity of the Site. The Project Site is developed with paved surfaces and current stormwater runoff flows to the local storm drain system. Further, the project would comply with NPDES best management practices during construction and LID regulations during operations. Therefore, the Project would result in a less than significant impact in relation to surface water hydrology and would not result in substantial erosion or siltation on- or off-Site.

The Project would not substantially alter the existing drainage pattern of the Site or area, including through the alteration of the course of a stream or river, or substantially increase the rate or amount of surface runoff in a manner which would result in flooding on- or off-Site., Construction and operation of the Project would not result in a significant increase in Site runoff or any changes in the local drainage patterns that would result in flooding on- or off-Site. The Project Applicant would be required to prepare a SWPPP and implement BMPs to reduce runoff and preserve water quality during construction of the Project. Compliance with the LID Ordinance would also reduce the amount of surface water runoff leaving the Project Site as compared to the current conditions. Impacts related to substantial alteration or drainage patterns or increase in runoff, which would cause flooding would be less than significant.

The Project would not create or contribute runoff water which would exceed the capacity of existing or planned stormwater drainage systems or provide substantial additional sources of polluted runoff. Runoff from the Project Site currently is and would continue to be collected on the Site and directed towards existing storm drains in the Project vicinity that have adequate capacity to serve the Site. Pursuant to City policy, stormwater retention would be required as part of the LID/SUSMP implementation features (despite no increase of imperviousness surfaces on the Site). Any contaminants gathered during routine cleaning of construction equipment would be disposed of in compliance with applicable stormwater pollution prevention permits. Further, pollutants from the subterranean parking garage and surface parking lot would be subject to the requirements and regulations of the NPDES and applicable LID Ordinance requirements. The Project would not create or contribute surface runoff that would exceed the capacity of existing or planned stormwater drainage systems or provide substantial additional sources of polluted runoff. Impacts would be less than significant.

The Project would not otherwise substantially degrade water quality. During construction, groundwater dewatering would be required on the Project Site and would occur in compliance with requirements of the Waste Discharge Requirements for Discharges of Groundwater from Construction and Project Dewatering to Surface Waters in Coastal Watersheds of Los Angeles and Ventura Counties (Order No. R4-2008-0032 NPDES No. CAG994004) or subsequent permit. The Project would be required to comply with the NPDES General Construction Permit, the City's Stormwater and Urban Runoff Pollution Control regulations (Ordinance No. 172,176 and No. 173,494), and the City's LID Ordinance. Compliance with these plans would ensure that operation of the Project would not violate water quality standard and discharge requirements or otherwise substantially degrade water quality. Impacts would be less than significant.

The Project would not place housing within a 100-year flood hazard area as mapped on a federal Flood Hazard Boundary or Flood Insurance Rate Map or other flood hazard delineation map. As discussed in the Initial Study prepared for the project, the Project Site is located in an area of insignificant flood risk (Zone X) and is not located within a 100-year zone, as mapped by the

Federal Emergency Management Agency (FEMA). Thus, the Project would not place housing within a 100-year flood hazard area as mapped on a federal Flood Hazard Boundary or Flood Insurance Rate Map or other flood hazard delineation map. Therefore, no impacts related to this issue would occur.

The Project would not place within a 100-year flood hazard area structures which would impede or redirect flood flows. As discussed above, the Project Site is not located within a 100-year flood hazard area. Thus, the Project would not place housing within a 100-year flood hazard area and structures would not impede or redirect flood flows. Therefore, no impacts related to this issue would occur.

The Project would not expose people or structures to a significant risk of loss, injury or death involving flooding, including flooding as a result of the failure of a levee or dam. The Project Site is not located in any area susceptible to floods associated with a levee or dam. Therefore, the Project would not expose people or structures to a significant risk of loss, injury, or death involving flooding, including flooding as a result of the failure of a levee or dam.

The Project would not expose people or structures to a significant risk of loss, injury or death involving inundation by seiche, tsunami, or mudflow. As discussed in the Initial Study prepared for the project, the Project Site is not in an area susceptible to seiches, tsunamis, or mudflows, because the Project Site is not located in proximity to any large bodies of water and is not located near any hillsides. Therefore, the Project would not expose people or structures to a significant risk of loss, injury, or death involving inundation by seiche, tsunami, or mudflow.

Cumulative Impacts

As discussed in above, the project would not considerably contribute to a cumulative impact related to Hydrology and Water Quality.

Land Use and Planning

The Project would not physically divide an established community. The Project Site is located in an urbanized area of the City in the Central City Community Plan Area. The Project would not create a physical barrier causing an impediment to travel or access the area surrounding the Project Site. Thus, the Project would not physically divide, disrupt, or isolate an established community. Therefore, no impacts related to this issue would occur.

The Project would not conflict with any applicable land use plan, policy, or regulation of an agency with jurisdiction over the Project (including, but not limited to the general plan, specific plan, local coastal program, or zoning ordinance) adopted for the purpose of avoiding or mitigating an environmental effect. As discussed in Draft EIR Section H, Land Use and Planning, the Project's conformance with applicable land use plans was analyzed, and found to be in conformance. Therefore, impacts related to conflict with any applicable land use plan, policy, , or regulation of an agency with jurisdiction over the Project (including, but not limited to the general plan, specific plan, local coastal program, or zoning ordinance) adopted for the purpose of avoiding or mitigating an environmental effect would be less than significant.

The Project would not conflict with any applicable habitat conservation plan or natural community conservation plan. The Project Site is located in an urbanized area of the City and developed a building, paving, and minimal landscaping. The Project Site does not support any natural habitat and/or natural community. There are no sensitive ecological areas and/or other biological resources on and/or near the Project Site. Thus, development of the Project Site is not subject to any applicable habitat conservation plan or natural community conservation plan. The Project would not conflict with any applicable habitat conservation plan or natural community conservation plan.

The Project would not have significant cumulative impacts on land use and planning. Cumulative land use impacts could occur if any of the related projects would result in incompatible land uses, or result in land uses that are inconsistent with adopted land use plans when combined with the

impacts of the Project. As discussed in Draft EIR Section H, Land Use, the project would not result in a physical separation of a community, conflict with plans, policies, or regulations adopted to avoid or mitigate environmental effects, or an adopted habitat plan, therefore, the project would not contribute considerably to cumulative land use and planning impact. The associated related projects would be required to address land use and planning concerns in the respective environmental documents prepared for those projects, while discretionary projects would be in conformance with plans and unlikely to physically separate a community.

Mineral Resources

The Project would not result in the loss of availability of a known mineral resource that would be of value to the region and the residents of the state. As discussed in the Initial Study prepared for the project, there are no known mineral resources on the Project Site or in the vicinity. Thus, the Project would not result in the loss of availability of a known mineral resource that would be of value to the region and the residents of the state. Therefore, no impacts related to issue would occur.

The Project would not result in the loss of availability of a locally-important mineral resource recovery Site delineated on a local general plan, specific plan or other land use plan. As discussed in the Initial Study prepared for the project, the Project Site is not identified as a mineral resource recovery Site. Thus, the Project would not result in the loss of availability of a locally-important mineral resource recovery Site delineated on a local general plan, specific plan or other land use plan. Therefore, no impacts related the loss of availability of a locally important mineral resource recovery site delineated on a local plan would occur.

Noise

The Project would not result in a substantial permanent increase in ambient noise levels in the Project Site vicinity above levels existing without the Project. As discussed in Draft EIR Section I, Noise, the Project would not result in a substantial increase in ambient noise levels in the vicinity of the Project.

The Project would not result in a substantial temporary or periodic increase in ambient noise levels in the Project Site vicinity above levels existing without the Project. As discussed in Draft EIR Section I, Noise, the Project would not result in a substantial increase in ambient noise levels in the vicinity of the Project.

The Project would not expose people residing or working in the Project Site area to excessive noise levels associated with an airport or private airstrip. As discussed in Draft EIR Section I, Noise, the Project Site is not located within an airport land use plan or within two miles of a public airport or public use airport. The closest airport to the Project Site is the Bob Hope Airport located approximately 15.4 miles northwest of the Site. Based on the above the Project would not exacerbate the existing airport noise conditions so as to expose people residing or working in the Project Site area to excessive noise levels. Therefore, the Project would not expose people residing or working in the Project Site area to excessive noise levels and no impact would occur.

The Project would not have significant cumulative impacts related to noise. As discussed in Draft EIR Section I, Noise, the project would not result in a cumulatively considerable contribution to a cumulative impact.

Population and Housing

The Project would not induce substantial population growth in the area, either directly (for example, by proposing new homes or businesses) or indirectly (for example, through extension of roads or other infrastructure). As discussed in Draft EIR Section J, Population and Housing, the project's population is accounted for in SCAG growth projections for the City and region. Thus, the Project would not result in unexpected population growth. Therefore, Project impacts related to population and housing would be less than significant.

The Project would not displace substantial numbers of existing housing, necessitating the construction of replacement housing elsewhere. As discussed in Draft EIR Section J, Population and Housing, no housing currently exists on the Project Site. The Project Site is currently developed with a commercial building, paving, and minimal landscaping. The Project would not displace any existing housing, necessitating the construction of replacement housing elsewhere. Thus, no impact would occur.

The Project would not displace substantial numbers of people, necessitating the construction of replacement housing elsewhere. The Project Site is not developed with any residential units. Therefore, the Project would not displace any residents, necessitating the construction of replacement housing elsewhere. Thus, no impact would occur.

The Project would not have significant cumulative impacts on population and housing. As discussed in Draft EIR Section J, Population and Housing, the Project's housing and population growth would be consistent with the anticipated growth for the Community Plan Area and the City. The Project would not create unplanned growth, and impacts related to population and housing would be less than significant. As such, regardless of whether the related projects would result in unplanned growth, the Project would not have the potential to contribute to any potential cumulative impact.

Public Services – Fire Protection

The Project would not result in substantial adverse physical impacts associated with the provision of new or physically altered governmental facilities, or the need for new or physically altered governmental facilities, the construction of which could cause significant environmental impacts, in order to maintain acceptable service ratios, response times, or other performance objectives for fire protection. As discussed in Draft EIR Section K.1, Fire Protection, project impacts with respect to the provision of new or altered governmental facilities (Fire facilities) would be less than significant.

The Project would not have significant cumulative impacts related to the provision of fire protection public services. As discussed in Draft EIR Section K.1, Fire Protection, cumulative impacts on fire protection services would be less than significant.

Public Services – Police Protection

The Project would not result in substantial adverse physical impacts associated with the provision of new or physically altered governmental facilities, or the need for new or physically altered governmental facilities, the construction of which could cause significant environmental impacts, in order to maintain acceptable service ratios, response times, or other performance objectives for police protection. As discussed in Draft EIR Section K.2, Police Protection, project impacts with respect to the provision of new or altered governmental facilities (Police facilities) would be less than significant.

The Project would not have significant cumulative impacts on the provision of police protection public services. As discussed in Draft EIR Section K.2, Police Protection, cumulative impacts related to police protection services would be less than significant.

Public Services – Schools

The Project would not result in substantial adverse physical impacts associated with the provision of new or physically altered school facilities, need for new or physically altered schools facilities, the construction of which could cause significant environmental impacts, in order to maintain acceptable service ratios or performance objectives for the school district. As discussed in Draft EIR Section K.3, School Services, project impacts with respect to the provision of new or altered governmental facilities (School facilities) would be less than significant, in addition the project would be required to pay fees pursuant to state law (SB 50). Therefore, impacts are less than significant.

The Project would not result in significant cumulative impacts on the provision of public school services. As discussed in Draft EIR Section K.3, School Services, compliance with the provisions of SB 50 is deemed to provide full and complete mitigation of school facilities impacts. Therefore, cumulative impacts to school services would be less than significant.

Public Services – Parks and Recreational Services

The Project would not result in substantial adverse physical impacts associated with the provision of new or physically altered governmental facilities, need for new or physically altered governmental facilities, the construction of which could cause significant environmental impacts, in order to maintain acceptable service ratios, response times or other performance objectives for parks. As discussed in Draft EIR Section K.4, Parks and Recreational Services, the Project Applicant would be required to pay Parkland Fee to the City to mitigate for the Project's demand for parks and recreational facilities. Additionally, as shown on Table IV.K.4-2 of the Draft EIR, the Project would include open space in excess of LAMC requirements. Therefore, no significant impacts related to this issue would occur.

The Project would not increase the use of existing neighborhood and regional parks or other recreational facilities such that substantial physical deterioration of the facility would occur or be accelerated. As discussed in Draft EIR Section K.4, Parks and Recreational Services, the Project Applicant would be required to pay Parkland Fee to the City to mitigate for the Project's demand for parks and recreational facilities. Additionally, as shown on Table IV.K.4-2 of the Draft EIR, the Project would include open space in excess of LAMC requirements. Therefore, no significant impacts related to this issue would occur.

The Project would not include recreational facilities or require the construction or expansion of recreational facilities which might have an adverse physical effect on the environment. As discussed in Draft EIR Section K.4, Parks and Recreational Services, the Project does not include recreational facilities or require the construction or expansion of recreational facilities that might have an adverse physical effect on the environment, and no impacts related to this issue would occur.

The Project would not have a significant cumulative impact on the provision of public parks and recreational services. As discussed in Draft EIR Section K.4, Parks and Recreational Services, the Project Applicant would be required to pay Parkland Fee to the City to mitigate for the Project's demand for parks and recreational facilities. Additionally, the related projects would similarly be required to comply with regulatory open space requirements and impact fees. Therefore, cumulative impacts on parks and recreational facilities would be less than significant.

Public Services – Other Public Facilities

The Project would not result in substantial adverse physical impacts associated with the provision of new or physically altered governmental facilities, need for new or physically altered governmental facilities, the construction of which could cause significant environmental impacts, in order to maintain acceptable service ratios, response times or other performance objectives for library services. As discussed in Draft EIR Section K.5, Library services, the Project would not result in the alteration or provision of new governmental facilities (libraries) which would result in significant environmental impacts. Therefore, Project impacts on library services would be insignificant.

The Project would not have significant cumulative impacts on the provision of public library services. As discussed in Draft EIR Section K.5, Libraries, the Project would not result in the provision of new or altered government facilities. Therefore, the projects contribution to cumulative impacts to library services would not be considerable.

Transportation/Traffic

The Project would not conflict with an applicable congestion management program, including but not limited to level of service standards and travel demand measures, or other standards

established by the county congestion management agency for designated roads or highways. As discussed in Draft EIR Section L, Transportation/Traffic, the Project would not conflict with the 2010 Congestion Management Plan. Therefore, impacts would be less than significant.

The Project would not result in a change in air traffic patterns, including either an increase in traffic levels or a change in location that results in substantial safety risks. As discussed in Draft EIR Section L, Transportation/Traffic, the nearest airport is Bob Hope Airport, 15.6 miles away. Therefore, no impacts related to this issue would occur.

The Project would not substantially increase hazards due to a design feature (e.g., sharp curves or dangerous intersections) or incompatible uses (e.g., farm equipment). As discussed in Draft EIR Section L, Transportation/Traffic, the Project does not include development of any new roadways or intersections. Therefore, Project impacts related to roadway hazards would be less than significant.

The Project would not result in inadequate emergency access. As discussed in Draft EIR Section L, Transportation/Traffic, through compliance with existing City regulations, the Project would not result in any significant impacts related to emergency access.

The Project would not conflict with adopted policies, plans, or programs regarding public transit, bicycle, or pedestrian facilities, or otherwise decrease the performance or safety of such facilities. As discussed in Draft EIR Section L, Transportation/Traffic, the Project would not conflict with adopted policies, plans, or programs regarding public transit, bicycle, or pedestrian facilities, or otherwise decrease the performance or safety of such facilities, and impacts would be less than significant.

Tribal Cultural Resources

The Project would not cause a substantial adverse change in the significance of a tribal cultural resource, defined in Public Resources Code section 21074 as either a Site, feature, place, cultural landscape that is geographically defined in terms of size and scope of the landscape, sacred place, or object with cultural value to a California Native tribe, and that is listed or eligible for listing in the California Register of Historical Resources, or in a local register of historical resources as defined in Public Resources Code section 5020.1(k). As discussed in Draft EIR Section N, Tribal Cultural Resources, no previously recorded tribal cultural resources were identified within the Project Site area. The Project would not adversely affect known tribal cultural resources. As such, no significant impacts related to a substantial adverse change in the significance of a defined tribal cultural resource would occur.

The Project would not cause a substantial adverse change in the significance of a tribal cultural resource, defined in Public Resources Code section 21074 as either a Site, feature, place, cultural landscape that is geographically defined in terms of size and scope of the landscape, sacred place, or object with cultural value to a California Native tribe, and that is resource determined by the lead agency, in its discretion and supported by substantial evidence, to be significant pursuant to criteria set forth in subdivision (c) of Public Resources Code Section 5024.1, the lead agency shall consider the significance of the resource to a California Native American tribe. As discussed in Draft EIR Section N, Tribal Cultural Resources, no significant impacts related to a substantial adverse change in the significance of a defined tribal cultural resource would occur.

The Project would not have significant cumulative impacts related to tribal cultural resources. As discussed in Draft EIR Section N, Tribal Cultural Resources, the degree to which tribal cultural resources exist or could potential exist at the Sites of the related projects listed on Table II-2 in Section II (Environmental Setting) of the Draft EIR is unknown. However, as with the Project, the City would be required comply with AB 52 and contact appropriate tribal parties to offer consultation and conduct the consultation, if requested by the tribal parties. If consultation for those related projects identifies tribal cultural resources, then those related projects would be required to implement appropriate mitigation, as recommended/required by the tribal parties and/or City. As discussed above, the Project would not result in any significant impacts to any

tribal cultural resource. Thus, the Project would not have the potential to contribute toward any significant cumulative impacts related to tribal cultural resources. Therefore, cumulative impacts related to tribal cultural resources would be less than significant.

Utilities and Service Systems

The Project would not exceed wastewater treatment requirements of the applicable Regional Water Quality Control Board. As discussed in Draft EIR Section M, Utilities and Services Systems – Wastewater, the Project would be required to comply with the NPDES General Construction Permit including the preparation of a SWPPP and implementation of BMPs, required to minimize soil erosion and sedimentation from entering the storm drains during the construction period. In addition, the Project would be subject to the City's Stormwater and Urban Runoff Pollution Control regulations (Ordinance No. 172,176 and No. 173,494) Compliance with the NPDES and implementation of the SWPPP and BMPs, as well as the City's discharge requirements would ensure that construction stormwater runoff would not violate water quality and/or discharge requirements. During operation, the Project would be required to comply with the City's LID Ordinance. Compliance with the LID Plan and SUSMP, including the implementation of BMPs, would ensure that operation of the Project would not violate water quality standard and discharge requirements or otherwise substantially degrade water quality. The Project would not result in any significant impacts related to wastewater treatment requirements.

The Project would not require or result in the construction of a new water or wastewater treatment facility or expansion of existing facilities, the construction of which could cause significant environmental effects. As discussed in Draft EIR Sections M.1-M.2, Utilities and Services systems, sufficient water and wastewater facilities exist to serve the project site.. Therefore, Project impacts related to construction of new water or wastewater facilities would be less than significant.

The Project would not require or result in the construction of new storm water drainage facilities or expansion of existing facilities, the construction of which could cause significant environmental effects. As discussed in Draft EIR Sections M.1-M.2, Utilities and Services systems, pursuant to City policy, stormwater retention would be required as part of the LID/SUSMP implementation features. Additionally, the Project would be required to demonstrate compliance with LID Ordinance standards and retain or treat the first three-quarters inch of rainfall in a 24-hour period. The Project would not create or contribute surface runoff that would exceed the capacity of existing or planned stormwater drainage systems or provide substantial additional sources of polluted runoff. Impacts would be less than significant.

There would be sufficient water supplies available to serve the Project from existing entitlements and resources, or new or expanded facilities were needed. Pursuant to SB 610 and SB 221, a Water Supply Assessment was prepared for the Project by LADWP (refer to Appendix J of the Draft EIR). As shown on Table IV.M.2-3 of the Draft EIR, LADWP estimates that the Project would consume approximately 218 acre-feet per year ("AFY") of water.

The Project Applicant has voluntarily agreed to incorporate the water conservation measures listed below into the Project that are beyond those required by law (refer to WATER-PDF-1). The estimated additional water conservation calculations associated with these measures outlined on Table IV.M.2-4 of the Draft EIR.

As discussed in Draft EIR Sections M.1-M.2, Utilities and Services Systems, according to LADWP, the Project's water demand has been accounted for in the City's overall total demand projections in the LADWP 2015 UWMP using a service area-wide approach that does not rely on individual development demand. The LADWP 2015 UWMP used SCAG's RTP data that provide for more reliable water demand forecasts, taking into account changes in population, housing units, and employment.

Based on Planning Department's determination that the Project is consistent with the demographic forecasts for the City from SCAG's 2012-2035 RTP/SCS, LADWP finds that the

Project's water demand is included in the City's LADWP 2015 UWMP water demand projection. Furthermore, the LADWP 2015 UWMP forecasts adequate water supplies to meet all projected water demand in the City through the year 2040.

LADWP concludes that the 218 AFY increase in the total water demand for the Project falls within the available and projected water supplies for normal, single-dry, and multiple-dry years through the year 2040, as described in LADWP's 2015 UWMP. LADWP finds it will be able to meet the proposed water demand of the Project, as well as existing and planned future water demands of its service area. Thus, the Project would not require new or expanded water supplies. Therefore, Project impacts related to water supply would be less than significant.

Project Design Features

With the implementation WATER-PDF-1, the Project and cumulative impacts related to water supplies are less than significant and no mitigation measures are required.

WATER-PDF-1: Water Conservation Measures:

- High Efficiency Toilets with a flush volume of 1.1 gallons per flush or less
- Urinals – Waterless
- Showerheads with a flow rate of 1.5 gallons per minute or less
- ENERGY STAR Certified Residential Clothes Washers – Integrated Water Factor of 3.7 or less, front-loading, and capacity of 2.3 cubic feet
- ENERGY STAR Certified Residential Dishwashers – 3.07 gallons per cycle or less, standard type
- Centralized Domestic Water Heating System with hot water return branches
- Point of Use Water Heaters may be used where conditions warrant
- Individual metering and billing for water use for every residential dwelling unit and commercial unit
- Water-Saving pool filter
- Pool/Spa recirculating filtration equipment
- Pool splash troughs around the perimeter that drain back into the pool
- Install a meter on the pool make-up line so water use can be monitored and leaks can be identified and repaired
- Reuse pool backwash water for irrigation
- Leak Detection System for swimming pools and Jacuzzi
- Micro-Spray
- Hydro-zoning Irrigation – Commercial zoning with plant factor 0.3 and Residential zoning with plant factor 0.4
- Drip/Subsurface Irrigation to Commercial zone (4,251 square feet) and Residential zone (8,474 square feet)
- Primary (On-Site) Waste Water Treatment Systems – Possible uses are public toilets and irrigation. Exact usage information not yet known.

The Project would not result in a determination by the wastewater treatment provider which serves or may serve the Project that it has adequate capacity to serve the Project's projected demand in addition to the provider's existing commitments. As described above, the Project would not result in any significant impacts related to wastewater treatment requirements.

The Project would be served by a landfill with sufficient permitted capacity to accommodate the Project's solid waste disposal needs. As discussed in Draft EIR Sections M.3, Utilities and Services Systems – Solid Waste, sufficient capacity at existing landfills exists to serve the project. Therefore, Project impacts related to solid waste would be less than significant.

The Project would comply with federal, state, and local statutes and regulations related to solid waste. As discussed in Draft EIR Sections M.3, Utilities and Services Systems – Solid Waste, The Project would fully comply with all federal, state, and local statutes and regulations regarding proper disposal. Impacts would be less than significant.

The Project would not result in significant cumulative impacts related to utilities and service systems. As discussed in Draft EIR Sections M.1 – M.3, Utilities and Services Systems, project level impacts would be less than significant, and project contribution to cumulative impacts would be less than considerable.

Utilities (Energy)

The Project would not cause wasteful, inefficient, or unnecessary use of energy. As discussed in Draft EIR Sections M.4, Utilities and Services Systems – Energy Conservation, the project would not cause waste, inefficient, or unnecessary use of energy for each category of energy use.

The Project would not result in significant cumulative impacts on energy sources or facilities. As discussed in Draft EIR Sections M.4, Utilities and Services Systems – Energy Conservation, the project would not result in a cumulatively considerable contribution to impacts on energy sources or facilities.

Less than Significant Impacts with Mitigation

The EIR determined that the Project has potentially significant environmental impacts in the areas discussed below. The EIR identified feasible mitigation measures to avoid or substantially reduce the environmental impacts in these areas to a level of less than significant. Based on the information and analysis set forth in the EIR, the Project would not have any significant environmental impacts in these areas, as long as all identified feasible mitigation measures are incorporated into the Project. The City again ratifies, adopts, and incorporates the full analysis, explanation, findings, responses to comments, and conclusions of the EIR.

Air Quality

Description of Effects

Would the Project violate any air quality standard or contribute substantially to an existing or projected air quality violation?

Construction Phase Impacts – Regional Impacts

Construction-related emissions were estimated for the Project using SCAQMD's CalEEMod 2016.3.1 model based on assumptions from the Project Applicant, including the Project's construction schedule of 34 months. Construction-related emissions were estimated based on an estimated number of truck haul trips totaling 11,550 truck trips (assuming 115,500 cubic yards of export and use of 10-cubic-yard-capacity haul trucks), using a conservative haul trip length of 40 miles for all disposal requirements. The estimate of 115,000 cubic yards of export assumes bulk excavation of the basement (36,246 sf) at a depth of 64 feet, which results in an export of 85,916 cubic yards. Further, the Draft EIR estimated a soil swell factor of 20% (an additional 17,183 cubic yards) for a total of 103,099 cubic yards. An additional 12,000 cubic yards was included in the 115,000-cubic-yard estimate of the Draft EIR for potential export associated with the foundation design that will vary in depth. Table IV.C-6 of the Draft EIR summarizes the Project's construction schedule.

As shown on Table IV.C-7 of the Draft EIR, the construction of the Project would not produce VOC, CO, SO_x, PM₁₀, and PM_{2.5} emissions in excess of SCAQMD's regional thresholds. However, the Project's NO_x emissions would exceed the regional significance threshold. Therefore, prior to mitigation, the Project's construction-related regional emissions impact would be significant.

Construction Phase Impacts – Localized Impacts

In terms of local air quality, as shown on Table IV.C-7 of the Draft EIR, the Project would not produce significant emissions in excess of SCAQMD's recommended localized standards of significance for CO during the construction phase. However, construction activities could produce NO₂, PM₁₀ and PM_{2.5} emissions that exceed localized thresholds ("LSTs") recommended by the SCAQMD, primarily from vehicle exhaust and fugitive dust emissions from off-road construction vehicles during the brief overlap of construction phases in 2018. Without mitigation, the Project's construction-related localized emission impact would be significant.

Construction Phase Impacts – Sensitive Receptors

As illustrated on Table IV.C-7 of the Draft EIR, nearby sensitive receptors could be exposed to substantial concentrations of localized pollutants NO₂, PM₁₀ and PM_{2.5} from construction of the Project. Specifically, without mitigation, construction activities would exceed SCAQMD LSTs for NO₂, PM₁₀ and PM_{2.5} and represent a significant impact.

Construction Phase – Cumulative

Cumulative construction emissions are considered when projects within close proximity of each other could result in larger impacts on local sensitive receptors. There are five related projects within 1,000 feet of the Project Site. If any of these projects were to undertake construction concurrently with the Project, localized CO, NO₂, PM₁₀ and PM_{2.5} concentrations from those projects would not exceed ambient air quality standards at nearby receptors. The application of LST thresholds to each cumulative project in the local area would help ensure that each project does not produce localized hotspots of CO, NO₂, PM₁₀ and PM_{2.5}. Any projects that would exceed LST thresholds would perform dispersion modeling to confirm whether health-based air quality standards would be violated and mitigate any significant localized emissions accordingly. Receptors that are located further away would not be threatened with exceedances of health-based standards, and emissions significantly disperse as a function of atmospheric stability, mixing heights, and other variables, with distance a critical factor. As such, the cumulative impact of construction projects on local sensitive receptors would be considered less than significant.

Construction of the Project would produce cumulatively considerable emissions of localized nonattainment pollutants NO₂, PM₁₀ and PM_{2.5}, as the anticipated emissions would exceed LST thresholds set by the SCAQMD. Without mitigation, this would be considered a significant impact.

Operation

As discussed in Draft EIR Section C, Air Quality, operational emissions for the Project were found to be in compliance with air quality standards.

Project Design Features – No project design features are included in the Draft EIR with regard to air quality.

Mitigation Measures - Because the Project could result in significant construction-related emissions impacts and associated impacts on sensitive receptors, the following mitigation measures are required:

Mitigation Measure C-1 - All off-road construction equipment greater than 50 horsepower shall be required to meet USEPA Tier 4 emission standards to reduce NO_x, PM₁₀

and PM_{2.5} emissions at the Project Site. In addition, all construction equipment shall be outfitted with Best Available Control Technology devices certified by CARB. Any emissions control device used by the contractor shall achieve emissions reductions that are no less than what could be achieved by a Level 3 diesel emissions control strategy for a similarly sized engine as defined by CARB regulations. At the time of mobilization of each applicable unit of equipment, a copy of each unit's certified tier specification, BACT documentation, and CARB or SCAQMD operating permit shall be provided.

During plan check, the Project Applicant shall make available to the lead agency and SCAQMD a comprehensive inventory of all off-road construction equipment, equal to or greater than 50 horsepower that shall be used during any portion of demolition/excavation activities and concrete pour days for mat foundation for the Project. The inventory shall include the horsepower rating, engine production year, and certification of the specified Tier standard. A copy of each unit's certified tier specification, Best Available Control Technology documentation, and CARB or SCAQMD operating permit shall be available on-Site at the time of mobilization of each applicable unit of equipment to allow the Construction Monitor to compare the on-site equipment with the inventory and certified Tier specification and operating permit. Off road diesel-powered equipment within the construction inventory list described above shall meet Tier 4 CARB/U.S. EPA standards.

Mitigation Measure C-2 - The Project Applicant shall use 2010 model year or newer diesel haul trucks (e.g., material delivery trucks and soil import/export), and if the Lead Agency determines that 2010 model year or newer diesel trucks cannot be obtained, the Lead Agency shall require trucks that meet USEPA 2007 model year NO_x emissions requirements.

Finding - Changes or alterations have been required in, or incorporated into, the project that avoid or substantially lessen the significant impacts as identified in the EIR.

Rationale for Finding - Mitigation Measure C-1 requires the use of readily-available construction equipment that uses EPA-certified Tier 4 engines to reduce combustion-related NO₂, PM₁₀ and PM_{2.5} emissions from all off-road construction equipment greater than 50 horsepower. Tier 4-certified engines have been phased in nationwide since 2008 for all engine types. Today, all off-road engines are required to be manufactured to meet these standards using feasible technologies that reduce NO_x and particulate emissions by 99 percent from pre-1996 standards. Manufacturers of equipment with 56 to 130 horsepower engines had until the end of 2018 to phase in Tier 4-certified engines, while the manufactured of equipment with larger engines (130 horsepower or greater) had until the end of 2017. As a result, Tier 4-certified equipment is a commercially-available from all manufacturers. Tier 4 equipment is commercially-available product from multiple manufacturers. Enforcement of Mitigation Measure C-1 would occur through implementation of the Project's Mitigation Monitoring Plan (MMP) (refer to Section V [Mitigation Monitoring Plan] of the Final EIR). As part of the MMP, the City's Department of Building and Safety would confirm the use of Tier 4-certified equipment by reviewing certification of the tier specifications for engines in construction equipment prior to issuance of construction-related permits and throughout the construction process.

As shown on Table IV.C-9 of the Draft EIR, with implementation of Mitigation Measure C-1, the Project's regional emissions of NO_x and localized emissions of NO_x, PM₁₀ and PM_{2.5} would not exceed SCAQMD's significance thresholds. No additional mitigation measures are required to reduce the Project's construction-related air quality impacts. Therefore, the Project's regional and localized construction-related emissions impacts would be less than significant.

Mitigation Measure C-2 is a measure that SCAQMD recommends that Lead Agencies implement. However, the effectiveness of this measure at reducing emissions cannot be calculated. As such, although the measure would likely contribute to a reduction in emissions, the effectiveness of the measure has not been accounted for in the calculation of the Project's

post-mitigation emissions shown on Table IV.C-9. Additionally, the emissions shown on Table IV.C-9 do not take into account application of SCAQMD's Rule 403, which calls for Best Available Control Measures (BACM) that include watering portions of the Site that are disturbed during grading activities and minimizing tracking of dirt onto local streets. This watering process would further reduce localized emissions of PM₁₀ and PM_{2.5}.

Reference - For a complete discussion of the Project's impacts associated with air quality, see Section IV.C (Air Quality) of the Draft EIR. See also Appendix C (Air Quality Technical Modeling Results February 2017) of the Draft EIR and Appendix B-4 (Revised Air Quality Technical Modeling Results [January 2019]) and Appendix B-5 (Air Quality Technical Modeling Results for Haul Trips [January 2019]) of the Final EIR, as well as the Section III (Responses to Comments) of the Final EIR

Cultural Resources

Description of Effects

Substantial Adverse Change in the Significance of an Archaeological Resource

A CHRIS records search and archival research identified one historic archaeological resource (P-19-003287) within a 0.5-mile radius of the Project Site area. P-19-003287 was identified during construction monitoring and consisted of five refuse deposits and a scatter of artifacts dating to between ca. 1858 and 1971, though much of the sampled assemblage was dated around 1910. Importantly, the Site was located along an alignment of the West Branch of Zanja No. 8-R and later occupied by 1890s residences. No traces of the zanja were observed during construction monitoring for the Project.

Though no archaeological resources have been previously recorded within the Project Site area, it is possible that historic archaeological resources could be preserved below the current ground surface that are attributable to the structural remains, features, and artifacts associated with the residential and commercial use of the Project Site area beginning in the 1890s (higher likelihood), but also those attributable to Zanja No. 8-R in the area immediately fronting Figueroa Street (lower likelihood). Overall, the Project Site area has an elevated sensitivity for containing historic archaeological resources. Without mitigation, Project impacts related to historic archaeological resources could be significant.

Cumulative –Archaeological Resource

The Project itself would not result in indirect or direct impacts to any significant prehistorical or historical resource. However, it is possible that some of the related projects listed on Table II-2 in Section II (Environmental Setting) of the Draft EIR could result in significant impacts on prehistorical or historical resources. However, with the implementation of Mitigation Measures D-1 through D-4, Project impacts related to prehistoric and historic archaeological resources would be less than significant. Thus, the Project would not have the potential to contribute toward any significant cumulative impacts related to prehistoric or historic archaeological resources. Therefore, cumulative impacts related to archaeological resources would be less than significant.

Project Design Features – No project design features are included in the Draft EIR with regard to archaeological resources.

Mitigation Measures - To ensure that Project impacts related to archaeological resources would be less than significant, the following mitigation measures are required:

Mitigation Measure D-1 - Retain a Qualified Archaeologist. The Project Applicant shall retain a qualified archaeologist, defined as an archaeologist who meets the Secretary of the Interior's Standards for professional archaeology, during the initial excavation phase to carry out all mitigation measures related to archaeological resources.

Mitigation Measure D-2 - Prepare a Monitoring and Mitigation Plan. Before

excavation, an Archaeological Resources Monitoring and Mitigation Plan (Monitoring Plan) shall be prepared. The Monitoring Plan shall include, but not be limited to, monitoring protocol for excavation, a construction worker training program, and discovery and processing protocol for inadvertent discoveries of archaeological resources. The Monitoring Plan shall identify areas with moderate to high sensitivity determined for cultural resources that require monitoring and detail a protocol for determining circumstances in which additional or reduced levels of monitoring (e.g., spot-checking) may be appropriate. Specifically, the Monitoring Plan shall include a framework for assessing the geo-archaeological setting to determine whether sediments capable of preserving archaeological remains are present, and the depth at which these sediments would no longer be capable of containing archaeological material.

Mitigation Measure D-3 - Worker Training. Before excavation, at the Project kickoff, the selected qualified archaeologist or their designee shall provide a briefing to construction crews to provide information on regulatory requirements for the protection of archaeological resources. As part of this training, construction crews shall be briefed on proper procedures to follow should unanticipated archaeological resources discoveries be made during construction. Workers shall be provided contact information and protocols to follow if inadvertent discoveries are made. In addition, workers shall be shown examples of the types of archaeological resources that would require notification of the Project archaeologist.

Mitigation Measure D-4 - Monitoring for Archaeological Resources. Before ground disturbance, an archaeological monitor shall be present during initial excavation activities as stipulated in the Monitoring Plan. The qualified archaeologist may designate an archaeologist to conduct the monitoring under their direction. Specifically, field observations regarding the geo-archaeological setting shall be conducted to determine the presence of undisturbed sediments capable of preserving archaeological remains, and the depth at which these sediments would no longer be capable of containing archaeological material. The duration and timing of the monitoring shall be determined by the qualified archaeologist in consultation with the Department of City Planning and the Project Applicant. At the conclusion of monitoring activities, a technical report shall be prepared documenting the methods and results of all work completed under the Monitoring Plan. The report shall be prepared under the supervision of a qualified archaeologist and submitted to City Planning and the South Central Coastal Information Center.

Finding - Changes or alterations have been required in, or incorporated into, the project that avoid or substantially lessen the significant impacts as identified in the EIR.

Rationale for Finding - With implementation of Mitigation Measures D-1 through D-4, Project impacts related to archaeological resources and related cumulative impacts would be less than significant. Though no archaeological resources have been previously recorded within the Project Site area, it is possible that prehistoric or historic archaeological resources could be preserved below the current ground. Mitigation Measures D-1 through D-4 establish comprehensive measures to ensure that, if uncovered on the Project Site, prehistoric or historic archaeological resources would be properly treated without any significant impact on the significance of the archaeological resources, thereby ensuring no significant cumulative impact.

Reference - For a complete discussion of the Project's impacts associated with air quality, see Section IV.D (Cultural Resources) of the Draft EIR. See also Appendix D-B (Archaeological Resources Assessment for the Olympic Tower LA Project) of the Draft EIR.

Hazards and Hazardous Materials

Description of Effects

Reasonably Foreseeable Upset Conditions Involving the Release of Hazardous Materials – Soil Contamination

As discussed previously, the Project Site was used for residential and commercial purposes as early as 1890. By 1967, no buildings remained, and the Site was used for parking until it was redeveloped into a carwash and gasoline station in approximately 1979-1981. This land use configuration included five underground storage tanks ("USTs") associated with the gasoline station. These USTs were removed in 1998 and replaced with one split (9,000/6,000) gasoline UST and one 10,000 gasoline UST. The new USTs were placed in the location of the historic five USTs. At that time, a leaking UST case was opened with the LAFD based on the presence of gasoline and related constituents in Site soils.

A soil and groundwater investigation was conducted in 2002, and five rounds of quarterly groundwater sampling were conducted from 2002-2003. Oversight was transferred from LAFD to the LARWQCB. Soil and groundwater sampling was conducted in late 2011. The two tanks installed in 1998 were removed in January 2013. The LARWQCB closed the leaking UST case in July 2013. The monitoring wells were abandoned in September 2013.

Maximum residual concentrations in soil and groundwater are summarized on Table IV.G-5 of the Draft EIR. (See Section IV [Revisions, Clarifications, and Corrections] of the Final EIR.) The most recent maximum residual concentrations in soil and groundwater all fell below the applicable screening levels for soil and maximum contaminant levels for groundwater, as summarized on Table IV.G-5 of the Draft EIR. However, the presence of these residual concentrations constitutes a historical recognized environmental concern ("REC"). Residual contamination in the subsurface remains at the site that could pose an unknown environmental risk under certain site development activities such as site grading, excavation, and/or extraction of groundwater.

Operational Impacts

As discussed in Draft EIR Section G Hazards and Hazardous Materials, the Project Site is located in a City-designated Methane Buffer Zone/Methane Zone. As such, to ensure that no significant impacts related to this designation occurs as a result of the Project, the Project Applicant would be required to comply with Section 91.71 of the LAMC, which includes methane mitigation requirements and current construction standards to control potential methane intrusion into buildings. General requirements include measuring the concentration and pressure of methane gas and integration of an appropriate methane mitigation system into the design and construction of the Project as approved by the City's Department of Building and Safety. Through compliance with LAMC Section 91.71, Project impacts related to methane would be less than significant. Further as discussed in Draft EIR Section G Hazards and Hazardous Materials, other materials were evaluated and it was determined that the project would not create a significant hazard to the public or environment through upset, or accident conditions.

Project Design Features – No project design features are included in the Draft EIR with regard to hazards and hazardous materials.

Mitigation Measures - Because residual gasoline-related constituents in soil at the Project Site could pose an environmental hazard, the following mitigation measure is required:

Mitigation Measure G-1 - Prior to issuance of a grading permit, the Project Applicant shall prepare a Soil Management Plan (SMP) for the Project, which shall be approved by the Los Angeles Fire Department and the Department of Public Works. The SMP shall set forth procedures to be followed during the Project's excavation and development phases to properly manage the soil and minimize risks to workers and the public during construction in accordance with any requirements set forth by the Los Angeles Fire Department and/or Department of Public Works. The SMP shall address the delineation of the vertical and lateral extent of residual gasoline-related constituent impacts in Project Site soil. Soil management procedures shall be described so that hazardous soil can be separated from non-hazardous soil during excavation tasks. The SMP shall describe the transport and disposal of the soil at an appropriate waste management facility(ies). The SMP shall be

prepared and executed in accordance with South Coast Air Quality Management District (SCQAMD) Rule 1166, Volatile Organic Compound Emissions for Decontamination of Soil.

Finding - Changes or alterations have been required in, or incorporated into, the project that avoid or substantially lessen the significant impacts as identified in the EIR.

Rationale for Finding - With implementation of Mitigation Measure G-1, impacts related to hazards and hazardous materials would be less than significant. The residual concentrations of subsurface contaminants could pose unknown environmental risks during Site activities such as Site grading, excavation, and/or extraction of groundwater. By preparing the SMP subject to approval by the LA Fire Department and Department of Public Works, in accordance with SCQAMD Rule 1166, the Project Site will be graded, excavated and otherwise developed in accordance with proper regulatory requirements to minimize any risks posed by the upset or accidental release of hazardous materials. The SMP will have sufficiently objective standards to ensure mitigation of any potential significant effects.

Reference - For a complete discussion of the Project's impacts associated with hazards and hazardous materials, see Section IV.G (Hazards and Hazardous Materials) of the Draft EIR. See also Appendix E-A (Geotechnical Investigation) and Appendix E-B (GEOCON Email) of the Draft EIR, as well as the Section III (Responses to Comments) of the Final EIR.

Noise

Description of Effects

Generation of Excessive Noise – Construction

During all construction phases, noise-generating activities could occur at the Project Site between the hours of 7:00 A.M. and 9:00 P.M. Monday through Friday, and from 8:00 AM to 6:00 PM on Saturdays, with no construction activities on Sundays or national holidays, in accordance with Section 41.40(a) of the LAMC. On-Site activities could include the use of heavy equipment such as excavators, loaders, and graders, as well as smaller equipment such as saws, hammers, and pneumatic tools. The Project's construction equipment source noise levels for excavators and front-end loaders would nonetheless exceed LAMC Section 112.05's 75 dBA limit for powered construction equipment operating within 500 feet of residential zones, and thus require mitigation to limit the Project's construction equipment source noise levels to below 75 dBA.

Generation of Groundborne Vibration – Construction

As discussed previously, construction of the Project would require equipment such as excavators and loaders. These types of heavy-duty vehicles can produce peak vibration velocities of up to 0.089 inches per second at a distance of 25 feet. Auger drilling/boring rigs can produce similar vibration levels. Table IV.I-8 shows the Project's estimated construction vibration impacts at the nearest off-Site structures. Hotel Figueroa, built in 1926, could experience groundborne vibrations in excess of Caltrans' 0.25 inches per second PPV damage threshold for "Historic and some old buildings." Without mitigation, this impact could be significant.

Operational Impacts

As discussed in Draft EIR Section I, Noise, operational impacts for the Project with respect to vibration, were found to be in compliance with air quality standards.

Project Design Features – No project design features are included in the Draft EIR with regard to noise.

Mitigation Measures - To ensure that the Project's construction-related noise levels do not exceed 75 dBA or exceed groundborne vibration thresholds, the following mitigation

measures are required:

Mitigation Measure I-1 - All diesel-powered construction vehicles shall be equipped with exhaust mufflers or other suitable noise reduction devices capable of achieving a sound attenuation of at least 3 dBA. Should they be required, generators shall be solar-powered.

Mitigation Measure I-2 - Temporary sound barriers capable of achieving a sound attenuation of at least 5 dBA shall be erected along the Project's boundaries.

Mitigation Measure I-3 - Construction activities that produce vibration, such as demolition, excavation, and earthmoving, shall be sequenced so that vibration sources within 10 feet of Hotel Figueroa do not operate simultaneously.

Mitigation Measure I-4 - No pile driving shall occur as part of Project construction.

Mitigation Measure I-5 - Pre-construction surveys shall be performed to document the conditions of Hotel Figueroa. A structural monitoring program shall be implemented and recorded during part or all of the Project's construction phase. The performance standards of the structure-monitoring plan shall include the following:

- Documentation, consisting of video and/or photographic documentation of accessible and visible areas on the exterior of the building.
- A registered civil engineer or certified engineering geologist shall develop recommendations for a structure-monitoring program, including a timeline for monitoring.
- The structure-monitoring program shall survey for vertical and horizontal movement, as well as vibration thresholds (0.25 PPV in/sec) established specifically for the Project's construction activities and proximity to the Hotel Figueroa. If the thresholds are met or exceeded, or if noticeable structural damage becomes evident to the Project contractor, work shall stop in the area of the affected building until measures have been taken to prevent construction-related damage to the structure.
- The structure-monitoring program shall be submitted to the Department of Building and Safety for review and approval and received into the case file for the associated discretionary action permitting the Project prior to initiating any construction activities.

Finding - Changes or alterations have been required in, or incorporated into, the project that avoid or substantially lessen the significant impacts as identified in the EIR.

Rationale for Finding - Table IV.I-11 of the Draft EIR shows the Project's construction noise impacts with the implementation of Mitigation Measures I-1 and I-2. Implementation of these mitigation measures would reduce the Project's on-Site construction equipment source noise levels to below the LAMC's 75 dBA limit for powered equipment operations within 500 feet of residential zones. Though no sensitive receptor would experience a significant increase in noise as a result of the Project's unmitigated construction activities, these measures would further reduce the Project's impacts at these receptors. Therefore, the Project's construction-related noise impact would be less than significant.

Mitigation Measures I-3 through I-4 would reduce the Project's vibration sources near the Hotel Figueroa receptor. The monitoring program included as Mitigation Measure I-5 would ensure that vibration associated with Project construction would not cause any damage to the Hotel Figueroa. With implementation of Mitigation Measures I-3 through I-5, impacts related to construction vibration would be less than significant.

Reference - For a complete discussion of the Project's impacts associated with noise, see Section IV.I, Noise, of the Draft EIR. See also Appendix G, of the Draft EIR, as well as the

Section III of the Final EIR, Responses to Comments.

Significant and Unavoidable Impacts

The Final EIR determined that the environmental impacts set forth below are significant and unavoidable. In order to approve the project with significant unmitigated impacts, the City is required to adopt a Statement of Overriding Considerations, which is set forth below. No additional environmental impacts other than those identified below will have a significant effect or result in a substantial or potentially substantial adverse effect on the environment as a result of the construction or operation of the project.

Transportation and Traffic

Description of Effects

Intersection LOS – Operational

The future with Project (existing, ambient growth, related projects and Project) traffic volumes at the study intersections during the weekday AM and PM peak hours are illustrated on Figures IV.L-17 and IV.L-18 of the Draft EIR, respectively. As shown in column [4] on Table IV.L-16 of the Draft EIR, application of the City's threshold criteria for intersection levels of service ("LOS") to the "Future With Project" scenario indicates that the Project would result in significant impacts at two of the 18 study intersections as follows: Figueroa Street/9th Street and Figueroa Street/Olympic Boulevard.

Although not required by LADOT, a supplemental traffic analysis of all of the study intersections was prepared assuming that access to/from the Cottage Place/Olympic Boulevard intersection (alley driveway intersection) would be restricted to right-turn ingress and egress turning movements for the Project. As shown in column [4] of Appendix Table D-1 of the Traffic Study, Appendix I of the Draft EIR, similar to the results for the "Future With Project" scenario, the same two study intersections are forecast to be significantly impacted under this supplemental traffic analysis scenario: Figueroa Street/9th Street and Figueroa Street/Olympic Boulevard.

Although not required by LADOT, a supplemental traffic analysis of all of the study intersections was also prepared assuming implementation of the Figueroa Streetscape (My Figueroa) project, since (i.e., at the time of the preparation of the Draft EIR), the City's project is starting construction. The My Figueroa project has since been completed. The supplemental traffic analysis determined the My Figueroa project would not affect the distribution of trips to and from the Project site (i.e., assuming that the Cottage Place/Olympic intersection was not restricted to right-turn ingress and egress turning movements). The general, directional traffic distribution patterns for the Project would be consistent with Figures IV.L-6 and IV.L-7 of the Draft EIR for the commercial and residential land use components, respectively. However, the lane configurations at some of the study intersections, particularly those along Figueroa Street, would be affected by the My Figueroa project. As shown in column [4] of Appendix Table E-1 of the Traffic Study, Appendix I of the Draft EIR, similar to the results for the "Future With Project" scenario, the same two study intersections are forecast to be significantly impacted under this supplemental traffic analysis scenario: Figueroa Street/9th Street and Figueroa Street/Olympic Boulevard. One more significant impact was identified as well: Figueroa Street/Pico Boulevard.

Cumulative – Construction

As noted above, under the "Future With Project" (i.e., cumulative) traffic scenario, the Project would result in significant impacts at the Figueroa Street/9th Street-James M. Wood Boulevard and the Figueroa Street/Olympic Boulevard study intersections. The Project's peak hour construction traffic generation would be much less than the Project's peak hour operational traffic generation, and would not be expected to result in any significant intersection LOS impacts. Further, vehicular movements into and out of the Project Site would be provided via three access points along Cottage Place: one driveway providing access for the residential land use component, a porte cochere (i.e., main drop-off and pick-up area) for all of the commercial land

use components, and a loading driveway for loading, trash collection, and waste management. Descriptions of the Project's vehicular access points are provided on pages 11 and 12 of the Traffic Impact Study included as Appendix I-A of the Draft EIR. Project Site access is also addressed on pages IV.L-59 and IV.L-60 of the Draft EIR. None of the Project's driveways are planned along either the Olympic Boulevard or Figueroa Street frontages. As such, no interference with existing bus transit stops would occur as a result of the Project.

Further, the City requires all projects to implement a Construction Traffic Management Plan, as described in Mitigation Measure L-2 (i.e., preparation and implementation of a Construction Traffic Management Plan) (refer to page IV.L-126). This measure would limit peak hour construction traffic trips and require all on-going cumulative construction projects within proximity to the Project Site to account for the nature and timing of specific related projects' construction activities. However, given the Project's peak hour construction traffic generation in combination with the peak hour construction traffic associated with the related projects, it is possible that this cumulative traffic generation could result in significant intersection LOS impacts at the study intersections mentioned above. Therefore, it is conservatively concluded that cumulative construction traffic impacts would be potentially significant.

Project Design Features – – No project design features are included in the Draft EIR with regard to transportation.

Mitigation Measures - To minimize the Project's operational and construction traffic impacts, the following mitigation measures are required:

Mitigation Measure L-1 – The Project Applicant shall prepare and provide to LADOT a preliminary Transportation Demand Management (TDM) Program to the satisfaction of LADOT and in accordance with the City's Trip Reduction Ordinance to reduce the Project's traffic generation. The final TDM Program shall be approved by LADOT prior to issuance of any Certificate of Occupancy. The preliminary TDM Program shall include, at a minimum, measures consistent with the City's Trip Reduction Ordinance. LADOT shall determine and approve the specific contents of the TDM Program and traffic-reduction strategies, which could include the following, as examples:

- *On-Site Employee Transportation Coordinator.* An on-site Employee Transportation Coordinator (ETC) could be designated for the Project. The ETC would manage all aspects of an enhanced TDM program and also would participate in City-sponsored workshops and information roundtables. The ETC would establish a Transportation Information Center and Transportation Fairs. The Transportation Information Center would provide on-site information at its buildings for employees and visitors about local public transit services (including bus lines, rail lines and connections, rideshare programs and shuttles), and bicycle facilities (including routes, rental and sales locations, on-site bicycle racks and showers). Walking and biking maps also would be provided for employees, visitors and residents, which would include but not be limited to information about convenient local services and restaurants within walking distance of the project. Such transportation information may be provided through a computer terminal with access to the Internet, as well as through the office of the ETC located at the Project site. Transportation information should be maintained at the administrative offices of the buildings, or by directing inquiries to the building's web site as a portal.
- *TDM Website Information.* Transportation information should be provided in a highly visible and accessible location on the building's web site, including links to local transit providers, area walking, bicycling maps, etc., to inform employees, visitors and residents of available alternative transportation modes to access the project, other amenities in the area and travel opportunities in the area. The website also should highlight the environmental benefits of utilization of alternative transportation modes.
- *TDM Promotional Material.* Provide and exhibit in public places information materials on

options for alternative transportation modes and opportunities. In addition, transit fare media and day/month passes should be made available to employees and visitors during typical business hours.

- *Transit Welcome Package.* All new employees could be provided with a Transit Welcome Package (TWP) in addition to holding Transportation Fair on an annual basis. The TWP at a minimum could include information regarding employer's arrangements for free or discounted use of the transit system, area bus/rail transit route and connections/transfers information, bicycle facilities (including routes, rental and sales locations, on-site bicycle racks, walking and biking maps), and convenient local services and restaurants within walking distance of the Project site.
- *Carpool Program for Employees.* Provide preferential parking within the parking garages for employees who commute to work in registered carpools. An employee who drives to work with at least one other employee to the site may register as a carpool entitled to preferential parking within the meaning of this provision.
- *Public Transit Stop Enhancements.* Working in cooperation with the City and other transit agencies to improve existing bus stops with enhanced shelters and transit information within the immediate vicinity of the buildings. Enhancements could include enhanced weather/sun protection, lighting, benches, and trash receptacles. These improvements would be intended to make riding the bus a safer and more attractive alternative.
- *Convenient Parking/Amenities for Bicycle Riders.* Provide locations at the Project site for convenient parking for bicycle commuters for working employees and visitors. The bicycle parking should be located within the buildings such that long-term and short-term parkers could be accommodated. Bicycle parking may mean bicycle racks, a locked cage, or other similar parking area. Provide shower facilities for employees who commute to work via bicycle.
- *Local Hiring Program.* To the extent feasible, when hiring, conduct outreach to residents who live within Downtown Los Angeles based on satisfaction of other requirements of the available positions.
- *Flexible/Alternative Work Schedules.* Encourage tenants in the building to offer flexible or alternative work schedules, as well as the opportunity to telecommute if feasible.
- *Parking Cash-Out Program.* Require in all leases it executes as landlord for space within the project that tenants offer a parking cash-out program. Parking cash-out program means an employer-funded program under which an employer offers in-lieu of any parking subsidy, a transit subsidy or cash allowance (for use of alternative modes such as walking and bicycling) of equal or greater value.
- *Unbundling and Lease of Parking Spaces for the Residential Land Use.* Offer options for buyers of the residential condominium dwelling units to purchase parking separately (i.e., unbundle parking from the unit price).
- *Participation in a Transportation Management Organization (TMO),* if one is established and the Project Site included. Project representatives would attend organization meetings for the TMO, provide parking and travel demand data to the TMO, pay any established dues to the TMO, and make available information to Project tenants relative to the services provided by the TMO.
- *Record a Covenant and Agreement* to ensure that the TDM Program shall be maintained.

The following improvements shall be part of the TDM Program:

- *Contribution to the Los Angeles Bicycle Plan* – Prior to the issuance of any certificates of occupancy, the Project Applicant shall contribute a one-time fixed-fee of \$100,000 to be deposited into the City's Bicycle Plan Trust Fund to implement bicycle improvements

within the Project Site area.

- The Project Applicant shall support existing and/or future efforts by LADOT for Mobility Hubs by providing amenities such as bicycle parking, rentals, shared vehicle rentals, transit information, etc. at the Project Site (subject to design feasibility).

Transportation Systems Management (TSM) Improvements

Some of the signalized intersections within the Project Site study area require an upgrade to the traffic signal equipment and hardware. Some of the traffic signals in the study area currently operate using a Type 170 traffic signal controller. Newer controllers (e.g., Type 2070) provide for enhanced and real-time operation of the traffic signal timing. Also, when supplemented by additional roadway system loops and closed-circuit television (CCTV) cameras at key locations, LADOT can identify the causes of delay and implement instant signal timing remedies to improve the traffic flow of vehicles and buses. These traffic signal upgrades provide a system-wide benefit by reducing delays experienced by motorists. To enhance the traffic signal system in the area and improve the network capacity for real-time video monitoring of intersection, corridor, transit, and pedestrian operations by reducing delays experienced by motorists at study intersections, the following TSM improvements shall be implemented by the Project Applicant:

- Install a new CCTV at Figueroa Street and Venice Boulevard, the cost of which is approximately \$40,000,
- Upgrade the fiber optic cable from 12SM to 48SM on Figueroa Street between Venice and Olympic Boulevards, the cost of which is approximately \$40,000.

The Project Applicant shall be responsible for the cost and implementation of any traffic signal equipment modifications and bus stop relocations associated with the proposed transportation improvements described above. All improvements and associated traffic signal work within the City must be guaranteed through Bureau of Engineering's (BOE) B-Permit process, prior to the issuance of any building permits and completed prior to the issuance of any certificates of occupancy. Temporary certificates of occupancy may be granted in the event of any delay through no fault of the Project Applicant, provided that, in each case, the Project Applicant has demonstrated reasonable efforts and due diligence to the satisfaction of LADOT. Prior to setting the bond amount, BOE shall require that the developer's engineer or contractor email LADOT's B-Permit Coordinator at ladot.planprocessing@lacity.org to arrange a predesign meeting to finalize the proposed design needed for the project. If a proposed transportation improvement does not receive the required approval, a substitute may be provided subject to the approval of LADOT upon demonstration that the substitute is environmentally equivalent or superior to the original

Mitigation Measure L-2 - Prior to issuance of a demolition permit, in coordination with LADOT and the Department of Building and Safety, the Project Applicant shall prepare a detailed Construction Traffic Management Plan, including street closure information, detour plans, haul routes, and staging plans. The Construction Traffic Management Plan shall outline how construction would be carried out and identify specific actions that would be required to reduce effects on the surrounding community. The Construction Traffic Management Plan shall be based on the nature and timing of specific construction activities and other projects in the vicinity, and shall include the following elements as appropriate:

- Provide for temporary traffic control during all construction activities within public rights-of-way to improve traffic flow on public roadways (e.g., flagmen);
- Schedule of construction activities to reduce the effect on traffic flow on surrounding arterial streets;
- Reroute construction trucks to reduce travel on congested streets to the extent feasible;
- Prohibit construction-related vehicles from parking on surrounding public streets;

- Provide safety precautions for pedestrians and bicyclists through such measures as alternate routing and protection barriers;
- Accommodate all equipment on-Site; and
- Obtain the required permits for truck haul routes from the City prior to issuance of any permit for the Project.

FindingIntersection LOS – Operational

Specific economic, legal, social, technological, other considerations, including considerations for the provision of employment opportunities for highly trained workers, make infeasible the mitigation measures or alternatives identified in the EIR.

Cumulative – Construction

Specific economic, legal, social, technological, other considerations, including considerations for the provision of employment opportunities for highly trained workers, make infeasible the mitigation measures or alternatives identified in the EIR.

Rationale for FindingIntersection LOS – Operational

Under the Future With Project traffic scenario, the Draft EIR determined the Project would result in significant impacts at 2 of the 18 study intersections (Int. No. 7: Figueroa Street/9th Street and Int. No. 8: Figueroa Street/Olympic Boulevard). Under a scenario where access to/from the Cottage Place/Olympic Boulevard intersection (alley driveway intersection) would be restricted to right-turn ingress and egress turning movements for the Project, the Project would result in significant impacts at 2 of the 18 study intersections (Int. No. 7: Figueroa Street/9th Street and Int. No. 8: Figueroa Street/Olympic Boulevard). Under the My Figueroa project scenario, the Project would result in significant impacts at 3 of the 18 study intersections (Int. No. 7: Figueroa Street/9th Street, Int. No. 8: Figueroa Street/Olympic Boulevard and Int. No. 9: Figueroa Street). Because the My Figueroa project has now been completed, the Project would result in significant impacts at 3 of the 18 study intersections (Int. No. 7: Figueroa Street/9th Street, Int. No. 8: Figueroa Street/Olympic Boulevard and Int. No. 9: Figueroa Street).

Implementation of Mitigation Measure L-1 would reduce the Project's traffic generation. However, the specific degree to which traffic trips would be reduced through these mitigation measures cannot be calculated at this time. As such, the effectiveness of these mitigation measures at reducing the Project's significant impacts under the Future With Project traffic condition at Intersection No. 7 (Figueroa Street/9th Street) during the AM and PM peak hours and at Intersection No. 8 (Figueroa Street/Olympic Boulevard) during the AM and PM peak hours cannot be determined at this time. Mitigation measures such as road widening or other physical improvements were evaluated and determined infeasible for economic or technical reasons. Therefore, Project impacts at these intersections would be significant and unavoidable.

Cumulative – Construction

The City requires all projects to implement a Construction Traffic Management Plan, as described in Mitigation Measure L-2. This measure would limit peak hour construction traffic trips and require all on-going cumulative construction projects within proximity to the Project Site to account for the nature and timing of specific related projects' construction activities. However, the Project's peak hour construction traffic generation in combination with the peak hour construction traffic associated with the related projects plus the potential limited roadway capacity through the Project Site area, it is possible that this cumulative traffic generation

could result in significant intersection LOS impacts at Intersection No. 7 (Figueroa Street/9th Street) and at Intersection No. 8 (Figueroa Street/Olympic Boulevard). Therefore, it is conservatively concluded that cumulative construction traffic impacts would be potentially significant.

Reference - For a complete discussion of the Project's impacts associated with traffic and transportation, see Section IV.L (Transportation/Traffic) of the Draft EIR. See also Appendix I-A (Traffic Impact Study) and I-B (Traffic Impact Study Appendices) of the Draft EIR, as well as the Section III (Responses to Comments) of the Final EIR.

Alternatives

CEQA requires that an EIR analyze a reasonable range of feasible alternatives that could substantially reduce or avoid the significant impacts of a project while also meeting the project's basic objectives. An EIR must identify ways to substantially reduce or avoid the significant effects that a project may have on the environment (Public Resources Code Section 21002.1). Accordingly, the discussion of alternatives shall focus on alternatives to a project or its location which are capable of avoiding or substantially reducing any significant effects of the project, even if these alternatives would impede to some degree the attainment of the project objectives, or would be more costly. The alternative analysis included in the Draft EIR, therefore, identified a reasonable range of project alternatives focused on avoiding or substantially reducing the project's significant impacts.

Summary of Findings

Based upon the following analysis, the City finds, pursuant to CEQA Guidelines Section 15096(g)(2), that no feasible alternative or mitigation measure will substantially lessen any significant effect of the Project, reduce the significant unavoidable impacts of the Project to a level that is less than significant, or avoid any significant effect the Project would have on the environment.

Project Objectives

Section 15124(b) of the CEQA Guidelines states that a project description shall contain "a statement of the objectives sought by the proposed project." In addition, Section 15124(b) of the CEQA Guidelines further declares that "the statement of objectives should include the underlying purpose of the project." The objectives of the Project are as follows:

1. Develop an iconic, architecturally-compelling tower that adds visual distinction and a unique feature to the Downtown Los Angeles skyline.
2. Capitalize on a smart growth opportunity by intensifying a currently underutilized Site with residential, office, and visitor-serving hotel uses near public transit lines (Metro Rail and Bus) and the Los Angeles Sports and Entertainment District.
3. Create a pedestrian friendly commercial retail zone that is accessible to future residents, hotel guests, and L.A. Live patrons.
4. Contribute unique housing opportunities toward the City's Regional Housing Needs Assessment allocation.
5. Provide residential uses in the same location as commercial and office uses.
6. Contribute to the City's economic growth by developing commercial, residential, and hotel uses that generate local tax revenues, provide new construction jobs, and generate residents who support local businesses.
7. Provide a variety of residential unit sizes to cover the needs of different size households.

Alternatives Analyzed in the Draft EIR and Final EIR

CEQA requires that an EIR analyze a reasonable range of feasible alternatives that could substantially reduce or avoid the significant impacts of a project while also meeting a project's basic objectives.

Each decision-making body of the City finds that given the potential impacts of the Project, the Final EIR considered a reasonable range of alternatives to the Project to provide informed decision-making in accordance with Section 15126.6 of the CEQA Guidelines.

Based on the significant environmental impacts of the Project and the objectives established for the Project, the following alternatives to the project were evaluated in the Final EIR:

- Alternative A: No Project (Continuation of Existing Project Site Conditions)
- Alternative B: No Transfer of Floor Area Ratio and No Hotel
- Alternative C: No Office and Reduced Retail

Alternative A - No Project (Continuation of Existing Project Site Conditions)

Description of Alternative

CEQA requires the alternatives analysis to include a “no project” alternative, which is the circumstance under which the Project does not proceed. The purpose of analyzing a No Project Alternative is to allow decision makers to compare the impacts of approving the project with the impacts of not approving the project (CEQA Guidelines Section 15126.6[e][1]). Pursuant to CEQA Guidelines Section 15126.6(e)(2), requirements of the analysis of the “no project” alternative are as follows:

The “no project” analysis shall discuss the existing conditions at the time the notice of preparation is published, or if no notice of preparation is published, at the time the environmental analysis is commenced, as well as what would reasonably be expected to occur in the foreseeable future if the proposed project were not approved, based on current plans, and consistent with available infrastructure and community services.

At the time the notice of preparation (“NOP”) was published for the Project, there was no evidence that another development at the Project Site would be forthcoming in the event the Project is not approved. Thus, for the purposes of the Draft EIR, Alternative A assumes that the Project Site would remain in its current condition as described in Section II (Environmental Setting) of the Draft EIR. Although no new development would occur on the Project Site under Alternative A, this alternative assumes the development of the related projects in the area of the Project Site. The potential environmental impacts associated with Alternative A are described below and are compared to the environmental impacts associated with the Project (also refer to Table VI-15 of the Draft EIR). No discretionary actions would be required by local, state, or federal agencies for this alternative.

Impact Summary of Alternative

Aesthetics - Alternative A includes continuation of the existing conditions at the Project Site; no new development would occur. As such, this alternative would avoid the less than significant impacts related to scenic vistas, visual character, light and glare, and shade and shadow that would occur under the Project. Further, no scenic resources are located on the Project Site. Similar to the Project, no impacts related to scenic resources would occur under Alternative A.

Air Quality - Alternative A includes continuation of the existing conditions at the Project Site; no new development would occur. Alternative A would not add any population growth to the Project Site and would not have the potential to conflict with SCAQMD's AQMP. As such, this alternative would avoid the less than significant impact related to consistency with SCAQMD's AQMP that would occur under the Project. Also, this alternative would avoid the less than significant (with mitigation) impact related to construction emissions/sensitive receptors that

would occur under the Project. Further, this alternative would not generate any new operational emissions. As such, this alternative would avoid the less than significant impact related to operational emissions/sensitive receptors that would occur under the Project. Similarly, this alternative would not generate any new operational emissions. As such, this alternative would avoid the less than significant impact related to operational emissions/sensitive receptors that would occur under the Project.

Cultural Resources - Alternative A includes continuation of the existing conditions at the Project Site; no new development would occur. As such, this alternative would avoid the less than significant impact related to historical resources that would occur under the Project. Also, Alternative A would not have the potential to encounter any archaeological resources that could exist at the Project Site. As such, this alternative would avoid the less than significant (with mitigation) impact related to archaeological resources that would occur under the Project.

Geology and Soils - Alternative A includes continuation of the existing conditions at the Project Site; no new development would occur. As such, this alternative would avoid the less than significant impact related to geology and soils that would occur under the Project.

GHG Emissions - Alternative A includes continuation of the existing conditions at the Project Site; no new development would occur, and no additional GHG emissions would occur at the Project Site. As such, this alternative would avoid the less than significant impact related to GHG emissions that would occur under the Project.

Hazards and Hazardous Materials - Alternative A includes continuation of the existing conditions at the Project Site; no new development would occur, and no additional transport, use, storage, disposal, and/or emissions of hazardous materials would occur at the Project Site. As such, this alternative would avoid the less than significant impact related to transport, use, storage, disposal, and/or emissions of hazardous materials that would occur under the Project. Further, this alternative would avoid the less than significant (with mitigation) impact related to residual soil contamination and the less than significant impacts related to methane and asbestos-containing materials and lead-based paint that would occur under the Project. Also, this alternative would avoid the less than significant impact related to interfering with an emergency response plan that would occur under the Project.

Land Use and Planning - Alternative A includes continuation of the existing conditions at the Project Site; no new development would occur that would have the potential to conflict with applicable plans, policies, and regulations associated with development of the Project Site. As such, this alternative would avoid the less than significant impact related to consistency with applicable plans, policies, and regulations that would occur under the Project.

Noise - Alternative A includes continuation of the existing conditions at the Project Site; no new development would occur, and no construction noise would be generated. As such, this alternative would avoid the less than significant (with mitigation) impact related to construction noise that would occur under the Project. Further, this alternative would avoid the less than significant impact related to operational noise that would occur under the Project. Also, this alternative would avoid the less than significant (with mitigation) impact related to construction groundborne vibration and the less than significant impact related to operational groundborne vibration that would occur under the Project.

Population and Housing - Alternative A includes continuation of the existing conditions at the Project Site; no new land uses would be developed and no residential population would be added to the Project Site. As such, this alternative would avoid the less than significant impact related to population and housing that would occur under the Project.

Public Services - Alternative A includes continuation of the existing conditions at the Project Site; no new land uses would be developed, and there would be no increase in the need for fire protection services at the Project Site. As such, this alternative would avoid the less than

significant impacts related to fire protection services, police protection services, school services, parks and recreational services, and library services that would occur under the Project.

Transportation/Traffic - Alternative A includes continuation of the existing conditions at the Project Site; no new land uses would be developed, and this alternative would not generate any new traffic trips. As such, this alternative would avoid the significant and unavoidable impacts related to intersection LOS and construction traffic that would occur under the Project. Further, this alternative would avoid the less than significant impacts on CMP roadway facilities, CMP transit facilities, and Caltrans facilities that would occur under the Project.

Tribal Cultural Resources - Alternative A includes continuation of the existing conditions at the Project Site; no grading or excavation would occur. Thus, A would not have the potential to encounter any unknown tribal cultural resources that could exist at the Project Site. As such, this alternative would avoid the less than significant impact related to tribal cultural resources that would occur under the Project.

Utilities and Service Systems - Alternative A includes continuation of the existing conditions at the Project Site; no additional wastewater would be generated. As such, this alternative would avoid the less than significant impact related to wastewater services that would occur under the Project. Similarly, no additional water would be consumed, and this alternative would avoid the less than significant impact related to water services that would occur under the Project. Further, no additional solid waste would be generated, and this alternative would avoid the less than significant impact related to solid waste services that would occur under the Project. Finally, no additional energy would be consumed, and this alternative would avoid the less than significant impact related to energy that would occur under the Project.

Finding

Specific economic, legal, social, technological, other considerations, including considerations for the provision of employment opportunities for highly trained workers, make infeasible the mitigation measures or alternatives identified in the EIR.

Rationale for Finding

No new development would occur under the No Project Alternative (Alternative A) and the Project Site would continue to operate as it does currently. As such, Alternative A would not meet the underlying purpose of the Project or the Project objectives. While Alternative A would avoid the Project's significant environmental impacts, it would not meet the Project's underlying purpose and would not attain any of the Project's objectives. For these reasons, each decision making body of the City rejects the No Project Alternative (Alternative A) as infeasible.

Reference

For a complete discussion of impacts associated with Alternative A, see Section VI (Alternatives to the Proposed Project) of the Draft EIR.

Alternative B: No Transfer of Floor Area Ratio and No Hotel

Description of Alternative

The No TFAR and No Hotel (Alternative B) assumes development of the Project Site with land uses that are similar to those proposed under the Project and consistent with the existing zoning and land use designation for the Project Site, but without the requested TFAR and subsequently, reduced residential and retail development and reduced residential and retail development and no development of hotel land uses. Alternative B would include development of a 222,186-square-foot mixed-use building with 150 multi-family dwelling units, 20,000 square feet of ground floor retail land uses, 5,000 square feet of ground floor office land uses, and two levels of subterranean parking. The building would be 14 stories and 190 feet in height. The overall design, architecture, siting, and vehicle/bicycle/pedestrian would be

substantially similar to that described for the Project. A comparison of the general land uses proposed as part of the Project to those under Alternative B is shown on Table VI-1 of the Draft EIR.

Impact Summary of Alternative

Aesthetics - As stated previously, due to topography, vegetation, and development, medium and long-distance views are not available from the Project Site area. Also, the Project Site is not visible within any scenic views. Thus, Alternative B would not result in any impacts related to scenic vistas, similar to the Project. Further, no scenic resources are located on the Project Site. Similar to the Project, no impacts related to scenic resources would occur under Alternative B. Also, the building under Alternative B would be 124 feet shorter than the building under the Project. Alternative B would be considered a transit priority project located in a designated transit-priority area for which aesthetic impacts (including those related to visual character) shall not be considered significant. Because Alternative B includes development of the Project Site with land uses that similar to those proposed as part of the Project but reduced in size, impacts related to visual character under this alternative would be less than significant. Similarly, because Alternative B includes development of the Project Site with land uses that similar to those proposed as part of the Project but reduced in size, the amount of lighting and sources of glare, as well as shade and shadow associated with Alternative B would be less than under the Project.

Air Quality - Based on an estimated persons-per-household for the year 2016 of 1.89 persons per household, Alternative B would add approximately 284 residents to the Project Site, 423 fewer residents than under the Project. As such, Alternative B would not result in unexpected population growth, and impacts related to consistency with SCAQMD's AQMP would be less than significant, similar to the Project. Further, although this alternative would require less excavation than the Project and would include construction of less overall square footage, the maximum construction day scenario under Alternative B could generate regional NO_x emissions and localized NO_x, PM₁₀, and PM_{2.5} emissions in excess of SCAQMD's significance thresholds, similar to the Project. Without mitigation, sensitive receptors near the Project Site could be exposed to these construction emissions. However, Mitigation Measure C-1 identified for the Project also would apply to this alternative and would reduce the referenced emissions to below the relevant significance thresholds. Thus, impacts related to construction emissions/sensitive receptors under Alternative B would be less than significant, similar to the Project. Additionally, because this alternative includes land uses that are similar to those proposed as part of the Project but less overall square footage, Alternative B would generate less area source, energy source, and mobile source emissions than under the Project. As such, operational emissions under Alternative B would not exceed SCAQMD's significance thresholds. Sensitive receptors in the vicinity of the Project Site would not be exposed to substantial operational emissions. Thus, operational emissions/sensitive receptors impacts under Alternative B would be less than significant, similar to the Project. Finally, the amount of TACs generated under Alternative B would be less than under the Project. Thus, impacts related to TACs under this alternative would be less than significant, similar to the Project.

Cultural Resources - No historical resources would be demolished, altered, or relocated as a result of Alternative B. The building under Alternative B would be substantially smaller in scale and height than under the Project, but would be of similar design and architecture. The building under Alternative B would meet LAMC setback requirements, similar to the Project, and would not affect the physical integrity or historical significance of any of the three historical resources near the Project Site. Thus, Alternative B would not result in any direct or indirect impacts to historical resources, similar to the Project. Yet, because the Project Site area has a high sensitivity for containing historic archaeological resources, any development of the Project Site that includes ground-disturbing activities such as grading and excavation could result in encounters with unknown historic archaeological resources. Mitigation Measures D-1 through D4 would apply to any development of the Project Site (including that under

Alternative B), and impacts would be less than significant, similar to the Project.

Geology and Soils - Because the Project Site is the same under Alternative B as it is for the Project, any development of the Project Site would be subject to the same geotechnical issues identified for the Project and would be subject to the most recently adopted California Building Code design parameters to ensure that impacts related to geology and soils would be less than significant.

GHG Emissions - Because Alternative B includes the construction and operation of land uses that are similar to those proposed as part of the Project but less in overall square footage, the amount of GHG emissions that would be generated as a result of construction and long-term operation of the alternative would be less than those of the Project. Similar to the Project, Alternative B would be required to comply with numerous regulatory compliance measures, particularly those associated with the City's Green Building Code that would reduce the alternative's GHG emissions profile and would represent improvements with respect to the NAT scenario. Thus, Alternative B's GHG emissions reductions as compared to the NAT scenario demonstrate consistency with GHG Reduction Plans, Executive Orders S-3- 05 and B-30-15, SCAG's Sustainable Communities Strategy, and the City's Green Building Ordinance. Thus, Alternative B's contribution to global climate change would not be cumulatively considerable and would be less than significant, similar to the Project.

Hazards and Hazardous Materials - Similar to the Project, during the construction and operational phases for Alternative B, this alternative would involve the transport, use, and storage of relatively small amounts of potentially hazardous materials, such as paints, adhesives, surface coatings, cleaning agents, waxes, fuels, and oils. However, compliance with applicable city, state, and federal regulations related to the handling, storage, transport, and disposal of hazardous materials and waste during operation of this alternative would ensure that no significant hazard to the public or the environment occurs. Therefore, impacts related to the transport, use, storage, disposal, and/or emissions of hazardous materials under Alternative B would be less than significant, similar to the Project. Additionally, any development of the Project Site (including development under Alternative B) that includes ground-disturbing activities would result in the same potential to encounter residual soil contamination, as identified for the Project. Mitigation Measure G-1 identified for the Project would also apply to Alternative B and would ensure that impacts related to residual soil contamination would be less than significant. Also, any development of the Project Site (including development under Alternative B) would be required to comply with LAMC Section 91.71 to ensure that impact related to methane would be less than significant. Because the existing structure on the Project Site was constructed after 1978, no development of the Project Site would result in impacts related to asbestos-containing materials or lead-based paint. Finally, as with the Project, preparation and implementation of an emergency response plan would ensure that impacts related to emergency response would be less than significant under Alternative B, similar to the Project.

Land Use and Planning - Similar to the Project, Alternative B also would be substantially consistent with all applicable plans, policies, and regulations (such as SCAG policies that call for developing mixed-use projects near transit to reduce vehicle miles traveled and associated pollutant emissions) that govern development of the Project Site. Thus, impacts related to land use and planning under Alternative B would be less than significant, similar to the Project.

Noise - This alternative would require the use of the same mix of construction equipment identified for the Project. As such, similar to the Project, use of construction equipment under Alternative B would exceed 75 dBA limit in LAMC Section 112.05 limit for powered construction equipment operating within 500 feet of residential zones. Mitigation Measures I-1 and I-2 identified for the Project would also apply to Alternative B and would ensure that impacts related to construction noise would be less than significant, similar to the Project. Additionally, similar to the Project, all on-Site noises, including HVAC and mechanical

equipment use, would be subject to the requirements of the City's Noise Ordinance to ensure compliance with the City's noise standards. Because Alternative B would generate less traffic than the Project, the increase in traffic noise under this alternative also would not be noticeable. Thus, impacts related to operational noise under Alternative B would be less than significant, similar to the Project. Finally, this alternative would also include the use of excavators and loaders, which could impact the Hotel Figueroa. However, Mitigation Measures I-3 through I-5 identified for the Project would also apply to Alternative B and would ensure that impacts related to construction groundborne vibration would be less than significant, similar to the Project. Additionally, Alternative B would not include the use stationary sources of groundborne vibration and would generate less traffic than the Project. As such, impacts related to operational groundborne vibration under Alternative B would be less than significant with mitigation, similar to the Project.

Population and Housing - Using the same persons-to-household number used for the Project (1.89), Alternative B would add approximately 284 residents to the Project Site, 423 fewer than under the Project. As shown on Table VI-3 of the Draft EIR, Alternative B would generate approximately 55 employees, 503 fewer than under the Project. Because this alternative would add fewer residents and employees to the Project Site than would the Project, the growth associated with Alternative B would fall within growth projections for the Community Plan area and the City, as well. Thus, impacts related to population and housing under Alternative B would be less than significant, similar to the Project.

Public Services - The construction phase associated with Alternative B would be shorter in duration than that under the Project. As such, impacts on fire protection services associated with construction under this alternative would be less than significant, similar to the Project. Additionally, any and all development of the Project Site (including development under Alternative B) would be required to comply with City Fire Code, California Fire Code, City Building Code, and National Fire Protection Association standards, thereby ensuring that new development would not create any undue fire hazard. Also, LAFD would require Alternative B to incorporate a sprinkler system into the development to assist with fire suppression, in the event of a fire. Similar to the Project, Alternative B would not require the need for new or altered fire station facilities, and impacts would be less than significant.

Similarly, impacts on police protection services associated with construction under this alternative would be less than significant, similar to the Project. Additionally, all of the security and crime prevention features described above for the Project also would be incorporated into Alternative B. Further, Alternative B would be required to comply with LAPD review requirements and emergency access requirements and would be required to contribute funding to police protection services in the area by generating annual revenue from property taxes that would be deposited into the City's General Fund, which could be used to hire additional police officers. Alternative B's direct population increase and associated demand for police services, along with the provision of on-Site security features, coordination with LAPD, and incorporation of crime prevention features, would not require the provision of new or physically altered police stations in order to maintain acceptable service ratios or other performance objectives for police protection. Therefore, impacts related to police protection services under Alternative B would be less than significant.

Furthermore, as shown on Table VI-5 of the Draft EIR, Alternative B would generate approximately 39 students (19 high school students, 10 middle school students, and 10 elementary school students). Similar to the Project, based on the remaining capacity of the schools serving the Project Site, the Belmont High School Zone would have sufficient capacity to accommodate Alternative B's student generation. However, the elementary school and middle school serving the Project Site could experience further overcrowding in accommodating Alternative B's student generation. Nonetheless, pursuant to the California Government Code, the Project Applicant's payment of the school fees established by the LAUSD in accordance with existing rules and regulations regarding the calculation and

payment of such fees would, by law, provide full and complete mitigation for Alternative B's direct and indirect impacts to schools. Therefore, impacts to school services under Alternative B would be less than significant, similar to the Project.

Also, similar to the Project, the increased residential population associated with Alternative B (approximately 411 residents) in a currently underserved area would potentially increase the demand on existing parks and recreational facilities. However, in accordance with the City's applicable codes for mitigating impacts to parks, the Project Applicant would be required to pay Parkland Fee to the City to mitigate for the Project's demand for parks and recreational facilities. Additionally, Alternative B would be required to meet/exceed LAMC requirements for open space at the Project Site. Through compliance with LAMC requirements, impacts related to parks and recreational services under Alternative B would be less than significant, similar to the Project. Similarly, Alternative B would generate further residents than would the Project and would have less of an impact on library services than the Project. Therefore, impacts related to library services under Alternative B would be less than significant, similar to the Project.

Transportation/Traffic - As shown on Table VI-6 of the Draft EIR, Alternative B would generate a net decrease of approximately 37 daily trips (4,460 fewer than the Project), a net increase of 51 AM peak hour trips (285 fewer than the Project), and a net decrease of 9 PM peak hour trips (383 fewer than the Project). Because Alternative B would generate fewer peak hour trips than the Project, this alternative would not result in any significant intersection LOS impacts under the Existing Plus Project traffic scenario, similar to the Project. In addition, as shown on Table VI-7 of the Draft EIR, Alternative B would not result in any significant intersection LOS impacts under the Future Plus Project traffic scenario, unlike the Project. Thus, Alternative B would avoid the significant and unavoidable intersection LOS impacts that would occur under the Project.

A supplemental analysis was prepared to address impacts under the Future Condition "with the My Fig project" given the completion of the My Fig project. This supplemental analysis is also consistent with the inclusion of that supplemental analysis for the Project in the Draft EIR (Section IV.L Transportation/Traffic) for informational purposes, even though such analysis was not required by LADOT. As shown on Table VI-8, assuming completion and operation of the My Fig project, Alternative B would not result in any significant impacts at any of the study intersections and would avoid the Project's significant unavoidable impacts at Intersection No. 7 (AM and PM peak hours), Intersection No. 8 (AM and PM peak hours), and Intersection No. 9 (AM and PM peak hours).

Similarly, because of the reduced amount of construction traffic and construction phase duration, alternative-specific and cumulative construction traffic impacts under Alternative B would be less than significant. As such, Alternative B would avoid the significant and unavoidable cumulative construction traffic impact that would occur under the Project.

Furthermore, Alternative B would generate fewer peak hour trips than the Project. As such, impacts related to CMP roadway facilities under Alternative B would be less than significant, similar to the Project. Given that Alternative B would generate fewer daily transit trips than the Project, the 46 transit lines serving the Project Site would be able to accommodate Alternative B, and impacts related to transit services under this alternative would be less than significant, similar to the Project. Similarly, because this alternative would generate fewer daily and peak hour trips than the Project, impacts related to Caltrans facilities would be less than significant under Alternative B, similar to the Project.

Tribal Cultural Resources - Any development of the Project Site that includes ground-disturbing activities such as grading and excavation could result in encounters with unknown tribal cultural resources. As such, any developer of the Project Site would be required to comply with the City's Standard Condition of Approval for the Inadvertent Discovery of Tribal Cultural Resources, and any potential impacts would be reduced to less than significant,

similar to the Project.

Utilities and Service Systems - As shown on Table VI-12 of the Draft EIR, Alternative B would generate a net total of approximately 19,047 gpd of wastewater (or 0.019 mgd), 154,450 gpd of wastewater less than the Project. Thus, impacts related to wastewater service under Alternative B would be less than significant, similar to the Project. Further, as shown on Table VI-14 of the Draft EIR, Alternative B would consume a net total of approximately 14,772 gpd of water (or 0.014 mgd), 179,804 gpd of water less than the Project. Thus, impacts related to water supply under Alternative B would be less than significant, similar to the Project. Similarly, the amount of demolition and construction waste and long-term operational waste generation under Alternative B would be less than under the Project. As such, impacts related to solid waste under Alternative B would be less than significant, similar to the Project. Finally, because LADWP and SoCalGas could accommodate the Project's demand for electricity and natural gas (respectively), the demand for electricity and natural gas associated with Alternative B also could be accommodated. Thus, the demand for electricity and natural gas under Alternative B would not result in a wasteful or inefficient use of energy, similar to the Project.

Finding

Specific economic, legal, social, technological, other considerations, including considerations for the provision of employment opportunities for highly trained workers, make infeasible the mitigation measures or alternatives identified in the EIR.

Rationale for Finding

Given the reduced residential and retail development and no development of hotel uses under Alternative B, this Alternative would only partially meet most of the Project Objectives and would meet those objectives to a lesser degree as compared to the Project.

Alternative B could be developed to meet Project Objective 1 (DTLA skyline). However, due to the reduction in building height as compared to the Project, the building under Alternative B might not contribute to the Downtown Los Angeles skyline. Given the reduced height, Alternative B would not achieve this objective to the same degree as the Project. It would partially meet Project Objective 2 (smart growth) because the alternative includes a reduced amount of housing, office, and retail land uses. However, Alternative B would not meet this objective to the extent the objective supports developing visitor-serving hotel uses near public transit and the Los Angeles Sports and Entertainment District. Given the reduced residential, retail, and office uses, and no hotel uses, Alternative B would achieve Project Objective 3 (pedestrian-friendly retail zone) to a lesser degree as compared to the Project. Alternative B would partially meet this objective because the alternative includes a reduced amount of housing, office, and retail land uses. However, Alternative B would not meet this objective to the extent the objective supports developing a pedestrian friendly commercial retail zone accessible to future hotel guests. Given the reduced residential, retail, and office uses, and no hotel uses, Alternative B would achieve this objective to a lesser degree as compared to the Project. Alternative B would meet Project Objective 4 (unique housing), but to a lesser degree as compared to the Project, because the alternative reduces the number of proposed residential units by more than half of the units proposed in the Project. It would partially meet Project Objective 5 (multi-use location) because the alternative includes a reduced amount of housing, office, and retail land uses on the Project Site. Given the reduced number of residential units and reduced commercial and office uses, Alternative B would meet this objective to a lesser degree as compared to the Project. Alternative B would partially meet Project Objective 6 (City economic growth) because the alternative includes a reduced amount of housing, office, and retail land uses. However, Alternative B would not meet this objective to the extent the objective supports contributing to the City's economic growth by developing hotel uses. Given the reduction in proposed uses, Alternative B would meet this objective to a lesser degree as compared to the Project. Alternative B would meet Project Objective 7 (different sized residential units) but to a lesser degree as compared to the Project,

because the alternative reduces the number of proposed residential units by more than half of the units proposed in the Project.

In addition, the City's planning goals and policies indicate that redevelopment of the Project Site should be high-density. Alternative B would not maximize developable area on the Project Site due to the reduced proposed density of the alternative. Moreover, the City's has stated its vision for the Project Site in several documents, which indicate that the Project Site should contain high density uses to maximize density on redevelopment sites located adjacent to transit and within the transit core areas identified in the City's planning and policy documents. (See e.g., 2008 RCP Land Use and Housing Policy LU-4; General Plan Framework Element: Land Use Chapter, Policies 3.1.1, 3.2.2; General Plan Housing Element, Policy 1.3.5; Central City Community Plan Residential Policy 1-1.1.) The reduced density associated with Alternative B conflicts with the City's planning goals and is undesirable from a policy standpoint.

Furthermore, regarding social and other considerations, the Project Site is located in an area of the City that is undergoing rapid change and densification. The existing conditions and development trends immediately surrounding the Project Site are maximizing density because the area is transit rich, located adjacent to the Los Angeles Convention Center and regional entertainment venues. Thus, there are several social and other considerations that warrant maximizing the density of development on the Project Site to implement a hotel project that can deliver the amount and type of hotel rooms and amenities desired by the City to support hotel room demand caused by convention business, regional entertainment venues, domestic and international tourism, and the Olympics.

Reference

For a complete discussion of impacts associated with Alternative B, see Section VI (Alternatives to the Proposed Project) of the Draft EIR.

Alternative C: No Office and Reduced Retail

Description of Alternative

The No Office and Reduced Retail (Alternative C) assumes implementation of the Project as described in Section III (Project Description) of the Draft EIR but without any of the proposed office land uses and with a reduced amount of retail square footage. Alternative C would include development of a 710,675-square-foot mixed-use building with 374 multi-family dwelling units (and 18,004 square feet of residential amenities), 30,074 square feet of retail land uses, a 373-room hotel (and a 10,801-square-foot conference center/ballroom and 13,029 square feet of lobby/hotel amenities), four levels of subterranean parking, and 6 levels of above-ground parking. The building would be 54 stories and 682 feet in height. The overall design, architecture, siting, and vehicle/bicycle/pedestrian would be substantially similar to that described for the Project. A comparison of the general land uses proposed as part of the Project to those under Alternative C is shown on Table VI-2 of the Draft EIR.

Impact Summary of Alternative

Aesthetics - As stated previously, due to topography, vegetation, and development, medium and long-distance views are not available from the Project Site area. Also, the Project Site is not visible within any scenic views. Thus, Alternative C would not result in any impacts related to scenic vistas, similar to the Project. Further, no scenic resources are located on the Project Site. Similar to the Project, no impacts related to scenic resources would occur under Alternative C. Also, because Alternative C includes development of the Project Site with land uses that similar to those proposed as part of the Project but reduced in size, impacts related to visual character under this alternative would be less than significant. Finally, because Alternative C includes development of the Project Site with land uses that similar to those proposed as part of the Project but reduced in size, the amount of lighting and sources of glare, as well as shade and shadow associated with Alternative C would be less than under

the Project. Thus, impacts related to light and glare, as well as shade and shadow under this alternative would be less than significant, similar to the Project.

Air Quality - Alternative C includes the same number of residential dwelling as the Project and would add the same number of residents to the Project Site, 707. As such, Alternative C would not result in unexpected population growth, and impacts related to consistency with SCAQMD's AQMP would be less than significant, similar to the Project. Further, although this alternative would require less excavation than the Project and would include construction of less overall square footage, the maximum construction day scenario under Alternative C could generate regional NOx emissions and localized NOx, PM10, and PM2.5 emissions in excess of SCAQMD's significance thresholds, similar to the Project. Without mitigation, sensitive receptors near the Project Site could be exposed to these construction emissions. However, Mitigation Measure C1 identified for the Project also would apply to this alternative and would reduce the referenced emissions to below the relevant significance thresholds. Thus, impacts related to construction emissions/sensitive receptors under Alternative C would be less than significant, similar to the Project. Additionally, because this alternative includes land uses that are similar to those proposed as part of the Project but less overall square footage, Alternative C would generate less area source, energy source, and mobile source emissions than under the Project. Sensitive receptors in the vicinity of the Project Site would not be exposed to substantial operational emissions. As such, operational emissions under Alternative C would not exceed SCAQMD's significance thresholds. Thus, operational emissions/sensitive receptors impacts under Alternative C would be less than significant, similar to the Project. Finally, the amount of TACs generated under Alternative C would be less than under the Project. Thus, impacts related to TACs under this alternative would be less than significant, similar to the Project.

Cultural Resources - No historical resources would be demolished, altered, or relocated as a result of Alternative C. The building under Alternative C would meet LAMC setback requirements, similar to the Project, and would not affect the physical integrity or historical significance of any of the three historical resources near the Project Site. Thus, Alternative C would not result in any direct or indirect impacts to historical resources, similar to the Project. Yet because the Project Site area has a high sensitivity for containing historic archaeological resources, any development of the Project Site that includes ground-disturbing activities such as grading and excavation could result in encounters with unknown historic archaeological resources. Mitigation Measures D-1 through D-4 would apply to any development of the Project Site (including that under Alternative C), and impacts would be less than significant, similar to the Project.

Geology and Soils - Because the Project Site is the same under Alternative C as it is for the Project, any development of the Project Site would be subject to the same geotechnical issues identified for the Project and would be subject to the most recently adopted California Building Code design parameters to ensure that impacts related to geology and soils would be less than significant.

GHG Emissions - Because Alternative C includes the construction and operation of land uses that are similar to those proposed as part of the Project but somewhat less in overall square footage, the amount of GHG emissions that would be generated as a result of construction and long-term operation of the alternative would be less than those of the Project. Similar to the Project, Alternative C would be required to comply with numerous regulatory compliance measures, particularly those associated with the City's Green Building Code that would reduce the alternative's GHG emissions profile and would represent improvements with respect to the NAT scenario. Thus, Alternative C's GHG emissions reductions as compared to the NAT scenario demonstrate consistency with GHG Reduction Plans, Executive Orders S-3-05 and B-30-15, SCAG's Sustainable Communities Strategy, and the City's Green Building Ordinance. Thus, Alternative C's contribution to global climate change would not be cumulatively considerable and would be less than significant, similar to the Project.

Hazards and Hazardous Materials - Similar to the Project, during the construction and operational phases for Alternative C, this alternative would involve the transport, use, and storage of relatively small amounts of potentially hazardous materials, such as paints, adhesives, surface coatings, cleaning agents, waxes, fuels, and oils. However, compliance with applicable city, state, and federal regulations related to the handling, storage, transport, and disposal of hazardous materials and waste during operation of this alternative would ensure that no significant hazard to the public or the environment occurs. Therefore, impacts related to the transport, use, storage, disposal, and/or emissions of hazardous materials under Alternative C would be less than significant, similar to the Project. Additionally, any development of the Project Site (including development under Alternative C) that includes ground-disturbing activities would result in the same potential to encounter residual soil contamination, as identified for the Project. Mitigation Measure G-1 identified for the Project would also apply to Alternative C and would ensure that impacts related to residual soil contamination would be less than significant. Also, any development of the Project Site (including development under Alternative C) would be required to comply with LAMC Section 91.71 to ensure that impact related to methane would be less than significant. Because the existing structure on the Project Site was constructed after 1978, no development of the Project Site would result in impacts related to asbestos-containing materials or lead-based paint. Finally, Preparation and implementation of an emergency response plan would ensure that impacts related to emergency response would be less than significant under Alternative C, similar to the Project.

Land Use and Planning - Similar to the Project, Alternative C would be substantially consistent with all applicable plans, policies, and regulations that govern development of the Project Site. Thus, impacts related to land use and planning under Alternative C would be less than significant, similar to the Project.

Noise - This alternative would require the use of the same mix of construction equipment identified for the Project. As such, similar to the Project, use of construction equipment under Alternative C would exceed LAMC Section 112.05's 75 dBA limit for powered construction equipment operating within 500 feet of residential zones. Mitigation Measures I-1 and I-2 identified for the Project would also apply to Alternative C and would ensure that impacts related to construction noise would be less than significant, similar to the Project. Furthermore, similar to the Project, all on-Site noises, including HVAC and mechanical equipment use, would be subject to the requirements of the City's Noise Ordinance to ensure compliance with the City's noise standards. Additionally, because Alternative C would generate less traffic than the Project, the increase in traffic noise under this alternative also would not be noticeable. Thus, impacts related to operational noise under Alternative C would be less than significant, similar to the Project. Finally, this alternative would also include the use of excavators and loaders, which could impact the Hotel Figueroa. However, Mitigation Measures I-3 through I-5 identified for the Project would also apply to Alternative C and would ensure that impacts related to construction groundborne vibration would be less than significant, similar to the Project. Additionally, Alternative C would not include the use stationary sources of groundborne vibration and would generate less traffic than the Project. As such, impacts related to operational groundborne vibration under Alternative C would be less than significant with mitigation, similar to the Project.

Population and Growth - Because Alternative C includes the same number of residential dwelling units as does the Project, this alternative would add the same number residents to the Project Site – 707 residents. As shown on Table VI-4, Alternative C would generate approximately 344 employees, 214 fewer than under the Project. Because this alternative would add the same number of residents and fewer employees to the Project Site than would the Project, the growth associated with Alternative C would fall within growth projections for the Community Plan area and the City, as well. Thus, impacts related to population and housing under Alternative C would be less than significant, similar to the Project.

Public Services - The construction phase associated with Alternative C would likely be somewhat similar in duration than that under the Project. As such, impacts on fire protection services associated with construction under this alternative would be less than significant, similar to the Project. Additionally, any and all development of the Project Site (including development under Alternative C) would be required to comply with City Fire Code, California Fire Code, City Building Code, and National Fire Protection Association standards, thereby ensuring that new development would not create any undue fire hazard. Also, LAFD would require Alternative C to incorporate a sprinkler system into the development to assist with fire suppression, in the event of a fire. Similar to the Project, Alternative C would not require the need for new or altered fire station facilities, and impacts would be less than significant.

Similarly, impacts on police protection services associated with construction under this alternative would be less than significant, similar to the Project. Additionally, all of the security and crime prevention features described above for the Project also would be incorporated into Alternative C. Further, Alternative C would be required to comply with LAPD review requirements and emergency access requirements and would be required to contribute funding to police protection services in the area by generating annual revenue from property taxes that would be deposited into the City's General Fund, which could be used to hire additional police officers. Alternative C's direct population increase and associated demand for police services, along with the provision of on-Site security features, coordination with LAPD, and incorporation of crime prevention features, would not require the provision of new or physically altered police stations in order to maintain acceptable service ratios or other performance objectives for police protection. Therefore, impacts related to police protection services under Alternative C would be less than significant.

Additionally, because Alternative C includes the same number of dwelling units as the Project, the number of students generated under Alternative would be the same as for the Project. Therefore, impacts to school services under Alternative C would be less than significant, similar to the Project. Similar to the Project, the increased residential population associated with Alternative C (approximately 707 residents) in a currently underserved area would potentially increase the demand on existing parks and recreational facilities. Through compliance with LAMC requirements, impacts related to parks and recreational services under Alternative C would be less than significant, similar to the Project. Finally, Alternative C would generate the same number of residents as the Project and would generate a similar demand for library services as the Project. Therefore, impacts related to library services under Alternative C would be less than significant, similar to the Project.

Transportation/Traffic - As shown on Table VI-9 of the Draft EIR, Alternative C would not result in any significant intersection LOS impacts under the Existing Plus Project traffic scenario, similar to the Project. Alternative C would result in significant unavoidable impacts during the AM peak hour at Intersection No. 7 and during the PM peak hour at Intersection No. 8 (similar to the Project), but Alternative C would avoid the significant unavoidable impacts during the PM peak hour at Intersection No. 7 and the AM peak hour at Intersection No. 8 that would occur under the Project.

A supplemental analysis was prepared to address impacts under the Future Condition "with the My Fig project" given the completion of the My Fig project. This supplemental analysis is also consistent with the inclusion of that supplemental analysis for the Project in the Draft EIR (Section IV.L Transportation/Traffic) for informational purposes, even though such analysis was not required by LADOT. As shown on Table VI-11, assuming completion and operation of the My Fig project, Alternative C would result in significant impacts at three study intersections – Intersection No. 7 (AM peak hour), Intersection No. 8 (AM and PM peak hours), and Intersection No. 9 (AM and PM peak hours) – resulting in the reduction of one peak-hour impact as compared to the Project (i.e., peak-hour impact at Intersection No. 7).

Further, although Alternative C includes development of 68,498 less square feet than the

Project, the overall amount of construction traffic that would be generated and the overall construction phase duration under Alternative C would be substantially similar to those under the Project. Similar to the Project, Alternative C would be required to implement a Construction Traffic Management Plan (Mitigation Measure L-1), which would minimize construction traffic impacts on the roadways in the Project Site area. Also similar to the Project, alternative-specific construction traffic impacts would be less than significant. However, cumulative construction traffic impacts under Alternative C would be significant and unavoidable.

Alternative C would generate fewer peak hour trips than the Project. As such, impacts related to CMP roadway facilities under Alternative C would be less than significant, similar to the Project. Further, given that Alternative C would generate fewer daily transit trips than the Project, the 46 transit lines serving the Project Site would be able to accommodate Alternative C, and impacts related to transit services under this alternative would be less than significant, similar to the Project. Finally, because this alternative would generate fewer daily and peak hour trips than the Project, impacts related to Caltrans facilities would be less than significant under Alternative C, similar to the Project.

Tribal Cultural Resources - Any development of the Project Site that includes ground-disturbing activities such as grading and excavation could result in encounters with unknown tribal cultural resources. As such, any developer of the Project Site would be required to comply with the City's Standard Condition of Approval for the Inadvertent Discovery of Tribal Cultural Resources, and any potential impacts would be reduced to less than significant, similar to the Project.

Utilities and Service Systems - As shown on Table VI-13 of the Draft EIR, Alternative C would generate a net total of approximately 92,802 gpd of wastewater (or 0.09 mgd), 80,695 gpd of wastewater less than the Project. Thus, impacts related to wastewater service under Alternative C would be less than significant, similar to the Project. Also, Alternative C would consume approximately 157,556 gpd of water, 37,020 gpd of water less than the Project. Thus, impacts related to water supply under Alternative C would be less than significant, similar to the Project. Further, because this alternative includes development of the same Site as under the Project and with similar land uses but with less overall square footage, the amount of demolition and construction waste and long-term operational waste generation under Alternative C would be less than under the Project. As such, impacts related to solid waste under Alternative C would be less than significant, similar to the Project. Finally, because LADWP and SoCalGas could accommodate the Project's demand for electricity and natural gas (respectively), the demand for electricity and natural gas associated with Alternative C also could be accommodated, as it includes less overall square footage as the Project on the same Site. Thus, the demand for electricity and natural gas under Alternative C would not result in a wasteful or inefficient use of energy, similar to the Project.

Finding

Specific economic, legal, social, technological, other considerations, including considerations for the provision of employment opportunities for highly trained workers, make infeasible the mitigation measures or alternatives identified in the EIR.

Rationale for Finding

Given the reduced residential and retail development and no development of hotel uses under Alternative C, this Alternative would only partially meet most of the Project Objectives and would meet those objectives to a lesser degree as compared to the Project.

Alternative C could be developed to meet Project Objective 1 (DTLA skyline). However, due to the reduction in building height as compared to the Project, the building under Alternative C might not contribute to the Downtown Los Angeles skyline. Given the reduced height, Alternative C would not achieve this objective to the same degree as the Project. It would partially meet Project Objective 2 (smart growth) because the alternative includes a reduced amount of retail

land uses and does not include any office uses. Given the reduced retail and elimination of hotel uses, Alternative C would meet this objective to a lesser degree as compared to the Project. It would meet Project Objective 3 (pedestrian-friendly retail zone), although possibly to a lesser degree as compared to the Project due to the reduction retail square footage. Alternative C would meet Project Objective 4 (unique housing). Alternative C would partially meet Project Objective 5 (multi-use location) because the alternative includes residential uses in the same location as commercial uses. However, Alternative C would not meet this objective to the extent the objective supports providing residential uses in the same location as office uses. Given the reduction in commercial uses and elimination of office uses, this Alternative will meet this objective to a lesser degree as compared to the Project. Alternative C would meet Project Objective 6 (City economic growth), but to a lesser degree than the Project due to the reduced retail uses and elimination of office uses. It would meet Project Objective 7 (different sized residential units).

In addition, the City's planning goals and policies indicate that redevelopment of the Project Site should be high-density. Alternative B would not maximize developable area on the Project Site due to the reduced proposed density of the alternative. Moreover, the City's has stated its vision for the Project Site in several documents, which indicate that the Project Site should contain high density uses to maximize density on redevelopment Sites located adjacent to transit and within the transit core areas identified in the City's planning and policy documents. (See e.g., 2008 RCP Land Use and Housing Policy LU-4; General Plan Framework Element: Land Use Chapter, Policies 3.1.1, 3.2.2; General Plan Housing Element, Policy 1.3.5; Central City Community Plan Residential Policy 1-1.1.) The reduced density associated with Alternative C conflicts with the City's planning goals and is undesirable from a policy standpoint.

Furthermore, regarding social and other considerations, the Project Site is located in an area of the City that is undergoing rapid change and densification. The existing conditions and development trends immediately surrounding the Project Site are maximizing density because the area is transit rich, located adjacent to other major office buildings and regional entertainment venues. Thus, there are several social and other considerations that warrant maximizing the density of development on the Project Site to implement an office project that can deliver the amount and type of office rooms and amenities desired by the City to support business demand.

Reference

For a complete discussion of impacts associated with Alternative C, see Section VI (Alternatives to the Proposed Project) of the Draft EIR.

Environmentally Superior Alternative

Section 15126.6(e)(2) of the CEQA Guidelines indicates that an analysis of alternatives to a project shall identify an environmentally superior alternative among the alternatives evaluated in an EIR. The CEQA Guidelines also state that should it be determined that the No Project Alternative is the Environmentally Superior Alternative, the EIR shall identify another Environmentally Superior Alternative among the remaining alternatives. An environmentally superior alternative is an alternative to a project that would reduce and/or eliminate the significant, unavoidable environmental impacts associated with the project without creating other significant impacts and without substantially reducing and/or eliminating the environmental benefits attributable to the project.

Alternative A (the No Project Alternative) would be environmentally superior to the Project, since this alternative would avoid all of the significant (but mitigatable) impacts, including Air Quality (Regional and Localized Construction Emissions and Sensitive Receptors), Cultural Resources (Archaeological Resources) Hazards and Hazardous Materials (Upset Conditions Involving the Release of Hazardous Materials), Noise (Construction Noise and Construction Vibration), and Utilities and Service Systems (Water Services), and the significant unavoidable impacts related to Transportation/Traffic (Operational Intersection LOS and Construction Traffic) that would occur under the Project. Also, Alternative A would not achieve any of the Project objectives.

In accordance with CEQA Guidelines Section 15126.6(e), if the environmentally superior alternative is the “no project” alternative, the EIR shall also identify an environmentally superior alternative among the other alternatives, which include Alternative B and Alternative C.

Because Alternative B would likely lessen the degree to which any impact would occur under the Project, given the reduction in overall square footage, and would avoid the significant unavoidable construction traffic and intersection LOS impacts that would occur under the Project, Alternative B is the Environmentally Superior Alternative. However, Alternative B would only partially meet the Project Objectives and would meet those objectives to a lesser degree as compared to the Project.

Alternatives Rejected as Being Infeasible

Section 15126.6(c) of the CEQA Guidelines requires EIRs to identify any alternatives that were considered by the lead agency but were rejected as infeasible, and briefly explain the reasons underlying the lead agency's determination. According to the CEQA Guidelines, among the factors that may be used to eliminate an alternative from detailed consideration are the alternative's failure to meet project objectives, the alternative's infeasibility, or the alternative's inability to avoid significant environmental impacts. Alternatives can be rejected by the City for specific economic, legal, social, technological, or other considerations, including provision of employment opportunities for highly trained workers, that make infeasible the project alternatives identified in the final EIR. Alternatives to the Project that have been considered and rejected as infeasible include the following:

Alternate Project Site - This alternative considered development of the Project on an alternate Site within the Project Site area. However, this alternative was rejected for further analysis, because the Project Applicant does not own or have control over any other developable property in the Project Site area and cannot “reasonably acquire, control or otherwise have access to [an] alternative Site” (refer to Section 15126.6[f][1] of the CEQA Guidelines). Thus, this alternative was deemed infeasible.

All Office Alternative - This alternative considered development of the Project Site with only an office land use and associated parking. However, this alternative was rejected for further analysis, because developing a single land use at the Project Site would not meet nearly all of the Project Objectives, including the most basic and important purpose the Project, which is to develop a mix of land uses at the Project Site that aim to ensure the activation of the City streetscape, where retail land uses on the first three levels, followed by office land uses, and topped with hotel and residential land uses would attract pedestrians from within the Project Site area, while providing support to local businesses, attractions, and places of employment. Because this alternative would not meet nearly all of the Project Objectives, this alternative was considered infeasible.

Significant Irreversible Environmental Changes

Section 15126.2(c) of the CEQA Guidelines indicates that an EIR should evaluate any significant irreversible environmental changes that would occur should the proposed project be implemented. The types and level of development associated with the project would consume limited, slowly renewable, and non-renewable resources. This consumption would occur during construction of the project and would continue throughout its operational lifetime. The development of the Project would require a commitment of resources that would include: (1) building materials and associated solid waste disposal effects on landfills; (2) water; and (3) energy resources (e.g., fossil fuels) for electricity, natural gas, and transportation.

Pursuant to section 15126.2(c) of the CEQA Guidelines, the City considered the potential significant irreversible environmental changes that could result from the Project. Construction of the Project would require the use of nonrenewable resources (i.e., wood, metals, sand, gravel, fossil fuels) for building materials and to fuel construction vehicles and equipment.

Subsequent use and maintenance of the Project would also require the long-term consumption of these non-renewable resources at reduced levels. Recently, shortages of water, steel, and concrete ingredients have been issues of concern. The commitment of resources required for the construction and operation of the Project would limit the availability of such resources for future generations or for other uses during the life of the Project. Although these resource commitments and environmental changes would occur gradually, their combined loss could be considered significant and irreversible. However, continued use of such resources is consistent with the anticipated growth and planned changes on the Project Site and in the City. As such, any irreversible damage caused by the Project from use of nonrenewable resources, including irretrievable commitments of nonrenewable resources, would be less than significant.

The Project would also result in commitment of the land at the Project Site, eliminating other options for its use. The existing Site would be replaced with a new mixed-use development. Along with the long-term commitment of land uses is an increased commitment of certain public services to the Project. This includes the provision of police, fire and emergency medical services, water supply services, wastewater treatment services, and solid waste disposal. As explained above, the Project would not create significant or irreversible damage resulting from the commitment of land at the Project Site, including the increased commitment of certain public services.

The Project would allow for the development of residential and retail land uses. During long-term operation of the Project, some hazardous materials such as solvents, cleaners, and petroleum products could be used and stored at the Site. However, the amounts of these materials that would be present at the Site would be insignificant, and the users of these materials would be required to comply with all local, state, and federal laws pertaining to the management of hazardous materials and wastes. Through compliance with these laws, the Project would not create irreversible damage resulting from environmental accidents associated with the Project.

Growth-Inducing Impacts

Pursuant to section 15126.2(d) of the CEQA Guidelines, the City considered the Project's potential growth-inducing impacts. Generally, a Project may foster or encourage population growth in a geographic area if it meets any of the following criteria: (i) economic expansion or growth (e.g., changes in revenue base, employment expansion, etc.); (ii) removal of an impediment to growth (e.g., establishment of an essential public service or the provision of new access to an area); (iii) establishment of a precedent-setting action (e.g., an innovation, a change in zoning, or general plan amendment approval); or (iv) development of or encroachment on an isolated adjacent area of open space (being distinct from an "infill" type of encroachment).

As discussed in Section IV.J (Population and Housing) of the Draft EIR, based on the 2016 persons-per household rate for the Central City Community Plan, the Project would add a residential population of approximately 707 people to the Project Site. The Project's residential population would represent approximately 0.73 percent of the forecasted growth between 2016 and 2040 in the Central City Community Plan Area. The Project's housing units would represent approximately 0.37 percent of forecasted growth between 2016 and 2040 in the Community Plan area. Thus, the Project's population growth would fall within the forecasted growth for the Community Plan area.

The Project's residential population would represent 0.21 percent of the forecasted growth between 2020 and 2035 in the City and 0.11 percent of the forecasted growth between 2020 and 2040. The Project's housing units would represent approximately 0.21 percent of forecasted growth between 2020 and 2035 in the City and 0.15 percent between 2020 and 2040. The Project's employment would represent approximately 0.62 percent of the forecasted growth between 2020 and 2035 in the City and 0.15 percent between 2020 and

2040. Thus, the Project's population growth would fall within the forecasted growth for the City.

The land use designation for the Project Site in the Community Plan is Regional Center Commercial, with an underlying corresponding C2-4D (Commercial, Height District 4 with Development Limitation) zoning designation. The Project's proposed land uses are allowed under the existing land use designation and zoning. The Development Limitation associated with the existing zoning of the Project Site limits the developable FAR to 6:1. However, pursuant to Section 14.5 of the LAMC, the Project Applicant is seeking a TFAR of 559,452 square feet from a "donor" Site to the Project Site that would allow an increase in the FAR associated with the Project to 13:1. With the TFAR, the Project would not result in an increase in housing and associated residential population within the Community Plan area or City that was not already anticipated. Thus, the Project would not result in unexpected population growth. Therefore, Project impacts related to population and housing would be less than significant.

The Project would include improvements to infrastructure, including drainage, sewer, water, electricity, and natural gas near and at the Project Site to serve the Project only. Such infrastructure improvements would be limited to the Project Site and would not extend onto adjacent parcels. Therefore, Project impacts related to substantial population growth resulting from infrastructure improvements would be less than significant.

Additionally, as discussed in Section IV.I (Noise) of the Draft EIR, the Project's commercial development would generate approximately 558 employees. However, the types of jobs associated with the Project (i.e., hotel employees, retail cashiers and clerks, office workers) could be accommodated by people in the existing workforce in the Project Site vicinity and/or other areas of the City.

Statement of Overriding Considerations

The Final EIR for the Project has identified unavoidable and significant impacts that will result from implementation of the Project. Section 21081 of the Public Resources Code and Section 15093(b) of the CEQA Guidelines provide that when a public agency's decision allows the occurrence of a significant impact identified in a Final EIR that is not at least substantially mitigated to an insignificant level or eliminated, the lead agency must state in writing the reasons to support its action based on the completed EIR and/or other information in the record. Article I of the City of Los Angeles CEQA Guidelines incorporates all of the State CEQA Guidelines contained in title 15, California Code of Regulations, sections 15000 et seq., and hereby requires, pursuant to CEQA Guidelines Section 15093(b) that the decision-maker adopt a Statement of Overriding Considerations at the time of approval of a project if it finds that significant adverse environmental effects have been identified in the Final EIR that cannot be substantially mitigated to an insignificant level or be eliminated. These Findings and the Statement of Considerations are based on the record of proceedings, including, but not limited to, the Final EIR, and other documents and materials that constitute the record of proceedings.

Based on the analysis provided in the Final EIR, implementation of the Project would result in significant impacts that cannot be feasibly mitigated with respect to Traffic and Transportation.

Accordingly, the City adopts this Statement of Overriding Considerations. Having (i) adopted all feasible mitigation measures; (ii) determined that Alternatives A, B and C would not meet the Project objectives to the same degree as the Project, as discussed above in Section VII; (iii) recognized the significant and unavoidable impacts; and (iv) balanced the benefits of the Project against its significant and unavoidable impacts, the City hereby finds that each of the benefits outweigh and override the significant unavoidable impacts for the reasons stated below.

The City further finds and determines that:

- a) All significant environmental impacts that can be feasibly avoided have been eliminated, or substantially lessened through implementation of the project design features and/or mitigation measures; and
- b) Based on the Final EIR, the Statement of Overriding Considerations herein, and other documents and information in the record with respect to the construction and operation of the project, all remaining unavoidable significant impacts, as set forth in these findings, are overridden by the benefits of the project as described in the Statement of Overriding Considerations for the construction and operation of the project and implementing actions.

The below stated reasons summarize the benefits, goals, and objectives of the Project and provide the rationale for the benefits of the Project. Any one of the overriding considerations of economic, social, aesthetic and environmental benefits listed below would be sufficient to outweigh the adverse environmental impacts of the Project and justify its approval.

1. **Smart Growth.** The Project is consistent with the City's current and long-term planning visions for the Project Site. The City desires to locate density near mass transit to reduce environmental impacts and implement smart growth planning decisions. This strategy is particularly relevant to reduce traffic, air quality, greenhouse gas, and health impacts that are caused by vehicular travel. The Project is near Metro Expo Line and Blue Line transit stations and existing and new pedestrian and bicycle infrastructure developed as part of the MyFigueroa project. In addition, the Project is within the downtown Los Angeles regional center, and in proximity to the Los Angeles Convention Center and the Los Angeles Sports and Entertainment District, including the L.A. Live complex. In these respects, the Project is consistent with planning goals and policies to improve the area, and results in a beneficial reduction in Vehicle Miles Travelled and related environmental and land use impacts. Implementation of the Project will capitalize on smart growth by substantially improving existing conditions on the site, which contains limited residential and commercial opportunities, with an infill mixed-use development containing residential, office, and visitor-serving hotel uses that fulfill policy directives to focus housing and employment growth within High-Quality Transit Areas (HQTAs) designated by the Southern California Association of Governments (SCAG).
2. **Supports City's Hotels Goals and Tourism.** The City has an established mandate to develop 8,000 hotel rooms within walking distance to the Los Angeles Convention Center, and the Project provides a material benefit to the City accomplishing this goal by contributing 373 hotel guest rooms located near the Los Angeles Convention Center. Hence, the Project is a substantial benefit for the City by accommodating visitors and tourism and to become more competitive with other cities that attract large conventions and the related direct and indirect economic benefits.
3. **Supports City's Housing Goals.** The Project helps achieve the Mayor's goal to build 100,000 units of housing by 2021 and provide support toward the City's Regional Housing Needs Assessment allocation, by developing 374 new multi-family residential condominiums, in a mix of unit sizes, thereby significantly enhancing the diversity and stock of housing in the downtown area.
4. **Employment and Tax Revenue.** The Project will develop new retail, restaurant, commercial office, and ancillary hotel uses that provide short- and long-term employment opportunities for the City. The Project would provide substantial economic benefits for the City as it would generate construction jobs, and operation will create 558 permanent jobs. In addition, the Project would result in construction revenues of approximately \$4.4 million

and annual generation of approximately \$8.3 million. In addition, the Project will attract new hotel guests and residents which are likely to support the local businesses contained within the mixed-use project and in the vicinity of the site.

5. **Pedestrian Enhancements.** The project proposes ample bike parking, a pedestrian-friendly environment, and a Traffic Demand Management (TDM) program that supports multi-modal options for residents, employees, and visitors of the site, including payments for bicycle infrastructure improvements and pedestrian continental crosswalks in the vicinity. The Project would also focus growth along major transportation corridors and within walking distance of a transit station, and would provide bicycle facilities in proximity to the MyFigueroa project, supporting multi-modal mobility options and enhancing the predominantly restaurant and hotel options presently available in and around L.A. Live.
6. **Public Benefits.** The project will contribute \$22,158,132 as part of the Transfer of Development Rights proposed in public benefits, with 50% of that total being assigned to the Public Benefit Payment Trust Fund, and other payments assigned to specific initiatives in the downtown area, which may include affordable housing and public park improvements.
7. **Contribution to Downtown Architecture.** Implementation of the Project will include the development of an iconic, architecturally-compelling tower, which contributes visual distinction and a unique feature to the Downtown Los Angeles skyline, particularly when viewed from the south.
8. **Sustainability.** The Project will be consistent with the City's Green Building Code and Mayor's Green New Deal by incorporating sustainable and green building design and construction to promote resource conservation, including electric-vehicle charging, solar-panels, and water conservation measures in excess of Code requirements.

General Findings

1. The City, acting through the Department of City Planning, is the "Lead Agency" for the project evaluated in the EIR. The City finds that the EIR was prepared in compliance with CEQA and the CEQA Guidelines. The City finds that it has independently reviewed and analyzed the EIR for the project, that the Draft EIR which was circulated for public review reflected its independent judgment and that the Final EIR reflects the independent judgment of the City.
2. The EIR evaluated the following potential project and cumulative environmental impacts: Aesthetics, Air Quality, Cultural Resources, Geology and Soils, Greenhouse Gases, Hazards and Hazardous Materials, Hydrology and Water Quality, Land Use and Planning, Noise, Population and Housing, Public Services, Transportation, Tribal Cultural Resources, Utilities and Service Systems, Energy conservation and Infrastructure, alternatives, and other CEQA considerations. Additionally, the EIR considered, in separate sections, Significant Irreversible Environmental Changes and Growth Inducing Impacts. The significant environmental impacts of the project and the alternatives were identified in the EIR.
3. The City finds that the EIR provides objective information to assist the decision makers and the public at large in their consideration of the environmental consequences of the project. The public review periods provided all interested jurisdictions, agencies, private organizations, and individuals the opportunity to submit comments regarding the Draft

EIR. The Final EIR was prepared after the review periods and responds to comments made during the public review periods.

5. The Department of City Planning evaluated comments on environmental issues received from persons who reviewed the Draft EIR. In accordance with CEQA, the Department of City Planning prepared written responses describing the disposition of significant environmental issues raised. The Final EIR provides adequate, good faith and reasoned responses to the comments. The Department of City Planning reviewed the comments received and responses thereto and has determined that neither the comments received nor the responses to such comments add significant new information regarding environmental impacts to the Draft EIR. The Lead Agency has based its actions on full appraisal of all viewpoints, including all comments received up to the date of adoption of these findings, concerning the environmental impacts identified and analyzed in the EIR.
6. The Final EIR documents changes to the Draft EIR. Having reviewed the information contained in the Draft EIR, the Final EIR, and the administrative record, as well as the requirements of CEQA and the CEQA Guidelines regarding recirculation of Draft EIRs, the City finds that there is no new significant impact, substantial increase in the severity of a previously disclosed impact, significant new information in the record of proceedings or other criteria under CEQA that would require additional recirculation of the Draft EIR, or that would require preparation of a supplemental or subsequent EIR. Specifically, the City finds that:
 - The City has thoroughly reviewed the public comments received regarding the project and the Final EIR as it relates to the project to determine whether under the requirements of CEQA, any of the public comments provide substantial evidence that would require recirculation of the EIR prior to its adoption and has determined that recirculation of the EIR is not required.
 - None of the information submitted after publication of the Final EIR, including testimony at the public hearings on the project, constitutes significant new information or otherwise requires preparation of a supplemental or subsequent EIR. The City does not find this information and testimony to be credible evidence of a significant impact, a substantial increase in the severity of an impact disclosed in the Final EIR, or a feasible mitigation measure or alternative not included in the Final EIR.
 - The mitigation measures identified for the project were included in the Draft EIR and Final EIR. As revised, the final mitigation measures for the project are described in the Mitigation Monitoring Program (MMP). Each of the mitigation measures identified in the MMP is incorporated into the project. The City finds that the impacts of the project have been mitigated to the extent feasible by the mitigation measures identified in the MMP.
7. The Responses to Comments contained in the Final EIR fully considered and responded to comments claiming that the project would have significant impacts or more severe impacts not disclosed in the Draft EIR and include substantial evidence that none of these comments provided substantial evidence that the project would result in changed circumstances, significant new information, considerably different mitigation measures, or new or more severe significant impacts than were discussed in the Draft EIR.
8. CEQA requires the Lead Agency approving a project to adopt a MMP or the changes to the project which it has adopted or made a condition of project approval in order to ensure compliance with the mitigation measures during project implementation. The mitigation measures included in the EIR as certified by the City and revised in the MMP as adopted by the City serve that function. The MMP includes all of the mitigation measures and

project design features adopted by the City in connection with the approval of the project and has been designed to ensure compliance with such measures during implementation of the project. In accordance with CEQA, the MMP provides the means to ensure that the mitigation measures are fully enforceable. In accordance with the requirements of Public Resources Code Section 21081.6, the City hereby adopts the MMP.

9. In accordance with the requirements of Public Resources Code Section 21081.6, the City hereby adopts each of the mitigation measures expressly set forth herein as conditions of approval for the project.
10. The custodian of the documents or other materials which constitute the record of proceedings upon which the City decision is based is the City of Los Angeles, Department of City Planning.
11. The City finds and declares that substantial evidence for each and every finding made herein is contained in the EIR, which is incorporated herein by this reference, or is in the record of proceedings in the matter.
12. The City is certifying an EIR for, and is approving and adopting findings for, the entirety of the actions described in these Findings and in the EIR as comprising the project.
13. The EIR is a project EIR for purposes of environmental analysis of the project. A project EIR examines the environmental effects of a specific project. The EIR serves as the primary environmental compliance document for entitlement decisions regarding the project by the City and the other regulatory jurisdictions.

PUBLIC HEARING AND COMMUNICATIONS

A joint public hearing was held at City Hall for the proposed project entitlements on August 28, 2019 and was attended by the applicant, their representatives, and approximately 40 members of the public. At the public hearing, the project applicant and their representatives provided testimony. A total of 18 speakers addressed the project, 17 members of the public spoke in favor of the project. A representative from the Central City Association spoke in favor of the project.

Summary of Public Hearing Testimony

At the hearing, the project applicant presented the project features and project design. The applicant described the design concept within the context of the surrounding area. The applicant stated that public outreach has been conducted, and that the neighborhood council has voted to support the Project.

Members of the public spoke in support of the Project. Numerous members of the public were members of labor unions, and voiced their support for local hire provisions of the Project, and the economic opportunities the Project would provide. Unions speaking in favor of the project included: Laborer's International Union, Laborer's Local Union 300, IBEW Local II, Iron Workers Local 416, Local 250 Welders Union, Plumber Union 78, UA Local 709, Creed LA, Ironworkers of Los Angeles, and the Sheet Metal Workers Local 105. Unions speaking against the project included Unite Here Local 11.

A representative of the Golden State Environmental State Alliance spoke against the project based on the Environmental Impact Report's claimed deficiencies.

A representative from HED Architects spoke in favor of the project, particularly its design. A member of the public spoke in favor of the project.

Communications Received

The Central City Association, the South Park Business Improvement District and the Downtown Neighborhood Council submitted letters of support for the project at or prior to the hearing.

Additional public comments regarding the Draft Environmental Impact Report (EIR) for the project are addressed in the Final EIR: https://planning.lacity.org/eir/1001_Olympic/FEIR/

A tall, modern skyscraper with a distinctive diamond-patterned glass facade. The building features a large vertical green wall section on its right side. It is situated in an urban environment with other high-rise buildings and a street with cars visible at the base.

CONSULTANT DIRECTORY

Scale

Urban and Architecture Design Strategy

The project has been conceived (along Olympic Boulevard) as a metaphorical "bent salutation" to Downtown's Entertainment area (LA Live, Staples Center, Microsoft Theatre, etc.) while creating South facing landscaped elevated open atriums at the Condominium amenities and Hotel levels.

o At the street level the project is pedestrian friendly, utilizing the side alley to provide all the vehicular access to the different functions and levels while maintaining the sidewalks and parkways along Figueroa Street and Olympic Boulevard for the exclusive uses of pedestrian traffic and potentially sidewalk seating. The Retail ground level and upper two floors are designed to encourage the flowing connection to the pedestrian traffic by weaving its storefronts and accesses into the main lobbies.

The underground parking (directly accessed from the side alley) is dedicated solely to the residential units while the above ground parking garage provides 24/7 valet service for the Commercial (Retail and Offices) and the Hotel use; both parking areas also provide valet bicycle parking.

Given that Olympic Tower is a multi-use complex, the building integrates several independent vertical circulations connecting the ground floor (street level). The Hotel, Office, Residential and Conference Center small access lobbies are located at the ground floor, while the large spaces dedicated to lobbies for each use and the amenities are provided in the upper floors connected through exclusive vertical circulations.

Structural Design Strategy

o Following the larger vision of the architectural expression for the project, the exterior diagonalized grid of the envelope is utilized as a key feature of the structural vertical and lateral support of the tower. The "diagrid" is in-fact a steel tube exoskeleton for the building that supports the floor at the perimeter of the building thereby requiring few columns within the narrow footprint of the tower by spanning the floor system from a central spine column grid at the corridor to the exterior diagrid.

o At several positions in the tower, outrigger portal frames in the short direction of the tower are used to connect the two "sides" of the exoskeleton, collecting lateral and vertical gravity loads and distributing the loads to the diaphragm. These portal outrigger frames are an important component in establishing load path continuity from one program through the next, ultimately terminating at the transfer level to the parking levels below.

o The below grade parking levels are mild-steel reinforced concrete two-way flat slabs supported by a continuation of the concrete column grid from the above-grade parking levels. The perimeter retaining walls are envisioned to be constructed with shotcrete construction methods.

Landscape Design Strategy

o The intention of the landscape design is to create a pedestrian-friendly environment which includes shade trees and landscape along the street, enhanced sidewalk paving, lighting and seating

- o The open spaces terrace of the building are designed to enhance the inside-outside experience to take advantage of the Southern California climate.

- o The upper garden terraces are intended to create a strong residential community by including areas for socializing and experience of nature. These social and community spaces will include gardens, group gathering areas, outdoor viewing terraces, barbeque and outdoor dining areas and recreation places for fitness and yoga, as well as quiet and intimate spaces.

The landscape will include drought tolerant plants using both native and adaptive native plants materials. The design will incorporate an efficient irrigation system that will meet the SB1881 state regulation.

Sustainability Concepts

o Exploring the use of photovoltaic translucent film contained within the glass panels that will provide power to the building exterior lighting and LED lighting as part of the visual continuation of the vines at lower atrium.

- o Use of renewable and recyclable materials for flooring and partitions

- o Drought tolerant landscapes



VICINITY MAP

NTS

Architecture Urban Design Interiors

805 S. Shamrock Avenue
Monrovia, CA 91016
t: 626.599.1776
f: 626.599.9399
e: office@nardi-associates.com
w: nardi-associates.com

OLYMPIC TOWER
811 WEST OLYMPIC BLVD
LOS ANGELES, CA 90015

OWNER
NEMAN REAL ESTATE INVESTMENTS, LLC
1433 GRIFFITH AVENUE
LOS ANGELES, CA 90021
(213) 765-7700

CONSULTANTS

ENTITLEMENTS & DEVELOPMENT CONSULTANTS
NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016

LAND USE ENTITLEMENTS
ALSTON & BIRD
333 SOUTH HOPE ST 16TH
LOS ANGELES, CA 90071

CIVIL ENGINEER
PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071

STRUCTURAL ENGINEERING
NABIH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071

LANDSCAPE ARCHITECTURE
AHBE/MIG LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017


GEOTECHNICAL ENGINEERING
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92806

ENVIRONMENTAL CONSULTANT
CAJA ENVIRONMENTAL SERVICES, LLC
11990 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049


HISTORIC CONSULTANT
GPA CONSULTING
617 S. OLIVE STREET, SUITE 91
LOS ANGELES, CA 90014

TRAFFIC CONSULTANT
LINSOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106

KEY MAP:



STAMP:



All ideas, designs, arrangements, and plans indicated or represented by these drawings are owned by and are the property of nardi associates llp and were created, evolved, and developed for use on and in connection with the specified project. none of such ideas, design, arrangements, or plans shall be used by or disclosed to any person, firm, or corporation, without the written permission of nardi associates llp.

© 2019 NARDI ASSOCIATES LLP

ISSUE/REVISION

[illegible]

PROJECT NARRATIVE

Project number	85-10130
Date	08/22/2019
Drawn by	YP
Checked by	NFN

G0.05

Scale

Architecture Urban Design Interiors

OLYMPIC TOWER	

OWNER	
-------	--

CONCLUSIONS

ENTITLEMENTS & DEVELOPMENT CONSULTANTS
NARDI ASSOCIATES, LLP

LAND USE ENTITLEMENTS
ALSTON & BIRD

CIVIL ENGINEER PSOMAS	
--------------------------	--

STRUCTURAL ENGINEERING
NABIH YOUSSEF

LANDSCAPE ARCHITECTURE
AHBE/MIG LANDSCAPE ARCHITECTS

GEOTECHNICAL ENGINEERING
GEODESIGN, INC.

ENVIRONMENTAL CONSULTANT
CAJA ENVIRONMENTAL SERVICES, LLC

HISTORIC CONSULTANT
GPA CONSULTING


TRAFFIC CONSULTANT
LINSOTT, LAW & GREENSPAN ENGINEERS


[illegible]

ISSUE/REVISION

NO.	REV.	DESCRIPTION	DATE
-----	------	-------------	------

00 10





② OLYMPIC TOWER RELATIONSHIP WITH HOTEL FIGUEROA ALONG FIGUEROA STREET
NTS

C. SPACING

Tower Spacing

Towers should be spaced to provide privacy, natural light and air, as well as to contribute to an attractive skyline.

1. Generally, the portion of a tower above 150 feet shall be spaced at least 80 feet from all existing or possible future towers, both on the same block and across the street, except where 1) the towers are offset (staggered), 2) the largest windows in primary rooms are not facing one another, or 3) the towers are curved or angled, as illustrated in Figure 6-2.

Where there is an existing adjacent tower, the distance should be measured from the wall of the existing adjacent tower to the proposed tower. Where there is no existing adjacent tower, but one could be constructed in the future, the proposed tower must be 40 feet from an interior property line and 40 feet from the alley center line shared with the potential new tower as shown in Figure 6-2.






Figure 6-2 Plan and axonometric diagram showing minimum tower spacing to existing and future adjacent towers and exceptions.


Legend
Building height greater than 150'
Existing
New
Building height 150' or less:
Existing
New

Exceptions. Towers over 150' in height may vary from the minimums shown in the plan diagram above in the following conditions:


1) Offset Towers




2) Adjacent Towers



3) Curved or Angled Towers



LAMC 12.22 A.18 (c)(3)
(3) No yard requirement shall apply to the residential portions of buildings located in lots in the CR, C1, C1.5, C2, C4, and C5 Zones used for combined commercial and residential uses, if such portions are used exclusively for residential uses, abut a street, private street or alley, and the first floor of such buildings at ground level is used for commercial



① TOWER SPACING DIAGRAM
1/32" = 1'-0"

805 S. Shamrock avenue
Monrovia, California 91016
T.626.599.1776 F.626.599.9399

Project:
OLYMPIC TOWER
811 West Olympic Blvd.
Los Angeles, CA 90015

Client:
Neman Real Estate Investments, LLC
1433 Griffith Avenue
Los Angeles, CA 90021
(213) 765-7700 tel.

CONSULTANTS

ENTITLEMENTS & DEVELOPMENT CONSULTANTS
NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016

LAND USE ENTITLEMENTS
ALSTON & BIRD
333 SOUTH HOPE ST 16TH FL
LOS ANGELES, CA 90071

CIVIL ENGINEER
PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071

STRUCTURAL ENGINEERING
NASHI YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071

LANDSCAPE ARCHITECTURE
AHBEIMIG LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017

GEOTECHNICAL ENGINEERING
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92806

ENVIRONMENTAL CONSULTANT
CAJA ENVIRONMENTAL SERVICES, LLC
11590 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049

HISTORIC CONSULTANT
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014

TRAFFIC CONSULTANT
LINSKOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106


Revisions:

No	Date	Description
1	12/16/2015	1ST ENT. SUBMITTAL



Sheet Title:
TOWER DIAGRAMS

Key Plan:



ALL IDEAS, DESIGNS, ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THESE DRAWINGS ARE OWNED BY AND ARE THE PROPERTY OF NARDI ASSOCIATES LLP AND WERE CREATED, EVOLVED, AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH IDEAS, DESIGN, ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PERSON, FIRM, OR CORPORATION, WITHOUT THE WRITTEN PERMISSION OF NARDI ASSOCIATES LLP.

© 2010 NARDI ASSOCIATES LLP

Scale:
1/32" = 1'-0"







Date:
12/16/2015

Drawn by: WC Project No: 85-10130

Phase:
ENTITLEMENT

Sheet No:


G0.12






Level 53, 55

- Area Not Included in FAR
- Area Included in FAR = 15,823 SF



Level 56

- Area Not Included in FAR
- Area Included in FAR = 5,085 SF



Level 57

- Area Not Included in FAR
- Area Included in FAR = 4,471 SF

Project:
OLYMPIC TOWER
811 West Olympic Blvd.
Los Angeles, CA 90015
Client:
Neman Real Estate Investments, LLC
1433 Griffith Avenue
Los Angeles, CA 90021
(213) 765-7700 tel.


CONSULTANTS

ENTITLEMENTS & DEVELOPMENT CONSULTANTS
NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016
LAND USE ENTITLEMENTS
ALSTON & BIRD
333 SOUTH HOPE ST. 16TH FL.
LOS ANGELES, CA 90071
CIVIL ENGINEER
PSOMAS
655 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071
STRUCTURAL ENGINEERING
NABH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071
LANDSCAPE ARCHITECTURE
ANHEIM LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017
GEOTECHNICAL ENGINEERING
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92805
ENVIRONMENTAL CONSULTANT
CALIA ENVIRONMENTAL SERVICES, LLC
11990 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049
HISTORIC CONSULTANT
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014
TRAFFIC CONSULTANT
LINSOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106

Revisions:		
No	Date	Description
1	12/16/2015	1ST ENT. SUBMITTAL



Sheet Title:
FAR Diagrams



ALL IDEAS, DESIGNS, ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THESE DRAWINGS ARE OWNED BY AND ARE THE PROPERTY OF NARDI ASSOCIATES LLP AND WERE CREATED, EVOLVED, AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH IDEAS, DESIGN, ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PERSON, FIRM, OR CORPORATION, WITHOUT THE WRITTEN PERMISSION OF NARDI ASSOCIATES LLP.
© 2010 NARDI ASSOCIATES LLP

Scale:
NTS
Date:
12/16/2015
Drawn by:
CR
Project No:
85-10130
Phase:
ENTITLEMENT

Sheet No:
G 0.15


Project:
OLYMPIC TOWER
811 West Olympic Blvd.
Los Angeles, CA 90015
Client:
Neman Real Estate Investments, LLC
1433 Griffith Avenue
Los Angeles, CA 90021
(213) 765-7700 tel.

Consultant:
ENTITLEMENTS & DEVELOPMENT CONSULTANTS
NGR Development, LLC
805 S. Shamrock Ave.
Monrovia, CA 91016
LAND USE ENTITLEMENTS:
PSOMAS
555 South Flower Street, Suite 4300
Los Angeles, CA 90071
CIVIL ENGINEER:
PSOMAS
555 South Flower Street, Suite 4300
Los Angeles, CA 90071
STRUCTURAL ENGINEERING:
NABIH YOUSSEF
550 S. Hope ST., Suite 1700
Los Angeles, CA 90071
LANDSCAPE ARCHITECTURE:
ANBE Landscape Architects
617 West Seventh Street, Suite 304
Los Angeles, CA 90017
GEOTECHNICAL ENGINEERING:
GeoDesign, Inc.
2121 S. Towne Centre Place, Suite 130
Anaheim, CA 92806
ENVIRONMENTAL CONSULTANT:
CAJA Environmental Services, LLC
11990 San Vicente Boulevard, Suite 250
Los Angeles, CA 90049
HISTORIC CONSULTANT:
GPA Consulting
617 S. Olive Street, Suite 910
Los Angeles, CA 90014
TRAFFIC CONSULTANT:
Linscott, Law & Greenspan, Engineers
600 South Lake Avenue, Suite 500
Pasadena, CA 91106

Revisions:		
No	Date	Description
1	12/16/2015	1ST ENT. SUBMITTAL




Sheet Title:
Open Space Diagrams




ALL IDEAS, DESIGNS, ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THESE DRAWINGS ARE OWNED BY AND ARE THE PROPERTY OF NARDI ASSOCIATES LLP AND WERE CREATED, EVOLVED, AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH IDEAS, DESIGN, ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PERSON, FIRM, OR CORPORATION, WITHOUT THE WRITTEN PERMISSION OF NARDI ASSOCIATES LLP.
© 2010 NARDI ASSOCIATES LLP

Scale:
NTS
Date:
12/16/2015
Drawn by:
CR
Project No:
85-10130
Phase:
ENTITLEMENT
Sheet No:



Level 13

- Common Open Space = 11,370 SF
- Common Cover Recreational Space = 5,290 SF
- Common Semi-Cover Recreational Space = 2,820 SF



Level 52,54

- Private Open Space = 431 SF / Floor
- Private Cover Recreational Space = 1,195 SF / Floor




Level 32-35

- Private Open Space = 400 SF / Floor
- Private Cover Recreational Space = 1,010 SF / Floor




Level 53,55

- Private Open Space = 366 SF / Floor
- Private Cover Recreational Space = 952 SF / Floor




Level 36-47

- Private Open Space = 400 SF / Floor
- Private Cover Recreational Space = 1,010 SF / Floor




Level 56

- Common Open Space = 13,703 SF / Floor
- Common Cover Recreational Space = 5,085 SF / Floor





Level 48-51

- Private Open Space = 194 SF / Floor
- Private Cover Recreational Space = 471 SF / Floor



Level 57


- Common Open Space = 721 SF / Floor
- Common Cover Recreational Space = 3,749 SF / Floor



PARKING BREAKDOWN PER FLOOR PER RAMP/PLATFORM:

LOCATION	LEVEL		RAMP/PLATFORM	No. OF PARKING SPACES	
ABOVE GROUND	4		MAIN PLATFORM	12	
	4		WEST PLATFORM	3	
	4		EAST PLATFORM	2	
	4		NORTHEAST DOWN RAMP	NA	
	4		SOUTHEAST DOWN RAMP	11	
	4		NORTHWEST UP RAMP	NA	
	4		SOUTHWEST UP RAMP	12	
	5		MAIN PLATFORM	1	
	5		WEST PLATFORM	3	
	5		EAST PLATFORM	2	
	5		NORTHEAST DOWN RAMP	16	
	5		SOUTHEAST DOWN RAMP	11	
	5		NORTHWEST UP RAMP	16	
	5		SOUTHWEST UP RAMP	12	
	6		MAIN PLATFORM	0	
	6		WEST PLATFORM	3	
	6		EAST PLATFORM	2	
	6		NORTHEAST DOWN RAMP	16	
	6		SOUTHEAST DOWN RAMP	9	
	6		NORTHWEST UP RAMP	16	
	6		SOUTHWEST UP RAMP	6	
	7		MAIN PLATFORM	0	
	7		WEST PLATFORM	3	
	7		EAST PLATFORM	2	
	7		NORTHEAST DOWN RAMP	16	
	7		SOUTHEAST DOWN RAMP	9	
	7		NORTHWEST UP RAMP	16	
	7		SOUTHWEST UP RAMP	6	
	8		MAIN PLATFORM	0	
	8		WEST PLATFORM	3	
	8		EAST PLATFORM	2	
	8		NORTHEAST DOWN RAMP	16	
	8		SOUTHEAST DOWN RAMP	9	
	8		NORTHWEST UP RAMP	16	
	8		SOUTHWEST UP RAMP	6	
	9		MAIN PLATFORM	0	
	9		WEST PLATFORM	3	
	9		EAST PLATFORM	2	
	9		NORTHEAST DOWN RAMP	16	
	9		SOUTHEAST DOWN RAMP	9	
	9		NORTHWEST UP RAMP	16	
	9		SOUTHWEST UP RAMP	6	
	10		MAIN PLATFORM	0	
	10		WEST PLATFORM	3	
10		EAST PLATFORM	2		
10		NORTHEAST DOWN RAMP	16		
10		SOUTHEAST DOWN RAMP	9		
10		NORTHWEST UP RAMP	16		
10		SOUTHWEST UP RAMP	6		
11		MAIN PLATFORM	0		
11		WEST PLATFORM	NA		
11		EAST PLATFORM	NA		
11		NORTHEAST DOWN RAMP	16		
11		SOUTHEAST DOWN RAMP	5		
11		NORTHWEST UP RAMP	16		
TOTAL	11		SOUTHWEST UP RAMP	2	
				400	
UNDERGROUND	B1		MAIN PLATFORM	5	
	B1		WEST PLATFORM	2	
	B1		EAST PLATFORM	3	
	B1		NORTHEAST UP RAMP	NA	
	B1		SOUTHEAST UP RAMP	11	
	B1		NORTHWEST DW RAMP	NA	
	B1		SOUTHWEST DW RAMP	11	
	B2		MAIN PLATFORM	2	
	B2		WEST PLATFORM	2	
	B2		EAST PLATFORM	3	
	B2		NORTHEAST UP RAMP	16	
	B2		SOUTHEAST UP RAMP	11	
	B2		NORTHWEST DW RAMP	16	
	B2		SOUTHWEST DW RAMP	17	
	B3		MAIN PLATFORM	2	
	B3		WEST PLATFORM	17	
	B3		EAST PLATFORM	3	
	B3		NORTHEAST UP RAMP	16	
	B3		SOUTHEAST UP RAMP	11	
	B3		NORTHWEST DW RAMP	16	
	B3		SOUTHWEST DW RAMP	17	
	B4		MAIN PLATFORM	2	
	B4		WEST PLATFORM	17	
	B4		EAST PLATFORM	3	
	B4		NORTHEAST UP RAMP	16	
	B4		SOUTHEAST UP RAMP	11	
	B4		NORTHWEST DW RAMP	16	
	B4		SOUTHWEST DW RAMP	17	
	B5		MAIN PLATFORM	2	
	B5		WEST PLATFORM	17	
	B5		EAST PLATFORM	3	
	B5		NORTHEAST UP RAMP	16	
	B5		SOUTHEAST UP RAMP	11	
	B5		NORTHWEST DW RAMP	16	
	B5		SOUTHWEST DW RAMP	17	
	B6		MAIN PLATFORM	2	
	B6		WEST PLATFORM	22	
	B6		EAST PLATFORM	9	
	B6		NORTHEAST UP RAMP	16	
	B6		SOUTHEAST UP RAMP	11	
		B6		NORTHWEST DW RAMP	16
	TOTAL				438
	FULL TOTAL	B6		SOUTHWEST DW RAMP	17
					838

Scale




Level 57

◀.....▶ Path of Travel




Level 36

◀.....▶ Path of Travel




Level 56

◀.....▶ Path of Travel




Level 26

◀.....▶ Path of Travel




Level 52

◀.....▶ Path of Travel




Level 16

◀.....▶ Path of Travel



Level 48

◀.....▶ Path of Travel



Level 15

◀.....▶ Path of Travel

- Hotel Lobby Elevator Level 1 to Level 14
- Residential Lobby Elevator B7 to Level 13
- Retail Elevator Level 1 to Level 11
- Freight & Fire Marshal Elevator Level 1 to Level 57
- Hotel Room Elevator Level 14 to Level 30
- Residential Unit Elevator Level 13 to Level 57
- Office Elevator Level 1 to Level 11

Project:
OLYMPIC TOWER
811 West Olympic Blvd.
Los Angeles, CA 90015
Client:
Neman Real Estate Investments, LLC
1433 Griffith Avenue
Los Angeles, CA 90021
(213) 765-7700 tel.

CONSULTANTS

ENTITLEMENTS & DEVELOPMENT CONSULTANTS
NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016

LAND USE ENTITLEMENTS
ALSTON & BIRD
333 SOUTH HOPE ST 16TH FL
LOS ANGELES, CA 90071

CIVIL ENGINEER
PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071

STRUCTURAL ENGINEERING
NASH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071

LANDSCAPE ARCHITECTURE
AHBEIMIG LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017

GEOTECHNICAL ENGINEERING
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92806

ENVIRONMENTAL CONSULTANT
CAJA ENVIRONMENTAL SERVICES, LLC
11980 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049

HISTORIC CONSULTANT
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014

TRAFFIC CONSULTANT
LINSOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106


Revisions:		
No	Date	Description
1	12/16/2015	1ST ENT. SUBMITTAL



Sheet Title:

Circulation Diagrams


Key Plan:



ALL IDEAS, DESIGNS, ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THESE DRAWINGS ARE OWNED BY AND ARE THE PROPERTY OF NARDI ASSOCIATES LLP AND WERE CREATED, EVOLVED, AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH IDEAS, DESIGN, ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PERSON, FIRM, OR CORPORATION, WITHOUT THE WRITTEN PERMISSION OF NARDI ASSOCIATES LLP.
© 2010 NARDI ASSOCIATES LLP

Scale:
NTS
Date:
12/16/2015
Drawn by:
CR
Project No:
85-10130
Phase:
ENTITLEMENT


Sheet No:




1




4



2




5



3



6



VIEWPOINT REFERENCE

1

4

2

3


Project:
OLYMPIC TOWER
811 West Olympic Blvd.
Los Angeles, CA 90015
Client:
Neman Real Estate Investments, LLC
1433 Griffith Avenue
Los Angeles, CA 90021
(213) 765-7700 tel.

CONSULTANTS
ENTITLEMENTS & DEVELOPMENT CONSULTANTS
NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016
LAND USE ENTITLEMENTS
ALSTON & BIRD
333 SOUTH HOPE ST 16TH FL
LOS ANGELES, CA 90071
CIVIL ENGINEER
PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071
STRUCTURAL ENGINEERING
NASH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071
LANDSCAPE ARCHITECTURE
AHBEIMIG LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017
GEOTECHNICAL ENGINEERING
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92806
ENVIRONMENTAL CONSULTANT
CAJA ENVIRONMENTAL SERVICES, LLC
11990 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049
HISTORIC CONSULTANT
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014
TRAFFIC CONSULTANT
LINSOOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106

Revisions:		
No	Date	Description
1	12/16/2015	1ST ENT. SUBMITTAL



Sheet Title:
**PHOTOS OF PHYSICAL
MODEL**



ALL IDEAS, DESIGNS, ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THESE DRAWINGS ARE OWNED BY AND ARE THE PROPERTY OF NARDI ASSOCIATES LLP AND WERE CREATED, EVOLVED, AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH IDEAS, DESIGN ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PERSON, FIRM OR CORPORATION, WITHOUT THE WRITTEN PERMISSION OF NARDI ASSOCIATES LLP.
© 2010 NARDI ASSOCIATES LLP

Scale:
NTS
Date:
12/16/2015
Drawn by:
WC
Project No:
85-10130
Phase:
ENTITLEMENT
Sheet No:

G0.22



SOUTH FACADE FROM OLYMPIC



NORTH FACADE FROM FIGUEROA

NARDI ASSOCIATES LLP
Architecture Urban Design Interiors

805 S. Shamrock Avenue
Monrovia, CA 91016
t: 626.599.1776
f: 626.599.9399
e: office@nardi-associates.com
w: nardi-associates.com

OLYMPIC TOWER
811 WEST OLYMPIC BLVD.
LOS ANGELES, CA 90015

OWNER
NEMAN REAL ESTATE INVESTMENTS, LLC
1433 GRIFFITH AVENUE
LOS ANGELES, CA 90021
(213) 765-7700

CONSULTANTS

ENTITLEMENTS & DEVELOPMENT CONSULTANTS
NADLI ASSOCIATES, L.L.C.

NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016

LAND USE ENTITLEMENTS
ALSTON & BIRD
333 SOUTH HOPE ST 16TH FL
LOS ANGELES CA 90071

CIVIL ENGINEER
PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071

STRUCTURAL ENGINEERING
NABIH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071

LANDSCAPE ARCHITECTURE
AHBE/MIG LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017


GEOTECHNICAL ENGINEERING
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92806

ENVIRONMENTAL CONSULTANT
CAJA ENVIRONMENTAL SERVICES, LLC
11990 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049


HISTORIC CONSULTANT
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014

TRAFFIC CONSULTANT
LINSOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106

KEY MAP:



STAMP:



All ideas, designs, arrangements, and plans indicated or represented by these drawings are owned by and are the property of nardi associates llp and were created, evolved, and developed for use on and in connection with the specified project. none of such ideas, design, arrangements, or plans shall be used by or disclosed to any person, firm, or corporation, without the written permission of nardi associates llp.

© 2019 NARDI ASSOCIATES LLP

ISSUE/REVISION

[illegible]

NORTH & SOUTH
FACADE RENDERINGS

Project number	85-10130
Date	08/22/2019
Drawn by	YP
Checked by	NFN

G0.23


Scale



Scale	
-------	--



Scale



HOTEL ATRIUM

NARDI ASSOCIATES LLP

Architecture Urban Design Interiors

805 S. Shamrock Avenue
Monrovia, CA 91016
t: 626.599.1776
f: 626.599.9399
e: office@nardi-associates.com
w: nardi-associates.com

OLYMPIC TOWER

811 WEST OLYMPIC BLVD.
LOS ANGELES, CA 90015

OWNER
NEMAN REAL ESTATE INVESTMENTS, LLC
1433 GRIFFITH AVENUE
LOS ANGELES, CA 90021
(213) 765-7700

CONSULTANTS

ENTITLEMENTS & DEVELOPMENT CONSULTANTS

NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016

LAND USE ENTITLEMENTS
ALSTON & BIRD

ALSTON & BIRD
333 SOUTH HOPE ST 16T
LOS ANGELES, CA 90071

CIVIL ENGINEER

PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071

STRUCTURAL ENGINEERING

NABIH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071

LANDSCAPE ARCHITECTUR

LAHBE/MIG LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017

GEOTECHNICAL ENGINEERING

GEOTECHNICAL ENGINEERING
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92802

ENVIRONMENTAL CONSULTANT

ENVIRONMENTAL CONSULTANT
CAJA ENVIRONMENTAL SERVICES, LLC
11990 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049


HISTORIC CONSULTANT

GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014


TRAFFIC CONSULTANT

LINSCOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106

KEY MAP:



STAMP:



All ideas, designs, arrangements, and plans indicated or represented by these drawings are owned by and are the property of nardi associates llp and were created, evolved, and developed for use on and in connection with the specified project. none of such ideas, design, arrangements, or plans shall be used by or disclosed to any person, firm, or corporation, without the written permission of nardi associates llp.

© 2019 NARDI ASSOCIATES LLP

ISSUE/REVISION

[illegible]

EXTERIOR RENDERING

Project number	85-10130
Date	08/22/2019
Drawn by	YP
Checked by	NFN

G0.26

Scale



805 S. Shamrock Avenue
Monrovia, CA 91016
t: 626.599.1776
f: 626.599.9399
e: office@nardi-associates.com
w: nardi-associates.com

OLYMPIC TOWER
811 WEST OLYMPIC BLVD.
LOS ANGELES, CA 90015

OWNER
NEMAN REAL ESTATE INVESTMENTS, LLC
1433 GRIFFITH AVENUE
LOS ANGELES, CA 90021
(213) 765-7700

CONSULTANTS

ENTITLEMENTS & DEVELOPMENT CONSULTANTS

NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016

LAND USE ENTITLEMENTS
ALSTON & BIDD

ALSTON & BIRD
333 SOUTH HOPE ST 16T
LOS ANGELES, CA 90071

CIVIL ENGINEER

PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071

STRUCTURAL ENGINEERING

NABIH YOUSSEF
550 S. HOPE ST., SUITE 1
LOS ANGELES, CA 90071

LANDSCAPE ARCHITECTURE

AHBE/MIG LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017

GEOTECHNICAL ENGINEERING

GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 110
ANAHEIM, CA 92806

ENVIRONMENTAL CONSULTANT

CAJA ENVIRONMENTAL SERVICES, LLC
11990 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90040


HISTORIC CONSULTANT

HISTORIC CONSULTANT
GPA CONSULTING
617 S. OLIVE STREET, SUITE 91
LOS ANGELES, CA 90014

TRAFFIC CONSULTANT

TRAFFIC CONSULTANT
LINSOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PALMDALE, CA 91366

KEY MAP:



ISSUE/REVISION

EXTERIOR RENDERING

G0.27

Scale



HOTEL LOBBY AND AMENITIES AT LEVEL 14TH



RETAIL ENTRY VIEW FROM OLYMPIC BLVD.



HOTEL ENTRY VIEW FROM OLYMPIC BLVD.

NARDI ASSOCIATES LLP
Architecture Urban Design Interiors

805 S. Shamrock Avenue
Monrovia, CA 91016
t: 626.599.1776
f: 626.599.9399
e: office@nardi-associates.com
w: nardi-associates.com

OLYMPIC TOWER
811 WEST OLYMPIC BLVD.
LOS ANGELES, CA 90015

OWNER
NEMAN REAL ESTATE INVESTMENTS, LLC
1433 GRIFFITH AVENUE
LOS ANGELES, CA 90021
(213) 765-7700

CONSULTANTS

ENTITLEMENTS & DEVELOPMENT CONSULTANTS
NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016

LAND USE ENTITLEMENTS
ALSTON & BIRD
333 SOUTH HOPE ST 16TH FL
LOS ANGELES, CA 90071

CIVIL ENGINEER
PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071

STRUCTURAL ENGINEERING
NABIIH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071

LANDSCAPE ARCHITECTURE
AHBE/MIG LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017


GEOTECHNICAL ENGINEERING
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92806

ENVIRONMENTAL CONSULTANT
CAJA ENVIRONMENTAL SERVICES, LLC
11990 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049


HISTORIC CONSULTANT
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014

TRAFFIC CONSULTANT
LINSCOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106

KEY MAP:



STAMP:



All ideas, designs, arrangements, and plans indicated or represented by these drawings are owned by and are the property of nardi associates llp and were created, evolved, and developed for use on and in connection with the specified project. none of such ideas, design, arrangements, or plans shall be used by or disclosed to any person, firm, or corporation, without the written permission of nardi associates llp.

© 2019 NARDI ASSOCIATES LLP

ISSUE/REVISION



[illegible]

PEDESTRIAN RENDERINGS

Project number	85-10130
Date	08/22/2019
Drawn by	YP
Checked by	NFN

G0.29

Scale



NARDIASSOCIATES LLP

Architecture	Urban Design	Interiors
--------------	--------------	-----------

805 S. Shamrock Avenue
Monrovia, CA 91016
t: 626.599.1776
f: 626.599.9399
e: office@nardi-associates.com
w: nardi-associates.com

OLYMPIC TOWER
811 WEST OLYMPIC BLVD.
LOS ANGELES, CA 90015

OWNER
NEMAN REAL ESTATE INVESTMENTS, LLC
1433 GRIFFITH AVENUE
LOS ANGELES, CA 90021
(213) 765-7700

CONSULTANTS

ENTITLEMENTS & DEVELOPMENT CONSULTANTS
NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016

LAND USE ENTITLEMENTS
ALSTON & BIRD
333 SOUTH HOPE ST 16TH
LOS ANGELES, CA 90071

CIVIL ENGINEER
PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071

STRUCTURAL ENGINEERING
NABIH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071

LANDSCAPE ARCHITECTURE
AHBE/MIG LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 300
LOS ANGELES, CA 90017


GEOTECHNICAL ENGINEERING
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130

ENVIRONMENTAL CONSULTANT
CAJA ENVIRONMENTAL SERVICES, LLC
11990 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049


HISTORIC CONSULTANT
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014

TRAFFIC CONSULTANT
LINSOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106

KEY MAP:



STAMP:



All ideas, designs, arrangements, and plans indicated or represented by these drawings are owned by and are the property of nardi associates llp and were created, evolved, and developed for use on and in connection with the specified project. none of such ideas, design, arrangements, or plans shall be used by or disclosed to any person, firm, or corporation, without the written permission of nardi associates llp.

© 2019 NARDI ASSOCIATES, L.L.P.

ISSUE/REVISION

[illegible]

PARKING FACADE RENDERING


Project number	85-10130
Date	08/22/2019
Drawn by	YP
Checked by	NFN

G0.30

Scale	1 1/2" = 1'-0"
-------	----------------



Scale



TRAFFIC CONSULTANT
LINSKOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106

Scale	As indicated
-------	--------------

[illegible]

SITE SURVEY

ALL IDEAS, DESIGNS, ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THESE DRAWINGS ARE OWNED BY AND ARE THE PROPERTY OF NARDI ASSOCIATES LLP AND WERE CREATED, EVOLVED, AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH IDEAS, DESIGN, ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PERSON, FIRM, OR CORPORATION, WITHOUT THE WRITTEN PERMISSION OF NARDI ASSOCIATES LLP.

© 2010 NARDI ASSOCIATES LLP

NTS


Date: 12/16/2015

Drawn by: WC	Project No: 85-10130
-----------------	-------------------------

Phase: ENTITLEMENT

Sheet No:

M1.00



Architecture Urban Design Interiors

805 S. Shamrock Avenue
Monrovia, CA 91016
t: 626.599.1776
f: 626.599.9399
e: office@nardi-associates.com
w: nardi-associates.com

OLYMPIC TOWER
811 WEST OLYMPIC BLVD.
LOS ANGELES, CA 90015

OWNER
NEMAN REAL ESTATE INVESTMENTS, LLC
1433 GRIFFITH AVENUE
LOS ANGELES, CA 90021
(213) 765-7700

CONSULTANTS	
--------------------	--

ENTITLEMENTS & DEVELOPMENT CONSULTANTS
NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016

LAND USE ENTITLEMENTS
AL STON & BIRD

333 SOUTH HOPE ST 16TH FL
LOS ANGELES, CA 90071

CIVIL ENGINEER
PSOMAS

555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071

STRUCTURAL ENGINEERING
NABIH YOUSSEF
550 S. HOPE ST., SUITE 1700

LOS ANGELES, CA 90071
LANDSCAPE ARCHITECTURE

LANDSCAPE ARCHITECTURE
AHBE/MIG LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
P.O. BOX 100000, DENVER, CO 80201-0000

LOS ANGELES, CA 90017

GEOTECHNICAL ENGINEERING

GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92806

ENVIRONMENTAL CONSULTANT
GALIA ENVIRONMENTAL SERVICES, LLC

CASA ENVIRONMENTAL SERVICES, LLC
11990 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049


HISTORIC CONSULTANT
GPA CONSULTING

617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014


TRAFFIC CONSULTANT
LINSOTT, LAW & GREENSPAN ENGINEERS
200 SOUTH LAKE AVENUE, SUITE 500

600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106

KEY MAP:



STAMP:



All ideas, designs, arrangements, and plans indicated or represented by these drawings are owned by and are the property of nardi associates llp and were created, evolved, and developed for use on, and in connection with the specified project. none of such ideas, design, arrangements, or plans shall be used by or disclosed to any person, firm, or corporation, without the written permission of nardi associates llp.

© 2019 NARDI ASSOCIATES LLP

ISSUE/REVISION


[illegible]

ROOF PLAN




Project number	
Date	09 July, 2019
Drawn by	YP
Checked by	NFN

A100

Scale



1 Site
1/16" = 1'-0"



NARDI ASSOCIATES LLP
Architecture Urban Design Interiors

805 S. Shamrock Avenue
Monrovia, CA 91016
t: 626.599.1776
f: 626.599.9399
e: office@nardi-associates.com
w: nardi-associates.com

OLYMPIC TOWER
811 WEST OLYMPIC BLVD.
LOS ANGELES, CA 90015

OWNER
NEMAN REAL ESTATE INVESTMENTS, LLC
1433 GRIFFITH AVENUE
LOS ANGELES, CA 90021
(213) 765-7700

CONSULTANTS

ENTITLEMENTS & DEVELOPMENT CONSULTANTS
NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016

LAND USE ENTITLEMENTS
ALSTON & BIRD
333 SOUTH HOPE ST 16TH FL
LOS ANGELES, CA 90071

CIVIL ENGINEER
PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071

STRUCTURAL ENGINEERING
NABIH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071

LANDSCAPE ARCHITECTURE
AHBE/MIG LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017


GEOTECHNICAL ENGINEERING
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92806

ENVIRONMENTAL CONSULTANT
CAJA ENVIRONMENTAL SERVICES, LLC
11990 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049


HISTORIC CONSULTANT
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014

TRAFFIC CONSULTANT
LINSOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106

KEY MAP:



STAMP:



All ideas, designs, arrangements, and plans indicated or represented by these drawings are owned by and are the property of nardi associates llp and were created, evolved, and developed for use on and in connection with the specified project. None of such ideas, design, arrangements, or plans shall be used by or disclosed to any person, firm, or corporation, without the written permission of nardi associates llp.

© 2019 NARDI ASSOCIATES LLP

ISSUE/REVISION


[illegible]

GROUND LEVEL RETAIL FLOOR PLAN

Project number	85-10130
Date	07/14/2019
Drawn by	YP
Checked by	NFN

A101

Scale	As indicated
-------	--------------



Architecture Urban Design Interiors

OLYMPIC TOWER
811 WEST OLYMPIC BLVD.
LOS ANGELES, CA 90015

CONSULTANTS

LAND USE ENTITLEMENTS
ALSTON & BIRD
333 SOUTH HOPE ST 16TH FL
LOS ANGELES, CA 90071

STRUCTURAL ENGINEERING
NABIH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071

GEOTECHNICAL ENGINEERING
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92806

HISTORIC CONSULTANT
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910

PASADENA, CA 91106


LICENSED ARCHITECT
 NORBERTO F. NARDI
 NO. C-28794
 REN. 1-31-21
 STATE OF CALIFORNIA

ISSUE/REVISION


[illegible]

Project number	85-10130
Date	07/14/2019
Drawn by	YP
Checked by	NFN


Scale	1/16" = 1'-0"
-------	---------------



① LEVEL 3 - RETAIL
1/16" = 1'-0"



Scale	1/16" = 1'-0"
-------	---------------



TRAFFIC CONSULTANT
LINSKOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106

Scale	1/16" = 1'-0"
-------	---------------

Los Angeles, CA 90015

(213) 765-7700 tel

MONROVIA, CA 91016

CIVIL ENGINEER
REGULATED

550 S. HOPE ST., SUITE
100, ANN ARBOR, MI 48106

2007/10/26 00:00

CAJA ENVIRONM


LOS ANGELES, CA 90014

PASADENA, CA 91106


LEVEL - PARKING
FLOOR PLAN

© 2010 NARDI ASSOCIATES LLC

A1B3



PARKING LEVELS - FUNCTIONAL DIAGRAM



① BASEMENT 3 - 6
1/16" = 1'-0"

Project:
OLYMPIC TOWER
811 West Olympic Blvd.
Los Angeles, CA 90015
Client:
Neman Real Estate Investments, LLC
1433 Griffith Avenue
Los Angeles, CA 90021
(213) 765-7700 tel.

CONSULTANTS

ENTITLEMENTS & DEVELOPMENT CONSULTANTS
NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016

LAND USE ENTITLEMENTS
ALSTON & BIRD
333 SOUTH HOPE ST 16TH FL
LOS ANGELES, CA 90071

CIVIL ENGINEER
PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071

STRUCTURAL ENGINEERING
NABIH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071

LANDSCAPE ARCHITECTURE
AHBEIM LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017

GEOTECHNICAL ENGINEERING
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92806

ENVIRONMENTAL CONSULTANT
CALIA ENVIRONMENTAL SERVICES, LLC
11950 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049

HISTORIC CONSULTANT
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014

TRAFFIC CONSULTANT
LINSOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106


Revisions:

No	Date	Description
1	12/16/2015	1ST ENT. SUBMITTAL



Sheet Title:
**4TH LEVEL - PARKING
FLOOR PLAN - ABOVE
GROUND**

Key Plan:



ALL IDEAS, DESIGNS, ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THESE DRAWINGS ARE OWNED BY AND ARE THE PROPERTY OF NARDI ASSOCIATES LLP AND WERE CREATED, EVOLVED, AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH IDEAS, DESIGN, ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PERSON, FIRM, OR CORPORATION, WITHOUT THE WRITTEN PERMISSION OF NARDI ASSOCIATES LLP.

© 2010 NARDI ASSOCIATES LLP

Scale:
1/16" = 1'-0"


Date:
12/16/2015

Drawn by: WC Project No: 85-10130


Phase:
ENTITLEMENT

Sheet No:

A104



PARKING LEVELS - FUNCTIONAL DIAGRAM



① 4th FLOOR PARKING - ABOVE GROUND
1/16" = 1'-0"

OLYMPIC TOWER
811 West Olympic Blvd.
Los Angeles, CA 90015

Client:
Neman Real Estate Investments, LLC
1433 Griffith Avenue
Los Angeles, CA 90021
(213) 765-7700 tel.

NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016

LAND USE ENTITLEMENTS
ALSTON & BIRD
333 SOUTH HOPE ST 16TH FL
LOS ANGELES, CA 90071

CIVIL ENGINEER
PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071

STRUCTURAL ENGINEERING
NABIH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071

LANDSCAPE ARCHITECTURE
AHBE/MIG LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017

GEOTECHNICAL ENGINEERING
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92806

ENVIRONMENTAL CONSULTANT
CAJA ENVIRONMENTAL SERVICES, LLC
11990 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049

HISTORIC CONSULTANT
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014

TRAFFIC CONSULTANT
LINSOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106

[illegible]

5TH LEVEL - PARKING FLOOR PLAN

ALL IDEAS, DESIGNS, ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THESE DRAWINGS ARE OWNED BY AND ARE THE PROPERTY OF NARDI ASSOCIATES LLP AND WERE CREATED, EVOLVED, AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH IDEAS, DESIGN, ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PERSON, FIRM, OR CORPORATION, WITHOUT THE WRITTEN PERMISSION OF NARDI ASSOCIATES LLP.

© 2010 NARDI ASSOCIATES LLP

Scale: $1/16" = 1'-0"$


Date: 12/16/2015

Drawn by: WC	Project No: 85-10130
-----------------	-------------------------


Phase: ENTITLEMENT

Sheet No:


A105



PARKING LEVELS - FUNCTIONAL DIAGRAM



① 5th FLOOR PARKING
1/16" = 1'-0"



Scale	1/16" = 1'-0"
-------	---------------

Project:
OLYMPIC TOWER
811 West Olympic Blvd.
Los Angeles, CA 90015
Client:
Neman Real Estate Investments, LLC
1433 Griffith Avenue
Los Angeles, CA 90021
(213) 765-7700 tel.


CONSULTANTS

ENTITLEMENTS & DEVELOPMENT CONSULTANTS
NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016
LAND USE ENTITLEMENTS
ALSTON & BIRD
333 SOUTH HOPE ST. 16TH FL.
LOS ANGELES, CA 90071
CIVIL ENGINEER
PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071
STRUCTURAL ENGINEERING
NABH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071
LANDSCAPE ARCHITECTURE
ABEYING LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017
GEOTECHNICAL ENGINEERING
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92806
ENVIRONMENTAL CONSULTANT
CALIA ENVIRONMENTAL SERVICES, LLC
11950 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049
HISTORIC CONSULTANT
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014
TRAFFIC CONSULTANT
LINSOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106

Revisions:		
No	Date	Description
1	12/16/2015	1ST ENT. SUBMITTAL



Sheet Title:
**LEVEL 13 - CONDO. AM.
AND BALLROOM
FLOOR PLAN**



ALL IDEAS, DESIGNS, ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THESE DRAWINGS ARE OWNED BY AND ARE THE PROPERTY OF NARDI ASSOCIATES LLP AND WERE CREATED, EVOLVED, AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH IDEAS, DESIGN, ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PERSON, FIRM, OR CORPORATION, WITHOUT THE WRITTEN PERMISSION OF NARDI ASSOCIATES LLP.

© 2010 NARDI ASSOCIATES LLP

Scale:
1/16" = 1'-0"


Date:
12/16/2015

Drawn by: WC Project No: 85-10130

Phase:
ENTITLEMENT

Sheet No:

A113



1 LEVEL 13 - CONDO LOBBY & AMENITIES
1/16" = 1'-0"

Project:
OLYMPIC TOWER
811 West Olympic Blvd.
Los Angeles, CA 90015

Client:
Neman Real Estate Investments, LLC
1433 Griffith Avenue
Los Angeles, CA 90021
(213) 765-7700 tel.

CONSULTANTS

ENTITLEMENTS & DEVELOPMENT CONSULTANTS
NARDI ASSOCIATES, LLP
805 S. SHAMPOOK AVE.
MONROVIA, CA 91016

LAND USE ENTITLEMENTS
ALSTON & BIRD
333 SOUTH HOPE ST. 16TH FL.
LOS ANGELES, CA 90071

CIVIL ENGINEER
PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071

STRUCTURAL ENGINEERING
NABIN YOUSSEF
550 S. HOPE ST. SUITE 1700
LOS ANGELES, CA 90071

LANDSCAPE ARCHITECTURE
AHBEIMIG LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017

GEOTECHNICAL ENGINEERING
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92806

ENVIRONMENTAL CONSULTANT
CAJA ENVIRONMENTAL SERVICES, LLC
11590 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049


HISTORIC CONSULTANT
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014

TRAFFIC CONSULTANT
LINSICOTT, LAW & GREENSPAN ENGINEERS
800 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106

[illegible]

Sheet Title:
**LEVEL 14 & 15 - HOTEL
FLOOR PLAN**

Key Plan:



ALL IDEAS, DESIGNS, ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THESE DRAWINGS ARE OWNED BY AND ARE THE PROPERTY OF NARDI ASSOCIATES LLP AND WERE CREATED, EVOLVED, AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH IDEAS, DESIGN, ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PERSON, FIRM, OR CORPORATION, WITHOUT THE WRITTEN PERMISSION OF NARDI ASSOCIATES LLP.

© 2010 NARDI ASSOCIATES LLP

Scale: $1/16" = 1'-0"$


Date: 12/16/2015

Drawn by: WC	Project No: 85-10130
-----------------	-------------------------

Phase: ENTITLEMENT

Sheet No: _____

A114



OLYMPIC TOWER
811 West Olympic Blvd.
Los Angeles, CA 90015

Client:
Neman Real Estate Investments, LLC
1433 Griffith Avenue
Los Angeles, CA 90021
(213) 765-7700 tel.

CONSULTANTS

ENTITLEMENTS & DEVELOPMENT CONSULTANTS
NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016

LAND USE ENTITLEMENTS
ALSTON & BIRD
333 SOUTH HOPE ST 16TH F
LOS ANGELES, CA 90071

CIVIL ENGINEER
PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071

STRUCTURAL ENGINEERING
NABIH YOUSSEF
550 S. HOPE ST., SUITE 170
LOS ANGELES, CA 90071

LANDSCAPE ARCHITECTURE
AHBE/MIG LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017

GEOTECHNICAL ENGINEERING
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92806

ENVIRONMENTAL CONSULTANT
CAJA ENVIRONMENTAL SERVICES, LLC
11990 SAN VINCENT BOULEVARD, SUITE 25
LOS ANGELES, CA 90049


HISTORIC CONSULTANT
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014

TRAFFIC CONSULTANT
LINSOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106

[illegible]

Sheet Title:
LEVEL 16 & 17 - HOTEL
FLOOR PLAN

Key Plan:



ALL IDEAS, DESIGNS, ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THESE DRAWINGS ARE OWNED BY AND ARE THE PROPERTY OF NARDI ASSOCIATES LLP AND WERE CREATED, EVOLVED, AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH IDEAS, DESIGN, ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PERSON, FIRM, OR CORPORATION, WITHOUT THE WRITTEN PERMISSION OF NARDI ASSOCIATES LLP.

© 2010 NARDI ASSOCIATES LLP

Scale: $1/16" = 1'-0"$


Date: 12/16/2015

Drawn by: WC	Project No: 85-10130
-----------------	-------------------------


Phase: ENTITLEMENT

Sheet No:

A116



2 LEVEL 17 - HOTEL ROOM
1/16" = 1'-0"



1 LEVEL 16 - HOTEL ROOM
1/16" = 1'-0"

Project:
OLYMPIC TOWER
811 West Olympic Blvd.
Los Angeles, CA 90015
Client:
Neman Real Estate Investments, LLC
1433 Griffith Avenue
Los Angeles, CA 90021
(213) 765-7700 tel.

CONSULTANTS

ENTITLEMENTS & DEVELOPMENT CONSULTANTS
NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016

LAND USE ENTITLEMENTS
ALSTON & BIRD
333 SOUTH HOPE ST 16TH FL
LOS ANGELES, CA 90071

CIVIL ENGINEER
PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071

STRUCTURAL ENGINEERING
NABIH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071

LANDSCAPE ARCHITECTURE
AHBEHMG LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017

GEOTECHNICAL ENGINEERING
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92805

ENVIRONMENTAL CONSULTANT
CALIA ENVIRONMENTAL SERVICES, LLC
11950 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049


HISTORIC CONSULTANT
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014

TRAFFIC CONSULTANT
LINSOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106

Revisions:		
No	Date	Description
1	12/16/2015	1ST ENT. SUBMITTAL



Sheet Title:
**LEVEL 18 - HOTEL
FLOOR PLAN**



ALL IDEAS, DESIGNS, ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THESE DRAWINGS ARE OWNED BY AND ARE THE PROPERTY OF NARDI ASSOCIATES LLP AND WERE CREATED, EVOLVED, AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH IDEAS, DESIGN, ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PERSON, FIRM, OR CORPORATION, WITHOUT THE WRITTEN PERMISSION OF NARDI ASSOCIATES LLP.

© 2010 NARDI ASSOCIATES LLP

Scale:
1/16" = 1'-0"


Date:
12/16/2015

Drawn by: WC Project No: 85-10130

Phase:
ENTITLEMENT

Sheet No:

A118



① LEVEL 18 - HOTEL ROOM
1/16" = 1'-0"

OLYMPIC TOWER
811 West Olympic Blvd.
Los Angeles, CA 90015

Client:
Neman Real Estate Investments, LLC
1433 Griffith Avenue
Los Angeles, CA 90021
(213) 765-7700 tel.

CONSULTANTS

ENTITLEMENTS & DEVELOPMENT CONSULTANTS
INARDI ASSOCIATES, LLP
 1805 S. SHAMROCK AVE.
 MONROVIA, CA 91016

LAND USE ENTITLEMENTS
ALSTON & BIRD
333 SOUTH HOPE ST 16TH FL
LOS ANGELES, CA 90071

CIVIL ENGINEER
PSOMAS
 555 SOUTH FLOWER STREET, SUITE 4300
 LOS ANGELES, CA 90071

STRUCTURAL ENGINEERING
NABIH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071

LANDSCAPE ARCHITECTURE
HAUBE/MIG LANDSCAPE ARCHITECTS
 617 WEST SEVENTH STREET, SUITE 300
 LOS ANGELES, CA 90017

GEOTECHNICAL ENGINEERING
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92806

ENVIRONMENTAL CONSULTANT
CAJA ENVIRONMENTAL SERVICES, LLC
11990 SAN VINCENT BOULEVARD, SUITE 25
LOS ANGELES, CA 90049


**HISTORIC CONSULTANT
GPA CONSULTING**
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014

TRAFFIC CONSULTANT
LINSKOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106

[illegible]

Sheet Title:
LEVEL 19 & 20 - HOTEL
FLOOR PLAN

Key Plan:



ALL IDEAS, DESIGNS, ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THESE DRAWINGS ARE OWNED BY AND ARE THE PROPERTY OF NARDI ASSOCIATES LLP AND WERE CREATED, EVOLVED, AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH IDEAS, DESIGN, ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PERSON, FIRM, OR CORPORATION, WITHOUT THE WRITTEN PERMISSION OF NARDI ASSOCIATES LLP.

© 2010 NARDI ASSOCIATES LLP

Scale: $1/16" = 1'-0"$


Date: 12/16/2015

Drawn by: WC	Project No: 85-10130
-----------------	-------------------------


Phase: ENTITLEMENT

Sheet No:


A119




2 LEVEL 20 - HOTEL ROOM
1/16" = 1'-0"



① LEVEL 19 - HOTEL ROOM
1/16" = 1'-0"



② LEVEL 22 - HOTEL ROOM
1/16" = 1'-0"



① LEVEL 21 - HOTEL ROOM
1/16" = 1'-0"

Project:
OLYMPIC TOWER
811 West Olympic Blvd.
Los Angeles, CA 90015

Client:
Neman Real Estate Investments, LLC
1433 Griffith Avenue
Los Angeles, CA 90021
(213) 765-7700 tel.

CONSULTANTS

ENTITLEMENTS & DEVELOPMENT CONSULTANTS
NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016

LAND USE ENTITLEMENTS
ALSTON & BIRD
333 SOUTH HOPE ST 16TH FL
LOS ANGELES, CA 90071

CIVIL ENGINEER
PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071

STRUCTURAL ENGINEERING
NABH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071

LANDSCAPE ARCHITECTURE
ABEYME LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017

GEOTECHNICAL ENGINEERING
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92805


ENVIRONMENTAL CONSULTANT
CALIA ENVIRONMENTAL SERVICES, LLC
11950 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049

HISTORIC CONSULTANT
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014

TRAFFIC CONSULTANT
LINSOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106


Revisions:

No	Date	Description
1	12/16/2015	1ST ENT. SUBMITTAL



Sheet Title:
**LEVEL 21 & 22 - HOTEL
FLOOR PLAN**

Key Plan:



ALL IDEAS, DESIGNS, ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THESE DRAWINGS ARE OWNED BY AND ARE THE PROPERTY OF NARDI ASSOCIATES LLP AND WERE CREATED, EVOLVED, AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH IDEAS, DESIGN, ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PERSON, FIRM, OR CORPORATION, WITHOUT THE WRITTEN PERMISSION OF NARDI ASSOCIATES LLP.

© 2010 NARDI ASSOCIATES LLP

Scale:
1/16" = 1'-0"

Date:
12/16/2015

Drawn by: WC Project No: 85-10130

Phase:
ENTITLEMENT

Sheet No:

A121

Project:
OLYMPIC TOWER
811 West Olympic Blvd.
Los Angeles, CA 90015

Client:
Neman Real Estate Investments, LLC
1433 Griffith Avenue
Los Angeles, CA 90021
(213) 765-7700 tel.

CONSULTANTS

ENTITLEMENTS & DEVELOPMENT CONSULTANTS
NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016

LAND USE ENTITLEMENTS
ALSTON & BIRD
333 SOUTH HOPE ST 16TH FL
LOS ANGELES, CA 90071

CIVIL ENGINEER
PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071

STRUCTURAL ENGINEERING
NABIH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071

LANDSCAPE ARCHITECTURE
AHBEHME LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017


GEOTECHNICAL ENGINEERING
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92805

ENVIRONMENTAL CONSULTANT
CALIA ENVIRONMENTAL SERVICES, LLC
11950 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049


HISTORIC CONSULTANT
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014

TRAFFIC CONSULTANT
LINSOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106

Revisions:		
No	Date	Description
1	12/16/2015	1ST ENT. SUBMITTAL



Sheet Title:
LEVEL 23 - HOTEL
FLOOR PLAN



ALL IDEAS, DESIGNS, ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THESE DRAWINGS ARE OWNED BY AND ARE THE PROPERTY OF NARDI ASSOCIATES LLP AND WERE CREATED, EVOLVED, AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH IDEAS, DESIGN, ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PERSON, FIRM, OR CORPORATION, WITHOUT THE WRITTEN PERMISSION OF NARDI ASSOCIATES LLP.

© 2010 NARDI ASSOCIATES LLP

Scale:
1/16" = 1'-0"


Date:
12/16/2015

Drawn by: WC Project No: 85-10130

Phase:
ENTITLEMENT

Sheet No:

A123



1 LEVEL 23 - HOTEL ROOM
1/16" = 1'-0"

Architecture Urban Design Interiors

805 S. Shamrock Avenue
Monrovia, CA 91016
t: 626.599.1776
f: 626.599.9399
e: office@nardi-associates.com
w: nardi-associates.com

OLYMPIC TOWER
811 WEST OLYMPIC BLVD.
LOS ANGELES, CA 90015

OWNER
NEMAN REAL ESTATE INVESTMENTS, LLC
1433 GRIFFITH AVENUE
LOS ANGELES, CA 90021
(213) 765-7700

CONSULTANTS

ENTITLEMENTS & DEVELOPMENT CONSULTANTS
NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016

LAND USE ENTITLEMENTS
ALSTON & BIRD
333 SOUTH HOPE ST 16TH FL
LOS ANGELES, CA 90071

CIVIL ENGINEER
PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071

STRUCTURAL ENGINEERING
NABIH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071

LANDSCAPE ARCHITECTURE
AHBE/MIG LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017

GEOTECHNICAL ENGINEERING
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92806


ENVIRONMENTAL CONSULTANT
CAJA ENVIRONMENTAL SERVICES, LLC
11990 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049

HISTORIC CONSULTANT
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014


TRAFFIC CONSULTANT
LINSCOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106

[illegible]

KEY MAP:



STAMP:



All ideas, designs, arrangements, and plans indicated or represented by these drawings are owned by and are the property of nardi associates llp and were created, evolved, and developed for use on and in connection with the specified project. None of such ideas, design, arrangements, or plans shall be used by or disclosed to any person, firm, or corporation, without the written permission of nardi associates llp.

© 2019 NARDI ASSOCIATES LLP

ISSUE/REVISION


[illegible]

LEVEL 24 & 25 - HOTEL
FLOOR PLAN


Project number	10130
Date	08/14/2015
Drawn by	YP
Checked by	NFN

A124

Scale	1/16" = 1'-0"
-------	---------------



② LEVEL 25 - HOTEL ROOM
1/16" = 1'-0"



① LEVEL 24 - HOTEL ROOM
1/16" = 1'-0"

Architecture Urban Design Interiors

805 S. Shamrock Avenue
Monrovia, CA 91016
t: 626.599.1776
f: 626.599.9399
e: office@nardi-associates.com
w: nardi-associates.com

OLYMPIC TOWER
811 WEST OLYMPIC BLVD.
LOS ANGELES, CA 90015

OWNER
NEMAN REAL ESTATE INVESTMENTS, LLC
1433 GRIFFITH AVENUE
LOS ANGELES, CA 90021
(213) 765-7700

CONSULTANTS

ENTITLEMENTS & DEVELOPMENT CONSULTANTS
NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016

LAND USE ENTITLEMENTS
ALSTON & BIRD
333 SOUTH HOPE ST 16TH FL
LOS ANGELES, CA 90071

CIVIL ENGINEER
PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071

STRUCTURAL ENGINEERING
NABIH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071

LANDSCAPE ARCHITECTURE
AHBE/MIG LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017

GEOTECHNICAL ENGINEERING
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92806


ENVIRONMENTAL CONSULTANT
CAJA ENVIRONMENTAL SERVICES, LLC
11990 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049

HISTORIC CONSULTANT
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014


TRAFFIC CONSULTANT
LINSCOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106

[illegible]

KEY MAP:



STAMP:



All ideas, designs, arrangements, and plans indicated or represented by these drawings are owned by and are the property of nardi associates llp and were created, evolved, and developed for use on and in connection with the specified project. None of such ideas, design, arrangements, or plans shall be used by or disclosed to any person, firm, or corporation, without the written permission of nardi associates llp.

© 2019 NARDI ASSOCIATES LLP

ISSUE/REVISION



[illegible]

LEVEL 26 & 27 - HOTEL
FLOOR PLAN

Project number	10130
Date	08/14/2015
Drawn by	YP
Checked by	NFN

A126

Scale	1/16" = 1'-0"
-------	---------------



Architecture Urban Design Interiors

805 S. Shamrock Avenue
Monrovia, CA 91016
t: 626.599.1776
f: 626.599.9399
e: office@nardi-associates.com
w: nardi-associates.com

OLYMPIC TOWER
811 WEST OLYMPIC BLVD.
LOS ANGELES, CA 90015

OWNER
NEMAN REAL ESTATE INVESTMENTS, LLC
1433 GRIFFITH AVENUE
LOS ANGELES, CA 90021
(213) 765-7700

CONSULTANTS

ENTITLEMENTS & DEVELOPMENT CONSULTANTS
NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016

LAND USE ENTITLEMENTS
ALSTON & BIRD
333 SOUTH HOPE ST 16TH FL
LOS ANGELES, CA 90071

CIVIL ENGINEER
PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071

STRUCTURAL ENGINEERING
NABIH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071



LANDSCAPE ARCHITECTURE
AHBE/MIG LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017

GEOTECHNICAL ENGINEERING
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92806


ENVIRONMENTAL CONSULTANT
CAJA ENVIRONMENTAL SERVICES, LLC
11990 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049

HISTORIC CONSULTANT
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014


TRAFFIC CONSULTANT
LINS COTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106



KEY MAP:



STAMP:



All ideas, designs, arrangements, and plans indicated or represented by these drawings are owned by and are the property of nardi associates llp and were created, evolved, and developed for use on and in connection with the specified project. none of such ideas, design, arrangements, or plans shall be used by or disclosed to any person, firm, or corporation, without the written permission of nardi associates llp.

© 2019 NARDI ASSOCIATES LLP

ISSUE/REVISION

[illegible]

LEVEL 28 & 29 - HOTEL
FLOOR PLAN

Project number	10130
Date	08/14/2015
Drawn by	YP
Checked by	NFN

A128

Scale	1/16" = 1'-0"
-------	---------------

Architecture Urban Design Interiors

805 S. Shamrock Avenue
Monrovia, CA 91016
t: 626.599.1776
f: 626.599.9399
e: office@nardi-associates.com
w: nardi-associates.com

OLYMPIC TOWER
811 WEST OLYMPIC BLVD.
LOS ANGELES, CA 90015

OWNER
NEMAN REAL ESTATE INVESTMENTS, LLC
1433 GRIFFITH AVENUE
LOS ANGELES, CA 90021
(213) 765-7700

CONSULTANTS

ENTITLEMENTS & DEVELOPMENT CONSULTANTS
NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016

LAND USE ENTITLEMENTS
ALSTON & BIRD
333 SOUTH HOPE ST 16TH FL
LOS ANGELES, CA 90071

CIVIL ENGINEER
PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071

STRUCTURAL ENGINEERING
NABIH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071

LANDSCAPE ARCHITECTURE
AHBE/MIG LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017


GEOTECHNICAL ENGINEERING
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92806

ENVIRONMENTAL CONSULTANT
CAJA ENVIRONMENTAL SERVICES, LLC
11990 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049


HISTORIC CONSULTANT
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014

TRAFFIC CONSULTANT
LINSKOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106

KEY MAP:



STAMP:



All ideas, designs, arrangements, and plans indicated or represented by these drawings are owned by and are the property of nardi associates llp and were created, evolved, and developed for use on and in connection with the specified project. none of such ideas, design, arrangements, or plans shall be used by or disclosed to any person, firm, or corporation, without the written permission of nardi associates llp.

© 2019 NARDI ASSOCIATES LLP

ISSUE/REVISION


[illegible]


LEVEL 30 - HOTEL
FLOOR PLAN

Project number	10130
Date	08/14/2015
Drawn by	YP
Checked by	NFN

A130

Scale $1/16" = 1'-0"$





OWNER
NEMAN REAL ESTATE INVESTMENTS, LLC
1433 GRIFFITH AVENUE
LOS ANGELES, CA 90021
(213) 765-7700

TRAFFIC CONSULTANT
LINSOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106

STAMP:



The stamp is a circular professional seal for the State of California. The outer ring contains the text "LICENSED ARCHITECT" at the top and "STATE OF CALIFORNIA" at the bottom. Inside the ring, the name "ROBERTO E. NERI" is printed in an arc. Below the name is a handwritten signature "Roberto Neri". Under the signature is the license number "NO. C-28794". At the bottom of the seal, the expiration date "REN. 1-31-21" is printed. Two five-pointed stars are positioned on the left and right sides of the seal, separating the license number from the expiration date.

NO.	REV.	DESCRIPTION	DATE
XX		XX	XX/XX/2019

[illegible]

Project number	10130
Date	08/14/2015
Drawn by	YP
Checked by	NFN

Scale	1/16" = 1'-0"
-------	---------------





NARDIASSOCIATES LLP
Architecture Urban Design Interiors

805 S. Shamrock Avenue
Monrovia, CA 91016
t: 626.599.1776
f: 626.599.9399
e: office@nardi-associates.com
w: nardi-associates.com

OLYMPIC TOWER
811 WEST OLYMPIC BLVD.
LOS ANGELES, CA 90015

OWNER
NEMAN REAL ESTATE INVESTMENTS, LLC
1433 GRIFFITH AVENUE
LOS ANGELES, CA 90021
(213) 765-7700

CONSULTANTS

ENTITLEMENTS & DEVELOPMENT CONSULTANTS:
NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016

LAND USE ENTITLEMENTS
ALSTON & BIRD
333 SOUTH HOPE ST 16TH
LOS ANGELES, CA 90071

CIVIL ENGINEER
PSOMAS
555 SOUTH FLOWER STREET, SUITE 430
LOS ANGELES, CA 90071

STRUCTURAL ENGINEERING
NABIH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071

LANDSCAPE ARCHITECTURE
AHBE/MIG LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 300
LOS ANGELES, CA 90017


GEOTECHNICAL ENGINEERING
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92806

ENVIRONMENTAL CONSULTANT
CAJA ENVIRONMENTAL SERVICES, LLC
11990 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049


HISTORIC CONSULTANT
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014

TRAFFIC CONSULTANT
LINSOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106

KEY MAP:



STAMP:



All ideas, designs, arrangements, and plans indicated or represented by these drawings are owned by and are the property of nardi associates llp and were created, evolved, and developed for use on and in connection with the specified project. none of such ideas, design, arrangements, or plans shall be used by or disclosed to any person, firm, or corporation, without the written permission of nardi associates llp.

© 2019 NARDI ASSOCIATES LLP

ISSUE/REVISION

[illegible]

LEVEL 36 & 37 -
CONDOMINIUM FLOOR
PLAN

Project number	10130
Date	08/14/2015
Drawn by	YP
Checked by	NFN

A136

Scale	1/16" = 1'-0"
-------	---------------



PASADENA, CA 91106

Scale $1/16" = 1'-0"$



600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106


A140

Scale $1/16" = 1'-0"$

Scale $1/16" = 1'-0"$

Scale $1/16" = 1'-0"$

Scale $1/16" = 1'-0"$



NARDIASSOCIATES LLP
Architecture Urban Design Interiors

805 S. Shamrock Avenue
Monrovia, CA 91016
t: 626.599.1776
f: 626.599.9399
e: office@nardi-associates.com
w: nardi-associates.com

OLYMPIC TOWER
811 WEST OLYMPIC BLVD.
LOS ANGELES, CA 90015

OWNER
NEMAN REAL ESTATE INVESTMENTS, LLC
1433 GRIFFITH AVENUE
LOS ANGELES, CA 90021
(213) 765-7700

CONSULTANTS

ENTITLEMENTS & DEVELOPMENT CONSULTANTS:
NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016

LAND USE ENTITLEMENTS
ALSTON & BIRD
333 SOUTH HOPE ST 16TH
LOS ANGELES CA 90071

CIVIL ENGINEER
PSOMAS
555 SOUTH FLOWER STREET, SUITE 430
LOS ANGELES, CA 90071

STRUCTURAL ENGINEERING
NABIH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071

LANDSCAPE ARCHITECTURE
AHBE/MIG LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 3
LOS ANGELES, CA 90017


GEOTECHNICAL ENGINEERING
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92806

ENVIRONMENTAL CONSULTANT
CAJA ENVIRONMENTAL SERVICES, LLC
11990 SAN VINCENT BOULEVARD, SUITE 25
LOS ANGELES, CA 90049


HISTORIC CONSULTANT
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014

TRAFFIC CONSULTANT
LINSKOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106

KEY MAP:



STAMP:



All ideas, designs, arrangements, and plans indicated or represented by these drawings are owned by and are the property of nardi associates llp and were created, evolved, and developed for use on and in connection with the specified project. none of such ideas, design, arrangements, or plans shall be used by or disclosed to any person, firm, or corporation, without the written permission of nardi associates llp.

© 2019 NARDI ASSOCIATES LLP

ISSUE/REVISION

[illegible]

LEVEL 54 & 55 - 2-3
Bedroom Condo FLOOR
PLAN

Project number	10130
Date	08/14/2015
Drawn by	YP
Checked by	NFN

A154

Scale	1/16" = 1'-0"
-------	---------------

Project:
OLYMPIC TOWER
811 West Olympic Blvd.
Los Angeles, CA 90015

Client:
Neman Real Estate Investments, LLC
1433 Griffith Avenue
Los Angeles, CA 90021
(213) 765-7700 tel.

Consultant:
ENTITLEMENTS & DEVELOPMENT CONSULTANTS
NGR Development, LLC
805 S. Shamrock Ave.
Monrovia, CA 91016

LAND USE ENTITLEMENTS:
PSOMAS
555 South Flower Street, Suite 4300
Los Angeles, CA 90071

CIVIL ENGINEER:
PSOMAS
555 South Flower Street, Suite 4300
Los Angeles, CA 90071

STRUCTURAL ENGINEERING:
NABIH YOUSSEF
550 S. Hope ST., Suite 1700
Los Angeles, CA 90071

LANDSCAPE ARCHITECTURE:
AHBE Landscape Architects
617 West Seventh Street, Suite 304
Los Angeles, CA 90017

GEOTECHNICAL ENGINEERING:
GeoDesign, Inc.
2121 S. Towne Centre Place, Suite 130
Anaheim, CA 92806

ENVIRONMENTAL CONSULTANT:
CAJA Environmental Services, LLC
11990 San Vicente Boulevard, Suite 250
Los Angeles, CA 90049

HISTORIC CONSULTANT:
GPA Consulting
617 S. Olive Street, Suite 910
Los Angeles, CA 90014

TRAFFIC CONSULTANT:
Linscott, Law & Greenspan, Engineers
600 South Lake Avenue, Suite 500
Pasadena, CA 91106


Revisions:

No	Date	Description
1	12/16/2015	1ST ENT. SUBMITTAL



Sheet Title:
**LEVEL 56 & 57 -
PENTHOUSE AMEN.
FLOOR PLAN**

Key Plan:



ALL IDEAS, DESIGNS, ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THESE DRAWINGS ARE OWNED BY AND ARE THE PROPERTY OF NARDI ASSOCIATES LLP AND WERE CREATED, EVOLVED, AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH IDEAS, DESIGN, ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PERSON, FIRM, OR CORPORATION, WITHOUT THE WRITTEN PERMISSION OF NARDI ASSOCIATES LLP.

© 2010 NARDI ASSOCIATES LLP

Scale:
1/16" = 1'-0"


Date:
12/16/2015

Drawn by: WC Project No: 85-10130


Phase:
ENTITLEMENT

Sheet No:



A156



② LEVEL 57 - PENTHOUSE AMENITIES
1/16" = 1'-0"




① LEVEL 56 - PENTHOUSE AMENITIES
1/16" = 1'-0"





- 19

TRAFFIC CONSULTANT
LINSKOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106
TEL: 818/795-1100 FAX: 818/795-1101

MP: 

[illegible]

Scale	1" = 40'-0"
-------	-------------



- 13

- 20

- 11

- 9


- 14

- 21

- 6

- 1

Scale 1" = 40'-0"



Project:
OLYMPIC TOWER
811 West Olympic Blvd.
Los Angeles, CA 90015
Client:
Neman Real Estate Investments, LLC
1433 Griffith Avenue
Los Angeles, CA 90021
(213) 765-7700 tel.

CONSULTANTS

ENTITLEMENTS & DEVELOPMENT CONSULTANTS
NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016

LAND USE ENTITLEMENTS
ALSTON & BIRD
333 SOUTH HOPE ST 16TH FL
LOS ANGELES, CA 90071

CIVIL ENGINEER
PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071

STRUCTURAL ENGINEERING
NABIH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071

LANDSCAPE ARCHITECTURE
AHBEHMG LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017

GEOTECHNICAL ENGINEERING
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92805

ENVIRONMENTAL CONSULTANT
CALJA ENVIRONMENTAL SERVICES, LLC
11950 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049

HISTORIC CONSULTANT
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014

TRAFFIC CONSULTANT
LINSOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106


Revisions:

No	Date	Description
1	12/16/2015	1ST ENT. SUBMITTAL



Sheet Title: **SECTIONS**

Key Plan:



ALL IDEAS, DESIGNS, ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THESE DRAWINGS ARE OWNED BY AND ARE THE PROPERTY OF NARDI ASSOCIATES LLP AND WERE CREATED, EVOLVED, AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH IDEAS, DESIGN, ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PERSON, FIRM, OR CORPORATION, WITHOUT THE WRITTEN PERMISSION OF NARDI ASSOCIATES LLP.

© 2010 NARDI ASSOCIATES LLP

Scale: 1" = 40'-0"


Date: 12/16/2015

Drawn by: WC Project No: 85-10130


Phase: ENTITLEMENT

Sheet No:


A301




6 ENLARGE SECTION AT PENTHOUSE AMENITIES #2
1" = 20'-0"




3 ENLARGE SECTION AT PENTHOUSE AMENITIES #1
1" = 20'-0"




5 ENLARGE SECTION AT HOTEL LOBBY #2
1" = 20'-0"



2 ENLARGE SECTION AT HOTEL LOBBY #1
1" = 20'-0"



4 ENLARGE SECTION AT RETAIL #2
1" = 20'-0"



1 ENLARGE SECTION AT RETAIL #1
1" = 20'-0"

CONSULTANTS

ENTITLEMENTS & DEVELOPMENT CONSULTANTS
NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016

LAND USE ENTITLEMENTS
ALSTON & BIRD
333 SOUTH HOPE ST 16TH FL
LOS ANGELES, CA 90071

CIVIL ENGINEER
PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071

STRUCTURAL ENGINEERING
NABIH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071

LANDSCAPE ARCHITECTURE
AHBEHMG LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017

GEOTECHNICAL ENGINEERING
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92806

ENVIRONMENTAL CONSULTANT
CALIA ENVIRONMENTAL SERVICES, LLC
11950 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049

HISTORIC CONSULTANT
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014

TRAFFIC CONSULTANT
LINSOOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106


Revisions:

No	Date	Description
1	12/16/2015	1ST ENT. SUBMITTAL



Sheet Title:
ENLARGED SECTIONS

Key Plan:



ALL IDEAS, DESIGNS, ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THESE DRAWINGS ARE OWNED BY AND ARE THE PROPERTY OF NARDI ASSOCIATES LLP AND WERE CREATED, EVOLVED, AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH IDEAS, DESIGN, ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PERSON, FIRM, OR CORPORATION, WITHOUT THE WRITTEN PERMISSION OF NARDI ASSOCIATES LLP.

© 2010 NARDI ASSOCIATES LLP

Scale:
1" = 20'-0"

Date:
12/16/2015

Drawn by: WC Project No: 85-10130

Phase:
ENTITLEMENT

Sheet No:

A302




Project:
OLYMPIC TOWER
811 West Olympic Blvd.
Los Angeles, CA 90015
Client:
Neman Real Estate Investments, LLC
1433 Griffith Avenue
Los Angeles, CA 90021
(213) 765-7700 tel.

- CONSULTANTS**
- ENTITLEMENTS & DEVELOPMENT CONSULTANTS**
NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016
- LAND USE ENTITLEMENTS**
ALSTON & BIRD
333 SOUTH HOPE ST. 16TH FL.
LOS ANGELES, CA 90071
- CIVIL ENGINEER**
PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071
- STRUCTURAL ENGINEERING**
NABH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071
- LANDSCAPE ARCHITECTURE**
ARBERG LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017
- GEOTECHNICAL ENGINEERING**
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92806
- ENVIRONMENTAL CONSULTANT**
CALA ENVIRONMENTAL SERVICES, LLC
11950 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049
- HISTORIC CONSULTANT**
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014
- TRAFFIC CONSULTANT**
LINSOOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106

Revisions:		
No	Date	Description
1	12/16/2015	1ST ENT. SUBMITTAL




Sheet Title:
**LANDSCAPE
CONTEXT ANALYSIS**



ALL IDEAS, DESIGNS, ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THESE DRAWINGS ARE OWNED BY AND ARE THE PROPERTY OF NARDI ASSOCIATES LLP AND WERE CREATED, EVOLVED, AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH IDEAS, DESIGN, ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PERSON, FIRM, OR CORPORATION, WITHOUT THE WRITTEN PERMISSION OF NARDI ASSOCIATES LLP.
© 2010 NARDI ASSOCIATES LLP

Scale: 1/16" = 1'-0"
Date: 12/9/2015
Drawn by: HL Project No: 115035
Phase: ENTITLEMENT
Sheet No:


L-0.00




Project:
OLYMPIC TOWER
811 West Olympic Blvd.
Los Angeles, CA 90015
Client:
Neman Real Estate Investments, LLC
1433 Griffith Avenue
Los Angeles, CA 90021
(213) 765-7700 tel.

- CONSULTANTS**
- ENTITLEMENTS & DEVELOPMENT CONSULTANTS**
NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016
- LAND USE ENTITLEMENTS**
ALSTON & BIRD
333 SOUTH HOPE ST 16TH FL
LOS ANGELES, CA 90071
- CIVIL ENGINEER**
PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071
- STRUCTURAL ENGINEERING**
NABIH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071
- LANDSCAPE ARCHITECTURE**
ABEEMING LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017
- GEOTECHNICAL ENGINEERING**
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92805
- ENVIRONMENTAL CONSULTANT**
CALIA ENVIRONMENTAL SERVICES, LLC
11990 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049
- HISTORIC CONSULTANT**
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014
- TRAFFIC CONSULTANT**
LINSOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106

Revisions:		
No	Date	Description
1	12/16/2015	1ST ENT. SUBMITTAL



Sheet Title:
**LANDSCAPE
CONCEPT IMAGES**



ALL IDEAS, DESIGNS, ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THESE DRAWINGS ARE OWNED BY AND ARE THE PROPERTY OF NARDI ASSOCIATES LLP AND WERE CREATED, EVOLVED AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH IDEAS, DESIGN ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PERSON, FIRM, OR CORPORATION, WITHOUT THE WRITTEN PERMISSION OF NARDI ASSOCIATES LLP.
© 2010 NARDI ASSOCIATES LLP



Scale: 1/16" = 1'-0"

Date: 12/9/2015

Drawn by: HL	Project No: 115035
--------------	--------------------

Phase: ENTITLEMENT

Sheet No:
L-0.01




Project:
OLYMPIC TOWER
811 West Olympic Blvd.
Los Angeles, CA 90015
Client:
Neman Real Estate Investments, LLC
1433 Griffith Avenue
Los Angeles, CA 90021
(213) 765-7700 tel.

- CONSULTANTS**
- ENTITLEMENTS & DEVELOPMENT CONSULTANTS**
NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016
- LAND USE ENTITLEMENTS**
ALSTON & BIRD
333 SOUTH HOPE ST 16TH FL
LOS ANGELES, CA 90071
- CIVIL ENGINEER**
PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071
- STRUCTURAL ENGINEERING**
NABIH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071
- LANDSCAPE ARCHITECTURE**
AHECMG LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017
- GEOTECHNICAL ENGINEERING**
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92806
- ENVIRONMENTAL CONSULTANT**
CALIA ENVIRONMENTAL SERVICES, LLC
11950 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049
- HISTORIC CONSULTANT**
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014
- TRAFFIC CONSULTANT**
LINSOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106

Revisions:		
No	Date	Description
1	12/16/2015	1ST ENT. SUBMITTAL



Sheet Title:
**LANDSCAPE
CONCEPT IMAGES**




ALL IDEAS, DESIGNS, ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THESE DRAWINGS ARE OWNED BY AND ARE THE PROPERTY OF NARDI ASSOCIATES LLP AND WERE CREATED, EVOLVED AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH IDEAS, DESIGN ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PERSON, FIRM, OR CORPORATION, WITHOUT THE WRITTEN PERMISSION OF NARDI ASSOCIATES LLP.
© 2010 NARDI ASSOCIATES LLP

Scale: 1/16" = 1'-0"
Date: 12/9/2015
Drawn by: HL Project No: 115035
Phase: ENTITLEMENT

Sheet No:
L-1.00



- 1 LA Entertainment District Paving and Planting
- 2 Interior Paving
- 3 Banded Cobble Pavers
- 4 Drop-off Entry Pavers
- 5 Overhead Planted Vine Cables
- 6 Planted Buffer Area
- 7 Water Wall Feature
- 8 Existing Bus Shelter
- 9 Existing Street Light / Signage



NARDI ASSOCIATES LLP
Architecture Urban Design Interiors
805 S. Shamrock avenue
Monrovia, California 91016
T.626.599.1776 F.626.599.9399


Project:
OLYMPIC TOWER
811 West Olympic Blvd.
Los Angeles, CA 90015
Client:
Neman Real Estate Investments, LLC
1433 Griffith Avenue
Los Angeles, CA 90021
(213) 765-7700 tel.

- CONSULTANTS**
- ENTITLEMENTS & DEVELOPMENT CONSULTANTS**
NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016
- LAND USE ENTITLEMENTS**
ALSTON & BIRD
333 SOUTH HOPE ST 16TH FL
LOS ANGELES, CA 90071
- CIVIL ENGINEER**
PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071
- STRUCTURAL ENGINEERING**
NABIH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071
- LANDSCAPE ARCHITECTURE**
AHBEHME LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017
- GEOTECHNICAL ENGINEERING**
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92806
- ENVIRONMENTAL CONSULTANT**
CALIA ENVIRONMENTAL SERVICES, LLC
11950 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049
- HISTORIC CONSULTANT**
GPA CONSULTING
817 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014
- TRAFFIC CONSULTANT**
LINSOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106

Revisions:		
No	Date	Description
1	12/16/2015	1ST ENT. SUBMITTAL




Sheet Title:
**LANDSCAPE
PLAN - GROUND**



ALL IDEAS, DESIGNS, ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THESE DRAWINGS ARE OWNED BY AND ARE THE PROPERTY OF NARDI ASSOCIATES LLP AND WERE CREATED, EVOLVED, AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH IDEAS, DESIGN, ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PERSON, FIRM, OR CORPORATION, WITHOUT THE WRITTEN PERMISSION OF NARDI ASSOCIATES LLP.
© 2010 NARDI ASSOCIATES LLP

Scale: 1/16" = 1'-0"
Date: 12/9/2015
Drawn by: HL Project No: 115035
Phase: ENTITLEMENT

Sheet No:
L-1.01



Project:
OLYMPIC TOWER
811 West Olympic Blvd.
Los Angeles, CA 90015
Client:
Neman Real Estate Investments, LLC
1433 Griffith Avenue
Los Angeles, CA 90021
(213) 765-7700 tel.


- CONSULTANTS**
- ENTITLEMENTS & DEVELOPMENT CONSULTANTS**
NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016
- LAND USE ENTITLEMENTS**
ALSTON & BIRD
333 SOUTH HOPE ST 16TH FL
LOS ANGELES, CA 90071
- CIVIL ENGINEER**
PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071
- STRUCTURAL ENGINEERING**
NABIH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071
- LANDSCAPE ARCHITECTURE**
ABC&MG LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017
- GEOTECHNICAL ENGINEERING**
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92805
- ENVIRONMENTAL CONSULTANT**
CALIA ENVIRONMENTAL SERVICES, LLC
11950 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049
- HISTORIC CONSULTANT**
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014
- TRAFFIC CONSULTANT**
LINSOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106

Revisions:

No	Date	Description
1	12/16/2015	1ST ENT. SUBMITTAL



Sheet Title:
**GROUND LEVEL
IMAGES**



ALL IDEAS, DESIGNS, ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THESE DRAWINGS ARE OWNED BY AND ARE THE PROPERTY OF NARDI ASSOCIATES LLP AND WERE CREATED, EVOLVED, AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH IDEAS, DESIGN ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PERSON, FIRM, OR CORPORATION, WITHOUT THE WRITTEN PERMISSION OF NARDI ASSOCIATES LLP.
© 2010 NARDI ASSOCIATES LLP

Scale:
1/16 = 1'-0"
Date:
12/9/2015
Drawn by:
HL
Project No:
115035
Phase:
ENTITLEMENT

Sheet No:
L-1.02

Project:
OLYMPIC TOWER
811 West Olympic Blvd.
Los Angeles, CA 90015

Client:
Neman Real Estate Investments, LLC
1433 Griffith Avenue
Los Angeles, CA 90021
(213) 765-7700 tel.

CONSULTANTS

ENTITLEMENTS & DEVELOPMENT CONSULTANTS
NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016

LAND USE ENTITLEMENTS
ALSTON & BIRD
333 SOUTH HOPE ST 16TH FL
LOS ANGELES, CA 90071

CIVIL ENGINEER
PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071

STRUCTURAL ENGINEERING
NABIH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071

LANDSCAPE ARCHITECTURE
ARBEING LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017

GEOTECHNICAL ENGINEERING
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92806


ENVIRONMENTAL CONSULTANT
CALJA ENVIRONMENTAL SERVICES, LLC
11950 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049

HISTORIC CONSULTANT
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014

TRAFFIC CONSULTANT
LINSOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106

Revisions:


No	Date	Description
1	12/16/2015	1ST ENT. SUBMITTAL



Sheet Title:

**LANDSCAPE
PLAN - LEVEL 13**

Key Plan:



ALL IDEAS, DESIGNS, ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THESE DRAWINGS ARE OWNED BY AND ARE THE PROPERTY OF NARDI ASSOCIATES LLP AND WERE CREATED, EVOLVED, AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH IDEAS, DESIGN, ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PERSON, FIRM, OR CORPORATION, WITHOUT THE WRITTEN PERMISSION OF NARDI ASSOCIATES LLP.
© 2010 NARDI ASSOCIATES LLP

Scale:
1/16" = 1'-0"

Date:
12/9/2015


Drawn by: HL Project No: 115035

Phase:
ENTITLEMENT

Sheet No:

L-1.03

- 1 Pool Paving
- 2 Carved Planted Area
- 3 Garden and Seating Area
- 4 Community Table and BBQ
- 5 Exercise Yoga Deck
- 6 Lounge Seating
- 7 Outdoor Ballroom Patio
- 8 Bartop Seating





Project:
OLYMPIC TOWER
811 West Olympic Blvd.
Los Angeles, CA 90015
Client:
Neman Real Estate Investments, LLC
1433 Griffith Avenue
Los Angeles, CA 90021
(213) 765-7700 tel.


CONSULTANTS

ENTITLEMENTS & DEVELOPMENT CONSULTANTS
NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016
LAND USE ENTITLEMENTS
ALSTON & BIRD
333 SOUTH HOPE ST 16TH FL
LOS ANGELES, CA 90071
CIVIL ENGINEER
PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071
STRUCTURAL ENGINEERING
NABIH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071
LANDSCAPE ARCHITECTURE
AHEBEMG LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017
GEOTECHNICAL ENGINEERING
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92805
ENVIRONMENTAL CONSULTANT
CALIA ENVIRONMENTAL SERVICES, LLC
11950 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049
HISTORIC CONSULTANT
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014
TRAFFIC CONSULTANT
LINSOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106

Revisions:		
No	Date	Description
1	12/16/2015	1ST ENT. SUBMITTAL



Sheet Title:
LEVEL 13 IMAGES





ALL IDEAS, DESIGNS, ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THESE DRAWINGS ARE OWNED BY AND ARE THE PROPERTY OF NARDI ASSOCIATES LLP AND WERE CREATED, EVOLVED, AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH IDEAS, DESIGN, ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PERSON, FIRM, OR CORPORATION WITHOUT THE WRITTEN PERMISSION OF NARDI ASSOCIATES LLP.
© 2010 NARDI ASSOCIATES LLP

Scale: 1/16 = 1'-0"
Date: 12/9/2015
Drawn by: HL Project No: 115035
Phase: ENTITLEMENT

Sheet No:
L-1.04

1. Iconic Paving Pattern
2. Lounge Area
- 3.Bay Area
4. Hanging Planting



NARDI ASSOCIATES LLP
Architecture Urban Design Interiors
805 S. Shamrock avenue
Monrovia, California 91016
T.626.599.1776 F.626.599.9399

Project:
OLYMPIC TOWER
811 West Olympic Blvd.
Los Angeles, CA 90015
Client:
Neman Real Estate Investments, LLC
1433 Griffith Avenue
Los Angeles, CA 90021
(213) 765-7700 tel.

CONSULTANTS

ENTITLEMENTS & DEVELOPMENT CONSULTANTS
NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016

LAND USE ENTITLEMENTS
ALSTON & BIRD
333 SOUTH HOPE ST 16TH FL
LOS ANGELES, CA 90071

CIVIL ENGINEER
PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071

STRUCTURAL ENGINEERING
NABIH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071

LANDSCAPE ARCHITECTURE
AHBEHMG LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017

GEOTECHNICAL ENGINEERING
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92805

ENVIRONMENTAL CONSULTANT
CALIA ENVIRONMENTAL SERVICES, LLC
11950 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049

HISTORIC CONSULTANT
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014

TRAFFIC CONSULTANT
LINSOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106


Revisions:

No	Date	Description
1	12/16/2015	1ST ENT. SUBMITTAL



Sheet Title:
**LANDSCAPE
PLAN - LEVEL 14**

Key Plan:



ALL IDEAS, DESIGNS, ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THESE DRAWINGS ARE OWNED BY AND ARE THE PROPERTY OF NARDI ASSOCIATES LLP AND WERE CREATED, EVOLVED, AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH IDEAS, DESIGN, ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PERSON, FIRM, OR CORPORATION WITHOUT THE WRITTEN PERMISSION OF NARDI ASSOCIATES LLP.
© 2010 NARDI ASSOCIATES LLP

Scale:
1/16" = 1'-0"



Date:
12/9/2015

Drawn by: HL Project No: 115035

Phase:
ENTITLEMENT

Sheet No:

L-1.05




Project:
OLYMPIC TOWER
811 West Olympic Blvd.
Los Angeles, CA 90015
Client:
Neman Real Estate Investments, LLC
1433 Griffith Avenue
Los Angeles, CA 90021
(213) 765-7700 tel.

- CONSULTANTS**
- ENTITLEMENTS & DEVELOPMENT CONSULTANTS**
NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016
- LAND USE ENTITLEMENTS**
ALSTON & BIRD
333 SOUTH HOPE ST. 16TH FL.
LOS ANGELES, CA 90071
- CIVIL ENGINEER**
PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071
- STRUCTURAL ENGINEERING**
NABH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071
- LANDSCAPE ARCHITECTURE**
ARBEKING LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017
- GEOTECHNICAL ENGINEERING**
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92805
- ENVIRONMENTAL CONSULTANT**
CALIA ENVIRONMENTAL SERVICES, LLC
11950 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049
- HISTORIC CONSULTANT**
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014
- TRAFFIC CONSULTANT**
LINSOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106

Revisions:		
No	Date	Description
1	12/16/2015	1ST ENT. SUBMITTAL



Sheet Title:
LEVEL 14 IMAGES



ALL IDEAS, DESIGNS, ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THESE DRAWINGS ARE OWNED BY AND ARE THE PROPERTY OF NARDI ASSOCIATES LLP AND WERE CREATED, EVOLVED, AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH IDEAS, DESIGN, ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PERSON, FIRM, OR CORPORATION WITHOUT THE WRITTEN PERMISSION OF NARDI ASSOCIATES LLP.
© 2010 NARDI ASSOCIATES LLP

Scale:
1/16" = 1'-0"


Date:
12/9/2015

Drawn by:
HL


Project No:
115035

Phase:
ENTITLEMENT

Sheet No:
L-1.06



- 1 Pool Paving and Banding
- 2 Wood Stepped Seating
- 3 Wood Exercise Deck
- 4 Moveable Seating
- 5 Game Tables
- 6 Trellis
- 7 Flexible Event Green Space



Project:
OLYMPIC TOWER
811 West Olympic Blvd.
Los Angeles, CA 90015
Client:
Neman Real Estate Investments, LLC
1433 Griffith Avenue
Los Angeles, CA 90021
(213) 765-7700 tel.

CONSULTANTS

ENTITLEMENTS & DEVELOPMENT CONSULTANTS
NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016

LAND USE ENTITLEMENTS
ALSTON & BIRD
333 SOUTH HOPE ST 16TH FL
LOS ANGELES, CA 90071

CIVIL ENGINEER
PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071

STRUCTURAL ENGINEERING
NABIH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071

LANDSCAPE ARCHITECTURE
AHBEHMG LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017

GEOTECHNICAL ENGINEERING
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92805


ENVIRONMENTAL CONSULTANT
CALIA ENVIRONMENTAL SERVICES, LLC
11990 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049

HISTORIC CONSULTANT
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014

TRAFFIC CONSULTANT
LINSOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106


Revisions:

No	Date	Description
1	12/16/2015	1ST ENT. SUBMITTAL



Sheet Title:
**LANDSCAPE
PLAN - LEVEL 56**

Key Plan:



ALL IDEAS, DESIGNS, ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THESE DRAWINGS ARE OWNED BY AND ARE THE PROPERTY OF NARDI ASSOCIATES LLP AND WERE CREATED, EVOLVED, AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH IDEAS, DESIGN, ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PERSON, FIRM, OR CORPORATION WITHOUT THE WRITTEN PERMISSION OF NARDI ASSOCIATES LLP.
© 2010 NARDI ASSOCIATES LLP

Scale:
1/16" = 1'-0"

Date:
12/9/2015

Drawn by: HL Project No: 115035

Phase:
ENTITLEMENT

Sheet No:

L-1.07



Project:
OLYMPIC TOWER
811 West Olympic Blvd.
Los Angeles, CA 90015
Client:
Neman Real Estate Investments, LLC
1433 Griffith Avenue
Los Angeles, CA 90021
(213) 765-7700 tel.


CONSULTANTS

ENTITLEMENTS & DEVELOPMENT CONSULTANTS
NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016
LAND USE ENTITLEMENTS
ALSTON & BIRD
333 SOUTH HOPE ST 16TH FL
LOS ANGELES, CA 90071
CIVIL ENGINEER
PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071
STRUCTURAL ENGINEERING
NABIH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071
LANDSCAPE ARCHITECTURE
AHBEHMG LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017
GEOTECHNICAL ENGINEERING
GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92805
ENVIRONMENTAL CONSULTANT
CALIA ENVIRONMENTAL SERVICES, LLC
11950 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049
HISTORIC CONSULTANT
GPA CONSULTING
617 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014
TRAFFIC CONSULTANT
LINSOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106

Revisions:		
No	Date	Description
1	12/16/2015	1ST ENT. SUBMITTAL



Sheet Title:
LEVEL 56 IMAGES



ALL IDEAS, DESIGNS, ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THESE DRAWINGS ARE OWNED BY AND ARE THE PROPERTY OF NARDI ASSOCIATES LLP AND WERE CREATED, EVOLVED, AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH IDEAS, DESIGN, ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PERSON, FIRM, OR CORPORATION WITHOUT THE WRITTEN PERMISSION OF NARDI ASSOCIATES LLP.
© 2010 NARDI ASSOCIATES LLP


Scale:
1/16" = 1'-0"
Date:
12/9/2015
Drawn by:
HL
Project No:
115035
Phase:
ENTITLEMENT

Sheet No:
L-1.08

[illegible]

Sheet Title: _____

Key Plan:



ALL IDEAS, DESIGNS, ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THESE DRAWINGS ARE OWNED BY AND ARE THE PROPERTY OF NARDI ASSOCIATES LLP AND WERE CREATED, EVOLVED, AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH IDEAS, DESIGN, ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PERSON, FIRM, OR CORPORATION, WITHOUT THE WRITTEN PERMISSION OF NARDI ASSOCIATES LLP.

© 2010 NARDI ASSOCIATES LLP


Scale: **NTS**

Date: **12/9/2015**

Drawn by: RW	Project No: 14350
------------------------	-----------------------------

Phase: **ENTITLEMENT**

Sheet No: _____



Project:
OLYMPIC TOWER
811 West Olympic Blvd.
Los Angeles, CA 90015

Client:
Neman Real Estate Investments, LLC
1433 Griffith Avenue
Los Angeles, CA 90021
(213) 765-7700 tel.

CONSULTANTS

ENTITLEMENTS & DEVELOPMENT CONSULTANTS

NARDI ASSOCIATES, LLP
805 S. SHAMROCK AVE.
MONROVIA, CA 91016

LAND USE ENTITLEMENTS

ALSTON & BIRD
333 SOUTH HOPE ST 16TH FL
LOS ANGELES, CA 90071

CIVIL ENGINEER

PSOMAS
555 SOUTH FLOWER STREET, SUITE 4300
LOS ANGELES, CA 90071

STRUCTURAL ENGINEERING

NABIH YOUSSEF
550 S. HOPE ST., SUITE 1700
LOS ANGELES, CA 90071

LANDSCAPE ARCHITECTURE

ABEEMING LANDSCAPE ARCHITECTS
617 WEST SEVENTH STREET, SUITE 304
LOS ANGELES, CA 90017

GEOTECHNICAL ENGINEERING

GEODESIGN, INC.
2121 S. TOWNE CENTRE PLACE, SUITE 130
ANAHEIM, CA 92808

ENVIRONMENTAL CONSULTANT

CAJA ENVIRONMENTAL SERVICES, LLC
11990 SAN VINCENT BOULEVARD, SUITE 250
LOS ANGELES, CA 90049

HISTORIC CONSULTANT

GPA CONSULTING
911 S. OLIVE STREET, SUITE 910
LOS ANGELES, CA 90014

TRAFFIC CONSULTANT

LINSCHOTT, LAW & GREENSPAN ENGINEERS
600 SOUTH LAKE AVENUE, SUITE 500
PASADENA, CA 91106


Revisions:

No	Date	Description
A	12/14/2015	CONCEPTUAL PLAN

Sheet Title:

**PRELIMINARY
GRADING PLAN**

Key Plan:



ALL IDEAS, DESIGNS, ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THESE DRAWINGS ARE OWNED BY AND ARE THE PROPERTY OF NARDI ASSOCIATES LLP AND WERE CREATED, EVOLVED, AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH IDEAS, DESIGN, ARRANGEMENTS, OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PERSON, FIRM, OR CORPORATION, WITHOUT THE WRITTEN PERMISSION OF NARDI ASSOCIATES LLP
© 2010 NARDI ASSOCIATES LLP

Scale:

1" = 20'

Date:

12/14/2015

Drawn by:

LINDA LUU

Project No:


1NEM010200

Phase:

CONCEPTUAL


Sheet No:

C2.0



GENERAL NOTE:

- GRADING WITHIN LIMIT OF SUBTERRANEAN PARKING STRUCTURE PER ARCHITECTURAL AND STRUCTURAL PLANS. ELEVATION PROVIDED HERE WITHIN THE STRUCTURE LIMIT FOR REFERENCE ONLY.
- CONTRACTOR TO CONFIRM DEPTH OF DRY UTILITIES WITHIN RIGHT-OF-WAY AS NEEDED.



PLAN

SCALE: 1" = 20'



GRAPHIC SCALE

Note: For reduced sized prints, original scale is in inches

V. MITIGATION MONITORING PROGRAM

1. INTRODUCTION

Section 21081.6 of the Public Resources Code requires a Lead Agency to adopt a “reporting or monitoring program for the changes made to the project or conditions of project approval, adopted in order to mitigate or avoid significant effects on the environment” (Mitigation Monitoring Program, Section 15097 of the CEQA Guidelines provides additional direction on mitigation monitoring or reporting). This Mitigation Monitoring Program (MMP) has been prepared in compliance with the requirements of CEQA, specifically Public Resources Code Section 21081.6, and Section 15097 of the CEQA Guidelines. The City of Los Angeles (City) is the Lead Agency for Olympic Tower Project.

An Environmental Impact Report (EIR) has been prepared to address the potential environmental impacts of the Project. Where appropriate, the EIR applied mitigation measures needed to avoid or reduce potentially significant environmental impacts. In addition, Project Design Features (PDFs) that would reduce impacts of the Project on the environment were identified. This Mitigation Monitoring Program (MMP) is designed to monitor implementation of the mitigation measures and PDFs identified in the EIR.

The MMP is subject to review and approval by the City, as the Lead Agency, as part of the approval process of the Project and adoption of Project conditions. The required mitigation measures and other PDFs are listed below and categorized by impact area, as identified in the EIR.

2. ORGANIZATION

As shown on the following pages, each identified mitigation measure and PDF for the Project is listed and categorized by environmental issue area, with accompanying discussion of the following:

Enforcement Agency – the agency with the power to enforce the mitigation measure and/or PDF.

Monitoring Agency – the agency to which reports involving feasibility, compliance, implementation and development are made, or who physically monitors the Project for compliance with mitigation measures and/or PDFs.

Monitoring Phase – the phase of the Project during which the mitigation measure and/or PDF shall be monitored. Examples include the following general categories:

- Pre-Construction, including the design phase
- Construction

- Pre-Operation
- Operation (Post-construction)

Monitoring Frequency – the frequency of which the mitigation measure and/or PDF shall be monitored.

Action Indicating Compliance – the action of which the Enforcement or Monitoring Agency indicates that compliance with the required mitigation measure and/or PDF has been implemented.

The Project Applicant shall be responsible for implementing all mitigation measures and/or PDFs, unless otherwise noted and shall be obligated to provide documentation concerning implementation of the listed mitigation measures and/or PDFs to the appropriate monitoring agency and the appropriate enforcement agency. All departments listed in the MMP are within the City, unless otherwise noted. It is noted that while certain agencies outside of the City are listed as the monitoring/enforcement agencies for individual mitigation measures and/or PDFs listed in this MMP, the City, as Lead Agency for the Project, is responsible for overseeing and enforcing implementation of the MMP as a whole.

3. ADMINISTRATIVE PROCEDURES AND ENFORCEMENT

This MMP shall be enforced throughout all phases of the Project. The Project Applicant shall be responsible for implementing each mitigation measure and/or PDF and shall be obligated to provide certification, as identified below, to the appropriate monitoring agency and the appropriate enforcement agency that each mitigation measure and/or PDF has been implemented. The Project Applicant shall maintain records demonstrating compliance with each mitigation measure and/or PDF. Such records shall be made available to the City upon request.

Further, specifically during the construction phase and prior to the issuance of building permits, the Applicant shall retain an independent Construction Monitor (either via the City or through a third-party consultant), approved by the Department of City Planning, who shall be responsible for monitoring implementation of mitigation measures and/or PDFs during construction activities consistent with the monitoring phase and frequency set forth in this MMP.

The Construction Monitor shall also prepare documentation of the Project Applicant's compliance with the mitigation measures and/or PDFs during construction every 90 days in a form satisfactory to the Department of City Planning. The documentation must be signed by the Project Applicant and Construction Monitor and be included as part of the Project Applicant's Annual Compliance Report. The Construction Monitor shall be obligated to promptly notify the Project Applicant of any non-compliance with the mitigation measures and/or PDFs. If the Project Applicant does not correct the non-compliance within two days from the time of notification, the Construction Monitor

shall report such non-compliance to the Enforcement Agency. Any continued non-compliance shall be appropriately addressed by the Enforcement Agency.

4. PROGRAM MODIFICATION

After review and approval of the final MMP by the Lead Agency, minor changes and modifications to the MMP are permitted, but can only be made subject to City approval. The Lead Agency, in conjunction with any appropriate agencies or departments, will determine the adequacy of any proposed change or modification. This flexibility is necessary in light of the nature of the MMP and the need to protect the environment. No changes will be permitted unless the MMP continues to satisfy the requirements of CEQA, as determined by the Lead Agency.

The Project shall be in substantial conformance with the mitigation measures and/or PDFs contained in this MMP. The enforcing departments or agencies may determine substantial conformance with the mitigation measures and/or PDFs in the MMP in their reasonable discretion. If the department or agency cannot find substantial conformance, a mitigation measure and/or PDF may be modified or deleted, if the enforcing department or agency, or the decision maker for a subsequent discretionary project related approval, finds that the modification or deletion complies with CEQA, including CEQA Guidelines Sections 15162 and 15164, including by preparing an addendum or subsequent environmental clearance, if necessary, to analyze the impacts from the modification to or deletion of mitigation measures and/or PDFs. Any addendum or subsequent CEQA clearance that may be required in connection with the modification or deletion shall explain why the mitigation measure and/or PDF is no longer needed, not feasible, or the other basis for modifying or deleting the mitigation measure and or PDF. Under this process, the modification or deletion of a mitigation measure and/or PDF shall not in and of itself require a modification to any Project discretionary approval unless the Director of Planning also finds that the change to the mitigation measures results in a substantial change to the Project or the non-environmental conditions of approval.

5. MITIGATION MEASURES AND PDFS

Air Quality

MM-C-1: All off-road construction equipment greater than 50 hp shall be required to meet U.S. EPA Tier 4 emission standards to reduce NO_x, PM₁₀, and PM_{2.5} emissions at the Project Site. In addition, all construction equipment shall be outfitted with Best Available Control Technology (BACT) devices certified by the California Air Resources Board (CARB). Any emissions control device used by the contractor shall achieve emissions reductions that are no less than what could be achieved by a Level 3 diesel emissions control strategy for a similarly sized engine as defined by CARB regulations. At the time of mobilization of each applicable unit of equipment, a copy of each unit's certified tier specification, BACT

documentation, and CARB or the South Coast Air Quality Management District (SCAQMD) operating permit shall be provided.

During plan check, the Project Applicant shall make available to the lead agency and SCAQMD a comprehensive inventory of all off-road construction equipment, equal to or greater than 50 horsepower that shall be used during any portion of demolition/excavation activities and concrete pour days for the mat foundation for the Project. The inventory shall include the horsepower rating, engine production year, and certification of the specified Tier standard. A copy of each unit's certified tier specification, Best Available Control Technology documentation, and CARB or SCAQMD operating permit shall be available on-site at the time of mobilization of each applicable unit of equipment to allow the Construction Monitor to compare the on-site equipment with the inventory and certified Tier specification and operating permit. Off road diesel-powered equipment within the construction inventory list described above shall meet Tier 4 CARB/USEPA standards.

Enforcement Agency: City of Los Angeles Department of City Planning

Monitoring Agency: City of Los Angeles Department of City Planning; City of Los Angeles Department of Building and Safety

Monitoring Phase: Pre-Construction; Construction

Monitoring Frequency: Once at Project plan check; Periodic field inspection

Action Indicating Compliance: Field inspection sign-off

MM-C-2: The Project Applicant shall use of 2010 or newer diesel haul trucks (e.g., material delivery trucks and soil import/export), and if the Lead Agency determines that 2010 model year or newer diesel trucks cannot be obtained, the Lead Agency shall require trucks that meet U.S. EPA 2007 model year NO_x emissions requirements.

Enforcement Agency: City of Los Angeles Department of Building and Safety

Monitoring Agency: City of Los Angeles Department of Building and Safety

Monitoring Phase: Construction

Monitoring Frequency: Periodic field inspection

Action Indicating Compliance: Field inspection sign-off

Cultural Resources

MM-D-1: Retain a Qualified Archaeologist. The Project Applicant shall retain a qualified archaeologist, defined as an archaeologist who meets the Secretary of the Interior's Standards for professional archaeology, during the initial excavation phase to carry out all mitigation measures related to archaeological resources.

Enforcement Agency: City of Los Angeles Department of Building and Safety

Monitoring Agency: City of Los Angeles Department of Building and Safety

Monitoring Phase: Construction

Monitoring Frequency: Once prior to issuance of Building Permit

Action Indicating Compliance: Compliance report prepared by qualified archaeologist

MM-D-2: Prepare a Monitoring and Mitigation Plan. Before excavation, an Archaeological Resources Monitoring and Mitigation Plan (Monitoring Plan) shall be prepared. The Monitoring Plan shall include, but not be limited to, monitoring protocol for excavation, a construction worker training program, and discovery and processing protocol for inadvertent discoveries of archaeological resources. The Monitoring Plan should identify areas with moderate to high sensitivity determined for cultural resources that require monitoring and detail a protocol for determining circumstances in which additional or reduced levels of monitoring (e.g., spot-checking) may be appropriate. Specifically, the Monitoring Plan shall include a framework for assessing the geo-archaeological setting to determine whether sediments capable of preserving archaeological remains are present, and the depth at which these sediments would no longer be capable of containing archaeological material.

Enforcement Agency: City of Los Angeles Department of Building and Safety

Monitoring Agency: City of Los Angeles Department of Building and Safety

Monitoring Phase: Pre-construction

Monitoring Frequency: Once prior to issuance of Grading Permit

Action Indicating Compliance: Issuance of Monitoring Plan to City

MM-D-3: Worker Training. Before excavation, at the Project kickoff, the selected qualified archaeologist or their designee will provide a briefing to construction crews to provide information on regulatory requirements for the protection of archaeological resources. As part of this training, construction crews shall be briefed on proper procedures to follow should unanticipated archaeological resources discoveries be made during construction. Workers shall be provided contact information and protocols to follow if inadvertent discoveries are made. In addition, workers shall be shown examples of the types of archaeological resources that would require notification of the Project archaeologist.

Enforcement Agency: City of Los Angeles Department of Building and Safety

Monitoring Agency: City of Los Angeles Department of Building and Safety

Monitoring Phase: Pre-construction

Monitoring Frequency: Once prior to issuance of Grading Permit

Action Indicating Compliance: Compliance report prepared by qualified archaeologist

MM-D-4: Monitoring for Archaeological Resources. Before ground disturbance, an archaeological monitor shall be present during initial excavation activities as stipulated in the Monitoring Plan. The qualified archaeologist may designate an archaeologist to conduct the monitoring under their direction. Specifically, field observations regarding the geo-archaeological setting shall be conducted to determine the presence of undisturbed sediments capable of preserving archaeological remains, and the depth at which these sediments would no longer be capable of containing archaeological material. The duration and timing of the monitoring shall be determined by the qualified archaeologist in consultation with the Department of City Planning and the Project Applicant. At the conclusion of monitoring activities, a technical report shall be prepared documenting the methods and results of all work completed under the Monitoring Plan. The report shall be prepared under the supervision of a qualified archaeologist and submitted to City Planning and the South Central Coastal Information Center.

Enforcement Agency: City of Los Angeles Department of Building and Safety

Monitoring Agency: City of Los Angeles Department of Building and Safety

Monitoring Phase: Pre-construction/Grading and Excavation Phase

Monitoring Frequency: Once prior to issuance of Building Permit

Action Indicating Compliance: Compliance report prepared by qualified archaeologist

Greenhouse Gas Emissions

PDF-GHG-1: The Project shall include rooftop photovoltaic panels, calculated to provide power to common and amenity areas (refer to Figure III-4 and Figure III-35 in Section III [Project Description]).

Enforcement Agency: City of Los Angeles Department of Building and Safety

Monitoring Agency: City of Los Angeles Department of Building and Safety

Monitoring Phase: Construction

Monitoring Frequency: Once prior to issuance of Certificate of Occupancy

Action Indicating Compliance: Issuance of Certificate of Occupancy

PDF-GHG-2: The Project shall include façade photovoltaic panels contained within the glass panels to provide power to the building exterior lighting and LED lighting (refer to Figure III-32 and Figure III-33 in Section III [Project Description]).

Enforcement Agency: City of Los Angeles Department of Building and Safety

Monitoring Agency: City of Los Angeles Department of Building and Safety

Monitoring Phase: Construction

Monitoring Frequency: Once prior to issuance of Certificate of Occupancy

Action Indicating Compliance: Issuance of Certificate of Occupancy

Hazards and Hazardous Materials

MM-G-1: Prior to issuance of a grading permit, the Project Applicant shall prepare a Soil Management Plan (SMP) for the Project in accordance with all applicable requirements of the Los Angeles Fire Department, the Los Angeles Regional Water Quality Control Board, and the Department of Toxic Substances Control. The SMP shall be approved by the Department of Building and Safety, Grading Division. The SMP shall set forth procedures to be followed during the Project's excavation and development phases to properly manage the soil and minimize risks to workers and the public during construction in accordance with any requirements set forth by the Los Angeles Fire Department, the Los Angeles Regional Water Quality Control Board, and/or the Department of Toxic Substances Control. The SMP shall address the delineation of the vertical and lateral extent of residual gasoline-related constituent impacts in Project site soil. Soil management procedures shall be described so that hazardous soil can be separated from non-hazardous soil during excavation tasks. The SMP shall describe the transport and disposal of the soil at an appropriate waste management facility(ies).

Enforcement Agency: City of Los Angeles Department of Public Works; Los Angeles Fire Department

Monitoring Agency: City of Los Angeles Department of Public Works

Monitoring Phase: Pre-Construction/Construction

Monitoring Frequency: Periodic field inspection

Action Indicating Compliance: Field inspection sign off

Noise

MM-I-1: All diesel-powered construction vehicles shall be equipped with exhaust mufflers or other suitable noise reduction devices capable of achieving a sound attenuation of at least 3 dBA. Should they be required, generators would be solar-powered.

Enforcement Agency: City of Los Angeles Department of City Planning

Monitoring Agency: City of Los Angeles Department of Building and Safety

Monitoring Phase: Construction

Monitoring Frequency: Periodic field inspection

Action Indicating Compliance: Field inspection sign off

MM-I-2: Temporary sound barriers capable of achieving a sound attenuation of at least 5 dBA shall be erected along the Project's boundaries.

Enforcement Agency: City of Los Angeles Department of City Planning

Monitoring Agency: City of Los Angeles Department of Building and Safety

Monitoring Phase: Pre-construction; construction

Monitoring Frequency: Periodic field inspection

Action Indicating Compliance: Field inspection sign off

MM-I-3: Construction activities that produce vibration, such as demolition, excavation, and earthmoving, shall be sequenced so that vibration sources within 10 feet of Hotel Figueroa do not operate simultaneously.

Enforcement Agency: City of Los Angeles Department of City Planning

Monitoring Agency: City of Los Angeles Department of Building and Safety

Monitoring Phase: Construction

Monitoring Frequency: Periodic field inspection

Action Indicating Compliance: Field inspection sign off

MM-I-4: No pile driving shall occur as part of Project construction.

Enforcement Agency: City of Los Angeles Department of City Planning

Monitoring Agency: City of Los Angeles Department of Building and Safety

Monitoring Phase: Construction

Monitoring Frequency: Periodic field inspection

Action Indicating Compliance: Field inspection sign off

MM-I-5: Pre-construction surveys shall be performed to document the conditions of Hotel Figueroa. A structural monitoring program shall be implemented and recorded during part or all of the Project's construction phase. The performance standards of the structure-monitoring plan shall include the following:

- Documentation, consisting of video and/or photographic documentation of accessible and visible areas on the exterior of the building.
- A registered civil engineer or certified engineering geologist shall develop recommendations for a structure-monitoring program, including a timeline for monitoring.
- The structure-monitoring program shall survey for vertical and horizontal movement, as well as vibration thresholds (0.25 PPV in/sec) established specifically for the Project's construction activities and proximity to the Hotel Figueroa. If the thresholds are met or exceeded, or if noticeable structural damage becomes evident to the Project contractor, work shall stop in the area of the affected building until measures have been taken to prevent construction-related damage to the structure.
- The structure-monitoring program shall be submitted to the Department of Building and Safety for review and approval and received into the case file for the associated discretionary action permitting the Project prior to initiating any construction activities.

Enforcement Agency: City of Los Angeles Department of City Planning

Monitoring Agency: City of Los Angeles Department of Building and Safety

Monitoring Phase: Pre-construction

Monitoring Frequency: Once prior to issuance of Grading Permit

Action Indicating Compliance: Issuance of structure-monitoring plan to City

Transportation/Traffic

MM-L-1: The Project Applicant shall prepare and provide to LADOT a preliminary Transportation Demand Management (TDM) Program to the satisfaction of LADOT and in accordance with the City's Trip Reduction Ordinance to reduce the Project's traffic generation. The final TDM Program shall be approved by LADOT prior to issuance of any Certificate of Occupancy. The preliminary TDM Program shall include, at a minimum, measures consistent with the City's Trip Reduction Ordinance. LADOT shall determine and approve the specific contents of the TDM Program and traffic-reduction strategies, which could include the following, as examples:

- *On-Site Employee Transportation Coordinator.* An on-site Employee Transportation Coordinator (ETC) could be designated for the Project. The ETC would manage all aspects of an enhanced TDM program and also would participate in City-sponsored workshops and information roundtables. The ETC would establish a Transportation Information Center and Transportation Fairs. The Transportation Information Center would provide on-site information at its buildings for employees and visitors about local public transit services (including bus lines, rail lines and connections, rideshare programs and shuttles), and bicycle facilities (including routes, rental and sales locations, on-site bicycle racks and showers). Walking and biking maps also would be provided for employees, visitors and residents, which would include but not be limited to information about convenient local services and restaurants within walking distance of the project. Such transportation information may be provided through a computer terminal with access to the Internet, as well as through the office of the ETC located at the Project site. Transportation information should be maintained at the administrative offices of the buildings, or by directing inquiries to the building's web site as a portal.
- *TDM Website Information.* Transportation information should be provided in a highly visible and accessible location on the building's web site, including links to local transit providers, area walking, bicycling maps, etc., to inform employees, visitors and residents of available alternative transportation modes to access the project, other amenities in the area and travel opportunities in the area. The website also should highlight the environmental benefits of utilization of alternative transportation modes.
- *TDM Promotional Material.* Provide and exhibit in public places information materials on options for alternative transportation modes and opportunities. In

addition, transit fare media and day/month passes should be made available to employees and visitors during typical business hours.

- *Transit Welcome Package.* All new employees could be provided with a Transit Welcome Package (TWP) in addition to holding Transportation Fair on an annual basis. The TWP at a minimum could include information regarding employer's arrangements for free or discounted use of the transit system, area bus/rail transit route and connections/transfers information, bicycle facilities (including routes, rental and sales locations, on-site bicycle racks, walking and biking maps), and convenient local services and restaurants within walking distance of the Project site.
- *Carpool Program for Employees.* Provide preferential parking within the parking garages for employees who commute to work in registered carpools. An employee who drives to work with at least one other employee to the site may register as a carpool entitled to preferential parking within the meaning of this provision.
- *Public Transit Stop Enhancements.* Working in cooperation with the City and other transit agencies to improve existing bus stops with enhanced shelters and transit information within the immediate vicinity of the buildings. Enhancements could include enhanced weather/sun protection, lighting, benches, and trash receptacles. These improvements would be intended to make riding the bus a safer and more attractive alternative.
- *Convenient Parking/Amenities for Bicycle Riders.* Provide locations at the Project site for convenient parking for bicycle commuters for working employees and visitors. The bicycle parking should be located within the buildings such that long-term and short-term parkers could be accommodated. Bicycle parking may mean bicycle racks, a locked cage, or other similar parking area. Provide shower facilities for employees who commute to work via bicycle.
- *Local Hiring Program.* To the extent feasible, when hiring, conduct outreach to residents who live within Downtown Los Angeles based on satisfaction of other requirements of the available positions.
- *Flexible/Alternative Work Schedules.* Encourage tenants in the building to offer flexible or alternative work schedules, as well as the opportunity to telecommute if feasible.

- *Parking Cash-Out Program.* Require in all leases it executes as landlord for space within the project that tenants offer a parking cash-out program. Parking cash-out program means an employer-funded program under which an employer offers in-lieu of any parking subsidy, a transit subsidy or cash allowance (for use of alternative modes such as walking and bicycling) of equal or greater value.
- *Unbundling and Lease of Parking Spaces for the Residential Land Use.* Offer options for buyers of the residential condominium dwelling units to purchase parking separately (i.e., unbundle parking from the unit price).
- *Participation in a Transportation Management Organization (TMO),* if one is established and the Project Site included. Project representatives would attend organization meetings for the TMO, provide parking and travel demand data to the TMO, pay any established dues to the TMO, and make available information to Project tenants relative to the services provided by the TMO.
- *Record a Covenant and Agreement* to ensure that the TDM Program shall be maintained.

The following improvements shall be part of the TDM Program:

- Contribution to the Los Angeles Bicycle Plan – Prior to the issuance of any certificates of occupancy, the Project Applicant shall contribute a one-time fixed-fee of \$100,000 to be deposited into the City's Bicycle Plan Trust Fund to implement bicycle improvements within the Project Site area.
- The Project Applicant shall support existing and/or future efforts by LADOT for Mobility Hubs by providing amenities such as bicycle parking, rentals, shared vehicle rentals, transit information, etc. at the Project Site (subject to design feasibility).

Transportation Systems Management (TSM) Improvements

Some of the signalized intersections within the Project Site study area require an upgrade to the traffic signal equipment and hardware. Some of the traffic signals in the study area currently operate using a Type 170 traffic signal controller. Newer controllers (e.g., Type 2070) provide for enhanced and real-time operation of the traffic signal timing. Also, when supplemented by additional roadway system loops and closed-circuit television (CCTV) cameras at key locations, LADOT can identify the causes of delay and implement instant signal timing remedies to improve the traffic flow of vehicles and buses. These traffic signal upgrades provide a system-

wide benefit by reducing delays experienced by motorists. To enhance the traffic signal system in the area and improve the network capacity for real-time video monitoring of intersection, corridor, transit, and pedestrian operations by reducing delays experienced by motorists at study intersections, the following TSM improvements shall be implemented by the Project Applicant:

- Install a new CCTV at Figueroa Street and Venice Boulevard, the cost of which is approximately \$40,000,
- Upgrade the fiber optic cable from 12SM to 48SM on Figueroa Street between Venice and Olympic Boulevards, the cost of which is approximately \$40,000.

The Project Applicant shall be responsible for the cost and implementation of any traffic signal equipment modifications and bus stop relocations associated with the proposed transportation improvements described above. All improvements and associated traffic signal work within the City must be guaranteed through Bureau of Engineering's (BOE) B-Permit process, prior to the issuance of any building permits and completed prior to the issuance of any certificates of occupancy. Temporary certificates of occupancy may be granted in the event of any delay through no fault of the Project Applicant, provided that, in each case, the Project Applicant has demonstrated reasonable efforts and due diligence to the satisfaction of LADOT. Prior to setting the bond amount, BOE shall require that the developer's engineer or contractor email LADOT's B-Permit Coordinator at ladot.planprocessing@lacity.org to arrange a predesign meeting to finalize the proposed design needed for the project. If a proposed transportation improvement does not receive the required approval, a substitute may be provided subject to the approval of LADOT upon demonstration that the substitute is environmentally equivalent or superior to the original.

Enforcement Agency: City of Los Angeles Department of Transportation

Monitoring Agency: City of Los Angeles Department of Transportation

Monitoring Phase: Prior to issuance of Building Permit; pre-occupancy

Monitoring Frequency: Once prior to issuance of Certificate of Occupancy

Action Indicating Compliance: Approval of TDM program from Los Angeles Department of Transportation; issuance of Certificate of Occupancy; submittal of compliance report to City

MM-L-2: Prior to issuance of a demolition permit, in coordination with LADOT and the Department of Building and Safety, the Project Applicant shall prepare a detailed Construction Traffic Management Plan, including street closure information, detour plans, haul routes, and staging plans. The Construction Traffic Management Plan shall outline how construction would be carried out and identify specific actions that would be required to reduce effects on the surrounding community. The Construction Traffic Management Plan shall be based on the nature and timing of specific construction activities and other projects in the vicinity, and shall include the following elements as appropriate:

- Provide for temporary traffic control during all construction activities within public rights-of-way to improve traffic flow on public roadways (e.g., flagmen);
- Schedule of construction activities to reduce the effect on traffic flow on surrounding arterial streets;
- Reroute construction trucks to reduce travel on congested streets to the extent feasible;
- Prohibit construction-related vehicles from parking on surrounding public streets;
- Provide safety precautions for pedestrians and bicyclists through such measures as alternate routing and protection barriers;
- Accommodate all equipment on-site; and
- Obtain the required permits for truck haul routes from the City prior to issuance of any permit for the Project.

Enforcement Agency: City of Los Angeles Department of Building and Safety

Monitoring Agency: City of Los Angeles Department of Transportation; City of Los Angeles Department of Transportation

Monitoring Phase: Prior to issuance of Demolition Permit; construction

Monitoring Frequency: Periodic field inspection

Action Indicating Compliance: Field inspection sign off

Utilities and Service Systems – Water

PDF-WATER-1: Water Conservation Measures

- High Efficiency Toilets with a flush volume of 1.1 gallons per flush or less
- Urinals – Waterless
- Showerheads with a flow rate of 1.5 gallons per minute or less
- ENERGY STAR Certified Residential Clothes Washers – Integrated Water Factor of 3.7 or less, front-loading, and capacity of 2.3 cubic feet
- ENERGY STAR Certified Residential Dishwashers – 3.07 gallons per cycle or less, standard type
- Centralized Domestic Water Heating System with hot water return branches
- Point of Use Water Heaters may be used where conditions warrant
- Individual metering and billing for water use for every residential dwelling unit and commercial unit
- Water-Saving pool filter
- Pool/Spa recirculating filtration equipment
- Pool splash troughs around the perimeter that drain back into the pool
- Install a meter on the pool make-up line so water use can be monitored and leaks can be identified and repaired
- Reuse pool backwash water for irrigation
- Leak Detection System for swimming pools and Jacuzzi
- Micro-Spray
- Hydro-zoning Irrigation – Commercial zoning with plant factor 0.3 and Residential zoning with plant factor 0.4

- Drip/Subsurface Irrigation to Commercial zone (4,251 square feet) and Residential zone (8,474 square feet)
- Primary (On-Site) Waste Water Treatment Systems – Possible uses are public toilets and irrigation. Exact usage information not yet known.

Enforcement Agency: City of Los Angeles Department of Building and Safety

Monitoring Agency: City of Los Angeles Department of Building and Safety

Monitoring Phase: Construction

Monitoring Frequency: Prior to issuance of a Certificate of Occupancy

Action Indicating Compliance: Issuance of a Certificate of Occupancy

ERRATA TO THE ENVIRONMENTAL IMPACT REPORT

FOR THE OLYMPIC TOWER PROJECT

This Errata revises Mitigation Measure L-1 that was included in the Draft Environmental Impact Report (EIR) and the Final EIR for the Olympic Tower Project. Mitigation Measure L-1 calls for preparation and implementation of a Transportation Demand Management (TDM) Plan to the satisfaction of LADOT and in accordance with the City's Trip Reduction Ordinance to reduce the Project's traffic generation, in addition to implementation of traffic signal upgrades. The requirements of Mitigation Measure L-1 are substantially similar to the Transportation Improvement and Mitigation Program included in the Los Angeles Department of Transportation's (LADOT) Traffic Impact Assessment letter, dated June 12, 2017 (refer to item A on page 3).

To ensure consistency between Mitigation Measure L-1 and LADOT's TDM Program and Transportation Systems Management (TSM) Improvements for the Olympic Tower Project, Mitigation Measure L-1 on pages IV.L-91 through IV.L-94 in the Draft EIR and on pages V-11 through V-13 in the Final EIR has been revised as follows to more closely reflect LADOT's language in their Traffic Impact Assessment letter (deleted text shown in ~~strike through~~; new text shown in underline):

L-1: ~~Prior to issuance of a Certificate of Building Permit, the~~The Project Applicant shall prepare and provide to LADOT a preliminary Transportation Demand Management (TDM) ~~Plan~~Program to the satisfaction of LADOT and in accordance with the City's Trip Reduction Ordinance to reduce the Project's traffic generation. The final TDM Program shall be required approved by LADOT prior to issuance of any Certificate of Occupancy. ~~This~~The preliminary ~~TDM plan~~Program ~~also shall include, at a minimum, measures consistent with the City's Trip Reduction Ordinance. The final TDM Plan shall be required prior to issuance of any Certificate of Occupancy.~~ LADOT shall determine and approve the specific contents of the TDM ~~Plan~~Program and traffic-reduction strategies, which could include the following, as examples:

- *On-Site Employee Transportation Coordinator.* An on-site Employee Transportation Coordinator (ETC) could be designated for the Project. The ETC would manage all aspects of an enhanced TDM program and also would participate in City-sponsored workshops and information roundtables. The ETC would establish a Transportation Information Center and Transportation Fairs. The Transportation Information Center would provide on-site information at its buildings for employees and visitors about local public transit services (including bus lines, rail lines and connections, rideshare programs and shuttles), and bicycle facilities (including routes, rental and sales locations,

on-site bicycle racks and showers). Walking and biking maps also would be provided for employees, visitors and residents, which would include but not be limited to information about convenient local services and restaurants within walking distance of the project. Such transportation information may be provided through a computer terminal with access to the Internet, as well as through the office of the ETC located at the Project site. Transportation information should be maintained at the administrative offices of the buildings, or by directing inquiries to the building's web site as a portal.

- *TDM Website Information.* Transportation information should be provided in a highly visible and accessible location on the building's web site, including links to local transit providers, area walking, bicycling maps, etc., to inform employees, visitors and residents of available alternative transportation modes to access the project, other amenities in the area and travel opportunities in the area. The website also should highlight the environmental benefits of utilization of alternative transportation modes.
- *TDM Promotional Material.* Provide and exhibit in public places information materials on options for alternative transportation modes and opportunities. In addition, transit fare media and day/month passes should be made available to employees and visitors during typical business hours.
- *Transit Welcome Package.* All new employees could be provided with a Transit Welcome Package (TWP) in addition to holding Transportation Fair on an annual basis. The TWP at a minimum could include information regarding employer's arrangements for free or discounted use of the transit system, area bus/rail transit route and connections/transfers information, bicycle facilities (including routes, rental and sales locations, on-site bicycle racks, walking and biking maps), and convenient local services and restaurants within walking distance of the Project site.
- *Carpool Program for Employees.* Provide preferential parking within the parking garages for employees who commute to work in registered carpools. An employee who drives to work with at least one other employee to the site may register as a carpool entitled to preferential parking within the meaning of this provision.
- *Public Transit Stop Enhancements.* Working in cooperation with the City and other transit agencies to improve existing bus stops with enhanced shelters and transit information within the immediate vicinity of the buildings. Enhancements could include enhanced weather/sun protection, lighting,

benches, and trash receptacles. These improvements would be intended to make riding the bus a safer and more attractive alternative.

- *Convenient Parking/Amenities for Bicycle Riders.* Provide locations at the Project site for convenient parking for bicycle commuters for working employees and visitors. The bicycle parking should be located within the buildings such that long-term and short-term parkers could be accommodated. Bicycle parking may mean bicycle racks, a locked cage, or other similar parking area. Provide shower facilities for employees who commute to work via bicycle.
- *Local Hiring Program.* To the extent feasible, when hiring, conduct outreach to residents who live within Downtown Los Angeles based on satisfaction of other requirements of the available positions.
- *Flexible/Alternative Work Schedules.* Encourage tenants in the building to offer flexible or alternative work schedules, as well as the opportunity to telecommute if feasible.
- *Parking Cash-Out Program.* Require in all leases it executes as landlord for space within the project that tenants offer a parking cash-out program. Parking cash-out program means an employer-funded program under which an employer offers in-lieu of any parking subsidy, a transit subsidy or cash allowance (for use of alternative modes such as walking and bicycling) of equal or greater value.
- *Unbundling and Lease of Parking Spaces for the Residential Land Use.* Offer options for buyers of the residential condominium dwelling units to purchase parking separately (i.e., unbundle parking from the unit price).
- *Participation in a Transportation Management Organization (TMO), if one is established and the Project Site included. Project representatives would attend organization meetings for the TMO, provide parking and travel demand data to the TMO, pay any established dues to the TMO, and make available information to Project tenants relative to the services provided by the TMO.*
- *Record a Covenant and Agreement to ensure that the TDM Program shall be maintained.*

The following improvements shall be part of the TDM Program:

- *Contribution to the Los Angeles Bicycle Plan – Prior to the issuance of any certificates of occupancy, the Project Applicant shall contribute a one-time*

fixed-fee of \$100,000 to be deposited into the City's Bicycle Plan Trust Fund to implement bicycle improvements within the Project Site area.

- The Project Applicant shall support existing and/or future efforts by LADOT for Mobility Hubs by providing amenities such as bicycle parking, rentals, shared vehicle rentals, transit information, etc. at the Project Site (subject to design feasibility).

Traffic Signal Upgrades Transportation Systems Management (TSM) Improvements

Some of the signalized intersections within the ~~project~~Project Site study area require an upgrade to the traffic signal equipment and hardware. Some of the traffic signals in the study area currently operate using a Type 170 traffic signal controller. Newer controllers (e.g., Type 2070) provide for enhanced and real-time operation of the traffic signal timing. Also, when supplemented by additional roadway system loops and closed-circuit television (CCTV) cameras at key locations, LADOT can identify the causes of delay and implement instant signal timing remedies to improve the traffic flow of vehicles and buses. These traffic signal upgrades provide a system-wide benefit by reducing delays experienced by motorists. To enhance the traffic signal system in the area and improve the network capacity for real-time video monitoring of intersection, corridor, transit, and pedestrian operations by reducing delays experienced by motorists at study intersections, the following TSM improvements shall be implemented by the Project Applicant:

- Install a new CCTV at Figueroa Street and Venice Boulevard, the cost of which is approximately \$40,000.
- Upgrade the fiber optic cable from 12SM to 48SM on Figueroa Street between Venice and Olympic Boulevards, the cost of which is approximately \$40,000.

The Project Applicant shall be responsible for the cost and implementation of any traffic signal equipment modifications and bus stop relocations associated with the proposed transportation improvements described above. All improvements and associated traffic signal work within the City must be guaranteed through Bureau of Engineering's (BOE) B-Permit process, prior to the issuance of any building permits and completed prior to the issuance of any certificates of occupancy. Temporary certificates of occupancy may be granted in the event of any delay through no fault of the Project Applicant, provided that, in each case, the Project Applicant has demonstrated reasonable efforts and due diligence to the

satisfaction of LADOT. Prior to setting the bond amount, BOE shall require that the developer's engineer or contractor email LADOT's B-Permit Coordinator at ladot.planprocessing@lacity.org to arrange a predesign meeting to finalize the proposed design needed for the project. If a proposed transportation improvement does not receive the required approval, a substitute may be provided subject to the approval of LADOT upon demonstration that the substitute is environmentally equivalent or superior to the original.

CEQA requires recirculation of a Draft EIR only when “significant new information” is added to a Draft EIR after public notice of the availability of the Draft EIR has occurred (refer to California Public Resources Code Section 21092.1 and CEQA Guidelines Section 15088.5), but before the EIR is certified. Section 15088.5 of the CEQA Guidelines specifically states the following:

- *New information added to an EIR is not “significant” unless the EIR is changed in a way that deprives the public of a meaningful opportunity to comment upon a substantial adverse environmental effect of the project or a feasible way to mitigate or avoid such an effect (including a feasible project alternative) that the project’s proponents have declined to implement. “Significant new information” requiring recirculation includes, for example, a disclosure showing that:*
- *A new significant environmental impact would result from the project or from a new mitigation measure proposed to be implemented.*
- *A substantial increase in the severity of an environmental impact would result unless mitigation measures are adopted to reduce the impact to a level of insignificance.*
- *A feasible project alternative or mitigation measure considerably different from others previously analyzed would clearly lessen the significant environmental impacts of the project, but the project’s proponents decline to adopt it.*
- *The draft EIR was so fundamentally and basically inadequate and conclusory in nature that meaningful public review and comment were precluded.*

CEQA Guidelines Section 15088.5 also provides that “[r]ecirculation is not required where the new information added to the EIR merely clarifies or amplifies or makes insignificant modifications in an adequate EIR [...] A decision not to recirculate an EIR must be supported by substantial evidence in the administrative record.”

The information added pursuant to this Errata does not disclose a new significant environmental impact that would result from the Project or from a new mitigation measure or substantial increase in the severity of an environmental impact, nor does the information in the Errata contain significant new information that deprives the public of a meaningful opportunity to comment upon a substantial adverse environmental effect of the Project or a feasible way to mitigate or avoid

such an effect that the Project Applicant has declined to adopt. Additionally, information provided in this Errata does not present a feasible Project alternative or mitigation measure considerably different from others previously analyzed in the EIR. The revisions to Mitigation Measure L-1 include additional traffic improvement measures to reduce the Project's traffic impacts and do not eliminate measures or requirements. The revisions provide consistency between Mitigation Measure L-1 and LADOT requirements.


The City has reviewed the information in this Errata and has determined that the information does not change any of the basic findings or conclusions of the EIR, does not constitute "significant new information" pursuant to CEQA Guidelines Section 15088.5, and does not require recirculation of the EIR.

CITY OF LOS ANGELES
INTER-DEPARTMENTAL CORRESPONDENCE

811 W Olympic Bl
DOT Case No. CEN 15-43386

Date: June 12, 2017

To: Karen Hoo, City Planner
Department of City Planning

From: 
Wes Pringle, Transportation Engineer
Department of Transportation

Subject: **TRANSPORTATION IMPACT ASSESSMENT FOR THE OLYMPIC TOWER MIXED-USE PROJECT LOCATED AT 811 WEST OLYMPIC BOULEVARD (ENV-2015-4558-EIR/CPC-2015-4557-MCUO-CUX-ZV-TDR-SPR/VTT-73966-CN)**

The Department of Transportation (DOT) has reviewed the transportation impact study, dated October 27, 2016, prepared by Linscott, Law & Greenspan, Engineers for the Olympic Tower Project located at 811 West Olympic Boulevard. The project is bordered by the Figueroa Hotel to the north, Olympic Boulevard to the south, Figueroa Street to the east, and Cottage Place to the west. In order to evaluate the effects of the project's traffic on the available transportation infrastructure, the significance of the project's traffic impacts is measured in terms of change to the volume-to-capacity (V/C) ratio between the "future no project" and the "future with project" scenarios. This change in the V/C ratio is compared to DOT's established threshold standards to assess the project-related traffic impacts. Based on DOT's current traffic impact criteria¹, the transportation study included the detailed analysis of 18 signalized intersections and determined that three of these study intersections would be significantly impacted by project-related traffic, assuming the future completion of the MyFigueroa Project. This report summarizes the results of the transportation analysis (see **Attachment 1**), which accounted for other known development projects in evaluating potential cumulative impacts and adequately evaluated the project's traffic impacts on the surrounding community. The transportation analysis identifies the transportation mitigation measures designed to reduce the project's potential traffic impacts although the impacts remain significant and unavoidable.

DISCUSSION AND FINDINGS

A. Project Description

The project proposes to construct a mixed-use development with a 373-room hotel, a 10,801-square-foot hotel conference center, 65,074 square feet of retail space, 374 condominiums, and 33,498 square feet of general office space and to remove the existing structures, which include a car wash, retail space, and restaurants. The development would be 57 stories above six subterranean parking levels with frontage facing Olympic Boulevard. The levels of the development would contain the following:

¹ Per the DOT Traffic Study Policies and Procedures, a significant impact is identified as an increase in the Critical Movement Analysis (CMA) value, due to project-related traffic, of 0.01 or more when the final ("with project") Level of Service (LOS) is LOS E or F; an increase of 0.020 or more when the final LOS is LOS D; or an increase of 0.040 or more when the final LOS is LOS C.

Level	Use
1-3	Retail Space
4-12	A combination of office/conference room space and ramp-accessed parking
13 and 31	Mechanical use
14 and 15	Hotel lobby and associated amenities
16 - 30	Hotel rooms
32 - 47	Residential condominiums
48 - 55	Residential penthouses
56 and 57	Rooftop amenities including the pool

Access to the project site would be provided via Cottage Place, which borders the westerly property frontage. The project is expected to be completed by the end of 2019.

B. Trip Generation

Prior to accounting for the trip reductions from the Transportation Demand Management program discussed below, the project is estimated to generate a net increase of approximately 4,423 daily trips, 336 trips during the a.m. peak hour and 374 trips during the p.m. peak hour. The trip generation estimates, summarized in **Attachment 2**, are based on rates and formulas published by the Institute of Transportation Engineers (ITE) Trip Generation, 9th Edition, 2012. These trip generation rates are typically derived from surveys of similar stand-alone (single) land use projects in suburban areas with little to no transit service. Therefore, DOT's transportation impact study guidelines allow projects to reduce their total trip generation to account for potential transit usage to and from the site and for the internal-trip making opportunities that are afforded by mixed-use projects. Consistent with these guidelines, the estimated trip generation includes trip credits to account for the mixed-use nature of the project and for the expected transit mode share.

C. Traffic Impacts

The transportation impact study presented an analysis for the proposed project and supplemental traffic analyses for four scenarios:

1. Proposed project development assuming full access to/from Cottage Place and Olympic Boulevard;
2. Proposed project development assuming access to/from Cottage Place and Olympic Boulevard intersection is restricted to right-turn ingress and egress turning movements;
3. Proposed project development assuming full access to/from Cottage Place and Olympic Boulevard intersection and completion of the MyFigueroa project;
4. Proposed project development assuming access to/from the Cottage Place and Olympic Boulevard intersection is restricted to right-turn ingress and egress turning movements and completion of the MyFigueroa Project.

The study determined that the project would result in significant traffic impacts during both peak hours at the following intersections before mitigation based on a project build-out year of 2019:

1. Figueroa Street and 9th Street (All scenarios)
2. Figueroa Street and Olympic Boulevard (All scenarios)
3. Figueroa Street and Pico Boulevard (Scenario 3 and 4)

In consideration of the City's Vision Zero initiative and the Mobility Plan 2035, the transportation study proposed a transportation mitigation program focused on reducing project-related trips and promotion of other travel modes. The transportation mitigation program would partially but not fully mitigate the project's significant traffic impacts during the peak commute hours at the above intersections.

D. Freeway Analysis

The traffic study included a freeway impact analysis that was prepared in accordance with the State-mandated Congestion Management Program (CMP) administered by the Los Angeles County Metropolitan Transportation Authority (MTA). According to this analysis, the project would not result in significant traffic impacts on any of the evaluated freeway mainline segments. To comply with the Freeway Analysis Agreement executed between Caltrans and DOT in December 2015, the study also included a screening analysis to determine if additional evaluation of freeway mainline and ramp segments was necessary beyond the CMP requirements. Exceeding one of the four screening criteria would require the applicant to work directly with Caltrans to prepare more detailed freeway analyses. However, the project did not meet or exceed any of the four thresholds defined in the agreement; therefore, no additional freeway analysis was required.

PROJECT REQUIREMENTS

A. Transportation Improvement and Mitigation Program

Consistent with City policies on sustainability and smart growth and with DOT's trip reduction and multi-modal transportation goals, the project's mitigation focuses on developing a trip reduction program and on solutions that promote other modes of travel. The traffic mitigation program includes the following improvements:

1. **Transportation Demand Management (TDM) Program**

A TDM program, which includes design elements and trip reduction strategies, would reduce the project's overall trip generation by discouraging single occupancy vehicle use and by promoting the use of alternative travel modes. Through strategic building design and orientation, this mixed-use project can facilitate access to existing and future transit services, provide a pedestrian-friendly environment, promote non-automobile travel and support the goals of an aggressive trip-reduction program.

A preliminary TDM program shall be prepared and provided for DOT review prior to the issuance of the first building permit for this project and a final TDM program approved by DOT is required prior to the issuance of the first certificate of occupancy for the project. The preliminary plan will include, at a minimum, measures consistent with the City's Trip Reduction Ordinance. As recommended by the transportation study, the TDM program could include, but is not be limited to the following:

- An on-site employee transportation coordinator;
- An on-site Transportation Information Center and Transportation Fairs;
- TDM Web Site Information;
- TDM Promotional Material – Provide and exhibit information materials on options for alternative transportation modes and opportunities;

- Transit Welcome Package – Provide all new employees with a Transit Welcome Package which could include information regarding employer’s arrangements for free or discounted use of the transit system, area bus/rail transit route and connections/transfers information, bicycle facilities, and convenient local services and restaurants within walking distance of the project;
- Carpool program for employees;
- Preferential rideshare parking location;
- Public transit stop enhancements including weather/sun protection, lighting, benches and trash receptacles;
- Convenient parking and facilities for bicycle riders;
- Local hiring program – To the extent feasible, when hiring, conduct outreach to residents who live within Downtown Los Angeles based on satisfaction of other requirements of the available positions;
- Allowance for flexible and alternative work schedules;
- Parking cash-out programs for the project and uses as appropriate;
- Unbundling and lease of parking spaces for residents;
- Participation in a Transportation Management Organization (TMO), if one is established and the project site included. Project representatives would attend organization meetings for the TMO, provide parking and travel demand data to the TMO, pay any established dues to the TMO, and make available information to project tenants relative to the services provided by the TMO;
- Record a Covenant and Agreement to ensure that the TDM program will be maintained.

The following improvements proposed by the project should be part of the TDM program:

- Contribution to the Los Angeles Bicycle Plan – Prior to the issuance of any certificates of occupancy, the project proposes to contribute a one-time fixed-fee of **\$100,000** to be deposited into the City’s Bicycle Plan Trust Fund to implement bicycle improvements within the Project area;
- Support existing and/or future efforts by LADOT for Mobility Hubs by providing amenities such as bicycle parking, rentals, shared vehicle rentals, transit information, etc. at the project site (subject to design feasibility).

2. **Transportation Systems Management (TSM) Improvements**

Some of the signalized intersections within the project study area require an upgrade to the traffic signal equipment and hardware. Many of the traffic signals at these intersections currently operate using newer controllers (Type 2070), which provide for enhanced and real-time operation of the traffic signal timing. When supplemented by additional roadway system loops and closed circuit television (CCTV) cameras, DOT can identify the causes of delay and implement instant signal timing remedies to improve the flow of vehicles and buses. Collectively, these traffic signal upgrades provide a system-wide benefit by reducing delays experienced by motorists at the study intersections. To enhance the traffic signal system in the area and improve the network capacity for real-time video monitoring of intersection, corridor, transit, and pedestrian

operations by reducing delays experienced by motorists at study intersections, the following TSM improvements were identified:

- Install a new CCTV at Figueroa Street and Venice Boulevard, the cost of which is approximately **\$40,000**,
- Upgrade the fiber optic cable from 12SM to 48SM on Figueroa Street between Venice and Olympic Boulevards, the cost of which is approximately **\$40,000**.

B. Voluntary Pedestrian Safety Enhancements

The City of Los Angeles provides various methods for safety enhancement of Pedestrian Crossings throughout the City. As part of the comprehensive response to pedestrian safety, LADOT's Vision Zero section proposes the installation of continental crosswalks, leading pedestrian intervals, and curb extensions within the project area. The approximate total cost to fund of these enhancements is **\$270,000**.

Intersection	Enhancement	Cost
Chick Hearn Court/LA Live Way	Continental Crosswalks	\$10,000
Olympic Boulevard/Georgia Street	Continental Crosswalks	\$10,000
Olympic Boulevard/Francisco Street	Continental Crosswalks	\$10,000
Olympic Boulevard/Flower Street	Leading Pedestrian Interval	\$10,000
	Continental Crosswalks	\$10,000
Olympic Boulevard/Hope Street	Leading Pedestrian Interval	\$10,000
	Continental Crosswalks	\$10,000
Olympic Boulevard/Grand Avenue	Leading Pedestrian Interval	\$10,000
	Median Island West Leg	\$50,000
9th Street/Flower Street	Leading Pedestrian Interval	\$10,000
	Continental Crosswalks	\$10,000
9th Street/Hope Street	Leading Pedestrian Interval	\$10,000
	Continental Crosswalks	\$10,000
9th Street/Grand Avenue	Leading Pedestrian Interval	\$10,000
	Continental Crosswalks	\$10,000
8th Street/Flower Street	Leading Pedestrian Interval	\$10,000
	Continental Crosswalks	\$10,000
6th Street/Figueroa Street	Leading Pedestrian Interval	\$10,000
5th Street/Figueroa Street	Westbound Dual Right-Turn Protected Phasing	\$50,000
Total Cost		\$270,000

C. Implementation of Improvements and Enhancements

The applicant shall be responsible for the cost and implementation of any traffic signal equipment modifications and bus stop relocations associated with the proposed transportation improvements and enhancements described above. All improvements, enhancements, and associated traffic signal work within the City of Los Angeles must be **guaranteed** through Bureau of Engineering's (BOE) B-Permit process, prior to the issuance of any building permits and **completed** prior to the issuance of any certificates of occupancy. Temporary certificates of occupancy may be granted in the event of any delay through no fault of the applicant, provided that, in each case, the applicant has demonstrated reasonable efforts and due diligence to the satisfaction of DOT. Prior to setting the bond amount, BOE shall require that the developer's engineer or contractor

email DOT's B-Permit Coordinator at ladot.planprocessing@lacity.org to arrange a pre-design meeting to finalize the proposed design needed for the project. If a proposed transportation improvement or enhancement does not receive the required approval, a substitute may be provided subject to the approval of DOT upon demonstration that the substitute is environmentally equivalent or superior to the original.

D. Construction Impacts

DOT recommends that a construction work site traffic control plan be submitted to DOT for review and approval prior to the start of any construction work. The plan should show the location of any roadway or sidewalk closures, traffic detours, haul routes, hours of operation, protective devices, warning signs and access to abutting properties. DOT also recommends that all construction-related traffic be restricted to off-peak hours.

E. Highway Dedication and Street Widening Requirements

On September 7, 2016, the City Council adopted the Mobility Plan 2035 which is the new Mobility Element of the General Plan. A key feature of the updated plan is to revise street standards in an effort to provide a more enhanced balance between traffic flow and other important street functions including transit routes and stops, pedestrian environments, bicycle routes, building design and site access, etc. The applicant should check with BOE's Land Development Group to determine the specific highway dedication, street widening and/or sidewalk requirements for this project. Per the new Mobility Element, **Olympic Boulevard** is designated as a Boulevard II which would require a 40-foot half-width roadway within a 55-foot half-width right-of-way and **Figueroa Street** is designated as a Modified Avenue I which would require 36.5-foot half-width roadway within a 50-foot half-width right-of-way. **Cottage Place** is classified as an alley which would require a 10-foot half-width right-of-way.

F. Parking Requirement

The project would provide the minimum code-required parking spaces for vehicles and bicycles. The developer should check with the Department of Building and Safety on the number of parking spaces needed.

G. Project Access and Circulation

Access to the project would be provided along Cottage Place by three driveways: one for residential land use, one for commercial use via porte cochere, and one for loading activities. Conceptually, the proposed site plan illustrated in **Attachment 3** is acceptable to DOT. The review of this study does not constitute approval of the driveway dimensions, access and circulation scheme, and loading/unloading area for the project. Any changes to the project's site access, circulation scheme, or loading/unloading area after issuance of this report would require separate review and approval and should be coordinated with DOT's Citywide Planning Coordination Section at 201 N. Figueroa Street, 5th Floor, Room 550, at (213) 482-7024. The applicant should contact DOT for driveway width and internal circulation requirements prior to the commencement of building or parking layout design efforts so that such traffic flow considerations are designed and incorporated early into the building and parking layout plans. All driveways should be Case 2 driveways and 30 feet for two-way operations. All delivery truck loading and unloading should take place on site with no vehicles having to back into the project via any of the project driveways.

H. Development Review Fees

An ordinance adding Section 19.15 to the Los Angeles Municipal Code relative to application fees paid to DOT for permit issuance activities was adopted by the Los Angeles City Council in 2009 and updated in 2014. This ordinance identifies specific fees for traffic study review, condition clearance, and permit issuance. The applicant shall comply with any applicable fees per this ordinance.

If you have any questions, please contact Eileen Hunt of my staff at (213) 972-8481.

Attachments

P:\Letters\2017\CEN15-43386_811 Olympic Tower_mu_ltr.doc

c: Kevin Ocubillo, Council District No. 14
Carl Mills, BOE Development Services
Mehrdad Moshksar, Central District Office, DOT
Taimour Tanavoli, Case Management Office, DOT
Clare M. Look-Jaeger, Linscott, Law & Greenspan, Engineers

Table 9-1
SUMMARY OF VOLUME TO CAPACITY RATIOS AND LEVELS OF SERVICE
WEEKDAY AM AND PM PEAK HOURS

NO.	INTERSECTION	PEAK HOUR	[1]		[2]				[3]		[4]			
			YEAR 2015 EXISTING V/C	LOS	YEAR 2015 EXISTING WITH PROJECT V/C	LOS	CHANGE V/C [2]-(1)	SIGNIF. IMPACT	YEAR 2019 FUTURE PRE-PROJECT V/C	LOS	YEAR 2019 FUTURE WITH PROJECT V/C	LOS	CHANGE V/C [(4)-(3)]	SIGNIF. IMPACT
1	Blaine Street/ Olympic Boulevard	AM PM	0.592 0.512	A A	0.608 0.530	B A	0.016 0.018	NO NO	0.763 0.684	C B	0.779 0.702	C C	0.016 0.018	NO NO
2	Blaine Street - SR-110 SB On-Ramp/ 11th Street	AM PM	0.395 0.600	A A	0.400 0.607	A B	0.005 0.007	NO NO	0.454 0.669	A B	0.460 0.675	A B	0.006 0.006	NO NO
3	LA Live Way - SR-110 NB On-Ramp/ 11th Street-Chick Hearn Court	AM PM	0.203 0.222	A A	0.207 0.227	A A	0.004 0.005	NO NO	0.261 0.311	A A	0.265 0.316	A A	0.004 0.005	NO NO
4	Georgia Street/ Olympic Boulevard	AM PM	0.353 0.406	A A	0.366 0.419	A A	0.013 0.013	NO NO	0.547 0.631	A B	0.560 0.645	A B	0.013 0.014	NO NO
5	Francisco Street/ Olympic Boulevard	AM PM	0.272 0.369	A A	0.280 0.383	A A	0.008 0.014	NO NO	0.361 0.488	A A	0.370 0.501	A A	0.009 0.013	NO NO
6	Figueroa Street/ [2], [3] 8th Street	AM PM	0.486 0.468	C D	0.491 0.473	C D	0.005 0.005	NO NO	0.664 0.629	E F	0.669 0.635	E F	0.005 0.006	NO NO
7	Figueroa Street/ [2], [3] 9th Street - James M. Wood Boulevard	AM PM	0.708 0.528	C C	0.721 0.542	C C	0.013 0.014	NO NO	0.924 0.812	E F	0.937 0.826	E F	0.013 0.014	YES YES
8	Figueroa Street/ [2] Olympic Boulevard	AM PM	0.753 0.713	C C	0.773 0.736	C C	0.020 0.023	NO NO	0.986 0.997	E E	1.000 1.020	E F	0.014 0.023	YES YES
9	Figueroa Street/ Pico Boulevard	AM PM	0.603 0.629	B B	0.619 0.643	B B	0.016 0.014	NO NO	0.821 0.883	D D	0.838 0.896	D D	0.017 0.013	NO NO
10	Flower Street/ 8th Street	AM PM	0.211 0.439	A A	0.212 0.445	A A	0.001 0.006	NO NO	0.323 0.625	A B	0.325 0.631	A B	0.002 0.006	NO NO
11	Flower Street/ 9th Street	AM PM	0.249 0.470	A A	0.257 0.483	A A	0.008 0.013	NO NO	0.382 0.731	A C	0.393 0.744	A C	0.011 0.013	NO NO
12	Flower Street/ Olympic Boulevard	AM PM	0.428 0.559	A A	0.463 0.572	A A	0.035 0.013	NO NO	0.613 0.827	B D	0.647 0.840	B D	0.034 0.013	NO NO
13	Francisco Street/ SR-110 NB Off-Ramp - James M. Wood Boulevard	AM PM	0.223 0.221	A A	0.226 0.225	A A	0.003 0.004	NO NO	0.421 0.528	A A	0.425 0.532	A A	0.004 0.004	NO NO
14	Blaine Street/ Connecticut Street - SR-110 SB Off-Ramp	AM PM	0.325 0.226	A A	0.337 0.233	A A	0.012 0.007	NO NO	0.467 0.293	A A	0.479 0.299	A A	0.012 0.006	NO NO
15	Georgia Street - SR-110 NB On-Ramp/ 9th Street - SR-110 SB Off-Ramp- James M. Wood Boulevard	AM PM	0.409 0.357	A A	0.413 0.362	A A	0.004 0.005	NO NO	0.527 0.495	A A	0.531 0.501	A A	0.004 0.006	NO NO
16	Bixel Street - SR-110 SB On-Ramp/ 8th Street	AM PM	0.537 0.587	A A	0.537 0.587	A A	0.000 0.000	NO NO	0.617 0.667	B B	0.617 0.667	B B	0.000 0.000	NO NO

Table 9-1 (Continued)
SUMMARY OF VOLUME TO CAPACITY RATIOS AND LEVELS OF SERVICE
WEEKDAY AM AND PM PEAK HOURS

NO.	INTERSECTION	PEAK HOUR	[1]		[2]				[3]		[4]					
			YEAR 2015 EXISTING		YEAR 2015 EXISTING WITH PROJECT		CHANGE V/C		SIGNIF. IMPACT	YEAR 2019 FUTURE PRE-PROJECT		YEAR 2019 FUTURE WITH PROJECT		CHANGE V/C		SIGNIF. IMPACT
			V/C	LOS	V/C	LOS	[(2)-(1)]	V/C		LOS	V/C	LOS	[(4)-(3)]			
17	Figueroa Street/ 6th Street - SR-110 NB and SB Off-Ramps [2]	AM	0.538	A	0.542	A	0.004	NO	0.633	B	0.637	B	0.004	NO		
		PM	0.490	A	0.494	A	0.004	NO	0.665	B	0.670	B	0.005	NO		
18	Figueroa Street/ 5th Street - SR-110 NB and SB On-Ramps [2]	AM	0.448	A	0.454	A	0.006	NO	0.554	A	0.561	A	0.007	NO		
		PM	0.673	B	0.680	B	0.007	NO	0.840	D	0.848	D	0.008	NO		

[1] According to LADOT's "Traffic Study Policies and Procedures," August 2014, a transportation impact on an intersection shall be deemed significant in accordance with the following table:

Final v/c	LOS	Project Related Increase in v/c
> 0.700 - 0.800	C	equal to or greater than 0.040
> 0.800 - 0.900	D	equal to or greater than 0.020
> 0.900	E,F	equal to or greater than 0.010

[2] Based on field observations and existing vehicle queuing, the intersection calculations and v/c ratios reflect a reduced intersection capacity of 1,200 vehicles per hour.

[3] LOS calculated as LOS A or B. LOS adjusted based on observations conducted in the field.

Note:

This analysis does not assume completion of The My Figueroa Project in the future baseline conditions.

Table 11-1
SUMMARY OF IMPACTED LOCATIONS BY SCENARIO

NO.	INTERSECTION	[1] PROPOSED PROJECT WITH EXISTING ROADWAY NETWORK		SUPPLEMENTAL IMPACT ANALYSIS					
				[2] ASSUMING COTTAGE PL./ OLYMPIC BOULEVARD RESTRICTED TO RIGHT TURNS		[3] ASSUMING IMPLEMENTATION OF MY FIGUEROA PROJECT		[4] ASSUMING COTTAGE PL./ OLYMPIC BL. & MY FIGUEROA PROJECT	
		Existing With Project Conditions	Future With Project Conditions	Existing With Project Conditions	Future With Project Conditions	Existing With Project Conditions	Future With Project Conditions	Existing With Project Conditions	Future With Project Conditions
7	Figueroa Street/ 9th Street	NO	YES	NO	YES	NO	YES	NO	YES
8	Figueroa Street/ Olympic Boulevard	NO	YES	NO	YES	NO	YES	NO	YES
9	Figueroa Street/ Pico Boulevard	NO	NO	NO	NO	NO	YES	NO	YES

[1] Refer to Table 9-1 for the study intersection LOS summary.

[2] This supplemental impact analysis scenario assumes that access to/from the Cottage Place/Olympic Boulevard intersection (alley driveway intersection) for the project is restricted to right-turn ingress and egress turning movements. Refer to Appendix Table D-1 for the study intersection LOS summary.

[3] This supplemental impact analysis scenario assumes implementation of the My Figueroa project which will affect lane configurations at some of the intersections along the Figueroa Street corridor. Refer to Appendix Table E-1 for the study intersection LOS summary.

[4] This supplemental impact analysis scenario assumes that access to/from the Cottage Place/Olympic Boulevard intersection (alley driveway intersection) for the project is restricted to right-turn ingress and egress turning movements and implementation of the My Figueroa project. Refer to Appendix Table F-1 for the study intersection LOS summary.

Table 7-1
PROJECT TRIP GENERATION [1]

LAND USE	SIZE	DAILY TRIP ENDS [2]	AM PEAK HOUR VOLUMES [2]			PM PEAK HOUR VOLUMES [2]		
		VOLUMES	IN	OUT	TOTAL	IN	OUT	TOTAL
<u>Proposed Project</u>								
Hotel [3]	373 Rooms	3,327	145	105	250	128	133	261
- Less Transit Adjustment (15%) [4]		(499)	(22)	(16)	(38)	(19)	(20)	(39)
- Less Walk Adjustment (5%) [4]		(166)	(7)	(5)	(12)	(6)	(7)	(13)
- Less Internal Capture (15%) [4]		(499)	(22)	(16)	(38)	(19)	(20)	(39)
Retail [5]	65,074 GLSF	2,779	38	24	62	116	125	241
- Less Transit Adjustment (15%) [4]		(417)	(6)	(4)	(10)	(17)	(19)	(36)
- Less Walk Adjustment (5%) [4]		(139)	(2)	(1)	(3)	(6)	(6)	(12)
- Less Internal Capture (15%) [4]		(417)	(6)	(4)	(10)	(17)	(19)	(36)
Condominium [6]	374 DU	2,173	28	137	165	130	64	194
- Less Transit Adjustment (15%) [4]		(326)	(4)	(21)	(25)	(20)	(10)	(30)
- Less Walk Adjustment (5%) [4]		(109)	(1)	(7)	(8)	(7)	(3)	(10)
- Less Internal Capture (15%) [4]		(326)	(4)	(21)	(25)	(20)	(10)	(30)
Office [7]	33,498 GSF	369	46	6	52	9	41	50
- Less Transit Adjustment (15%) [4]		(55)	(7)	(1)	(8)	(1)	(6)	(7)
- Less Walk Adjustment (5%) [4]		(18)	(2)	0	(2)	0	(2)	(2)
- Less Internal Capture (15%) [4]		(55)	(7)	(1)	(8)	(1)	(6)	(7)
Conference Center [7]	10,801 GSF	119	15	2	17	3	13	16
- Less Transit Adjustment (15%) [4]		(18)	(2)	0	(2)	0	(2)	(2)
- Less Walk Adjustment (5%) [4]		(6)	(1)	0	(1)	0	(1)	(1)
- Less Internal Capture (15%) [4]		(18)	(2)	0	(2)	0	(2)	(2)
Subtotal Proposed		5,699	177	177	354	253	243	496
<u>Less Existing</u>								
Retail [5]	(1,500) GLSF	(64)	(1)	0	(1)	(3)	(3)	(6)
- Less Transit Adjustment (15%) [4]		10	0	0	0	0	0	0
- Less Walk Adjustment (5%) [4]		3	0	0	0	0	0	0
- Less Pass-by Adjustment (20%) [4]		13	0	0	0	1	1	2
Automated Car Wash [8]	(9,130) GSF	(1,290)	Nom.	Nom.	Nom.	(65)	(64)	(129)
- Less Pass-by Adjustment (20%) [9]		258	0	0	0	13	13	26
Restaurant [10]	(2,500) GSF	(318)	(15)	(12)	(27)	(15)	(10)	(25)
- Less Transit Adjustment (15%) [4]		48	2	2	4	2	2	4
- Less Walk Adjustment (5%) [4]		16	1	1	2	1	1	2
- Less Internal Capture (15%) [4]		48	2	2	4	2	2	4
Subtotal Existing		(1,276)	(11)	(7)	(18)	(64)	(58)	(122)
NET INCREASE		4,423	166	170	336	189	185	374

[1] Source: ITE "Trip Generation Manual", 9th Edition, 2012.

[2] Trips are one-way traffic movements, entering or leaving.

[3] ITE Land Use Code 310 (Hotel) trip generation average rates.

- Daily Trip Rate: 8.92 trips/occupied rooms; 50% inbound/50% outbound

- AM Peak Hour Trip Rate: 0.67 trips/occupied rooms; 58% inbound/42% outbound

- PM Peak Hour Trip Rate: 0.70 trips/occupied rooms; 49% inbound/51% outbound

[4] Transit, walk and Central Business District (CBD) trip adjustments are based on site's proximity to Metro rail and bus transit opportunities and the site's location within the CBD.

[5] ITE Land Use Code 820 (Shopping Center) trip generation average rates.

- Daily Trip Rate: 42.7 trips/1,000 SF of floor area; 50% inbound/50% outbound

- AM Peak Hour Trip Rate: 0.96 trips/1,000 SF of floor area; 62% inbound/38% outbound

- PM Peak Hour Trip Rate: 3.71 trips/1,000 SF of floor area; 48% inbound/52% outbound

[6] ITE Land Use Code 230 (Residential Condominium/Townhouse) trip generation average rates.

- Daily Trip Rate: 5.81 trips/dwelling unit; 50% inbound/50% outbound

- AM Peak Hour Trip Rate: 0.44 trips/dwelling units; 17% inbound/83% outbound

- PM Peak Hour Trip Rate: 0.52 trips/dwelling units; 67% inbound/33% outbound

[7] ITE Land Use Code 710 (General Office Building) trip generation average rates.

- Daily Trip Rate: 11.03 trips/1,000 SF of floor area; 50% inbound/50% outbound

- AM Peak Hour Trip Rate: 1.56 trips/1,000 SF of floor area; 88% inbound/12% outbound

- PM Peak Hour Trip Rate: 1.49 trips/1,000 SF of floor area; 17% inbound/83% outbound

[8] ITE Land Use Code 948 (Automated Car Wash) trip generation average rates.

- Daily Trip Rate: As no ITE trip rate is provided, it was assumed that the PM peak hour volume represents 10% of daily trips

- Nom. = Nominal

- PM Peak Hour Trip Rate: 14.12 trips/1,000 SF of floor area; 50% inbound/50% outbound

[9] Source: LADOT policy on pass-by trip adjustments. Pass-by trips are made as intermediate stops on the way from an origin to a primary trip destination without a route diversion. Pass-by trips are attracted from the traffic passing the site on an adjacent street or roadway that offers direct access to the site.

[10] ITE Land Use Code 932 (High-Turnover [Sit-Down] Restaurant) trip generation average rates.


- Daily Trip Rate: 127.15 trips/1,000 SF of floor area; 50% inbound/50% outbound

- AM Peak Hour Trip Rate: 10.81 trips/1,000 SF of floor area; 55% inbound/45% outbound

- PM Peak Hour Trip Rate: 9.85 trips/1,000 SF of floor area; 60% inbound/40% outbound

- 6 -

o:\job_files\4122-2\dwg\12-3.dwg LDP 08:29:47 09/08/2016 rodriguez



NOT TO SCALE

MAP SOURCE: NARDI ASSOCIATES

FIGURE 2-3
GROUND FLOOR SITE PLAN



City of Los Angeles Department of City Planning

9/25/2019 PARCEL PROFILE REPORT

PROPERTY ADDRESSES

815 W OLYMPIC BLVD

ZIP CODES

90015

RECENT ACTIVITY

ENV-2015-4558-EIR

CASE NUMBERS

CPC-2017-432-CPU-CA

CPC-2015-4557-MCUP-CUX-TDR-
SPR-DD

CPC-2010-213-CA

CPC-2008-4502-GPA

CPC-2005-361-CA

CPC-2005-1124-CA

CPC-2005-1122-CA

CPC-2002-1128-CA

CPC-1986-606-GPC

ORD-175038

ORD-164307-SA2445

ORD-129944

ZA-2013-3696-CUB

ZA-1999-820-CUZ

VTT-73966-CN

ENV-2017-433-EIR

ENV-2015-4558-EIR

ENV-2013-3697-CE

ENV-2013-3392-CE

ENV-2010-214-ND

ENV-2008-4505-ND

ENV-2005-362-CE

ENV-2005-1125-CE

ENV-2005-1123-CE

ENV-2002-1131-ND

ENV-2002-1130-ND

PRIOR-06/01/1946

Address/Legal Information

PIN Number	127-5A207 17
Lot/Parcel Area (Calculated)	6,090.6 (sq ft)
Thomas Brothers Grid	PAGE 634 - GRID D5
Assessor Parcel No. (APN)	5138003014
Tract	CITY LANDS OF LOS ANGELES
Map Reference	M R 2-504/505 PAT 3-64/65
Block	None
Lot	PT "UNNUMBERED LT"
Arb (Lot Cut Reference)	225
Map Sheet	127-5A207

Jurisdictional Information

Community Plan Area	Central City
Area Planning Commission	Central
Neighborhood Council	Downtown Los Angeles
Council District	CD 14 - José Huizar
Census Tract #	2077.10
LADBS District Office	Los Angeles Metro

Planning and Zoning Information

Special Notes	None
Zoning	C2-4D
Zoning Information (ZI)	ZI-2374 LOS ANGELES STATE ENTERPRISE ZONE ZI-2427 Freeway Adjacent Advisory Notice for Sensitive Uses ZI-2385 Greater Downtown Housing Incentive Area ZI-2452 Transit Priority Area in the City of Los Angeles
General Plan Land Use	Regional Center Commercial
General Plan Note(s)	Yes
Hillside Area (Zoning Code)	No
Specific Plan Area	None
Subarea	None
Special Land Use / Zoning	None
Design Review Board	No
Historic Preservation Review	Yes
Historic Preservation Overlay Zone	None
Other Historic Designations	None
Other Historic Survey Information	None
Mills Act Contract	None
CDO: Community Design Overlay	None
CPIO: Community Plan Imp. Overlay	None
Subarea	None
CUGU: Clean Up-Green Up	None
HCR: Hillside Construction Regulation	No
NSO: Neighborhood Stabilization Overlay	No
POD: Pedestrian Oriented Districts	None
RFA: Residential Floor Area District	None
RIO: River Implementation Overlay	No
SN: Sign District	No

Streetscape	Los Angeles Sports and Entertainment District
Adaptive Reuse Incentive Area	Adaptive Reuse Incentive Area
Affordable Housing Linkage Fee	
Residential Market Area	Medium-High
Non-Residential Market Area	High
Transit Oriented Communities (TOC)	Tier 3
CRA - Community Redevelopment Agency	City Center Redevelopment Project
Central City Parking	Yes
Downtown Parking	Yes
Building Line	None
500 Ft School Zone	No
500 Ft Park Zone	No
Assessor Information	
Assessor Parcel No. (APN)	5138003014
Ownership (Assessor)	
Owner1	OLYMPIC26 LLC C/O C/O BEN NEMAN
Address	1433 S GRIFFITH AVE LOS ANGELES CA 90021
Ownership (Bureau of Engineering, Land Records)	
Owner	LOS ANGELES CAR WASH CORP
Address	811 W. OLYMPIC BLVD LOS ANGELES CA 90015
Owner	LOS ANGELES CAR WASH CORP.
Address	811 W OLYMPIC BLVD LOS ANGELES CA 90015
APN Area (Co. Public Works)*	0.840 (ac)
Use Code	2520 - Commercial - Service Station - With Car Wash - No Additional Services
Assessed Land Val.	\$23,099,247
Assessed Improvement Val.	\$1,076,937
Last Owner Change	05/01/2014
Last Sale Amount	\$22,000,220
Tax Rate Area	13264
Deed Ref No. (City Clerk)	406906
	35
	170546
Building 1	
Year Built	1981
Building Class	SX
Number of Units	0
Number of Bedrooms	0
Number of Bathrooms	0
Building Square Footage	16,329.0 (sq ft)
Building 2	No data for building 2
Building 3	No data for building 3
Building 4	No data for building 4
Building 5	No data for building 5
Additional Information	
Airport Hazard	None
Coastal Zone	None
Farmland	Area Not Mapped
Urban Agriculture Incentive Zone	YES
Very High Fire Hazard Severity Zone	No
Fire District No. 1	Yes
Flood Zone	None

This report is subject to the terms and conditions as set forth on the website. For more details, please refer to the terms and conditions at zimas.lacity.org
 (*) - APN Area is provided "as is" from the Los Angeles County's Public Works, Flood Control, Benefit Assessment.

Watercourse	No
Hazardous Waste / Border Zone Properties	No
Methane Hazard Site	Methane Buffer Zone Methane Zone
High Wind Velocity Areas	No
Special Grading Area (BOE Basic Grid Map A-13372)	No
Wells	None

Seismic Hazards

Active Fault Near-Source Zone	
Nearest Fault (Distance in km)	0.264014712
Nearest Fault (Name)	Puente Hills Blind Thrust
Region	Los Angeles Blind Thrusts
Fault Type	B
Slip Rate (mm/year)	0.70000000
Slip Geometry	Reverse
Slip Type	Moderately / Poorly Constrained
Down Dip Width (km)	19.00000000
Rupture Top	5.00000000
Rupture Bottom	13.00000000
Dip Angle (degrees)	25.00000000
Maximum Magnitude	7.10000000
Alquist-Priolo Fault Zone	No
Landslide	No
Liquefaction	No
Preliminary Fault Rupture Study Area	No
Tsunami Inundation Zone	No

Economic Development Areas

Business Improvement District	GREATER SOUTH PARK
Hubzone	Redesignated until Dec 2021
Opportunity Zone	No
Promise Zone	None
State Enterprise Zone	LOS ANGELES STATE ENTERPRISE ZONE

Housing

Direct all Inquiries to	Housing+Community Investment Department
Telephone	(866) 557-7368
Website	http://hcidla.lacity.org
Rent Stabilization Ordinance (RSO)	No
Ellis Act Property	No

Public Safety

Police Information	
Bureau	Central
Division / Station	Central
Reporting District	171
Fire Information	
Bureau	Central
Batallion	1
District / Fire Station	10
Red Flag Restricted Parking	No

CASE SUMMARIES

Note: Information for case summaries is retrieved from the Planning Department's Plan Case Tracking System (PCTS) database.

Case Number:	CPC-2017-432-CPU-CA
Required Action(s):	CA-CODE AMENDMENT CPU-COMMUNITY PLAN UPDATE
Project Descriptions(s):	COMMUNITY PLAN UPDATE
Case Number:	CPC-2015-4557-MCUP-CUX-TDR-SPR-DD
Required Action(s):	MCUP-MASTER CONDITIONAL USE PERMIT CUX-ADULT ENTERTAINMENTS DD-DIRECTOR'S DETERMINATION SPR-SITE PLAN REVIEW TDR-TRANSFER OF DEVELOPMENT RIGHTS (aka TFAR)
Project Descriptions(s):	PURSUANT TO SECTION 12.24-W.1, A MCP FOR THE SALE OF ALCOHOLIC BEVERAGES FOR ON-SITE AND OFF-SITE CONSUMPTION FOR A TOTAL OF 20 LICENSES (16 ON-SITE AND 4 OFF-SITE) FOR THE SUBJECT DEVELOPMENT, PURSUANT TO SECTION 12.24-X.18, A CUX TO ALLOW FOR DANCING AND LIVE ENTERTAINMENT, PURSUANT TO SECTION 12.27, A ZV TO ALLOW OUTDOOR DINING IN LOCATIONS OTHER THEN THE GROUND FLOOR, A ZV TO ALLOW LESS THEN ONE ON-SITE TREE PER FOUR RESIDENTIAL DWELLING UNITS, A ZV TO PROVIDE SHORT TERM AND LONG TERM PARKING ON A LEVEL OTHER THEN THE GROUND FLOOR OF THE DEVELOPMENT, PURSUANT TO SECTION 14.5.7, TFAR FOR THE TRANSFER OF MORE THEN 50,000 SQ FT, AND PURSUANT TO SECTION 16.05, SITE PLAN REVIEW AND APPROVAL FOR THE DEVELOPMENT OF A MIXED-USE PROJECT CONSISTING OF 374 RESIDENTIAL UNITS, 373 HOTEL ROOMS, 33,498 SQ FT OF OFFICE, 10,801 SQ FT OF CONFERENCE CENTER, AND 65,074 SQ FT OF COMMERCIAL SPACE.
Case Number:	CPC-2010-213-CA
Required Action(s):	CA-CODE AMENDMENT
Project Descriptions(s):	AN AMENDMENT TO ARTICLE 4.5 AND SECTION 16.05 OF ARTICLE 6.1 OF THE LOS ANGELES MUNICIPAL CODE (LAMC), AND RELEVANT SECTIONS OF THE LOS ANGELES ADMINISTRATIVE CODE, TO MODIFY THE AUTHORITY AND PROCEDURES FOR EFFECTUATING A TRANSFER OF FLOOR AREA RIGHTS (TFAR) AND TO MAKE OTHER TECHNICAL CHANGES TO REFLECT THE EXPIRATION OF THE AMENDED CENTRAL BUSINESS DISTRICT REDEVELOPMENT PROJECT AREA.
Case Number:	CPC-2008-4502-GPA
Required Action(s):	GPA-GENERAL PLAN AMENDMENT
Project Descriptions(s):	CENTRAL CITY PLAN AMENDMENT FOR URBAN DESIGN STANDARDS AND GUIDELINES AND MODIFIED STREETS, CODE CLARIFICATIONS
Case Number:	CPC-2005-361-CA
Required Action(s):	CA-CODE AMENDMENT
Project Descriptions(s):	CODE AMENDMENT TO UPDATE RESIDENTIAL STANDARDS AND INCENTIVIZE HOUSING IN THE CENTRAL CITY AREA.
Case Number:	CPC-2005-1124-CA
Required Action(s):	CA-CODE AMENDMENT
Project Descriptions(s):	TO REQUIRE PROJECTS IN THE CENTRAL CITY COMMUNITY PLAN TO COMPLY WITH DESIGN AND STREETSCAPE GUIDELINES
Case Number:	CPC-2005-1122-CA
Required Action(s):	CA-CODE AMENDMENT
Project Descriptions(s):	INCENTIVES FOR HTE PRODUCTION OF AFFORDABLE AND WORKFORCE HOUSING IN THE CENTRAL CITY PLAN AREA
Case Number:	CPC-2002-1128-CA
Required Action(s):	CA-CODE AMENDMENT
Project Descriptions(s):	
Case Number:	CPC-1986-606-GPC
Required Action(s):	GPC-GENERAL PLAN/ZONING CONSISTENCY (AB283)
Project Descriptions(s):	GENERAL PLAN/ZONE CONCSISTENCY - CENTRAL CITY AREA - COMMUNITYWIDE ZONE CHANGES AND COMMUNITY PLAN CHNAGES TO BRING THE ZONING INTO CONSISTENCY WITH THE COMMUNITY PLAN. INCLUDING CHANGESOF HEIGHT AS NEEDED
Case Number:	ZA-2013-3696-CUB
Required Action(s):	CUB-CONDITIONAL USE BEVERAGE-ALCOHOLI
Project Descriptions(s):	CONDITIONAL USE TO PERMIT THE CONTINUED SALE AND DISPENSING OF A FULL LINE OF ALCOHOLIC BEVERAGES IN CONJUNCTION WITH AN EXISTING 2,900 SQUARE FOOT RESTAURANT WITH OUTDOOR PATIO ACCOMMODATING 98 INTERIOR SEATS AND 20 EXTERIOR, PATIO SEATS. THE DAILY HOURS OF OPERATION WILL BE 10 A.M. TO 2 A.M. THE SUBJECT SITE CONSISTS OF 30,233.8 SQUARE FEET AND ZONED C2-4D.
Case Number:	ZA-1999-820-CUZ
Required Action(s):	CUZ-ALL OTHER CONDITIONAL USE CASES
Project Descriptions(s):	TO PERMIT THE CONSTRUCTION, USE AND MAINTENANCE OF A WIRELESS TELECOMMUNICATIONSFACILITIES IN THE C2-4D ZONE.

This report is subject to the terms and conditions as set forth on the website. For more details, please refer to the terms and conditions at zimas.lacity.org
(*) - APN Area is provided "as is" from the Los Angeles County's Public Works, Flood Control, Benefit Assessment.

Case Number:	VTT-73966-CN
Required Action(s):	CN-NEW CONDOMINIUMS
Project Descriptions(s):	PURSUANT TO SECTION 12.24-W.1, A MCP FOR THE SALE OF ALCOHOLIC BEVERAGES FOR ON-SITE AND OFF-SITE CONSUMPTION FOR A TOTAL OF 20 LICENSES (16 ON-SITE AND 4 OFF-SITE) FOR THE SUBJECT DEVELOPMENT, PURSUANT TO SECTION 12.24-X.18, A CUX TO ALLOW FOR DANCING AND LIVE ENTERTAINMENT, PURSUANT TO SECTION 12.27, A ZV TO ALLOW OUTDOOR DINING IN LOCATIONS OTHER THEN THE GROUND FLOOR, A ZV TO ALLOW LESS THEN ONE ON-SITE TREE PER FOUR RESIDENTIAL DWELLING UNITS, A ZV TO PROVIDE SHORT TERM AND LONG TERM PARKING ON A LEVEL OTHER THEN THE GROUND FLOOR OF THE DEVELOPMENT, PURSUANT TO SECTION 14.5.7, TFAR FOR THE TRANSFER OF MORE THEN 50,000 SQ FT, AND PURSUANT TO SECTION 16.05, SITE PLAN REVIEW AND APPROVAL FOR THE DEVELOPMENT OF A MIXED-USE PROJECT CONSISTING OF 374 RESIDENTIAL UNITS, 373 HOTEL ROOMS, 33,498 SQ FT OF OFFICE, 10,801 SQ FT OF CONFERENCE CENTER, AND 65,074 SQ FT OF COMMERCIAL SPACE.
Case Number:	ENV-2017-433-EIR
Required Action(s):	EIR-ENVIRONMENTAL IMPACT REPORT
Project Descriptions(s):	COMMUNITY PLAN UPDATE
Case Number:	ENV-2015-4558-EIR
Required Action(s):	EIR-ENVIRONMENTAL IMPACT REPORT
Project Descriptions(s):	PURSUANT TO SECTION 12.24-W.1, A MCP FOR THE SALE OF ALCOHOLIC BEVERAGES FOR ON-SITE AND OFF-SITE CONSUMPTION FOR A TOTAL OF 20 LICENSES (16 ON-SITE AND 4 OFF-SITE) FOR THE SUBJECT DEVELOPMENT, PURSUANT TO SECTION 12.24-X.18, A CUX TO ALLOW FOR DANCING AND LIVE ENTERTAINMENT, PURSUANT TO SECTION 12.27, A ZV TO ALLOW OUTDOOR DINING IN LOCATIONS OTHER THEN THE GROUND FLOOR, A ZV TO ALLOW LESS THEN ONE ON-SITE TREE PER FOUR RESIDENTIAL DWELLING UNITS, A ZV TO PROVIDE SHORT TERM AND LONG TERM PARKING ON A LEVEL OTHER THEN THE GROUND FLOOR OF THE DEVELOPMENT, PURSUANT TO SECTION 14.5.7, TFAR FOR THE TRANSFER OF MORE THEN 50,000 SQ FT, AND PURSUANT TO SECTION 16.05, SITE PLAN REVIEW AND APPROVAL FOR THE DEVELOPMENT OF A MIXED-USE PROJECT CONSISTING OF 374 RESIDENTIAL UNITS, 373 HOTEL ROOMS, 33,498 SQ FT OF OFFICE, 10,801 SQ FT OF CONFERENCE CENTER, AND 65,074 SQ FT OF COMMERCIAL SPACE.
Case Number:	ENV-2013-3697-CE
Required Action(s):	CE-CATEGORICAL EXEMPTION
Project Descriptions(s):	CONDITIONAL USE TO PERMIT THE CONTINUED SALE AND DISPENSING OF A FULL LINE OF ALCOHOLIC BEVERAGES IN CONJUNCTION WITH AN EXISTING 2,900 SQUARE FOOT RESTAURANT WITH OUTDOOR PATIO ACCOMMODATING 98 INTERIOR SEATS AND 20 EXTERIOR, PATIO SEATS. THE DAILY HOURS OF OPERATION WILL BE 10 A.M. TO 2 A.M. THE SUBJECT SITE CONSISTS OF 30,233.8 SQUARE FEET AND ZONED C2-4D.
Case Number:	ENV-2013-3392-CE
Required Action(s):	CE-CATEGORICAL EXEMPTION
Project Descriptions(s):	THE PROPOSED ORDINANCE MODIFIES SECTION 22.119 OF THE LOS ANGELES ADMINISTRATIVE CODE TO ALLOW ORIGINAL ART MURALS ON LOTS DEVELOPED WITH ONLY ONE SINGLE-FAMILY RESIDENTIAL STRUCTURE AND THAT ARE LOCATED WITHIN COUNCIL DISTRICTS 1, 9, AND 14.
Case Number:	ENV-2010-214-ND
Required Action(s):	ND-NEGATIVE DECLARATION
Project Descriptions(s):	AN AMENDMENT TO ARTICLE 4.5 AND SECTION 16.05 OF ARTICLE 6.1 OF THE LOS ANGELES MUNICIPAL CODE (LAMC), AND RELEVANT SECTIONS OF THE LOS ANGELES ADMINISTRATIVE CODE, TO MODIFY THE AUTHORITY AND PROCEDURES FOR EFFECTUATING A TRANSFER OF FLOOR AREA RIGHTS (TFAR) AND TO MAKE OTHER TECHNICAL CHANGES TO REFLECT THE EXPIRATION OF THE AMENDED CENTRAL BUSINESS DISTRICT REDEVELOPMENT PROJECT AREA.
Case Number:	ENV-2008-4505-ND
Required Action(s):	ND-NEGATIVE DECLARATION
Project Descriptions(s):	CENTRAL CITY PLAN AMENDMENT FOR URBAN DESIGN STANDARDS AND GUIDELINES AND MODIFIED STREETS, CODE CLARIFICATIONS
Case Number:	ENV-2005-362-CE
Required Action(s):	CE-CATEGORICAL EXEMPTION
Project Descriptions(s):	CODE AMENDMENT TO UPDATE RESIDENTIAL STANDARDS AND INCENTIVIZE HOUSING IN THE CENTRAL CITY AREA.
Case Number:	ENV-2005-1125-CE
Required Action(s):	CE-CATEGORICAL EXEMPTION
Project Descriptions(s):	TO REQUIRE PROJECTS IN THE CENTRAL CITY COMMUNITY PLAN TO COMPLY WITH DESIGN AND STREETSCAPE GUIDELINES
Case Number:	ENV-2005-1123-CE
Required Action(s):	CE-CATEGORICAL EXEMPTION
Project Descriptions(s):	INCENTIVES FOR HTE PRODUCTION OF AFFORDABLE AND WORKFORCE HOUSING IN THE CENTRAL CITY PLAN AREA
Case Number:	ENV-2002-1131-ND
Required Action(s):	ND-NEGATIVE DECLARATION
Project Descriptions(s):	
Case Number:	ENV-2002-1130-ND
Required Action(s):	ND-NEGATIVE DECLARATION

This report is subject to the terms and conditions as set forth on the website. For more details, please refer to the terms and conditions at zimas.lacity.org
 (*) - APN Area is provided "as is" from the Los Angeles County's Public Works, Flood Control, Benefit Assessment.

Project Descriptions(s):


DATA NOT AVAILABLE

ORD-175038

ORD-164307-SA2445

ORD-129944

PRIOR-06/01/1946



Address: 815 W OLYMPIC BLVD

Tract: CITY LANDS OF LOS
ANGELES

Zoning: C2-4D

APN: 5138003014

Block: None

General Plan: Regional Center Commercial

PIN #: 127-5A207 17

Lot #: PT "UNNUMBERED LT"

Arb: 225



LEGEND

GENERALIZED ZONING

- OS, GW
- A, RA
- RE, RS, R1, RU, RZ, RW1
- R2, RD, RMP, RW2, R3, RAS, R4, R5, PVSP
- CR, C1, C1.5, C2, C4, C5, CW, WC, ADP, LASED, CEC, USC, PPSP
- CM, MR, CCS, UV, UI, UC, M1, M2, LAX, M3, SL
- P, PB
- PF

GENERAL PLAN LAND USE

LAND USE

RESIDENTIAL

- Minimum Residential
- Very Low / Very Low I Residential
- Very Low II Residential
- Low / Low I Residential
- Low II Residential
- Low Medium / Low Medium I Residential
- Low Medium II Residential
- Medium Residential
- High Medium Residential
- High Density Residential
- Very High Medium Residential

COMMERCIAL

- Limited Commercial
- Limited Commercial - Mixed Medium Residential
- Highway Oriented Commercial
- Highway Oriented and Limited Commercial
- Highway Oriented Commercial - Mixed Medium Residential
- Neighborhood Office Commercial
- Community Commercial
- Community Commercial - Mixed High Residential
- Regional Center Commercial

FRAMEWORK

COMMERCIAL

- Neighborhood Commercial
- General Commercial
- Community Commercial
- Regional Mixed Commercial

INDUSTRIAL

- Commercial Manufacturing
- Limited Manufacturing
- Light Manufacturing
- Heavy Manufacturing
- Hybrid Industrial

PARKING

- Parking Buffer

PORT OF LOS ANGELES

- General / Bulk Cargo - Non Hazardous (Industrial / Commercial)
- General / Bulk Cargo - Hazard
- Commercial Fishing
- Recreation and Commercial
- Intermodal Container Transfer Facility Site

LOS ANGELES INTERNATIONAL AIRPORT

- Airport Landside / Airport Landside Support
- Airport Airside
- LAX Airport Northside

OPEN SPACE / PUBLIC FACILITIES

- Open Space
- Public / Open Space
- Public / Quasi-Public Open Space
- Other Public Open Space
- Public Facilities

INDUSTRIAL

- Limited Industrial
- Light Industrial

CIRCULATION

STREET

- Arterial Mountain Road
- Collector Scenic Street
- Collector Street
- Collector Street (Hillside)
- Collector Street (Modified)
- Collector Street (Proposed)
- Country Road
- Divided Major Highway II
- Divided Secondary Scenic Highway
- Local Scenic Road
- Local Street
- Major Highway (Modified)
- Major Highway I
- Major Highway II
- Major Highway II (Modified)

- Major Scenic Highway
- Major Scenic Highway (Modified)
- Major Scenic Highway II
- Mountain Collector Street
- Park Road
- Parkway
- Principal Major Highway
- Private Street
- Scenic Divided Major Highway II
- Scenic Park
- Scenic Parkway
- Secondary Highway
- Secondary Highway (Modified)
- Secondary Scenic Highway
- Special Collector Street
- Super Major Highway

FREEWAYS

- Freeway
- Interchange
- On-Ramp / Off- Ramp
- Railroad
- Scenic Freeway Highway

MISC. LINES

- Airport Boundary
- Bus Line
- Coastal Zone Boundary
- Coastline Boundary
- Collector Scenic Street (Proposed)
- Commercial Areas
- Commercial Center
- Community Redevelopment Project Area
- Country Road
- DWP Power Lines
- Desirable Open Space
- Detached Single Family House
- Endangered Ridgeline
- Equestrian and/or Hiking Trail
- Hiking Trail
- Historical Preservation
- Horsekeeping Area
- Local Street
- MSA Desirable Open Space
- Major Scenic Controls
- Multi-Purpose Trail
- Natural Resource Reserve
- Park Road
- Park Road (Proposed)
- Quasi-Public
- Rapid Transit Line
- Residential Planned Development
- Scenic Highway (Obsolete)
- Secondary Scenic Controls
- Secondary Scenic Highway (Proposed)
- Site Boundary
- Southern California Edison Power
- Special Study Area
- Specific Plan Area
- Stagecoach Line
- Wildlife Corridor

POINTS OF INTEREST

 Alternative Youth Hostel (Proposed)	 Horticultural Center	 Public Elementary School
 Animal Shelter	 Hospital	 Public Elementary School (Proposed)
 Area Library	 Hospital (Proposed)	 Public Golf Course
 Area Library (Proposed)	HW House of Worship	 Public Golf Course (Proposed)
 Bridge	e Important Ecological Area	 Public Housing
 Campground	 Important Ecological Area (Proposed)	 Public Housing (Proposed Expansion)
 Campground (Proposed)	 Interpretive Center (Proposed)	 Public Junior High School
 Cemetery	 Junior College	 Public Junior High School (Proposed)
HW Church	 MTA / Metrolink Station	 Public Middle School
 City Hall	 MTA Station	 Public Senior High School
 Community Center	 MTA Stop	 Public Senior High School (Proposed)
 Community Library	MWD MWD Headquarters	 Pumping Station
 Community Library (Proposed Expansion)	 Maintenance Yard	 Pumping Station (Proposed)
 Community Library (Proposed)	 Municipal Office Building	 Refuse Collection Center
 Community Park	P Municipal Parking lot	 Regional Library
 Community Park (Proposed Expansion)	 Neighborhood Park	 Regional Library (Proposed Expansion)
 Community Park (Proposed)	 Neighborhood Park (Proposed Expansion)	 Regional Library (Proposed)
 Community Transit Center	 Neighborhood Park (Proposed)	 Regional Park
 Convalescent Hospital	 Oil Collection Center	 Regional Park (Proposed)
 Correctional Facility	 Parking Enforcement	RPD Residential Plan Development
 Cultural / Historic Site (Proposed)	 Police Headquarters	 Scenic View Site
 Cultural / Historical Site	 Police Station	 Scenic View Site (Proposed)
 Cultural Arts Center	 Police Station (Proposed Expansion)	 School District Headquarters
DMV DMV Office	 Police Station (Proposed)	 School Unspecified Loc/Type (Proposed)
DWP DWP	 Police Training site	 Skill Center
 DWP Pumping Station	PO Post Office	 Social Services
 Equestrian Center	 Power Distribution Station	 Special Feature
 Fire Department Headquarters	 Power Distribution Station (Proposed)	 Special Recreation (a)
 Fire Station	 Power Receiving Station	 Special School Facility
 Fire Station (Proposed Expansion)	 Power Receiving Station (Proposed)	 Special School Facility (Proposed)
 Fire Station (Proposed)	C Private College	 Steam Plant
 Fire Supply & Maintenance	E Private Elementary School	 Surface Mining
 Fire Training Site	 Private Golf Course	 Trail & Assembly Area
 Fireboat Station	 Private Golf Course (Proposed)	 Trail & Assembly Area (Proposed)
 Health Center / Medical Facility	JH Private Junior High School	UTL Utility Yard
 Helistop	PS Private Pre-School	 Water Tank Reservoir
 Historic Monument	 Private Recreation & Cultural Facility	 Wildlife Migration Corridor
 Historical / Cultural Monument	SH Private Senior High School	 Wildlife Preserve Gate
 Horsekeeping Area	SF Private Special School	
 Horsekeeping Area (Proposed)	 Public Elementary (Proposed Expansion)	

SCHOOLS/PARKS WITH 500 FT. BUFFER

Existing School/Park Site Planned School/Park Site Inside 500 Ft. Buffer

- | | | |
|----------------------|----------------------------------|--------------------------|
| Aquatic Facilities | Other Facilities | Opportunity School |
| Beaches | Park / Recreation Centers | Charter School |
| Child Care Centers | Parks | Elementary School |
| Dog Parks | Performing / Visual Arts Centers | Span School |
| Golf Course | Recreation Centers | Special Education School |
| Historic Sites | Senior Citizen Centers | High School |
| Horticulture/Gardens | | Middle School |
| Skate Parks | | Early Education Center |

COASTAL ZONE

- Coastal Zone Commission Authority
- Calvo Exclusion Area
- Not in Coastal Zone
- Dual Jurisdictional Coastal Zone

TRANSIT ORIENTED COMMUNITIES (TOC)

- Tier 1
- Tier 2
- Tier 3
- Tier 4

Note: TOC Tier designation and map layers are for reference purposes only. Eligible projects shall demonstrate compliance with Tier eligibility standards prior to the issuance of any permits or approvals. As transit service changes, eligible TOC Incentive Areas will be updated.

WAIVER OF DEDICATION OR IMPROVEMENT

- Public Work Approval (PWA)
- Waiver of Dedication or Improvement (WDI)

LAMC SECTION 85.02 (VEHICLE DWELLING)

- No vehicle dwelling anytime
- No vehicle dwelling overnight between 9:00 PM - 6:00 AM. Must comply with all posted parking restrictions
- Vehicle dwelling allowed. Must comply with all posted parking restrictions

OTHER SYMBOLS

- | | | |
|------------------------|-----------------------|-------------------------------------|
| Lot Line | Airport Hazard Zone | Flood Zone |
| Tract Line | Census Tract | Hazardous Waste |
| Lot Cut | Coastal Zone | High Wind Zone |
| Easement | Council District | Hillside Grading |
| Zone Boundary | LADBS District Office | Historic Preservation Overlay Zone |
| Building Line | Downtown Parking | Specific Plan Area |
| Lot Split | Fault Zone | Very High Fire Hazard Severity Zone |
| Community Driveway | Fire District No. 1 | Wells |
| Building Outlines 2014 | Tract Map | |
| Building Outlines 2008 | Parcel Map | |