APPENDICES

APPENDIX A. Preliminary Soil Investigation

REPORT

PRELIMINARY SOIL INVESTIGATION

Proposed Residential Buildings
Lot 14, Arb 2 & 4, Tract No. 4226
11148 Lorne Street & 8032 Fair Avenue
Sun Valley, California 91352

CITY OF LOS ANGELES COPY

(please do not remove or assemble the pages)

This report contains a total of 33 pages including this page

GSS ENGINEERING, INC.
GEOTECHNICAL / ENVIRONMENTAL CONSULTANTS



REPORT

PRELIMINARY SOIL INVESTIGATION

Proposed Residential Buildings
Lot 14, Arb 2 & 4, Tract No. 4226
11148 Lorne Street & 8032 Fair Avenue
Sun Valley, California 91352

for

Mr. Sogomon Petrosyan
750 North Fairview Street
Burbank, California 91505

Project No. GSS-3095-1
February 16, 2022

REPORT
PRELIMINARY SOIL INVESTIGATION
PROPOSED RESIDENTIAL BUILDINGS
LOT 14, ARB 2 & 4, TRACT NO. 4226
11148 LORNE STREET AND 8032 FAIR AVENUE
SUN VALLEY, LOS ANGELES, CALIFORNIA 91352
FOR
MR. SOGOMON PETROSYAN

INTRODUCTION

The following report presents the results of a preliminary soil investigation conducted on the properties located at 11148 Lorne Street and 8032 Fair Avenue, in the Sun Valley area of the City of Los Angeles, California. The location of the site relative to surrounding streets and landmarks is shown on Plate 1, Vicinity Map.

The purpose of this investigation is to obtain the geotechnical engineering properties of the subsurface soils at the subject site on which to base conclusions and recommendations for foundations support and other geotechnical matters pertinent to the proposed construction. Implementation of the recommendations made in this report is intended to reduce certain risks associated with construction projects. The scope of this investigation does not include the work related in any way to identify asbestos and/or hazardous waste material, or soil infiltrating test.

This report has been prepared for use in design of the described project. It may not contain sufficient information for other purposes. Our professional services have been performed in accordance with generally accepted engineering procedures under similar circumstances. No other warranty, expressed or implied, is made as to the professional advice included in this report.

PROPOSED DEVELOPMENT

It is understood that the subject properties will be utilized for the development of three residential buildings at the locations shown on Plate 2. The proposed structures will be three stories in height, constructed of wood frame and stucco with slab on grade. No basement is proposed.

The finish grade of the project is expected to be at or near the existing ground surface. Grading other than removal and recompaction of the existing fill and unsuitable surface soils will be required to develop the building pad and to provide proper site drainage. No detailed grading plan and design loads are available at the time of this investigation.

FIELD EXPLORATIONS AND LABORATORY TESTING

Field explorations were performed to establish the geotechnical conditions of the site. Four (4) test borings were excavated at the locations shown on Plate 2. The explorations were logged by our field engineer and relatively undisturbed samples were obtained for laboratory testing and inspection. A detailed description of the exploration procedures and the logs of test borings are presented in the Appendix.

Laboratory tests were performed to evaluate static soil properties. A description of the test procedures and the test results are also presented in the Appendix.

SITE CONDITIONS

The subject properties are located on the south side of Lorne Street, between Fair Avenue and Vineland Avenue, in the Sun Valley area of the City of Los Angeles, California. The site is bordered by residential developments and vacant lots on the east, west, and south.

The site consists of two relatively level lots that measured approximately 75 to 148 feet wide by 300 feet long in plan dimensions totally. At the time of this investigation, the site is occupied by one-story houses. All existing buildings will be demolished for new constructions. Surface vegetation consists of common landscaping features with growth of grasses, plants, and trees.

SUBSURFACE CONDITIONS

Soil Conditions

In general, the natural soils disclosed in the test borings consist of medium dense to dense, fine to coarse, slightly silty sand with occasional gravels to a depth of 3 feet, underlain by dense, fine to coarse, slightly silty and slightly silty to silty, gravelly, rocky sand to the depths explored of 10 to 20 feet.

Fill was encountered in all test borings from the existing grade to a depth of one foot. It consists of medium dense, fine to medium, silty sand with occasional coarse grains.

Groundwater

No groundwater or seepage was encountered in any test borings penetrated to a maximum depth of 20 feet. It must be noted that fluctuations in the level of the groundwater may occur due to variations in rainfall, temperature, and other factors not evident at the time measurements were made and reported herein.

EARTHQUAKE HAZARDS

Seismicity

The subject property lies within the seismically active southern California region. As with all sites in southern California, the property will probably experience ground shaking from both near and distant earthquake sources during the life of the proposed structure. The type and

magnitude of seismic hazard affecting at the site are dependent on the distance of causative faults and the intensity and magnitude of the seismic event.

Surface Rupture

The site is not located within a currently designated Alquist-Priolo Earthquake Fault Zone. No faults, active or potentially active, are known to exist within the site. The probability of surface rupture at the site is, therefore, considered very low.

Ground Shaking

According to "Maps of Known Active Fault Near-Source Zones in California and Adjacent Portions of Nevada" by California Department of Conservation, the site is within 2 km of the Verdugo Fault Zone. It is our opinion that the intensity of future ground shaking at the site is not expected to be greater than any other sites in the immediate vicinity. The proposed structures shall be designed in accordance with the Earthquake Regulations of the California Building Code and the seismic design parameters provided in the other section of this report.

Soil Liquefaction Evaluation

Earthquake-induced liquefaction is a phenomenon in which loose to medium dense saturated cohesionless soils undergo extreme losses in shear strength due to earthquake shaking. The liquefaction potential is directly related to the groundwater conditions at the site as well as to the characteristics of the underlying soil deposits. Loose to medium dense sands below groundwater level are generally considered to be susceptible to liquefaction under strong ground shaking conditions.

The site is not located in the area as delineated by the State Geologist to have potential of soil liquefaction during strong earthquakes. Hence, liquefaction evaluation of the site is not performed. As no groundwater was encountered in any test borings to a maximum depth of 20 feet, it is our opinion that the potential of soil liquefaction at the site is considered low.

CONCLUSIONS AND RECOMMENDATIONS

General

Based on an evaluation of the site conditions and findings of this investigation, it is concluded that construction of the proposed residential buildings at the site as proposed is feasible from a geotechnical engineering viewpoint provided the following conclusions and recommendations are incorporated into design criteria and project specifications and are implemented during construction.

Conventional spread footings founded into competent dense undisturbed natural soil will provide adequate support to the proposed structures.

Site Preparation

General

Precautions should be taken during the performance of all work under the following sections, especially if construction is performed during the rainy season of approximately October 1 to April 15. Protection should be provided to the work site, particularly excavated areas, from flooding, ponding, and inundation due to poor or improper temporary surface drainage. During periods of impending inclement weather, temporary provisions should be made to adequately direct surface drainage, from all sources, away from and off the work site and to provide adequate pumps and sumps to handle any flow into the excavations.

Site Clearing

Clearing and grubbing should consist of the removal of asphalt, concrete slab, vegetation such as brush, grass, woods, stumps, trees, roots of trees and otherwise deleterious natural materials from the areas to be graded. Clearing and grubbing should extend to the outside of all proposed excavation and fill areas.

Debris generated during clearing, grubbing and/or demolition operations should be wasted from areas to be graded and disposed of off-site. During site grading, laborers should clear any roots, tree branches, and other deleterious materials missed during clearing and grubbing operations from all areas to receive fill.

The Soils Engineer should review the depths of excavation during actual construction. Any surface or subsurface obstructions, or questionable material, encountered during grading should be brought immediately to the attention of the Soils Engineer for proper exposure, removal or processing as directed. No underground obstructions or facilities should remain in any structural areas.

Existing Structures

Demolition and/or removal of the existing structures are to include removal of the supporting foundation system. Existing paving and concrete slabs should be removed from the site.

Utilities

Any underground utilities that are not to be reconnected should be cut off a minimum of 4 feet beyond the edge of building perimeters and entirely removed from within the area of future construction.

The ends of cut-off lines should be plugged a minimum of 5 feet with concrete exhibiting minimum shrinkage characteristics to prevent water migration to or from hollow lines. In addition, capping of lines may be required should the plug be subject to any line pressures.

Existing On-Site Sewage System

The location of the existing on-site sewage system (septic tank, seepage pits/cesspools), if any, should be determined.

Excavate and remove completely any underground tanks within areas of proposed construction. Contaminated soils resulting from leakage and tank removal will not be suitable for use as structural backfill and should be disposed of off site.

Trees and Surface Vegetation

Removal of designated trees and shrubs in areas of proposed construction should include rootballs. Resultant cavities should be cleansed of loose soils and roots and rolled to a firm unyielding surface prior backfilling.

Grass and weed growth in areas of future construction should be stripped and disposed of off site. Stripping should penetrate three to six inches into surface soils. Any soils sufficiently contaminated with organic matter (such as root systems or stripping mixed into the soils) so as to prevent proper compaction shall be disposed of off site or set aside for future use in landscape areas.

Subgrade Preparation

It is recommended that all of the existing onsite fill and/or loosed or disturbed natural soils within the proposed slab-on-grade or pavement areas be removed to underlying dense competent undisturbed natural soil, or to a depth of 1.5 feet below the existing grade, whichever is greater, and then replaced with properly compacted fill for slab or pavement support.

The exposed bottom surface in each removal area should first be scarified to a depth of at least 8 inches, processed, watered or air dried as necessary to achieve near optimum moisture conditions, and then compacted in-place to 90 percent of the maximum laboratory dry density (95 percent for cohesionless soil). Locally, some areas exposing loose or soft soils may require deeper removal than indicated above. Actual depth of removal is to be determined in the field at the time of grading.

Fill Placement

Unless otherwise specified, any new fill shall be brought to near optimum moisture, placed in layers not exceeding 8 inches thick, and compacted to at least 90 percent of the maximum laboratory dry density (95 percent for cohesionless soil).

Compaction characteristics of all fill soils shall be determined by ASTM D-1557-12 standard. The field density and degree of compaction shall be determined by ASTM D-1556, or by other ASTM standard methods that are acceptable to the governing public agency.

Shrinkage and Bulking

Volumetric changes in earth quantities will occur when excavated the onsite materials are replaced as properly compacted fill. Following is an estimate of shrinkage/bulking factors for the materials present onsite. These estimates are based on in-place densities of the various materials and on the estimated average degree of relative compaction achieved during grading.

Onsite Soil After Excavated	Bulking 8% to 10%
Onsite Soil After Compacted	Shrinkage 8% to 10%

The above estimates of shrinkage/bulking are intended as an aid for project planners in determining earthwork quantities. However, these estimates should be used with some caution since they are not absolute values. Contingencies should be made for balancing earthwork quantities based on actual shrinkage and subsidence that will occur during grading.

Seismic Design Parameters

Based on the results of this preliminary soil investigation and in accordance with 2020 City of Los Angeles Building Code, the following seismic data are applicable to the subject site.

Longitude	-118.374253
Latitude	34.216998
S_s	2.082
S_1	0.729
Site Class	D
F_a	1.0
F_v	1.7*
S_{MS}	2.082
S_{M1}	1.239*
S_{DS}	1.388
S_{D1}	0.826*

(*) Note: F_v = 1.7 may be utilized provided that the Seismic Response Coefficient (C_s) in the structural calculation is determined per ASCE 7-16 Section 11.4.8 Exception No. 2.

Foundation Recommendations

Allowable Bearing Value

An allowable bearing value of 2000 pounds per square foot is recommended for spread footings of at least 18 inches in width, placed at a depth of at least 1.5 feet below the lowest adjacent finish grade, founded into competent dense undisturbed natural soils.

The bearing value is for dead plus live load and may be increased by one-third for momentary wind or seismic loads.

Footing Settlement

Maximum ultimate settlement of footings up to 3 feet wide continuous and 3 feet square under the recommended bearing pressure is not expected to exceed ¾ an inch. Differential settlement between adjacent footings is not expected to exceed 1/4 of an inch within a span of 40 feet. Settlement will be approximately in direct proportion to the width of the footings and actual applied load.

Because of the granular nature of the supporting soils, the settlement will occur rapidly. It is expected that the majority of the anticipated settlement will occur during construction and immediately after application of loads.

Footing Reinforcement

Continuous footings should be reinforced with at least four No. 4 bars; two near the top and two near the bottom of the footings. Reinforcement of isolated footings shall be utilized as deemed necessary by the Structural Engineer for the project. This reinforcement is based on soil characteristics and is not intended to be in lieu of reinforcement necessary to satisfy structural considerations.

Footing Inspections

All foundation excavations should be inspected and approved by the Soils Engineer prior to placement of forms, reinforcement or concrete. The excavations should be trimmed neat, level and square. All loose, sloughed and moisture softened materials should be removed prior to the placement of concrete.

Footings should be located below a line measured upward at a 45-degree angle from the bottom of the adjacent footings or utility trench, unless review and approved by the Soils Engineer.

Materials from footings excavations should not be spread in slab-on-grade areas unless they are compacted and tested.

Lateral Design

An allowable lateral bearing value against the sides of footings of 250 pounds per square foot per foot of depth, to a maximum of 2000 pounds per square foot, may be used provided there is positive contact between the vertical bearing surface and undisturbed natural soil. Friction between the base of the footings and the underlying soil may be assumed to be 0.4 times the dead load. When combining passive pressure and friction for lateral resistance, the passive component should be reduced by one-third.

Slabs On Grade

Floor Slabs

Slabs on grade should be cast over properly prepared subgrade. Any loosened or over-excavated soils should be wasted from the site or properly compacted in-place.

The subgrade soil beneath the slab areas should be rechecked for disturbance resulting from footing and utility trench excavation prior to concrete pour. All fill soils should be moisture-conditioned to obtain near optimum water content and then compacted to at least 90 percent of the maximum laboratory dry density (95 percent for cohesionless soil) as determined by the ASTM D-1557-12 compaction test method.

It should be recognized that minor cracks normally occur in concrete slabs due to shrinkage during curing or redistribution of stresses and thus, some cracks should be anticipated. Such cracks are not necessarily indicative of excessive vertical movements.

Slab Reinforcement

Floor slabs constructed on-grade should be supported by a gravel or crushed rock layer per Green Code. Slabs shall be a minimum of 5 inches thick and reinforced with No. 4 bars spaced 16 inches on centers, both ways. All slab reinforcement should be supported on concrete chairs or brick to ensure the desired placement near mid-depth.

The above criteria are recommended to minimize potential distress to floor slabs related to the effects of subgrade soil conditions. The Structural Engineer for the project may need to address other factors that may require modification of the above recommendations.

Moisture Barrier

A moisture barrier beneath slabs-on-grade, consisting of a waterproof vapor barrier, such as a plastic membrane of at least 10 mils in thickness, is recommended in areas where slab moisture would be detrimental. The membrane should be overlain by a minimum of 2 inches of clean sands to provide a working surface and aid in concrete curing.

It is important that the soil subgrade, which will support the concrete slab, is maintained at the "as-graded" or has a sufficient soil water content. Prior to slab construction, the water content of the soil subgrade should be measured to verify that the subgrade has not dried out significantly. It is suggested that slab areas be thoroughly moistened prior to placing of moisture barrier and pouring of concrete.

Excavation

Excavation should be in accordance with all applicable requirements of the State of California Construction and General Industry Safety Order, the Occupational Safety and Health Act of 1970, the Construction Safety Act, and all other public agencies have jurisdiction. Construction specifications should clearly establish the responsibilities of the contractor for construction safety in accordance with CAL/OSHA requirements.

Your attention is directed to the fact that the onsite soils are relatively dry and cohesionless. It is likely that a trench or excavation in these materials would subject to caving.

No excavation shall be made during unfavorable weather. It is recommended that the excavated banks be entirely covered with plastic sheets when threatened by rains. When the excavation is interrupted by rain, operations shall not be resumed until the Soils Engineer indicates that conditions will permit satisfactory results.

Post Grading Considerations

Site Drainage

The provision and maintenance of adequate site drainage and moisture protection of supporting soil is an important design consideration. Foundation recommendations presented herein assume proper site drainage will be established and maintained.

To enhance future site performance, positive drainage devices such as sloping sidewalks, graded swales, and/or area drains should be provided around the building to collect and direct all water away from the structure. Neither rain nor excess irrigation water should be allowed to collect or pond on the property unless approved by the soil engineer. Where slabs or pavement are not feasible adjacent to the buildings, the ground surface should be provided with a minimum gradient away from the structures per 2019 California Building Code. All drainage should ultimately be directed to street or other designated area.

Water should be transported off the site in approved drainage devices or unobstructed swales. Drainage swales should have a minimum gradient per 2019 California Building Code. Where necessary, drainage paths could be shortened by use of area drains and collector pipes.

Planters adjacent to buildings should be avoided insofar as possible. Planting areas at grade should be provided with good positive drainage. Wherever possible, exposed soil areas should be above adjacent paved grades. Planters should not be depressed below adjacent paved grades unless provisions for drainage, such as catch basins and pipe drains are made.

Adequate drainage gradient, devices and curbing should be provided to prevent runoff from adjacent pavement or walks into planting areas. Consideration should be given to irrigation methods that will promote uniformity of moisture in planters and beneath adjacent concrete "flat-work". Over-watering and under-watering of landscape areas must be avoided.

All roof and wall surface drainage should be collected and conducted by a non-erosive device to the streets or to a designated area.

Trench Backfill

It is our opinion that utility trench and/or structural backfill consisting of the on-site material types could be best placed by mechanical compaction to a minimum of 90 percent of the maximum laboratory dry density (95 percent for cohesionless soil). Density testing, along with probing, should be performed by the project soils engineer, or his representative, to verify proper compaction.

If utility contractors indicate that it is undesirable to use compaction equipment in close proximity to a buried conduit, we would recommend the utilization of lightweight mechanical equipment and/or bedding of conduit with clean granular material prior to initiating mechanical compaction procedures. Other methods of utility trench compaction may also be appropriate as approved by the project geotechnical consultant at the time of construction.

Where utility trenches are proposed parallel to building footings (interior and/or exterior trenches), the bottom of the trench should not extend below a 1 horizontal to 1 vertical plane project downward from the outside bottom edge of the adjacent footing. Where this condition occurs, the adjacent footing should be deepened.

Plan Review

In order to prevent misinterpretation of this report by other consultants it is recommended that the Soils Engineer be provided the opportunity to review the final grading and foundation plans. The Soils Engineer will also determine whether any change in concept may have had any effect on the validity of the Soils Engineer's recommendations, and whether those recommendations have, in fact, been implemented in the design and specifications.

If the Soils Engineer is not accorded the privilege of making this recommended review, he can assume no responsibility for misinterpretation or misapplication of his recommendations or for their validity in the event changes have been made in the original design concept without this prior review.

Geotechnical Inspection

All rough grading of the property must be performed under engineering supervision of the geotechnical consultants. Rough grading includes, but is not limited to, site preparation, cleaning, over-excavation, and fill placement.

The geotechnical consultant should inspect all foundation excavations. Inspections should be made prior to installation of concrete forms and reinforcing steel to verify or modify, if necessary, conclusions and recommendations in this report.

Inspections of the finish grading, utility or other trench backfill, retaining wall backfill, or other earthwork completed for the subject project should also be performed by the geotechnical consultant.

If any of these inspections to verify site geotechnical conditions are not performed by the geotechnical consultant, liability for the safety and stability of the project is limited only to the actual portions of the project approved by the geotechnical consultant.

authority to reject the compacted fill ground until such time as corrective measures necessary are taken to comply with the specifications.

14) The Soils Engineer should be notified at least 2 days in advance of the start of grading. A joint meeting between a representative of the client, the contractor, and the Soils Engineer is recommended prior to grading to discuss specific procedures and scheduling.

INVESTIGATION LIMITATIONS

The conclusions and recommendations contained in this report are based on the data obtained from the test borings at the dates and locations indicated in the logs and the site plan. It is assumed that the soil conditions at the other areas do not deviate significantly from those disclosed in the test borings. If any variations, or undesirable conditions are encountered during construction, or if the proposed construction will differ from that planned at the present time, this office should be notified so as to consider the need for modifications.

No responsibility for construction compliance with the design concepts, specifications, or recommendations is assumed unless an on-site review by a representative of this office is performed during the course of construction that pertains to the specific areas covered by the recommendations contained herein.

This report has been compiled for the exclusive use of Mr. Sogomon Petrosyan, or his authorized agent. It shall not be transferred to any other party or to any other project without the consent and/or thorough review of this office.

The findings of this report are valid as of the present date. However, changes in the conditions of the property can occur with the passage of time, whether they are due to natural processes or to the works of man, on this or adjacent properties. In addition, changes in applicable or appropriate standards may occur, whether they result from legislation or the broadening of knowledge. Accordingly, the findings of this report may be invalidated, wholly or partially, by

changes outside of our control. Therefore, this report is subject to review and should not be relied upon after a period of one year without such a review.

This report is issued with the understanding that it is the responsibility of the owner, or the proper representative thereof, to ensure that the information and recommendations contained herein are called to the attention of all parties interested in the project and that the necessary steps are taken to see that the contractors and subcontractors carry out such recommendations in the field.

Final approval of plans and reports by all consultants, and issuance of any building and grading permits, rests with the controlling agencies. As the circumstances, which control the decision process, are clearly beyond the control of this facility, we cannot assume any responsibility for the success of obtaining proper authorizations, nor for the costs involved.

All exploratory borings used for subsurface exploration were backfilled with reasonable effort to restore the areas to their original condition. As with any backfill, some consolidation and subsidence of the backfill soils may result in time, causing some depression of the boring area and possibly a potentially hazardous condition. The client and/or owner of the property are advised to periodically examine the boring areas, and if necessary, backfill any resulting depressions. GSS Engineering, Inc. shall not be liable for any resulting injury or damage.

The report is subject to review by controlling public agencies having jurisdiction.

Respectfully submitted,
GSS ENGINEERING, INC.

Allen Lee, G
Principal Engineer

VICINITY MAP	Proposed Residential Buildings 11148 Lorne St & 8032 Fair Ave Sun Valley, Los Angeles, California
GSS ENGINEERING, INC. *Geotechnical Engineering Consultants*	**PROJECT No.** GSS-3095-1 **PLATE** 1



REFERENCE: "Site Plan", prepared by Approved Plans Inc., dated 06/15/19.

SCALE: 1" = 40'

PLOT PLAN AND BORING LOCATION	Proposed Residential Buildings 11148 Lorne St & 8032 Fair Ave Sun Valley, Los Angeles, California
GSS ENGINEERING, INC. *Geotechnical Engineering Consultants*	**PROJECT NO.** GSS-3095-1 — **PLATE** 2

APPENDIX

FIELD EXPLORATION AND LABORATORY TESTING

FIELD EXPLORATIONS

The subsurface conditions at the site were explored by excavating four (4) test borings at the locations shown on the Plot Plan, Plate 2. The test borings were excavated by means of an 8-inch diameter hollow stem auger to the depths of 10 to 20 feet below the existing ground surface. The approximate locations of the test borings were determined by tape measurements from the property boundaries and existing facilities. The locations of the test boring should be considered accurate only to the degree implied by the method used.

The soils encountered during excavation were logged by the field engineer. The soils are classified in accordance with the Unified Soil Classification System described on Plate A-1. Undisturbed samples of soils were extracted at selected intervals from the test borings in a barrel sampler with tapered cutting shoe. The undisturbed soil retained in 2.5-inch diameter by one-inch rings within the sampler were secured in moisture resistant bags and plastic sample cans as soon as taken to minimize the loss of field moisture while being transported to the laboratory for testing. The relative sampler penetration resistance exhibited by the soil types encountered is tabulated in the Blow per Foot column of the Log of Boring. Detailed logs of test boring are presented on Plates A-2 through A-5, Log of Test Boring.

The lines designating the interface between soil materials on the logs of test boring represent approximate boundaries. The transition between materials may be gradual.

LABORATORY TESTING

Moisture-Density

The field moisture content and dry density of the materials encountered were determined by performing tests on selected undisturbed samples to aid in the classification and correlation of the soil and to obtain qualitative information relative to their strengths and compressibility. The field moisture content and dry density of the samples were determined in accordance with ASTM-2216 and ASTM D-2937 standard. The results of the tests are shown on the Log of Test Boring, Plates A-2 through A-5.

Direct Shear Tests

Direct shear tests were performed in accordance with ASTM D-3080 standard on selected undisturbed samples of the onsite material to evaluate shear strength and supporting capacity of the foundation materials. Shear tests were made with a direct shear machine of the displacement control type at a displacement rate of approximately 0.005 inches per minute. The samples were soaked in water for at least 24 hours to approximately saturated moisture condition and then sheared under various normal stresses. The residual shear strength values determined from the tests are presented on Plate A-6, Direct Shear Test.

Consolidation Tests

Consolidation tests were performed on representative undisturbed samples of the natural soils in accordance with ASTM D-2435 standard to evaluate the volume changes of soil subjected to increased loads. Deformations of the specimen are recorded at selected intervals. The results of pressure consolidation curves, which are used to estimate the probable magnitude and rate of settlement of the tested soil under applied loads, are presented on Plates A-7 and A-8, Consolidation Test.

MAJOR DIVISIONS			GROUP SYMBOLS	TYPICAL NAMES
COARSE GRAINED SOILS (More than 50% of material is LARGER than No. 200 sieve size)	GRAVELS (More than 50% of coarse fraction is LARGER than No. 4 sieve size)	CLEAN GRAVELS (Little or no fines)	GW	Well graded gravels and gravel - sand mixtures, little or no fines
			GP	Poorly graded gravels and gravel - sand mixtures, little or no fines
		GRAVELS WITH FINES (Appreciable Amount of fines)	GM	Silty gravels, gravel - sand - silt mixtures
			GC	Clayey gravels, gravel - sand - clay mixtures
	SANDS (More than 50% of coarse fraction is SMALLER than No. 4 sieve size)	CLEAN SANDS (Little or no fines)	SW	Well graded sands and gravelly sands, little or no fines
			SP	Poorly graded sands and gravelly sands, little or no fines
		SANDS WITH FINES (Appreciable Amount of fines)	SM	Silty sands, sand - silt mixtures
			SC	Clayey sands, sand - clay mixtures
FINE GRAINED SOILS (More than 50% of material is SMALLER than No. 200 sieve size)	SILTS AND CLAYS (Liquid limit LESS than 50)		ML	Inorganic silts and very fine sands, rock flour, silty or clayey fine sands or clayey silts with slight plasticity
			CL	Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays, lean clays
			OL	Organic silts and organic silty clays of low plasticity
	SILTS AND CLAYS (Liquid limit GREATER than 50)		MH	Inorganic silts, micaceous or diatomaceous fine sands or silts, elastic silts
			CH	Inorganic clays of high plasticity, fat clays
			OH	Organic clays of medium to high plasticity, organic silts
HIGHLY ORGANIC SOILS			Pt	Peat, muck and other highly organic soils

BOUNDARY CLASSIFICATIONS Soils possessing characteristics of two groups are designated by combinations of group symbols.

Reference: The Unified Soil Classification System, Corps of Engineers, U. S. Army Technical Memorandum No. 3 - 357, Vol 1, March, 1953 (Revised April, 1960)

UNIFIED SOIL CLASSIFICATION SYSTEM

Proposed Residential Buildings
11148 Lorne St & 8032 Fair Ave
Sun Valley, Los Angeles, California

GSS ENGINEERING, INC. *Geotechnical Engineering Consultants*

PROJECT No. GSS-3095-1 **PLATE** A-1

NOTE: The data presented on this log is a simplification of actual subsurface conditions encountered and applies only at the location of this boring and the date of drilling. It is not warranted to be representative of subsurface conditions at other locations and times.

BORING NO. 1

Elevation: N/A

Depth in Feet	Blow per Foot	Field Moisture % of Dry Weight	Dry Density lbs./cu.ft.	Shear Resistance kips/sq.ft.	Confining Pressure kips/sq.ft.	Unified Classification	Soil Symbol					
						SM		FILL	SAND, fine to medium, silty, occasioanl coarse	drk gry	sl moist	m dense
	14	1.4	100.4			SW		SAND	fine to coarse, slightly silty, occ. gravels	white gray	slightly moist	m dense to dense
	29	0.7	114.5						fine to coarse, slightly silty, gravelly, rocky			dense
5												
	42	0.9	117.4									
10	bag	0.5										
15	50	0.7	108.0						fine to coarse, slightly silty to silty gravelly, rocky			
20	50	1.2	106.9									

End of Test Boring @ 20'

Date Drilled: 2/8/2022
Drilling Equipment: 8-inch diameter hollow stem auger
Driving Weight: 140 lbs @ 30-inch drop
Water Depth: not encountered

LOG OF TEST BORING

Proposed Residential Buildings
11148 Lorne St & 8032 Fair Ave
Sun Valley, Los Angeles, California

GSS ENGINEERING, INC. *Geotechnical Engineering Consultants*

PROJECT No. GSS-3095-1 **PLATE** A-2

NOTE: The data presented on this log is a simplification of actual subsurface conditions encountered and applies only at the location of this boring and the date of drilling. It is not warranted to be representative of subsurface conditions at other locations and times.

BORING NO. 2

Elevation: N/A

Depth in Feet	Blow per Foot	Field Moisture % of Dry Weight	Dry Density lbs./cu.ft.	Shear Resistance kips/sq.ft.	Confining Pressure kips/sq.ft.	Unified Classification	Soil Symbol					
						SM		FILL	SAND, fine to medium, silty, occasioanl coarse	drk gry	sl moist	m dense
	21	2.8	106.7			SW		SAND	fine to coarse, slightly silty, occ. gravels	white gray	slightly moist	dense
	24	2.2	107.2						fine to coarse, slightly silty, gravelly, rocky			
5												
	50	3.6	120.9									
10	50	1.5	124.3									

End of Test Boring @ 10'

Date Drilled: 2/8/2022
Drilling Equipment: 8-inch diameter hollow stem auger
Driving Weight: 140 lbs @ 30-inch drop
Water Depth: not encountered

LOG OF TEST BORING

Proposed Residential Buildings
11148 Lorne St & 8032 Fair Ave
Sun Valley, Los Angeles, California

GSS ENGINEERING, INC. *Geotechnical Engineering Consultants*

PROJECT No. GSS-3095-1 **PLATE** A-3

NOTE: The data presented on this log is a simplification of actual subsurface conditions encountered and applies only at the location of this boring and the date of drilling. It is not warranted to be representative of subsurface conditions at other locations and times.

BORING NO. 3

Elevation: N/A

Depth in Feet	Blow per Foot	Field Moisture % of Dry Weight	Dry Density lbs/cu.ft.	Shear Resistance kips/sq.ft.	Confining Pressure kips/sq.ft.	Unified Classification	Soil Symbol					
						SM		FILL	SAND, fine to medium, silty, occasioanl coarse	drk gry	sl moist	m dense
	21	2.2	110.4			SW		SAND	fine to coarse, slightly silty, occ. gravels	white gray	slightly moist	dense
	27	3.7	112.8						fine to coarse, slightly silty, gravelly, rocky			
5												
	45	2.2	122.4									
10	50	2.3	116.5									
15	50	1.2	113.9						fine to coarse, sl. silty to silty, gravelly, rocky			
									End of Test Boring @ 15'			

Date Drilled: 2/8/2022
Drilling Equipment: 8-inch diameter hollow stem auger
Driving Weight: 140 lbs @ 30-inch drop
Water Depth: not encountered

LOG OF TEST BORING

Proposed Residential Buildings
11148 Lorne St & 8032 Fair Ave
Sun Valley, Los Angeles, California

GSS ENGINEERING, INC. *Geotechnical Engineering Consultants*

PROJECT No. GSS-3095-1 **PLATE** A-4

NOTE: The data presented on this log is a simplification of actual subsurface conditions encountered and applies only at the location of this boring and the date of drilling. It is not warranted to be representative of subsurface conditions at other locations and times.

BORING NO. 4

Elevation: N/A

Depth in Feet	Blow per Foot	Field Moisture % of Dry Weight	Dry Density lbs/cu.ft.	Shear Resistance kips/sq.ft.	Confining Pressure kips/sq.ft.	Unified Classification	Soil Symbol					
						SM		FILL	SAND, fine to medium, silty, occasioanl coarse	drk gry	sl moist	m dense
	13	1.8	102.3			SW		SAND	fine to coarse, slightly silty, occ. gravels	white gray	slightly moist	m dense to dense
	28	2.5	117.4						fine to coarse, slightly silty, gravelly, rocky			dense
5												
	40	3.9	121.0									
10	38	4.6	107.9									

End of Test Boring @ 10'

Date Drilled: 2/8/2022
Drilling Equipment: 8-inch diameter hollow stem auger
Driving Weight: 140 lbs @ 30-inch drop
Water Depth: not encountered

LOG OF TEST BORING

Proposed Residential Buildings
11148 Lorne St & 8032 Fair Ave
Sun Valley, Los Angeles, California

GSS ENGINEERING, INC. *Geotechnical Engineering Consultants*

PROJECT No. GSS-3095-1 **PLATE** A-5



Samples were tested under saturated and drained conditions.

	Boring No.	Depth (feet)	UC	Initial Water Content (% of dry wt.)	Final Water Content (% of dry wt.)	Dry Density (lbs / cu.ft.)	Cohesion (lbs / sq. ft.)	Angle of Friction (degrees)
●	2	4	SW	2.2	20.2	107.2	40	39
							residual shear strength	
▲	4	7	SW	3.9	14.1	121.0	50	38
							residual shear strength	

DIRECT SHEAR TEST DATA

Proposed Residential Buildings
11148 Lorne St & 8032 Fair Ave
Sun Valley, Los Angeles, California

GSS ENGINEERING, INC. *Geotechnical Engineering Consultants* | **PROJECT No.** GSS-3095-1 | **PLATE** A-6



Boring No. 1 @ 7.0'

O Water Permitted to Contact Sample

CONSOLIDATION TEST	Proposed Residential Buildings 11146 Lorne St & 8032 Fair Ave Sun Valley, Los Angeles, California
GSS ENGINEERING, INC. *Geotechnical Engineering Consultants*	**PROJECT No.** GSS-3095-1 **PLATE** A-7



Boring No. 3 @ 4.0'

O Water Permitted to Contact Sample

CONSOLIDATION TEST	Proposed Residential Buildings 11148 Lorne St & 8032 Fair Ave Sun Valley, Los Angeles, California
GSS ENGINEERING, INC. *Geotechnical Engineering Consultants*	**PROJECT No.** GSS-3095-1 **PLATE** A-8